


# Curve Fitting Toolbox™

User's Guide



# MATLAB®

R2023b



## How to Contact MathWorks



Latest news: [www.mathworks.com](http://www.mathworks.com)  
Sales and services: [www.mathworks.com/sales\\_and\\_services](http://www.mathworks.com/sales_and_services)  
User community: [www.mathworks.com/matlabcentral](http://www.mathworks.com/matlabcentral)  
Technical support: [www.mathworks.com/support/contact\\_us](http://www.mathworks.com/support/contact_us)



Phone: 508-647-7000



The MathWorks, Inc.  
1 Apple Hill Drive  
Natick, MA 01760-2098

*Curve Fitting Toolbox™ User's Guide*

© COPYRIGHT 2001–2023 by The MathWorks, Inc.

The software described in this document is furnished under a license agreement. The software may be used or copied only under the terms of the license agreement. No part of this manual may be photocopied or reproduced in any form without prior written consent from The MathWorks, Inc.

FEDERAL ACQUISITION: This provision applies to all acquisitions of the Program and Documentation by, for, or through the federal government of the United States. By accepting delivery of the Program or Documentation, the government hereby agrees that this software or documentation qualifies as commercial computer software or commercial computer software documentation as such terms are used or defined in FAR 12.212, DFARS Part 227.72, and DFARS 252.227-7014. Accordingly, the terms and conditions of this Agreement and only those rights specified in this Agreement, shall pertain to and govern the use, modification, reproduction, release, performance, display, and disclosure of the Program and Documentation by the federal government (or other entity acquiring for or through the federal government) and shall supersede any conflicting contractual terms or conditions. If this License fails to meet the government's needs or is inconsistent in any respect with federal procurement law, the government agrees to return the Program and Documentation, unused, to The MathWorks, Inc.

### Trademarks

MATLAB and Simulink are registered trademarks of The MathWorks, Inc. See [www.mathworks.com/trademarks](http://www.mathworks.com/trademarks) for a list of additional trademarks. Other product or brand names may be trademarks or registered trademarks of their respective holders.

### Patents

MathWorks products are protected by one or more U.S. patents. Please see [www.mathworks.com/patents](http://www.mathworks.com/patents) for more information.

## Revision History

July 2001	First printing	New for Version 1 (Release 12.1)
July 2002	Second printing	Revised for Version 1.1 (Release 13)
June 2004	Online only	Revised for Version 1.1.1 (Release 14)
October 2004	Online only	Revised for Version 1.1.2 (Release 14SP1)
March 2005	Online only	Revised for Version 1.1.3 (Release 14SP2)
June 2005	Third printing	Minor revision
September 2005	Online only	Revised for Version 1.1.4 (Release 14SP3)
March 2006	Online only	Revised for Version 1.1.5 (Release 2006a)
September 2006	Online only	Revised for Version 1.1.6 (Release 2006b)
November 2006	Fourth printing	Minor revision
March 2007	Online only	Revised for Version 1.1.7 (Release 2007a)
September 2007	Online only	Revised for Version 1.2 (Release 2007b)
March 2008	Online only	Revised for Version 1.2.1 (Release 2008a)
October 2008	Online only	Revised for Version 1.2.2 (Release 2008b)
March 2009	Online only	Revised for Version 2.0 (Release 2009a)
September 2009	Online only	Revised for Version 2.1 (Release 2009b)
March 2010	Online only	Revised for Version 2.2 (Release 2010a)
September 2010	Online only	Revised for Version 3.0 (Release 2010b)
April 2011	Online only	Revised for Version 3.1 (Release 2011a)
September 2011	Online only	Revised for Version 3.2 (Release 2011b)
March 2012	Online only	Revised for Version 3.2.1 (Release 2012a)
September 2012	Online only	Revised for Version 3.3 (Release 2012b)
March 2013	Online only	Revised for Version 3.3.1 (Release 2013a)
September 2013	Online only	Revised for Version 3.4 (Release 2013b)
March 2014	Online only	Revised for Version 3.4.1 (Release 2014a)
October 2014	Online only	Revised for Version 3.5 (Release 2014b)
March 2015	Online only	Revised for Version 3.5.1 (Release 2015a)
September 2015	Online only	Revised for Version 3.5.2 (Release 2015b)
March 2016	Online only	Revised for Version 3.5.3 (Release 2016a)
September 2016	Online only	Revised for Version 3.5.4 (Release 2016b)
March 2017	Online only	Revised for Version 3.5.5 (Release 2017a)
September 2017	Online only	Revised for Version 3.5.6 (Release 2017b)
March 2018	Online only	Revised for Version 3.5.7 (Release 2018a)
September 2018	Online only	Revised for Version 3.5.8 (Release 2018b)
March 2019	Online only	Revised for Version 3.5.9 (Release 2019a)
September 2019	Online only	Revised for Version 3.5.10 (Release 2019b)
March 2020	Online only	Revised for Version 3.5.11 (Release 2020a)
September 2020	Online only	Revised for Version 3.5.12 (Release 2020b)
March 2021	Online only	Revised for Version 3.5.13 (Release 2021a)
September 2021	Online only	Revised for Version 3.6 (Release 2021b)
March 2022	Online only	Revised for Version 3.7 (Release 2022a)
September 2022	Online only	Revised for Version 3.8 (Release 2022b)
March 2023	Online only	Revised for Version 3.9 (Release 2023a)
September 2023	Online only	Revised for Version 23.2 (R2023b)





<b>1</b>	<b>Getting Started</b>
	<hr/>
	<b>Curve Fitting Toolbox Product Description . . . . . 1-2</b>
	<b>Curve Fitting Tools . . . . . 1-3</b>
	<b>Curve Fitting . . . . . 1-4</b>
	Interactive Curve Fitting . . . . . 1-4
	Programmatic Curve Fitting . . . . . 1-4
	<b>Surface Fitting . . . . . 1-6</b>
	Interactive Surface Fitting . . . . . 1-6
	Programmatic Surface Fitting . . . . . 1-6
	<b>Spline Fitting . . . . . 1-8</b>
	About Splines in Curve Fitting Toolbox . . . . . 1-8
	Interactive Spline Fitting . . . . . 1-8
	Programmatic Spline Fitting . . . . . 1-8

<b>2</b>	<b>Interactive Fitting</b>
	<hr/>
	<b>Interactive Curve and Surface Fitting . . . . . 2-2</b>
	Introducing Curve Fitter App . . . . . 2-2
	Fit Curve . . . . . 2-2
	Fit Surface . . . . . 2-4
	Model Types for Curves and Surfaces . . . . . 2-6
	Selecting Data to Fit in Curve Fitter App . . . . . 2-7
	Save and Reopen Sessions . . . . . 2-9
	<b>Data Selection . . . . . 2-11</b>
	Import Data to Workspace . . . . . 2-11
	Select Data to Fit at Command Line . . . . . 2-11
	Select Data to Fit in Curve Fitter App . . . . . 2-11
	Tabular Data . . . . . 2-13
	<b>Create Multiple Fits in Curve Fitter App . . . . . 2-15</b>
	Refining Your Fit . . . . . 2-15
	Creating Multiple Fits . . . . . 2-15
	Displaying Multiple Fits Simultaneously . . . . . 2-15
	Using the Statistics in the Table of Fits . . . . . 2-17

<b>Compare Fits in Curve Fitter App</b> .....	<b>2-19</b>
Interactive Curve Fitter Workflow .....	2-19
Loading Data and Creating Fits .....	2-19
Determining the Best Fit .....	2-21
Analyzing Best Fit in the Workspace .....	2-27
Saving Your Work .....	2-30
<b>Surface Fitting to Franke Data</b> .....	<b>2-32</b>

## Programmatic Curve and Surface Fitting

### 3

<b>Curve and Surface Fitting</b> .....	<b>3-2</b>
Fitting a Curve .....	3-2
Fitting a Surface .....	3-2
Model Types and Fit Analysis .....	3-2
Workflow for Command Line Fitting .....	3-3
<b>Curve and Surface Fitting Objects and Object Functions</b> .....	<b>3-5</b>
Curve Fitting Objects .....	3-5
Curve Fitting Object Functions .....	3-6
Surface Fitting Objects and Object Functions .....	3-8

## Linear and Nonlinear Regression

### 4

<b>Parametric Fitting</b> .....	<b>4-2</b>
Parametric Fitting with Library Models .....	4-2
Select Model Type .....	4-3
Center and Scale Data .....	4-4
Specify Fit Options and Optimized Starting Points .....	4-5
<b>List of Library Models for Curve and Surface Fitting</b> .....	<b>4-10</b>
Use Library Models to Fit Data .....	4-10
Library Model Types .....	4-10
Model Names and Equations .....	4-11
<b>Polynomial Models</b> .....	<b>4-15</b>
About Polynomial Models .....	4-15
Fit Polynomial Models Interactively .....	4-16
Fit Polynomials Using the Fit Function .....	4-17
Polynomial Model Fit Options .....	4-27
Defining Polynomial Terms for Polynomial Surface Fits .....	4-28
<b>Exponential Models</b> .....	<b>4-30</b>
About Exponential Models .....	4-30
Fit Exponential Models Interactively .....	4-30
Fit Exponential Models Using the fit Function .....	4-32

<b>Fit Fourier Models</b> .....	<b>4-37</b>
About Fourier Series Models .....	<b>4-37</b>
Fit Fourier Model Interactively in Curve Fitter App .....	<b>4-37</b>
Fit Fourier Model at the Command Line .....	<b>4-42</b>
<b>Gaussian Models</b> .....	<b>4-53</b>
About Gaussian Models .....	<b>4-53</b>
Fit Gaussian Models Interactively .....	<b>4-53</b>
Fit Gaussian Models Using the fit Function .....	<b>4-54</b>
<b>Fit Logarithmic Models</b> .....	<b>4-57</b>
About Logarithmic Models .....	<b>4-57</b>
Fit Logarithmic Models Using Curve Fitter .....	<b>4-57</b>
Fit Logarithmic Models from Command Line .....	<b>4-61</b>
<b>Power Series</b> .....	<b>4-63</b>
About Power Series Models .....	<b>4-63</b>
Fit Power Series Models Interactively .....	<b>4-63</b>
Fit Power Series Models Using the fit Function .....	<b>4-64</b>
<b>Rational Models</b> .....	<b>4-67</b>
Fit Rational Models Interactively .....	<b>4-67</b>
Selecting a Rational Fit at the Command Line .....	<b>4-68</b>
Example: Rational Fit .....	<b>4-68</b>
<b>Sum of Sines Models</b> .....	<b>4-74</b>
About Sum of Sines Models .....	<b>4-74</b>
Fit Sum of Sine Models Interactively .....	<b>4-74</b>
Selecting a Sum of Sine Fit at the Command Line .....	<b>4-75</b>
<b>Fit Sigmoidal Models</b> .....	<b>4-77</b>
Fit Sigmoidal Model Using Curve Fitter App .....	<b>4-77</b>
Fit Sigmoidal Model at Command Line .....	<b>4-80</b>
<b>Weibull Distributions</b> .....	<b>4-84</b>
About Weibull Distribution Models .....	<b>4-84</b>
Fit Weibull Models Interactively .....	<b>4-84</b>
Selecting a Weibull Fit at the Command Line .....	<b>4-85</b>
<b>Introduction to Least-Squares Fitting</b> .....	<b>4-87</b>
Calculating Residuals .....	<b>4-87</b>
Error Assumptions .....	<b>4-88</b>
Linear Least Squares .....	<b>4-88</b>
Weighted Least Squares .....	<b>4-89</b>
Robust Least Squares .....	<b>4-90</b>
Nonlinear Least Squares .....	<b>4-91</b>

## Custom Linear and Nonlinear Regression

# 5

<b>Custom Models</b> .....	<b>5-2</b>
Custom Models vs. Library Models .....	<b>5-2</b>

Selecting a Custom Equation Fit Interactively . . . . .	5-2
Selecting a Custom Equation Fit at the Command Line . . . . .	5-5
<b>Custom Linear Fitting . . . . .</b>	<b>5-7</b>
About Custom Linear Models . . . . .	5-7
Selecting a Linear Fitting Custom Fit Interactively . . . . .	5-7
Selecting Linear Fitting at the Command Line . . . . .	5-8
Fit Custom Linear Legendre Polynomials . . . . .	5-9
<b>Custom Nonlinear Census Fitting . . . . .</b>	<b>5-20</b>
<b>Custom Nonlinear ENSO Data Analysis . . . . .</b>	<b>5-23</b>
Load Data and Fit Library and Custom Fourier Models . . . . .	5-23
Use Fit Options to Constrain a Coefficient . . . . .	5-26
Create Second Custom Fit with Additional Terms and Constraints . . . . .	5-28
Create a Third Custom Fit with Additional Terms and Constraints . . . . .	5-29
<b>Gaussian Fitting with an Exponential Background . . . . .</b>	<b>5-32</b>
<b>Surface Fitting to Biopharmaceutical Data . . . . .</b>	<b>5-35</b>

## Interpolation and Smoothing

# 6

<b>Nonparametric Fitting . . . . .</b>	<b>6-2</b>
<b>Interpolation with Curve Fitting Toolbox . . . . .</b>	<b>6-3</b>
About Interpolation Methods . . . . .	6-3
Selecting an Interpolant Fit . . . . .	6-4
<b>Extrapolation for Interpolant Fit Types . . . . .</b>	<b>6-8</b>
Selecting an Extrapolation Method . . . . .	6-9
<b>Smoothing Splines . . . . .</b>	<b>6-14</b>
About Smoothing Splines . . . . .	6-14
Select Smoothing Spline Fit Interactively . . . . .	6-15
Fit Smoothing Spline Models Using the fit Function . . . . .	6-16
Compare Cubic and Smoothing Spline Fit Using Curve Fitter . . . . .	6-18
<b>Lowess Smoothing . . . . .</b>	<b>6-22</b>
About Lowess Smoothing . . . . .	6-22
Select Lowess Fit Interactively . . . . .	6-22
Fit Lowess Models Using the fit Function . . . . .	6-23
<b>Fit Smooth Surfaces to Investigate Fuel Efficiency . . . . .</b>	<b>6-26</b>
<b>Filtering and Smoothing Data . . . . .</b>	<b>6-34</b>
About Data Filtering and Smoothing . . . . .	6-34
Moving Average Filtering . . . . .	6-34
Savitzky-Golay Filtering . . . . .	6-35
Local Regression Smoothing . . . . .	6-36
Example: Smoothing Data . . . . .	6-40

## Fit Postprocessing

# 7

<b>Explore and Customize Plots</b> . . . . .	7-2
Displaying Fit and Residual Plots . . . . .	7-2
Viewing Surface Plots and Contour Plots . . . . .	7-3
Using Zoom, Pan, Data Cursor, and Outlier Exclusion . . . . .	7-5
Customizing the Fit Display . . . . .	7-5
Print to MATLAB Figures . . . . .	7-6
<b>Remove Outliers</b> . . . . .	7-8
Remove Outliers Interactively . . . . .	7-8
Exclude Data Ranges . . . . .	7-8
Remove Outliers Programmatically . . . . .	7-8
<b>Select Validation Data</b> . . . . .	7-12
<b>Generate Code and Export Fits to the Workspace</b> . . . . .	7-13
Generating Code from the Curve Fitter App . . . . .	7-13
Exporting a Fit to the Workspace . . . . .	7-14
<b>Evaluate Curve Fit</b> . . . . .	7-16
<b>Evaluate Surface Fit</b> . . . . .	7-24
<b>Compare Fits Programmatically</b> . . . . .	7-30
<b>Evaluating Goodness of Fit</b> . . . . .	7-42
How to Evaluate Goodness of Fit . . . . .	7-42
Goodness-of-Fit Statistics . . . . .	7-43
<b>Residual Analysis</b> . . . . .	7-46
Plotting and Analysing Residuals . . . . .	7-46
Example: Residual Analysis . . . . .	7-47
<b>Confidence and Prediction Bounds</b> . . . . .	7-50
About Confidence and Prediction Bounds . . . . .	7-50
Confidence Bounds on Coefficients . . . . .	7-50
Prediction Bounds on Fits . . . . .	7-51
Calculate Prediction Intervals from the Command Line . . . . .	7-53
Calculate Prediction Bounds Using Curve Fitter App . . . . .	7-54
<b>Differentiating and Integrating a Fit</b> . . . . .	7-58

### 8

<b>Introducing Spline Fitting</b> .....	<b>8-2</b>
Spline Overview .....	8-2
Interactive Spline Fitting .....	8-2
Programmatic Spline Fitting .....	8-3
<b>Curve Fitting Toolbox Splines and MATLAB Splines</b> .....	<b>8-4</b>
Curve Fitting Toolbox Splines .....	8-4
Splines .....	8-5
MATLAB Splines .....	8-5
Expected Background .....	8-6
Vector Data Type Support .....	8-6
Spline Function Naming Conventions .....	8-6
Arguments for Curve Fitting Toolbox Spline Functions .....	8-7
Acknowledgments .....	8-7

## Simple Spline Examples

### 9

<b>Cubic Spline Interpolation</b> .....	<b>9-2</b>
Cubic Spline Interpolant of Smooth Data .....	9-2
Periodic Data .....	9-3
Other End Conditions .....	9-4
General Spline Interpolation .....	9-4
Knot Choices .....	9-5
Smoothing .....	9-5
Least Squares .....	9-7
<b>Vector-Valued Functions</b> .....	<b>9-8</b>
<b>Fitting Values at N-D Grid with Tensor-Product Splines</b> .....	<b>9-10</b>
<b>Fitting Values at Scattered 2-D Sites with Thin-Plate Smoothing Splines</b> .....	<b>9-12</b>
<b>Postprocessing Splines</b> .....	<b>9-13</b>

<b>Types of Splines: ppform and B-form</b> .....	<b>10-2</b>
Polynomials vs. Splines .....	10-2
ppform .....	10-2
B-form .....	10-2
Knot Multiplicity .....	10-3
<b>B-Splines and Smoothing Splines</b> .....	<b>10-4</b>
B-Spline Properties .....	10-4
Variational Approach and Smoothing Splines .....	10-4
<b>Multivariate and Rational Splines</b> .....	<b>10-6</b>
Multivariate Splines .....	10-6
Rational Splines .....	10-7
<b>The ppform</b> .....	<b>10-8</b>
Introduction to ppform .....	10-8
Definition of ppform .....	10-8
<b>Constructing and Working with ppform Splines</b> .....	<b>10-10</b>
Constructing a ppform .....	10-10
Working With ppform Splines .....	10-10
Example ppform .....	10-11
<b>The B-form</b> .....	<b>10-13</b>
Introduction to B-form .....	10-13
Definition of B-form .....	10-13
B-form and B-Splines .....	10-13
B-Spline Knot Multiplicity .....	10-14
Choice of Knots for B-form .....	10-15
<b>Constructing and Working with B-form Splines</b> .....	<b>10-17</b>
Construction of B-form .....	10-17
Working With B-form Splines .....	10-17
Example: B-form Spline Approximation to a Circle .....	10-18
<b>Multivariate Tensor Product Splines</b> .....	<b>10-21</b>
Introduction to Multivariate Tensor Product Splines .....	10-21
B-form of Tensor Product Splines .....	10-21
Construction With Gridded Data .....	10-21
ppform of Tensor Product Splines .....	10-22
Example: The Mobius Band .....	10-22
<b>NURBS and Other Rational Splines</b> .....	<b>10-23</b>
Introduction to Rational Splines .....	10-23
rsform: rpform, rBform .....	10-23
<b>Constructing and Working with Rational Splines</b> .....	<b>10-25</b>
Rational Spline Example: Circle .....	10-25
Rational Spline Example: Sphere .....	10-26
Functions for Working With Rational Splines .....	10-26

<b>Constructing and Working with stform Splines</b> .....	<b>10-28</b>
Introduction to the stform .....	<b>10-28</b>
Construction and Properties of the stform .....	<b>10-28</b>
Working with the stform .....	<b>10-29</b>

## Advanced Spline Examples

# 11

<b>Least-Squares Approximation by Natural Cubic Splines</b> .....	<b>11-2</b>
Problem .....	<b>11-2</b>
General Resolution .....	<b>11-2</b>
Need for a Basis Map .....	<b>11-2</b>
A Basis Map for “Natural” Cubic Splines .....	<b>11-3</b>
The One-line Solution .....	<b>11-3</b>
The Need for Proper Extrapolation .....	<b>11-3</b>
The Correct One-Line Solution .....	<b>11-4</b>
Least-Squares Approximation by Cubic Splines .....	<b>11-5</b>
 <b>Solving A Nonlinear ODE</b> .....	 <b>11-6</b>
Problem .....	<b>11-6</b>
Approximation Space .....	<b>11-6</b>
Discretization .....	<b>11-6</b>
Numerical Problem .....	<b>11-7</b>
Linearization .....	<b>11-7</b>
Linear System to Be Solved .....	<b>11-7</b>
Iteration .....	<b>11-8</b>
 <b>Chebyshev Spline Construction</b> .....	 <b>11-10</b>
What Is a Chebyshev Spline? .....	<b>11-10</b>
Choice of Spline Space .....	<b>11-10</b>
Initial Guess .....	<b>11-10</b>
Remez Iteration .....	<b>11-11</b>
 <b>Approximation by Tensor Product Splines</b> .....	 <b>11-14</b>
Choice of Sites and Knots .....	<b>11-14</b>
Least Squares Approximation as Function of y .....	<b>11-14</b>
Approximation to Coefficients as Functions of x .....	<b>11-16</b>
The Bivariate Approximation .....	<b>11-16</b>
Switch in Order .....	<b>11-17</b>
Approximation to Coefficients as Functions of y .....	<b>11-18</b>
The Bivariate Approximation .....	<b>11-19</b>
Comparison and Extension .....	<b>11-20</b>

## Examples

# 12

<b>Polynomial Curve Fitting</b> .....	<b>12-2</b>
<b>Surface Fitting with Custom Equations to Biopharmaceutical Data</b> ..	<b>12-14</b>



<b>How to Construct Splines</b> .....	<b>12-20</b>
<b>Construct and Work with the B-form</b> .....	<b>12-40</b>
<b>Construct and Work with the PPFORM</b> .....	<b>12-57</b>
<b>How to Choose Knots</b> .....	<b>12-66</b>
<b>Cubic Spline Interpolation</b> .....	<b>12-74</b>
<b>Cubic Smoothing Splines</b> .....	<b>12-94</b>
<b>Fitting a Spline to Titanium Test Data</b> .....	<b>12-102</b>
<b>Splines in the Plane</b> .....	<b>12-115</b>
<b>Constructing Spline Curves in 2D and 3D</b> .....	<b>12-126</b>
<b>Smoothing a Histogram</b> .....	<b>12-130</b>
<b>Bivariate Tensor Product Splines</b> .....	<b>12-133</b>
<b>Solving a Nonlinear ODE with a Boundary Layer by Collocation</b> .....	<b>12-145</b>
<b>Construct Chebyshev Spline</b> .....	<b>12-156</b>
<b>Export Fit from Curve Fitter App to Simulink Lookup Table</b> .....	<b>12-164</b>
<b>Fit Polynomial Model to Data</b> .....	<b>12-173</b>
<b>Improve Model Fit with Weights</b> .....	<b>12-175</b>
<b>Compare Robust Fitting Methods</b> .....	<b>12-179</b>
<b>Fit Exponential Model to Data</b> .....	<b>12-185</b>

## Functions

**13**

## Bibliography

**A**



# Getting Started

---

- “Curve Fitting Toolbox Product Description” on page 1-2
- “Curve Fitting Tools” on page 1-3
- “Curve Fitting” on page 1-4
- “Surface Fitting” on page 1-6
- “Spline Fitting” on page 1-8

## **Curve Fitting Toolbox Product Description**

### **Fit curves and surfaces to data using regression, interpolation, and smoothing**

Curve Fitting Toolbox provides an app and functions for fitting curves and surfaces to data. The toolbox lets you perform exploratory data analysis, preprocess and post-process data, compare candidate models, and remove outliers. You can conduct regression analysis using the library of linear and nonlinear models provided or specify your own custom equations. The library provides optimized solver parameters and starting conditions to improve the quality of your fits. The toolbox also supports nonparametric modeling techniques, such as splines, interpolation, and smoothing.

After creating a fit, you can apply a variety of post-processing methods for plotting, interpolation, and extrapolation; estimating confidence intervals; and calculating integrals and derivatives.

## Curve Fitting Tools

Curve Fitting Toolbox software allows you to work in two different environments:

- An interactive environment, with the Curve Fitter app and the Spline Tool
- A programmatic environment that allows you to write object-oriented MATLAB® code using curve and surface fitting methods

To open the Curve Fitter app or Spline Tool, enter one of the following:

- `curveFitter` (see Curve Fitter)
- `splinetool`

To list the Curve Fitting Toolbox functions for use in MATLAB programming, type the following:

```
help curvefit
```

The code for any function can be opened in the MATLAB Editor by typing `edit`, followed by the function name. For example:

```
edit fittype
```

Brief command line help for any function is available by typing `help`, followed by the function name. For example:

```
help smooth
```

Complete documentation for any function is available by typing `doc`, followed by the function name. For example:

```
doc fit
```

You can change the way any toolbox function works by copying and renaming its file, examining your copy in the editor, and then modifying it.

You can also extend the toolbox by adding your own files, or by using your code in combination with functions from other toolboxes, such as Statistics and Machine Learning Toolbox or Optimization Toolbox software.

## Curve Fitting

### Interactive Curve Fitting

To interactively fit a curve, follow the steps in this simple example:

- 1 Load some data at the MATLAB command line.

```
load hahn1
```

- 2 Open the Curve Fitter app.

```
curveFitter
```

- 3 In the Curve Fitter app, on the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select **temp** as the **X data** value and **thermex** as the **Y data** value.

The Curve Fitter app creates a default polynomial fit to the data.

- 4 Choose a different model type from the fit gallery in the **Fit Type** section of the **Curve Fitter** tab.
- 5 In the **Fit Options** pane, try different fit options for your chosen model type.
- 6 In the **Export** section, click **Export** and select **Generate Code**.

The Curve Fitter app creates a file in the Editor containing MATLAB code to recreate the currently selected fit and its opened plots in your interactive session.

For more information about fitting curves in the Curve Fitter app, see “Interactive Curve and Surface Fitting” on page 2-2.

### Programmatic Curve Fitting

To programmatically fit a curve, follow the steps in this simple example:

- 1 Load some data.

```
load hahn1
```

- 2 Create a fit using the `fit` function, specifying the variables and a model type (in this case `rat23` is the model type).

```
f = fit(temp,thermex,"rat23")
```

- 3 Plot your fit and the data.

```
plot(f,temp,thermex)  
f(600)
```

To learn what functions you can use to create and work with fits, see “Curve and Surface Fitting” on page 3-2.

### See Also

Curve Fitter | `fit`

**Related Examples**

- “Interactive Curve and Surface Fitting” on page 2-2
- “Linear and Nonlinear Regression”
- “Interpolation”
- “Smoothing”
- “Fit Postprocessing”

## Surface Fitting

### Interactive Surface Fitting

To interactively fit a surface, follow the steps in this simple example:

- 1 Load some data at the MATLAB command line.

```
load franke
```

- 2 Open the Curve Fitter app.

```
curveFitter
```

- 3 In the Curve Fitter app, on the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select *x*, *y*, and *z* as the **X data**, **Y data**, and **Z data** values, respectively.

The Curve Fitter app creates a default interpolation fit to the data.

- 4 Choose a different model type from the fit gallery in the **Fit Type** section of the **Curve Fitter** tab.
- 5 In the **Fit Options** pane, try different fit options for your chosen model type.
- 6 In the **Export** section, click **Export** and select **Generate Code**.

The Curve Fitter app creates a file in the Editor containing MATLAB code to recreate the currently selected fit and its opened plots in your interactive session.

For more information about fitting surfaces in the Curve Fitter app, see “Interactive Curve and Surface Fitting” on page 2-2.

### Programmatic Surface Fitting

To programmatically fit a surface, follow the steps in this simple example:

- 1 Load some data.

```
load franke
```

- 2 Create a fit using the `fit` function, specifying the variables and a model type (in this case `poly23` is the model type).

```
f = fit([x y],z,"poly23")
```

- 3 Plot your fit and the data.

```
plot(f,[x y],z)
```

To learn what functions you can use to create and work with fits, see “Curve and Surface Fitting” on page 3-2.

### See Also

Curve Fitter | `fit`



**Related Examples**

- “Interactive Curve and Surface Fitting” on page 2-2
- “Linear and Nonlinear Regression”
- “Interpolation”
- “Smoothing”
- “Fit Postprocessing”

## Spline Fitting

In this section...
“About Splines in Curve Fitting Toolbox” on page 1-8
“Interactive Spline Fitting” on page 1-8
“Programmatic Spline Fitting” on page 1-8

### About Splines in Curve Fitting Toolbox

You can work with splines in Curve Fitting Toolbox in several ways.

Using the Curve Fitter app or the `fit` function you can:

- Fit cubic spline interpolants to curves or surfaces
- Fit smoothing splines and shape-preserving cubic spline interpolants to curves (but not surfaces)
- Fit thin-plate splines to surfaces (but not curves)

The toolbox also contains specific splines functions to allow greater control over what you can create. For example, you can use the `csapi` function for cubic spline interpolation. Why would you use `csapi` instead of the `fit` function 'cubicinterp' option? You might require greater flexibility to work with splines for the following reasons:

- You want to combine the results with other splines, for example, by addition.
- You want vector-valued splines. You can use `csapi` with scalars, vectors, matrices, and ND-arrays. The `fit` function only allows scalar-valued splines.
- You want other types of splines such as `ppform`, B-form, tensor-product, rational, and `stform` thin-plate splines.
- You want to create splines without data.
- You want to specify breaks, optimize knot placement, and use specialized functions for spline manipulation such as differentiation and integration.

If you require specialized spline functions, see the following sections for interactive and programmatic spline fitting.

### Interactive Spline Fitting

You can access all spline functions from the Spline Tool (`splinetool`).

See “Introducing Spline Fitting” on page 8-2.

### Programmatic Spline Fitting

To programmatically fit splines, see “Spline Construction” for descriptions of types of splines and numerous examples.

# Interactive Fitting

---

- “Interactive Curve and Surface Fitting” on page 2-2
- “Data Selection” on page 2-11
- “Create Multiple Fits in Curve Fitter App” on page 2-15
- “Compare Fits in Curve Fitter App” on page 2-19
- “Surface Fitting to Franke Data” on page 2-32

## Interactive Curve and Surface Fitting

### In this section...

- “Introducing Curve Fitter App” on page 2-2
- “Fit Curve” on page 2-2
- “Fit Surface” on page 2-4
- “Model Types for Curves and Surfaces” on page 2-6
- “Selecting Data to Fit in Curve Fitter App” on page 2-7
- “Save and Reopen Sessions” on page 2-9

### Introducing Curve Fitter App

You can fit curves and surfaces to data and view plots with the Curve Fitter app.

- Create, plot, and compare multiple fits.
- Use linear or nonlinear regression, interpolation, smoothing, and custom equations.
- View goodness-of-fit statistics, display confidence intervals and residuals, remove outliers, and assess fits with validation data.
- Automatically generate code to fit and plot curves and surfaces, or export fits to the workspace for further analysis.

### Fit Curve

- 1 Load some example data at the MATLAB command line.


```
load census
```

- 2 Open the Curve Fitter app.

```
curveFitter
```


Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click **Curve Fitter**.

- 3 On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select `cdate` as the **X data** value and `pop` as the **Y data** value. For details, see “Selecting Data to Fit in Curve Fitter App” on page 2-7.




The Curve Fitter app creates a default polynomial fit to the data.

- 4 Try different fit options. For example, in the **Fit Options** pane, change the polynomial **Degree** value to 3 to fit a cubic polynomial.



- 5 Select a different model type from the fit gallery in the **Fit Type** section on the **Curve Fitter** tab. For example, click the arrow to open the gallery, and click **Smoothing Spline** in the **Smoothing** group. For information about models you can fit, see “Model Types for Curves and Surfaces” on page 2-6.



- 6 In the **Export** section, click **Export** and select **Generate Code**.

The Curve Fitter app creates a file in the Editor containing MATLAB code to recreate the currently selected fit and its opened plots in your interactive session.

---

**Tip** For a detailed workflow example, see “Compare Fits in Curve Fitter App” on page 2-19.

---

To create multiple fits and compare them, see “Create Multiple Fits in Curve Fitter App” on page 2-15.

## Fit Surface


- 1 Load some example data at the MATLAB command line.

load franke

- 2 Open the Curve Fitter app.

curveFitter


- 3 On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select x as the **X data** value, y as the **Y data** value, and z as the **Z data** value. For more information, see “Selecting Data to Fit in Curve Fitter App” on page 2-7.



The Curve Fitter app creates a default interpolation fit to the data.

- 4 Select a different model type from the fit gallery in the **Fit Type** section on the **Curve Fitter** tab. For example, click the arrow to open the gallery, and click **Polynomial** in the **Regression Models** group.

For information about models you can fit, see “Model Types for Curves and Surfaces” on page 2-6.



- 5 Try different fit options for your chosen model type.
- 6 In the **Export** section, click **Export** and select **Generate Code**.

The Curve Fitter app creates a file in the Editor containing MATLAB code to recreate the currently selected fit and its opened plots in your interactive session.

---

**Tip** For a detailed example, see “Surface Fitting to Franke Data” on page 2-32.

---

To create multiple fits and compare them, see “Create Multiple Fits in Curve Fitter App” on page 2-15.

## Model Types for Curves and Surfaces

Based on your selected data, the fit gallery shows either curve or surface fit groups. The following table describes the options for curves and surfaces.




Fit Group	Fit Type	Curves	Surfaces
<b>Regression Models</b>	Polynomial on page 4-15	Yes (up to degree 9)	Yes (up to degree 5)
	Exponential on page 4-30	Yes	No
	Logarithmic on page 4-57	Yes	No
	Fourier on page 4-37	Yes	No
	Gaussian on page 4-53	Yes	No
	Power on page 4-63	Yes	No
	Rational on page 4-67	Yes	No
	Sum of Sine on page 4-74	Yes	No
	Weibull on page 4-84	Yes	No
	Sigmoidal on page 4-77	Yes	No
<b>Interpolation</b>	Interpolant on page 6-3	Yes, with methods: <ul style="list-style-type: none"> <li>• Nearest neighbor</li> <li>• Linear</li> <li>• Cubic</li> <li>• Shape-preserving (PCHIP)</li> </ul>	Yes, with methods: <ul style="list-style-type: none"> <li>• Nearest neighbor</li> <li>• Linear</li> <li>• Cubic</li> <li>• Biharmonic (v4)</li> <li>• Thin-plate spline</li> </ul>
<b>Smoothing</b>	Smoothing Spline on page 6-14	Yes	No
	Lowess on page 6-22	No	Yes
<b>Custom</b>	Custom Equation on page 5-2	Yes	Yes
	Linear Fitting on page 5-7	Yes	No

For information about these fit types, see:

- “Linear and Nonlinear Regression”
- “Custom Models” on page 5-2
- “Interpolation”
- “Smoothing”

## Selecting Data to Fit in Curve Fitter App

To interactively select data, import your data into a workspace variable from the command line. Then, open the Curve Fitter app and click **Select Data**. The **Select Data** button is in the **Data** section of the **Curve Fitter** tab.




The Curve Fitter app uses a snapshot of the data you select. Subsequent workspace changes to the data have no effect on your fits. To update your fit data from the workspace, first change the variable selection, and then reselect the variable with the drop-down controls.

### Selecting Data for Curve Fitting

To select data for curve fitting, import the Y data in a vector, table variable, or array. If you have X data, import it also in a vector, table variable, or array. Each of the X and Y variables can be a vector, array, or table variable. However, X and Y must have the same number of elements. Then, do one of the following:

- In the Select Fitting Data dialog box, select the variables in the **X data** and **Y data** drop-down menus. To select data contained in a table variable, select the table name to display a second drop-down menu to the right. Then, select the variable from the second drop-down menu.
- To plot the Y variable against its indices, select only the Y variable from the **Y data** drop-down menu.



If you specify weights, the weights variable must have the same number of elements as the other data variables.

### Selecting Data for Surface Fitting

To select data for surface fitting, save the X, Y and Z data each in a vector, table variable, or array. Each of the variables can be a vector, array, or table variable. However, they must satisfy one of the following:


- The X, Y, and Z variables contain the same number of elements.

**Note** Curve Fitter app expects data variables to be the same size. If the sizes are different but the number of elements are the same, then the app reshapes the variables to create a fit and displays a warning in the **Results** pane.

- The  $X$  variable is a vector containing  $n$  elements, the  $Y$  variable is a vector containing  $m$  elements, and the  $Z$  variable is an  $m$ -by- $n$  matrix. In this case, the  $Y$  and  $X$  data are treated as headers for table rows and columns, respectively. See “Tabular Data” on page 2-13 for more information.

**Note** If the  $Z$  variable is an  $n$ -by- $m$  matrix, the app creates a fit by transposing  $Z$  and provides a warning about the data transformation. You can see the warning in the **Results** pane.

In the Select Fitting Data dialog box, select the variables from the **X data**, **Y data**, and **Z data** drop-down menus. If a variable is saved in a table, select the table name to display a second drop-down menu to the right. Then, select the variable from the second drop-down menu.



Similarly, you can select any numeric variable in your workspace to use as **Weights**, including a numeric table column. If you specify weights, the weights variable must have the same number of elements as the  $Z$  variable.

## Save and Reopen Sessions

You can save and reopen sessions for easy access to multiple fits. The session file contains all the fits and variables in your session and remembers your layout.

To save your session, first click the **Save** button in the **File** section on the **Curve Fitter** tab to open your file browser. Next, select a name and location for your session file (with the file extension `.sfit`).

After you save your session once, you can click **Save** and select **Save Session** to overwrite that session with subsequent saves.

To save the current session under a different name, click **Save** and select **Save Session As**.

To reopen a session, click **Open** in the **File** section on the **Curve Fitter** tab to open a file browser where you can select a saved curve fitting session file to load.

## **See Also**

### **Related Examples**

- “Compare Fits in Curve Fitter App” on page 2-19
- “Create Multiple Fits in Curve Fitter App” on page 2-15

## Data Selection

### In this section...

“Import Data to Workspace” on page 2-11  
 “Select Data to Fit at Command Line” on page 2-11  
 “Select Data to Fit in Curve Fitter App” on page 2-11  
 “Tabular Data” on page 2-13

Curve Fitting Toolbox offers two ways of fitting curves and surfaces to data. You can create fits at the command line using the `fit` function, or create fits interactively using the Curve Fitter app. Both ways require you to select data before you fit the curve or surface. Curve fitting requires you to select  $Y$  data and, optionally,  $X$  data. Surface fitting requires you to select  $X$ ,  $Y$ , and  $Z$  data.

### Import Data to Workspace

Before you select data, you must import it into a MATLAB workspace variable. You can import sample data or data from a file by using the functions described in “Standard File Formats”.

### Select Data to Fit at Command Line


To select data at the command line, pass the data to the `fit` function during the fitting process.

- To select data for curve fitting, save the  $X$  and  $Y$  data as column vectors with the same number of rows. Then, pass the column vectors to the `fit` function as the `x` and `y` input arguments.
- To select data for surface fitting, do one of the following:
  - Save the  $X$ ,  $Y$ , and  $Z$  data as column vectors of the same size. Then, pass the vectors to the `fit` function as the `x`, `y`, and `z` input arguments.
  - Save the  $X$  and  $Y$  data as an array with two columns. Save the  $Z$  data as a column vector with the same number of rows as the array. Pass the array and vector to the `fit` function as the `x` and `y` input arguments, respectively.

For an example of fitting a curve to data at the command line, see “Fit a Quadratic Curve” on page 13-80. For an example of fitting a surface to data at the command line, see “Fit a Polynomial Surface” on page 13-81.

### Select Data to Fit in Curve Fitter App

To select data interactively, click the **Apps** tab, display the apps gallery, and then select Curve Fitter in the **Math, Statistics and Optimization** section. In the **Data** section of the **Curve Fitter** tab, click **Select Data**.




The Curve Fitter app uses a snapshot of the data you select. Subsequent workspace changes to the data have no effect on the fit. To update the fitted data from the workspace, first change the variable selection, and then reselect the variable with the drop-down controls.

### Select Data for Curve Fitting

To select data for curve fitting, import the Y data in a vector, table variable, or array. If you have X data, import it in a vector, table variable, or array. X and Y must have the same number of elements. Then, do one of the following:

- In the Select Fitting Data dialog box, select the variables using the **X data** and **Y data** menus. To select data contained in a table variable, select the table name to display a second menu to the right. Then, select the table variable from the second menu.
- To plot the Y variable against its indices, select only the Y variable from the **Y data** menu.

This Select Fitting Data dialog box shows a vector variable selected for the **X** data and a table variable selected for the **Y** data.



Similarly, you can select any numeric variable in the workspace to use as **Weights**, including a numeric table column. If you specify weights, the weights variable must have the same number of elements as the other data variables.

For an example of fitting curves and surfaces in the Curve Fitter app, see “Interactive Curve and Surface Fitting” on page 2-2.

### Select Data for Surface Fitting

To select data for surface fitting, save the X, Y, and Z data each in a vector, table variable, or array. One of the following conditions must be satisfied:

- The X, Y, and Z variables contain the same number of elements.

---

**Note** The Curve Fitter app expects data variables to be the same size. If the sizes are different but the number of elements is the same, the app reshapes the variables to create a fit and displays a warning in the **Results** pane.

---

- The  $X$  variable is a vector containing  $n$  elements, the  $Y$  variable is a vector containing  $m$  elements, and the  $Z$  variable is an  $m$ -by- $n$  matrix. In this case, the  $Y$  data and  $X$  data are treated as headers for table rows and columns, respectively. See “Tabular Data” on page 2-13 for more information.


---

**Note** If the  $Z$  variable is an  $n$ -by- $m$  matrix, the app creates a fit by transposing  $Z$  and displays a warning about the data transformation in the **Results** pane.

---

In the Select Fitting Data dialog box, select the variables using the **X data**, **Y data**, and **Z data** menus. If a variable is saved in a table, select the table name to display a second menu to the right. Then, select the table variable from the second menu.

This Select Fitting Data dialog box shows vector variables selected for the **X** and **Y** data and a table variable selected for the **Z** data.



Similarly, you can select any numeric variable in the workspace to use as **Weights**, including a numeric table column. If you specify weights, the weights variable must have the same number of elements as the  $Z$  variable.

For an example of fitting curves and surfaces using the Curve Fitter app, see “Interactive Curve and Surface Fitting” on page 2-2.

## Tabular Data

The data variables can form tabular data, where the  $Y$  data and  $X$  data represent the row and column headers, respectively, of a table (sometimes called breakpoints) and the  $Z$  data contains the table values.

Sizes are compatible when all of these conditions apply:

- The  $X$  data is saved in a vector of length  $n$ .
- The  $Y$  data is saved in a vector of length  $m$ .
- The  $Z$  data is saved in a matrix of size  $[m, n]$ .

The following table shows an example of data in tabular form with  $n = 4$  and  $m = 3$ .

	<b>x(1)</b>	<b>x(2)</b>	<b>x(3)</b>	<b>x(4)</b>
<b>y(1)</b>	z(1,1)	z(1,2)	z(1,3)	z(1,4)
<b>y(2)</b>	z(2,1)	z(2,2)	z(2,3)	z(2,4)
<b>y(3)</b>	z(3,1)	z(3,2)	z(3,3)	z(3,4)

For surface fitting at the command line with the `fit` function, use the `prepareSurfaceData` function when your data is in tabular form.

### **See Also**

`fit` | `prepareSurfaceData` | `prepareCurveData`

### **Related Examples**

- “Interactive Curve and Surface Fitting” on page 2-2
- “Fit a Quadratic Curve” on page 13-80
- “Fit a Polynomial Surface” on page 13-81
- “Standard File Formats”



## Create Multiple Fits in Curve Fitter App

### In this section...

“Refining Your Fit” on page 2-15  
 “Creating Multiple Fits” on page 2-15  
 “Displaying Multiple Fits Simultaneously” on page 2-15  
 “Using the Statistics in the Table of Fits” on page 2-17

### Refining Your Fit

After you create a single fit in the Curve Fitter app, you can refine your fit, using any of the following optional steps:

- Change the fit type and settings. Select a fit type from the gallery in the **Fit Type** section of the **Curve Fitter** tab. For fit settings for each model type, see “Linear and Nonlinear Regression”, “Interpolation”, and “Smoothing”.
- Exclude data by removing outliers in the Curve Fitter app. See “Remove Outliers” on page 7-8.
- Select weights. See “Data Selection” on page 2-11.
- Select validation data. See “Select Validation Data” on page 7-12
- Create multiple fits to compare different fit types and settings side by side in the Curve Fitter app. See “Creating Multiple Fits” on page 2-15.

### Creating Multiple Fits

After you create a single fit, it can be useful to create multiple fits for comparison. When you create multiple fits, you can compare different fit types and settings side by side in the Curve Fitter app.

After creating a fit, you can add a fit. On the **Curve Fitter** tab, in the **File** section, click **New** and select **New Fit**. Each additional fit appears as a new tab in the **Fits** pane and a new row in the **Table Of Fits** pane.

To create a copy of the current fit, click **Duplicate** in the **File** section of the **Curve Fitter** tab. You also can right-click a fit in the **Table Of Fits** pane and select the **Duplicate "Current Fit Name"** option. Each additional fit appears as a new tab in the **Fits** pane.

To delete a fit from your session, right-click the fit in the **Table Of Fits** pane and select the **Delete "Current Fit Name"** option.


Use sessions to save and reopen your fits. See “Save and Reopen Sessions” on page 2-9.

### Displaying Multiple Fits Simultaneously


After you have created multiple fits, you can compare different fit types and settings side by side in the Curve Fitter app. You can view plots simultaneously, and you can examine the goodness-of-fit statistics to compare your fits.

To compare plots and see multiple fits simultaneously, you can drag and drop the fit figure tabs in the **Fits** pane. Alternatively, you can click the Document Actions button located to the far right of the fit

figure tabs. Select the **Title All** option and specify the number and position of tiles you want to display.




Each fit figure displays the plots for a single fit. The following example shows two fit figures displayed side by side. You can see multiple fits in the session listed in the **Table Of Fits** pane.



You can close fit figure tabs in the **Fits** pane, but the fits remain in your session. The **Table Of Fits** pane displays all your fits (open and closed). Click a fit in the **Table Of Fits** pane to open the fit figure or bring focus to the figure if it is already open. To remove a fit, right-click the fit in the **Table Of Fits** pane and select the **Delete "Current Fit Name"** option.

**Tip** If you want more space to view and compare plots, you can collapse the **Fit Options**, **Results**, and **Table Of Fits** panes. Click and drag the left border of the **Fit Options** and **Results** panes until they become tabs. Similarly, click and drag the top border of the **Table Of Fits** pane.



## Using the Statistics in the Table of Fits

The **Table of Fits** pane shows all fits in the current session.

Table of Fits										
:: Fit State	:: Fit name	:: Data	:: Fit type	:: R-square	:: SSE ↑	:: DFE	:: Adj R-sq	:: RMSE	:: # Coeff	::
✓	poly6	pop vs....	poly6	0.99913	106.93	14	0.99876	2.7636	7	
✓	poly5	pop vs....	poly5	0.99883	144.17	15	0.99844	3.1002	6	
✓	poly4	pop vs....	poly4	0.99882	145.97	16	0.99852	3.0204	5	
✓	poly3	pop vs....	poly3	0.99879	149.77	17	0.99857	2.9682	4	
✓	poly2	pop vs....	poly2	0.99871	159.03	18	0.99857	2.9724	3	
✓	exp	pop vs....	exp1	0.98467	1894.2	19	0.98386	9.9847	2	

After using graphical methods to evaluate the goodness of fit, you can examine the goodness-of-fit statistics shown in the table to compare your fits. The goodness-of-fit statistics help you determine how well the model fits the data. Click the table column headers to sort by statistics, name, fit type, and so on.

The following guidelines help you use the statistics to determine the best fit:

- **R-square** is the square of the correlation between the response values and the predicted response values. A value closer to 1 indicates that a greater proportion of variance is accounted for by the model.
- **SSE** is the sum of squares due to error of the fit. A value closer to zero indicates a fit that is more useful for prediction.
- **DFE** is the degree of freedom in the error.
- **Adj R-sq** is the degrees of freedom adjusted R-square. A value closer to 1 indicates a better fit.
- **RMSE** is the root mean squared error or standard error. A value closer to 0 indicates a fit that is more useful for prediction.
- **# Coeff** is the number of coefficients in the model. When you have several fits with similar goodness-of-fit statistics, look for the smallest number of coefficients to help decide which fit is best. You must trade off the number of coefficients against the goodness of fit indicated by the statistics to avoid overfitting.

For a more detailed explanation of the Curve Fitting Toolbox statistics, see “Goodness-of-Fit Statistics” on page 7-43.

To compare the statistics for different fits and decide which fit is the best tradeoff between over- and under-fitting, use a similar process to that described in “Compare Fits in Curve Fitter App” on page 2-19.

## See Also

### Related Examples

- “Compare Fits in Curve Fitter App” on page 2-19
- “Compare Fits Programmatically” on page 7-30

## Compare Fits in Curve Fitter App

### In this section...

“Interactive Curve Fitter Workflow” on page 2-19  
 “Loading Data and Creating Fits” on page 2-19  
 “Determining the Best Fit” on page 2-21  
 “Analyzing Best Fit in the Workspace” on page 2-27  
 “Saving Your Work” on page 2-30

### Interactive Curve Fitter Workflow

The next topics fit census data using polynomial equations up to the sixth degree, and a single-term exponential equation. The steps demonstrate how to:

- Load data and explore various fits using different library models.
- Search for the best fit by:
  - Comparing graphical fit results
  - Comparing numerical fit results including the fitted coefficients and goodness-of-fit statistics
- Export your best fit results to the MATLAB workspace to analyze the model at the command line.
- Save the session and generate MATLAB code for all fits and plots.

### Loading Data and Creating Fits

You must load the data variables into the MATLAB workspace before you can fit data using the Curve Fitter app. For this example, the data is stored in the MATLAB file `census.mat`.

- 1 Load the data.

```
load census
```

The workspace contains two new variables.

- `cdate` is a column vector containing the years 1790 to 1990 in 10-year increments.
- `pop` is a column vector with the US population figures that correspond to the years in `cdate`.

- 2 Open the Curve Fitter app.

```
curveFitter
```

- 3 On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select the variable names `cdate` and `pop` from the **X data** and **Y data** lists, respectively.

The Curve Fitter app creates and plots a default fit to the X input (or predictor) data and the Y output (or response) data. The default fit is a linear polynomial fit type. Observe the fit settings display in the **Fit Options** pane. The fit is a first-degree polynomial.

- 4 In the **Fit Options** pane, change the fit to a second-degree polynomial by selecting 2 from the **Degree** list.

The Curve Fitter app plots the new fit. The Curve Fitter app calculates a new fit when you change fit settings because **Auto** is selected by default. If refitting is time consuming, as is

sometimes the case for large data sets, you can turn off the automatic behavior. On the **Curve Fitter** tab, in the **Fit** section, select **Manual**.

The Curve Fitter app displays results of fitting the census data with a quadratic polynomial in the **Results** pane, where you can view the library model, fitted coefficients, and goodness-of-fit statistics.

- 5 Change the name of the fit. In the **Table Of Fits** pane, double-click untitled fit 1 in the **Fit name** column and type `poly2`.
- 6 Display the residuals. On the **Curve Fitter** tab, in the **Visualization** section, click **Residuals Plot**.

The residuals indicate that a better fit might be possible. Therefore, continue exploring various fits to the census data set.

The screenshot shows the Curve Fitter app interface. The top toolbar includes options for File (New, Open, Save, Duplicate), Data (Select Data), Fit Type (Polynomial, Exponential), Fit (Update Fit: Auto, Manual), Visualization (Residuals Plot, Contour Plot, Prediction Bounds: None), and Export. The main workspace displays two plots: a 'Fit Plot' showing population (pop) vs. census date (cdate) with a blue exponential fit line, and a 'Residuals Plot' showing the residuals of the fit. The 'Fit Options' pane on the right is set to 'Exponential' with the equation  $f(x) = a \cdot \exp(b \cdot x) + c \cdot \exp(d \cdot x)$  and 2 terms. The 'Results' pane shows the fit name 'poly2' and the equation. Below the plots is a 'Table of Fits' pane.

Fit State	Fit name	Data	Fit type	R-square	SSE	DFE	Adj R-sq	RMSE
✔	poly2	pop vs....	exp2	0.89955	12412	17	0.88182	27.02

- 7 Add new fits to try the other library equations.
  - a Right-click the fit in the **Table Of Fits** pane, and select **Duplicate "poly2"**. Alternatively, on the **Curve Fitter** tab, in the **File** section, click **Duplicate**.

**Tip** For fits of a given type (for example, polynomials), duplicate a fit instead of creating a new fit because copying a fit requires fewer steps. The duplicated fit contains the same data selections and fit settings.

- b Change the polynomial **Degree** to 3 and rename the fit poly3.
- c When you fit higher degree polynomials, the **Results** pane displays this warning.

Equation is badly conditioned. Remove repeated data points or try centering and scaling.

Normalize the data by selecting the **Center and scale** check box in the **Fit Options** pane.

- d Repeat steps a and b to add polynomial fits up to the sixth degree. Then add an exponential fit. On the **Curve Fitter** tab, in the **File** section, click **New** and select **New Fit**. In the **Fit Type** section, click the arrow to open the gallery, and click **Exponential** in the **Regression Models** section.
- e For each new fit, look at the **Results** pane information, and the residuals plot in the app.

The residuals from a good fit should look random with no apparent pattern. A pattern, such as a tendency for consecutive residuals to have the same sign, can be an indication that a better model exists.

### About Scaling

The warning about scaling arises because the fitting procedure uses the `cdate` values as the basis for a matrix with very large values. The spread of the `cdate` values results in a scaling problem. To address this problem, you can normalize the `cdate` data. Normalization scales the predictor data to improve the accuracy of the subsequent numeric computations. For example, you can normalize `cdate` by centering and scaling the data to have zero mean and unit standard deviation.

```
(cdate - mean(cdate))./std(cdate)
```

---

**Note** Because the predictor data changes after normalizing, the values of the fitted coefficients also change when compared to the original data. However, the functional form of the data and the resulting goodness-of-fit statistics do not change. Additionally, the data is displayed in the Curve Fitter app plots using the original scale.


---


## Determining the Best Fit

To determine the best fit, you should examine both the graphical and numerical fit results.

### Examine the Graphical Fit Results

- 1 Determine the best fit by examining the graphs of the fits and residuals. To view plots for each fit in turn, click the fit in the **Table Of Fits** pane. The graphical fit results indicate that:
  - The fits and residuals for the polynomial equations are all similar, making it difficult to choose the best one.
  - The fit and residuals for the single-term exponential equation indicate it is a poor fit overall. Therefore, it is a poor choice and you can remove the exponential fit from the candidates for best fit.
- 2 Examine the behavior of the fits after the year 2000. The goal of fitting the census data is to extrapolate the best fit to predict future population values.
  - a Click the sixth-degree polynomial fit in the **Table Of Fits** pane to view the plots for this fit.

- b** In the fit plot, click the Pan button  in the axes toolbar and pan until the fit is visible for several years after the year 2000. The axes limits of the residuals plot adjust accordingly.
- c** Examine the fit plot. The behavior of the sixth-degree polynomial fit beyond the data range makes it a poor choice for extrapolation and you can reject this fit.



### Evaluate the Numerical Fit Results

When you can no longer eliminate fits by examining them graphically, you should examine the numerical fit results. The Curve Fitter app displays two types of numerical fit results:

- Goodness-of-fit statistics
- Confidence bounds on the fitted coefficients

The goodness-of-fit statistics help you determine how well the curve fits the data. The confidence bounds on the coefficients determine their accuracy.

Examine the numerical fit results.

- 1 For each fit, view the goodness-of-fit statistics in the **Results** pane.



**Results**

Fit Name: poly3

**Polynomial Curve Fit (poly3)**  
 $f(x) = p1*x^3 + p2*x^2 + p3*x + p4$   
 x is normalized by mean 1890 and std 62.05

**Coefficients and 95% Confidence Bounds**

	Value	Lower	Upper
p1	0.9210	-0.9743	2.8163
p2	25.1834	23.5736	26.7931
p3	73.8598	70.3308	77.3888
p4	61.7444	59.6907	63.7981

**Goodness of Fit**

	Value
SSE	149.7687
R-square	0.9988
DFE	17.0000
Adj R-sq	0.9986
RMSE	2.9682

- 2 Compare all fits simultaneously in the **Table Of Fits** pane. Click the column headings to sort by statistics results.

Table of Fits										
Fit State	Fit name	Data	Fit type	R-square	SSE ↑	DFE	Adj R-sq	RMSE	# Coeff	
✓	poly6	pop vs....	poly6	0.99913	106.93	14	0.99876	2.7636	7	
✓	poly5	pop vs....	poly5	0.99883	144.17	15	0.99844	3.1002	6	
✓	poly4	pop vs....	poly4	0.99882	145.97	16	0.99852	3.0204	5	
✓	poly3	pop vs....	poly3	0.99879	149.77	17	0.99857	2.9682	4	
✓	poly2	pop vs....	poly2	0.99871	159.03	18	0.99857	2.9724	3	
✓	exp	pop vs....	exp1	0.98467	1894.2	19	0.98386	9.9847	2	

- 3 Examine the sum of squares due to error (SSE) and the adjusted *R*-square statistics to help determine the best fit. The SSE statistic is the least-squares error of the fit, with a value closer to zero indicating a better fit. The adjusted *R*-square statistic is generally the best indicator of the fit quality when you add additional coefficients to your model.

The largest SSE for exp indicates it is a poor fit, which you already determined by examining the fit and residuals. The lowest SSE value is associated with poly6. However, the behavior of this fit


beyond the data range makes it a poor choice for extrapolation, so you already rejected this fit by examining the plots with new axes limits.

The next best SSE value is associated with the fifth-degree polynomial fit, `poly5`, suggesting it might be the best fit. However, the SSE and adjusted *R*-square values for the remaining polynomial fits are all very close to each other.

- 4 Resolve the best fit issue by examining the confidence bounds for the remaining fits in the **Results** pane. Click a fit in the **Table Of Fits** pane to open the fit figure (or select it, if the figure is already open), and view the **Results** pane. Each fit figure displays the plots for a single fit.

Display the fifth-degree polynomial `poly5` and the second-degree polynomial `poly2` fit figures side by side. Examining results side by side can help you assess fits.

- a To show two fit figures simultaneously, you can drag and drop the fit figure tabs in the **Fits** pane. Alternatively, you can click the Document Actions button located to the far right of the fit figure tabs. Select the **Tile All** option and specify a 1-by-2 or 2-by-1 layout.




- b Compare the coefficients and bounds ( $p_1$ ,  $p_2$ , and so on) in the **Results** pane for both fits, `poly5` and `poly2`. The toolbox calculates 95% confidence bounds on coefficients. The confidence bounds on the coefficients determine their accuracy. Check the equations in the **Results** pane ( $f(x) = p_1 * x + p_2 * x \dots$ ) to see the model terms for each coefficient. Note that  $p_2$  refers to the  $p_2 * x$  term in `Poly2` and the  $p_2 * x^4$  term in `Poly5`. Do not compare normalized coefficients directly with non-normalized coefficients.

---

**Tip** If you want more space to view and compare plots and results, as shown next, drag down the **Table Of Fits** pane. You can also hide the **Results** pane to show only plots.

---



The bounds cross zero on the p1, p2, and p3 coefficients for the fifth-degree polynomial. This means you cannot be sure that these coefficients differ from zero. If the higher order model terms might have coefficients of zero, they are not helping with the fit, which suggests that this model overfits the census data.

**Results**

Fit Name: poly5

**Polynomial Curve Fit (poly5)**  
 $f(x) = p1 \cdot x^5 + p2 \cdot x^4 + p3 \cdot x^3 + p4 \cdot x^2 + p5 \cdot x + p6$   
 x is normalized by mean 1890 and std 62.05

**Coefficients and 95% Confidence Bounds**

	Value	Lower	Upper
p1	0.5877	-2.3046	3.4801
p2	0.7047	-1.6841	3.0936
p3	-0.9193	-10.1943	8.3558
p4	23.4706	17.4213	29.5199
p5	74.9675	68.3655	81.5696
p6	62.2285	59.5102	64.9469

**Goodness of Fit**

	Value
SSE	144.1661
R-square	0.9988
DFE	15.0000
Adj R-sq	0.9984
RMSE	3.1002

However, the small confidence bounds do not cross zero on p1, p2, and p3 for the quadratic fit poly2, indicating that the fitted coefficients are known fairly accurately.

Results			
Fit Name: poly2			
Polynomial Curve Fit (poly2)			
$f(x) = p1*x^2 + p2*x + p3$			
Coefficients and 95% Confidence Bounds			
	Value	Lower	Upper
p1	0.0065	0.0061	0.0070
p2	-23.5097	-25.0859	-21.9336
p3	2.1130...	1.9641...	2.2618...
Goodness of Fit			
	Value		
SSE	159.0293		
R-square	0.9987		
DFE	18.0000		
Adj R-sq	0.9986		
RMSE	2.9724		


Therefore, after examining both the graphical and numerical fit results, you should select poly2 as the best fit to extrapolate the census data.

**Note** The fitted coefficients associated with the constant, linear, and quadratic terms are nearly identical for each normalized polynomial equation. However, as the polynomial degree increases, the coefficient bounds associated with the higher degree terms cross zero, which suggests overfitting.

## Analyzing Best Fit in the Workspace

You can export the selected fit and the associated fit results to the MATLAB workspace. On the **Curve Fitter** tab, in the **Export** section, click **Export** and select **Export to Workspace**. The fit is saved as a MATLAB object and the associated fit results are saved as structures.

- 1 Right-click the poly2 fit in the **Table Of Fits** pane, and select **Save "poly2" to Workspace**. Alternatively, click **Export** and select **Export to Workspace**. The app opens a dialog box.



- 2 Click **OK** to save the fit with the default names.

`fittedmodel` is saved as a Curve Fitting Toolbox `cf` object.

```
whos fittedmodel
```

Name	Size	Bytes	Class	Attributes
fittedmodel	1x1	925	cf	

Examine the `cf` object `fittedmodel` to display the model, the fitted coefficients, and the confidence bounds for the fitted coefficients.

```
fittedmodel
```

```
Linear model Poly2:
fittedmodel(x) = p1*x^2 + p2*x + p3
Coefficients (with 95% confidence bounds):
p1 =    0.006541 (0.006124, 0.006958)
p2 =   -23.51 (-25.09, -21.93)
p3 =  2.113e+04 (1.964e+04, 2.262e+04)
```

Examine the `goodness` structure to display goodness-of-fit results.

```
goodness
```

```
goodness =
```

```
struct with fields:
    sse: 159.0293
    rsquare: 0.9987
    dfe: 18
    adjrsquare: 0.9986
    rmse: 2.9724
```

Examine the `output` structure to display additional information associated with the fit, such as the residuals.

```
output
```

```
output =
```

```
struct with fields:
    numobs: 21
```

```
    numparam: 3
    residuals: [21×1 double]
    Jacobian: [21×3 double]
    exitflag: 1
    algorithm: 'QR factorization and solve'
    iterations: 1
```

You can evaluate (interpolate or extrapolate), differentiate, or integrate a fit over a specified data range with various postprocessing functions.

For example, evaluate `fittedmodel` at a vector of values to extrapolate to the year 2050.


```
x = 2000:10:2050;
y = fittedmodel(x)
```

```
y =
```

```
    274.6221
    301.8240
    330.3341
    360.1524
    391.2790
    423.7137
```

Plot the fit to the census data and the extrapolated fit values.

```
plot(fittedmodel,cdate,pop)
hold on
plot(fittedmodel,x,y,"k+")
hold off
legend(["data","", "extrapolated data", "fitted curve"], ...
       "Location", "northwest")
```



For more examples and instructions for interactive and command-line fit analysis, and a list of all postprocessing functions, see “Fit Postprocessing”.

For an example reproducing this interactive census data analysis using the command line, see “Polynomial Curve Fitting” on page 12-2.

## Saving Your Work

The Curve Fitter app provides several options for saving your work. You can save one or more fits and the associated fit results as variables to the MATLAB workspace. You can then use this saved information for documentation purposes, or to extend your data exploration and analysis. In addition to saving your work to MATLAB workspace variables, you can:

- Save the current curve fitting session. On the **Curve Fitter** tab, in the **File** section, click **Save** and select **Save Session**. The session file contains all the fits and variables in your session and remembers your layout. See “Save and Reopen Sessions” on page 2-9.
- Generate MATLAB code to recreate a fit and its associated plots. In the **Export** section, click **Export** and select **Generate Code**. The Curve Fitter app generates code for the currently selected fit and displays the file in the MATLAB Editor.

You can recreate your fit and plots by calling the file at the command line with your original data as input arguments. You can also call the file with new data, and automate the process of fitting multiple data sets. For more information, see “Generating Code from the Curve Fitter App” on page 7-13.



## See Also

### Related Examples

- “Create Multiple Fits in Curve Fitter App” on page 2-15
- “Evaluate Curve Fit” on page 7-16

## Surface Fitting to Franke Data

The Curve Fitter app provides some example data generated from Franke's bivariate test function. This data is suitable for trying various fit settings in the Curve Fitter app. Use the data to create, compare, and export surface fits.

- 1 At the MATLAB command line, load the `franke` data set. The variables `x`, `y`, and `z` appear in the workspace.

```
load franke
```

The example data is generated from Franke's bivariate test function, with added noise and scaling, to create suitable data for trying various fit settings in the Curve Fitter app. For details on the Franke function, see [1].

- 2 Divide the data into fitting and validation data.

```
xv = x(200:293);
yv = y(200:293);
zv = z(200:293);
x = x(1:199);
y = y(1:199);
z = z(1:199);
```


- 3 Fit a surface using the example data.

- a Open the Curve Fitter app.

```
curveFitter
```

Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click **Curve Fitter**.

- b In the Curve Fitter app, select the data variables. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, specify `x` as the **X data** variable, `y` as the **Y data** variable, and `z` as the **Z data** variable.



Alternatively, you can specify the data variables when you use `curveFitter` to open the Curve Fitter app and create a default fit (`curveFitter(x,y,z)`).

The Curve Fitter app plots the data points as you select variables. When you select  $x$ ,  $y$ , and  $z$ , the app automatically creates a default surface fit. The default fit is an interpolating surface that passes through the data points.

The screenshot shows the Curve Fitter app interface. The main window displays a 3D plot titled "Fit Plot" showing a surface fit to data points. The axes are labeled  $x$ ,  $y$ , and  $z$ . The  $z$ -axis ranges from 0 to 1, the  $y$ -axis from 0 to 3500, and the  $x$ -axis from 0 to 3500. The surface is colored with a gradient from blue to yellow. The data points are represented by small blue dots. The plot is titled "z vs. x, y".

The interface includes a menu bar with options like "New", "Open", "Save", "Duplicate", "Select Data", "Interpolant", "Lowess", "Update Fit", "Auto", "Manual", "Fit Plot", "Residuals Plot", "Contour Plot", "Prediction Bounds", "Export".


The "Fit Options" panel on the right shows the "Interpolant" method selected. The interpolation method is "Linear", the extrapolation method is "None", and "Center and scale" is checked. A link "Read about fit options" is also present.

The "Results" panel shows the fit name "untitled fit 1" and the fit type "Interpolating Surface Fit (linearinterp)". The fit equation is given as  $f(x,y) = \text{piecewise linear surface with no extrapolation}$ . The  $x$  axis is normalized by mean 1977 and std 866.5, and the  $y$  axis is normalized by mean 0.4932 and std 0.29.

The "Table of Fits" panel at the bottom shows a table with the following data:

Fit State	Fit name	Data	Fit type	R-square	SSE	DFE	Adj R-sq
✓	untitled fit 1	z vs. x, y	linearinterp	1	0	0	


- 4 Try a Lowess fit type. On the **Curve Fitter** tab, in the **Fit Type** section, click the arrow to open the gallery. Click **Lowess** in the **Smoothing** group.



The Curve Fitter app creates a local smoothing regression fit.

- 5 Try altering the fit settings. In the **Fit Options** pane, change the **Span (%)** value to 10.


By reducing the span from the default to 10% of the total number of data points, you produce a surface that follows the data more closely. The span defines the neighboring data points the app uses to determine each smoothed value.



- 6 In the **Table of Fits** pane, change the **Fit name** to Smoothing regression.
- 7 Use the validation data to check that your surface is a good model. In other words, compare the surface against data not used for fitting.

On the **Curve Fitter** tab, in the **Data** section, click **Validation Data**. In the Select Validation Data dialog box, select the validation variables in the drop-down lists for **X data**, **Y data**, and **Z data**:  $x_v$ ,  $y_v$ , and  $z_v$ .

Review your selected validation data in the plots and the validation statistics (SSE and RMSE) in the **Results** and **Table of Fits** panes.



- 8 Create another fit by making a copy of the current surface fit. On the **Curve Fitter** tab, in the **File** section, click **Duplicate**. Alternatively, right-click the fit in the **Table of Fits** pane, and then select **Duplicate "Smoothing regression"**.

The app creates a new fit figure with the same fit settings, data, and validation data. It also adds a new row to the table of fits at the bottom.


- 9 Change the fit type and name of the new fit. On the **Curve Fitter** tab, in the **Fit Type** section, click the arrow to open the gallery. Click **Polynomial** in the **Regression Models** group.

In the **Table of Fits** pane, change the **Fit name** to Polynomial.

- 10 In the **Fit Options** pane, change the **X Degree** and **Y Degree** values to 3, to fit a cubic polynomial in both dimensions.
- 11 Look at the scales on the x and y axes, and read the warning message in the **Results** pane.

Equation is badly conditioned. Remove repeated data points or try centering and scaling.

In the **Fit Options** pane, select the **Center and scale** check box to normalize and correct for the large difference in scales in x and y.




Normalizing the surface fit removes the warning message from the **Results** pane.

**12** Look at the **Results** pane. You can view the:

- Model equation
- Values of the estimated coefficients
- Goodness-of-fit statistics
- Goodness of validation statistics

▼ Results

Fit Name: Polynomial 

**Polynomial Surface Fit (poly33)**

$$f(x,y) = p00 + p10*x + p01*y + p20*x^2 + p11*x*y + p02*y^2 + p30*x^3 + p21*x^2*y + p12*x*y^2 + p03*y^3$$

x is normalized by mean 1977 and std 866.5  
y is normalized by mean 0.4932 and std 0.29

**Coefficients and 95% Confidence Bounds**

	Value	Lower	Upper
p00	0.4359	0.3974	0.4743
p10	-0.1375	-0.1940	-0.0810
p01	-0.4274	-0.4843	-0.3706
p20	0.0161	-0.0070	0.0392
p11	0.0716	0.0509	0.0923
p02	-0.0367	-0.0601	-0.0133
p30	0.0208	-0.0055	0.0471
p21	0.0243	0.0012	0.0474
p12	-0.0395	-0.0629	-0.0161
p03	0.1185	0.0916	0.1453

**Goodness of Fit**

	Value
SSE	4.1254
R-square	0.7760
DFE	189.0000
Adj R-sq	0.7653
RMSE	0.1477

**Goodness of Validation**


	Value
SSE	2.2675
RMSE	0.1553

- 13** To export this fit information to the workspace, click **Export** and select **Export to Workspace** in the **Export** section of the **Curve Fitter** tab. Executing this command also exports other information such as the number of observations and parameters, residuals, and the fitted model.


You can treat the fitted model as a function to make predictions or evaluate the surface at values of X and Y. For details see “Exporting a Fit to the Workspace” on page 7-14.



- 14 Display the residuals plot to check the distribution of points relative to the surface. On the **Curve Fitter** tab, in the **Visualization** section, click **Residuals Plot**.




- 15 Right-click the residuals plot to select **Go to X-Z view**. The X-Z view is not required, but the view makes it easier to see to remove outliers.

- 16 To remove outliers, click the Exclude outliers button  in the axes toolbar.


When you move the mouse cursor to the plot, it changes to a cross-hair to show you are in outlier selection mode.

- a Click a point that you want to exclude in the surface plot or residuals plot. Alternatively, click and drag to define a rectangle and remove all enclosed points.


The plots display removed points as red crosses.



- b If you have **Auto** selected in the **Fit** section of the **Curve Fitter** tab, the app refits the surface without the removed point. If you have **Manual** selected instead, you can click **Fit** to refit the surface.

- c To return to rotation mode in the plots, click the Exclude outliers button  again.

- 17 Compare your fits side-by-side. Click the Document Actions button located to the far right of the fit figure tabs. Select the **Tile All** option and specify a 1-by-2 layout.



- 18 Review the information in the **Table of Fits** pane. Compare the goodness-of-fit statistics for all fits in your session to determine which is best.
- 19 To save your interactive surface fitting session, click **Save** in the **File** section of the **Curve Fitter** tab. You can save and reopen sessions to access multiple fits. The session file contains all the fits and variables in your session.
- 20 After interactively creating and comparing fits, you can generate MATLAB code for each fit in your Curve Fitter app session. On the **Curve Fitter** tab, in the **Export** section, click **Export** and select **Generate Code**.

The Curve Fitter app generates code from your session and displays the file in the MATLAB Editor. The file includes the currently selected fit and its opened plots in your session.

- 21 Save the file with the default name `createFit.m`.
- 22 You can recreate your fit and its plots by calling the file from the command line (with your original data or new data as input arguments). In this case, your original variables still appear in the workspace.
  - Highlight and evaluate the first line of the file (excluding the word `function`). Either right-click and select **Evaluate Selection in Command Window**, press **F9**, or copy and paste the following code to the command line.

- ```
[fitresult,gof] = createFit(x,y,z,xv,yv,zv)
```
- The function creates a figure window for the fit you selected in your session. Observe that the polynomial fit figure shows both the surface and residuals plots that you created interactively in the Curve Fitter app.
  - If you want, you can use the generated code as a starting point to change the surface fits and plots to fit your needs. For a list of methods you can use, see `sfit`.

## References

- [1] Franke, Richard. "Scattered Data Interpolation: Tests of Some Methods." *Mathematics of Computation* 38, no. 157 (January 1, 1982): 181-200. <https://doi.org/10.1090/S0025-5718-1982-0637296-4>.

## See Also

### Related Examples

- "Create Multiple Fits in Curve Fitter App" on page 2-15
- "Linear and Nonlinear Regression"
- "Interpolation"
- "Smoothing"
- "Fit Postprocessing"



# Programmatic Curve and Surface Fitting

---

- “Curve and Surface Fitting” on page 3-2
- “Curve and Surface Fitting Objects and Object Functions” on page 3-5

## Curve and Surface Fitting

| In this section...                              |
|-------------------------------------------------|
| "Fitting a Curve" on page 3-2                   |
| "Fitting a Surface" on page 3-2                 |
| "Model Types and Fit Analysis" on page 3-2      |
| "Workflow for Command Line Fitting" on page 3-3 |

### Fitting a Curve

To programmatically fit a curve, follow the steps in this simple example:

- 1 Load some data.

```
load hahn1
```

- 2 Create a fit using the `fit` function, specifying the variables and a model type (`rat23` in this case is the model type).

```
f = fit(temp,thermex,"rat23")
```

- 3 Plot your fit and the data.

```
plot(f,temp,thermex)  
f(600)
```

For an example comparing various polynomial fits, see "Polynomial Curve Fitting" on page 12-2.

### Fitting a Surface

To programmatically fit a surface, follow the steps in this simple example:

- 1 Load some data.

```
load franke
```

- 2 Create a fit using the `fit` function, specifying the variables and a model type (`poly23` in this case is the model type).

```
f = fit([x, y],z,"poly23")
```

- 3 Plot your fit and the data.

```
plot(f,[x,y],z)
```

For an example fitting custom equations, see "Surface Fitting with Custom Equations to Biopharmaceutical Data" on page 12-14.

### Model Types and Fit Analysis

For details and examples of specific model types and fit analysis, see the following sections:

- "Linear and Nonlinear Regression"
- "Interpolation"

- “Smoothing”
- “Fit Postprocessing”

## Workflow for Command Line Fitting

Curve Fitting Toolbox software provides a variety of methods for data analysis and modeling.

---

**Tip** To quickly generate MATLAB code for curve and surface fits and plots, use the Curve Fitter app and then generate code. You can transform your interactive analysis of a single data set into a reusable function for command-line analysis or for batch processing of multiple data sets. For more details, see “Generate Code and Export Fits to the Workspace” on page 7-13.

---

To use curve fitting functions for programmatic fitting and analysis, follow this workflow:

- 1 Import your data into the MATLAB workspace using the `load` command (if your data has previously been stored in MATLAB variables) or any of the MATLAB functions for reading data from particular file types. You might need to reshape your data: see `prepareCurveData` or `prepareSurfaceData`.
- 2 (Optional) If your data is noisy, you might want to smooth it using the `smooth` function. Smoothing is used to identify major trends in the data that can assist you in choosing an appropriate family of parametric models. If a parametric model is not evident or appropriate, smoothing can be an end in itself, providing a nonparametric fit of the data.

---

**Note** Smoothing estimates the center of the distribution of the response at each predictor. It invalidates the assumption that errors in the data are independent, and so also invalidates the methods used to compute confidence and prediction intervals. Accordingly, once a parametric model is identified through smoothing, the *original* data should be passed to the `fit` function.

---

- 3 Specify a parametric model for the data—either a Curve Fitting Toolbox library model or a custom model that you define. You specify the model by passing a model name or expression to the `fit` function or (optional) with a `fittype` object you create with the `fittype` function.

To view available library models, see “List of Library Models for Curve and Surface Fitting” on page 4-10.

- 4 (Optional) You can create a fit options structure for the fit using the `fitoptions` function. Fit options specify things like weights for the data, fitting methods, and low-level options for the fitting algorithm.
- 5 (Optional) You can create an exclusion rule for the fit using the `excludedata` function. Exclusion rules indicate which data values will be treated as outliers and excluded from the fit.
- 6 Specify the x and y (and z, if surface fitting) data, a model (name, expression or `fittype` object), and (optionally) a fit options structure and an exclusion rule, with the `fit` function to perform the fit.

The `fit` function returns a `cfits` (for curves) or `sfits` (for surfaces) object that encapsulates the computed coefficients and the fit statistics. If you want to learn more about the fit objects, see “Curve and Surface Fitting Objects and Object Functions” on page 3-5.

- 7 You can postprocess the fit objects returned by the `fit` function, by passing them to a variety of functions, such as `feval`, `differentiate`, `integrate`, `plot`, `coeffvalues`, `probvalues`, `confint`, and `predint`.

Use the following functions to work with curve and surface fits.

| Curve or Surface Fit Method | Description                                                   |
|-----------------------------|---------------------------------------------------------------|
| <code>argnames</code>       | Get input argument names                                      |
| <code>category</code>       | Get fit category                                              |
| <code>coeffnames</code>     | Get coefficient names                                         |
| <code>coeffvalues</code>    | Get coefficient values                                        |
| <code>confint</code>        | Get confidence intervals for fit coefficients                 |
| <code>dependnames</code>    | Get dependent variable name                                   |
| <code>differentiate</code>  | Differentiate fit                                             |
| <code>excludedata</code>    | Exclude data from fit                                         |
| <code>feval</code>          | Evaluate model at specified predictors                        |
| <code>fittype</code>        | Construct <code>fittype</code> object                         |
| <code>formula</code>        | Get formula                                                   |
| <code>indepnames</code>     | Get independent variable name                                 |
| <code>integrate</code>      | Integrate curve fit                                           |
| <code>islinear</code>       | Determine if model is linear                                  |
| <code>numargs</code>        | Get number of input arguments                                 |
| <code>numcoeffs</code>      | Get number of coefficients                                    |
| <code>plot</code>           | Plot fit                                                      |
| <code>predint</code>        | Get prediction intervals                                      |
| <code>probnames</code>      | Get problem-dependent parameter names                         |
| <code>probvalues</code>     | Get problem-dependent parameter values                        |
| <code>quad2d</code>         | Numerically integrate surface fit ( <code>sfit</code> object) |
| <code>setoptions</code>     | Set model fit options                                         |
| <code>type</code>           | Get name of model                                             |

## See Also

`fit` | `fittype` | `fitoptions` | `excludedata` | `prepareCurveData` | `prepareSurfaceData`

## Related Examples

- “Generate Code and Export Fits to the Workspace” on page 7-13
- “List of Library Models for Curve and Surface Fitting” on page 4-10
- “Polynomial Curve Fitting” on page 12-2
- “Custom Nonlinear Census Fitting” on page 5-20
- “Surface Fitting with Custom Equations to Biopharmaceutical Data” on page 12-14
- “Evaluate Curve Fit” on page 7-16
- “Evaluate Surface Fit” on page 7-24
- “Fit Postprocessing”



## Curve and Surface Fitting Objects and Object Functions

### In this section...

“Curve Fitting Objects” on page 3-5

“Curve Fitting Object Functions” on page 3-6

“Surface Fitting Objects and Object Functions” on page 3-8

This topic describes how to create curve and surface fit objects and how to use their object functions to manipulate the fits. Use the Curve Fitting Toolbox objects and object functions at the MATLAB command line or to write MATLAB programs for curve and surface fit applications. You can also use Curve Fitting Toolbox in combination with other MATLAB toolboxes to create curve and surface fit workflows.

This topic focuses on how to create and manipulate curve and surface fits programmatically. Alternatively, the Curve Fitter app allows convenient, interactive use of Curve Fitting Toolbox objects and object functions, without programming. You can select a fit on the **Curve Fitter** tab, in the **Fit Type** section.


### Curve Fitting Objects

In MATLAB programming, all workspace variables are *objects* of a particular *class*. Familiar examples of MATLAB classes are `double`, `char`, and `function_handle`. You can also create custom MATLAB classes, using object-oriented programming.

*Object functions* are functions that operate exclusively on objects of a particular class. *Data types* package together objects and object functions so that the object functions operate exclusively on objects of their own type, and not on objects of other types. A clearly defined encapsulation of objects and object functions is the goal of object-oriented programming.

Curve Fitting Toolbox software provides you with new MATLAB data types for performing curve fitting:

- `fittype` — Objects allow you to encapsulate information describing a parametric model for your data. Object functions allow you to access and modify that information.
- `cfit` and `sfit` — Two subtypes of `fittype`, for curves and surfaces. Objects capture information from a particular fit by assigning values to coefficients, confidence intervals, fit statistics, etc. Object functions allow you to post-process the fit through plotting, extrapolation, integration, etc.



Because `cf` is a subtype of `fit`, `cf` inherits all `fit` object functions. In other words, you can apply `fit` object functions to both `fit` and `cf` objects, but `cf` object functions are used exclusively with `cf` objects. The same is true for `sf` objects.

As an example, the `fit` object function `islinear`, which determines if a model is linear or nonlinear, logically applies before or after a fit, that is, to both `fit` and `cf` objects. On the other hand, the `cf` object functions `coeffvalues` and `confint`, which, respectively, return fit coefficients and their confidence intervals, makes no sense to apply to a general `fit` object, which describes a parametric model with undetermined coefficients.

Curve fitting objects have properties that depend on their type, and also on the particulars of the model or the fit that they encapsulate. For example, the following code uses the constructor object functions for the two curve fitting types to create a `fit` object `f` and a `cf` object `c`:

```
f = fittype('a*x^2+b*exp(n*x)')
f =
    General model:
    f(a,b,n,x) = a*x^2+b*exp(n*x)

c = cfit(f,1,10.3,-1e2)
c =
    General model:
    c(x) = a*x^2+b*exp(n*x)
    Coefficients:
    a =          1
    b =         10.3
    n =        -100
```

Note that the display object function for `fit` objects returns only basic information, piecing together outputs from `formula` and `indepnames`.

`cf` and `fit` objects are evaluated at predictor values `x` using `feval`. You can call `feval` indirectly using the following functional syntax:

```
y = cfun(x); % cfit objects
y = ffun(coef1,coef2,...,x); % fit objects
```

## Curve Fitting Object Functions

Curve fitting object functions allow you to create, access, and modify curve fitting objects. They also allow you, through object functions like `plot` and `integrate`, to perform operations that uniformly process the entirety of information encapsulated in a curve fitting object.

The object functions listed in the following table are available for all `fit` objects, including `cf` objects.

| Fit Type Object Function | Description              |
|--------------------------|--------------------------|
| <code>argnames</code>    | Get input argument names |
| <code>category</code>    | Get fit category         |
| <code>coeffnames</code>  | Get coefficient names    |

| Fit Type Object Function | Description                            |
|--------------------------|----------------------------------------|
| dependnames              | Get dependent variable name            |
| feval                    | Evaluate model at specified predictors |
| fitttype                 | Construct <code>fitttype</code> object |
| formula                  | Get formula                            |
| indepnames               | Get independent variable name          |
| islinear                 | Determine if model is linear           |
| numargs                  | Get number of input arguments          |
| numcoeffs                | Get number of coefficients             |
| probnames                | Get problem-dependent parameter names  |
| setoptions               | Set model fit options                  |
| type                     | Get name of model                      |

The object functions listed in the following table are available exclusively for `cf` objects.

| Curve Fit Object Function  | Description                                   |
|----------------------------|-----------------------------------------------|
| <code>cf</code>            | Construct <code>cf</code> object              |
| <code>coeffvalues</code>   | Get coefficient values                        |
| <code>confint</code>       | Get confidence intervals for fit coefficients |
| <code>differentiate</code> | Differentiate fit                             |
| <code>integrate</code>     | Integrate fit                                 |
| <code>plot</code>          | Plot fit                                      |
| <code>predint</code>       | Get prediction intervals                      |
| <code>probvalues</code>    | Get problem-dependent parameter values        |

A complete list of object functions for a curve fitting object can be obtained with the MATLAB `methods` command. For example,

```
f = fitttype('a*x^2+b*exp(n*x)');
methods(f)
```

Methods for class `fitttype`:

```
argnames      dependnames  fitttype      islinear      probnames
category      feval        formula       numargs       setoptions
coeffnames    fitoptions  indepnames    numcoeffs     type
```

Some of the object functions listed by `methods` do not appear in the tables above, and do not have reference pages in the Curve Fitting Toolbox documentation. These additional object functions are generally low-level operations used by the Curve Fitter app, and not of general interest when writing curve fitting applications.

There are no global accessor object functions, comparable to `getfield` and `setfield`, available for `fitttype` objects. Access is limited to the object functions listed above. This is because many of the properties of `fitttype` objects are derived from other properties, for which you do have access. For example,

```
f = fittype('a*cos( b*x-c )')  
f =  
    General model:  
    f(a,b,c,x) = a*cos( b*x-c )  
formula(f)  
ans =  
    'a*cos( b*x-c )'  
argnames(f)  
ans =  
    4x1 cell array  
    {'a'}  
    {'b'}  
    {'c'}  
    {'x'}
```

You construct the `fittype` object `f` by giving the formula, so you do have write access to that basic property of the object. You have read access to that property through the `formula` object function. You also have read access to the argument names of the object, through the `argnames` object function. You don't, however, have direct write access to the argument names, which are derived from the formula. If you want to set the argument names, set the formula.

## Surface Fitting Objects and Object Functions

The surface fit object (`sfit`) stores the results from a surface fitting operation, making it easy to plot and analyze fits at the command line.

Like `cfits` objects, `sfit` objects are a subclass of `fittype` objects, so they inherit all the same object functions of `fittype` listed in “Curve Fitting Object Functions” on page 3-6.

`sfit` objects also provide object functions exclusively for `sfit` objects. See `sfit`.

One way to quickly assemble code for surface fits and plots into useful programs is to generate a file from a fit in the Curve Fitter app. In this way, you can transform your interactive analysis of a single data set into a reusable function for command-line analysis or for batch processing of multiple data sets. You can use the generated file without modification, or edit and customize the code as needed. See “Generate Code and Export Fits to the Workspace” on page 7-13.

# Linear and Nonlinear Regression

---

- “Parametric Fitting” on page 4-2
- “List of Library Models for Curve and Surface Fitting” on page 4-10
- “Polynomial Models” on page 4-15
- “Exponential Models” on page 4-30
- “Fit Fourier Models” on page 4-37
- “Gaussian Models” on page 4-53
- “Fit Logarithmic Models” on page 4-57
- “Power Series” on page 4-63
- “Rational Models” on page 4-67
- “Sum of Sines Models” on page 4-74
- “Fit Sigmoidal Models” on page 4-77
- “Weibull Distributions” on page 4-84
- “Introduction to Least-Squares Fitting” on page 4-87

## Parametric Fitting

### In this section...

“Parametric Fitting with Library Models” on page 4-2

“Select Model Type” on page 4-3

“Center and Scale Data” on page 4-4

“Specify Fit Options and Optimized Starting Points” on page 4-5

### Parametric Fitting with Library Models

Parametric fitting involves finding coefficients (parameters) for one or more models that you fit to data. The data is assumed to be statistical in nature and is divided into two components:

$$\text{data} = \text{deterministic component} + \text{random component}$$

The deterministic component is given by a parametric model and the random component is often described as error associated with the data:

$$\text{data} = \text{parametric model} + \text{error}$$

The model is a function of the independent (predictor) variable and one or more coefficients. The error represents random variations in the data that follow a specific probability distribution (usually Gaussian). The variations can come from many different sources, but are always present at some level when you are dealing with measured data. Systematic variations can also exist, but they can lead to a fitted model that does not represent the data well.

The model coefficients often have physical significance. For example, suppose you collected data that corresponds to a single decay mode of a radioactive nuclide, and you want to estimate the half-life ( $T_{1/2}$ ) of the decay. The law of radioactive decay states that the activity of a radioactive substance decays exponentially in time. Therefore, the model to use in the fit is given by

$$y = y_0 e^{-\lambda t}$$

where  $y_0$  is the number of nuclei at time  $t = 0$ , and  $\lambda$  is the decay constant. The data can be described by

$$\text{data} = y_0 e^{-\lambda t} + \text{error}$$

Both  $y_0$  and  $\lambda$  are coefficients that are estimated by the fit. Because  $T_{1/2} = \ln(2)/\lambda$ , the fitted value of the decay constant yields the fitted half-life. However, because the data contains some error, the deterministic component of the equation cannot be determined exactly from the data. Therefore, the coefficients and half-life calculation will have some uncertainty associated with them. If the uncertainty is acceptable, then you are done fitting the data. If the uncertainty is not acceptable, then you might have to take steps to reduce it either by collecting more data or by reducing measurement error and collecting new data and repeating the model fit.

With other problems where there is no theory to dictate a model, you might also modify the model by adding or removing terms, or substitute an entirely different model.


The Curve Fitting Toolbox parametric library models are described in the following sections.

## Select Model Type

### Select Model Type Interactively

Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.

In the Curve Fitter app, go to the **Fit Type** section of the **Curve Fitter** tab. You can select a model type from the fit gallery. Click the arrow to open the gallery.



This table describes the models that you can fit for curves and surfaces.

| Fit Group                | Fit Category                  | Curves                                                                                                                                                         | Surfaces                                                                                                                                                                      |
|--------------------------|-------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Regression Models</b> | Polynomial on page 4-15       | Yes (up to degree 9)                                                                                                                                           | Yes (up to degree 5)                                                                                                                                                          |
|                          | Exponential on page 4-30      | Yes                                                                                                                                                            | No                                                                                                                                                                            |
|                          | Logarithmic on page 4-57      | Yes                                                                                                                                                            | No                                                                                                                                                                            |
|                          | Fourier on page 4-37          | Yes                                                                                                                                                            | No                                                                                                                                                                            |
|                          | Gaussian on page 4-53         | Yes                                                                                                                                                            | No                                                                                                                                                                            |
|                          | Power on page 4-63            | Yes                                                                                                                                                            | No                                                                                                                                                                            |
|                          | Rational on page 4-67         | Yes                                                                                                                                                            | No                                                                                                                                                                            |
|                          | Sum of Sine on page 4-74      | Yes                                                                                                                                                            | No                                                                                                                                                                            |
|                          | Weibull on page 4-84          | Yes                                                                                                                                                            | No                                                                                                                                                                            |
|                          | Sigmoidal on page 4-77        | Yes                                                                                                                                                            | No                                                                                                                                                                            |
| <b>Interpolation</b>     | Interpolant on page 6-3       | Yes, with methods: <ul style="list-style-type: none"> <li>• Nearest neighbor</li> <li>• Linear</li> <li>• Cubic</li> <li>• Shape-preserving (PCHIP)</li> </ul> | Yes, with methods: <ul style="list-style-type: none"> <li>• Nearest neighbor</li> <li>• Linear</li> <li>• Cubic</li> <li>• Biharmonic</li> <li>• Thin-plate spline</li> </ul> |
| <b>Smoothing</b>         | Smoothing Spline on page 6-14 | Yes                                                                                                                                                            | No                                                                                                                                                                            |
|                          | Lowess on page 6-22           | No                                                                                                                                                             | Yes                                                                                                                                                                           |

| Fit Group | Fit Category                        | Curves | Surfaces |
|-----------|-------------------------------------|--------|----------|
| Custom    | Custom Equation on page 5-2         | Yes    | Yes      |
|           | “Custom Linear Fitting” on page 5-7 | Yes    | No       |

The **Results** pane displays the model specifications, coefficient values, and goodness-of-fit statistics.

**Tip** If your fit has problems, messages in the **Results** pane help you identify better settings.

The Curve Fitter app provides a selection of fit types and settings in the **Fit Options** pane that you can change to try to improve your fit. Try the defaults first, and then experiment with other settings. For more details on how to use the available fit options, see “Specify Fit Options and Optimized Starting Points” on page 4-5.

You can try a variety of settings for a single fit and you can create multiple fits to compare. When you create multiple fits in the Curve Fitter app, you can compare different fit types and settings side by side. For more information, see “Create Multiple Fits in Curve Fitter App” on page 2-15.

### Select Model Type Programmatically

You can specify a library model name as a character vector or string scalar when you call the `fit` function. For example, you can specify a quadratic `poly2` model:

```
f = fit(x,y,"poly2")
```

To view all available library model names, see “List of Library Models for Curve and Surface Fitting” on page 4-10.

You can also use the `fittype` function to construct a `fittype` object for a library model, and use the `fittype` as an input to the `fit` function.

Use the `fitoptions` function to find out what parameters you can set, for example:

```
fitoptions(poly2)
```

For examples, see the sections for each model type, listed in the table in “Select Model Type Interactively” on page 4-3. For details on all the functions for creating and analysing models, see “Curve and Surface Fitting” on page 3-2.

### Center and Scale Data

Most fits in the Curve Fitter app provide the **Center and scale** option in the **Fit Options** pane. When you select this option, the app refits the model with the data centered and scaled. At the command line, use the `fitoptions` function with the `Normalize` option set to `'on'`.

To alleviate numerical problems with variables of different scales, normalize the input data (also known as *predictor data*). For example, suppose your surface fit inputs are engine speed with a range of 500–4500 r/min and engine load percentage with a range of 0–1. Then, **Center and scale** generally improves the fit because of the great difference in scale between the two inputs. However, if your inputs are in the same units or similar scale (for example, eastings and northings for



geographic data), then **Center and scale** is less useful. When you normalize inputs with this option, the values of the fitted coefficients change when compared to the original data.

If you are fitting a curve or surface to estimate coefficients, or the coefficients have physical significance, clear the **Center and scale** check box. The plots in the Curve Fitter app always use the original scale, regardless of the **Center and scale** status.

At the command line, to center and scale the data before fitting, create the `options` structure by using the `fitoptions` function with `options.Normal` specified as `'on'`. Then, use the `fit` function with the specified options.

```
options = fitoptions;
options.Normal = 'on';
options
options =

    basefitoptions with properties:

        Normalize: 'on'
        Exclude: []
        Weights: []
        Method: 'None'

load census
f1 = fit(cdate,pop,"poly3",options)
```

## Specify Fit Options and Optimized Starting Points

### Fit Options in Curve Fitter App

In the Curve Fitter app, you can specify fit options interactively in the **Fit Options** pane. All fits except **Interpolant**, **Smoothing Spline**, and **Lowess** have configurable fit options. The available options depend on the fit you select (that is, linear, nonlinear, or nonparametric fit).

- The options described here are available for nonlinear models.
- **Lower** and **Upper** coefficient constraints are the only fit options available in the **Fit Options** pane for **Polynomial** fits.
- Nonparametric fits (that is, **Interpolant**, **Smoothing Spline**, and **Lowess** fits) do not have **Advanced Options**.

The **Fit Options** pane for the single-term **Exponential** fit is shown here. The **Coefficient Constraints** values are for the census data.

**Fit Options**

**Advanced Options**

Method: NonlinearLeastSquares

Robust: Off

Algorithm: Trust-Region

DiffMinChange: 1e-8

DiffMaxChange: 0.1

MaxFunEvals: 600

MaxIter: 400

TolFun: 1e-6

TolX: 1e-6

**Coefficient Constraints**

| Coefficients | StartPoint | Lower | Upper |
|--------------|------------|-------|-------|
| a            | 0.2362     | 0     | Inf   |
| b            | 0.1194     | 0     | Inf   |

[Read about fit options](#)

### Fitting Method and Algorithm

- **Method** — Fit method

The app automatically selects the **Method** value based on the fit you use. For linear and nonlinear fits, the **Method** value is `LinearLeastSquares` and `NonlinearLeastSquares`, respectively.

- **Robust** — Option for using the robust least-squares fitting method
  - **Off** — Do not use robust fitting (default).
  - **On** — Fit with the default robust method (bisquare weights).
  - **LAR** — Fit by minimizing the least absolute residuals (LAR).
  - **Bisquare** — Fit by minimizing the summed square of the residuals, and reduce the weight of outliers using bisquare weights. In most cases, this option is the best choice for robust fitting.
- **Algorithm** — Algorithm used for fitting
  - **Trust-Region** — This option is the default algorithm and must be used if you specify **Lower** or **Upper** coefficient constraints.
  - **Levenberg-Marquardt** — If the trust-region algorithm does not produce a reasonable fit, and you do not have coefficient constraints, try the Levenberg-Marquardt algorithm.

### Finite Differencing Parameters

- **DiffMinChange** — Minimum change in coefficients for finite difference Jacobians. The default value is  $10^{-8}$ .

- **DiffMaxChange** — Maximum change in coefficients for finite difference Jacobians. The default value is 0.1.

Note that **DiffMinChange** and **DiffMaxChange** apply to:

- Any nonlinear custom equation, that is, a nonlinear equation that you write
- Some of the nonlinear equations provided with Curve Fitting Toolbox

**DiffMinChange** and **DiffMaxChange** do not apply to any linear equations.

### Fit Convergence Criteria

- **MaxFunEvals** — Maximum number of function (model) evaluations allowed. The default value is 600.
- **MaxIter** — Maximum number of fit iterations allowed. The default value is 400.
- **TolFun** — Termination tolerance used on stopping conditions involving the function (model) value. The default value is  $10^{-6}$ .
- **TolX** — Termination tolerance used on stopping conditions involving the coefficients. The default value is  $10^{-6}$ .

### Coefficient Parameters

- **Coefficients** — Symbols for the unknown coefficients to be fitted
- **StartPoint** — The coefficient starting values. The default values depend on the fit. For **Rational**, **Weibull**, and custom fits, the default values are randomly selected within the range [0 1]. For all other nonlinear models in the **Fit Type** gallery, the starting values depend on the data set and are calculated heuristically.
- **Lower** — Lower bounds of the fitted coefficients. The app uses these bounds only with the trust region fitting algorithm. The default lower bounds for most fits in the **Fit Options** pane are `-Inf`, which indicates that the coefficients are unconstrained. However, a few models have finite default lower bounds. For example, for **Gaussian** fits, the app constrains the width parameter so that it cannot be less than 0.
- **Upper** — Upper bounds of the fitted coefficients. The app uses these bounds only with the trust region fitting algorithm. The default upper bounds for all fits in the **Fit Options** pane are `Inf`, which indicates that the coefficients are unconstrained.

For more details, see “Optimized Starting Points and Default Constraints” on page 4-7.

For more information about these fit options, see the `lsqcurvefit` function.

### Optimized Starting Points and Default Constraints

The default coefficient starting points and constraints for fits in the **Fit Type** pane are shown in the following table. If the starting points are optimized, then they are calculated heuristically based on the current data set. Random starting points are defined on the interval [0 1] and linear models do not require starting points. If a model does not have constraints, the coefficients have neither a lower bound nor an upper bound. You can override the default starting points and constraints by providing your own values in the **Fit Options** pane.

| Fit            | Starting Points | Constraints |
|----------------|-----------------|-------------|
| Linear Fitting | N/A             | None        |

| Fit             | Starting Points | Constraints |
|-----------------|-----------------|-------------|
| Custom Equation | Random          | None        |
| Exponential     | Optimized       | None        |
| Logarithmic     | N/A             | None        |
| Fourier         | Optimized       | None        |
| Gaussian        | Optimized       | $c_i > 0$   |
| Polynomial      | N/A             | None        |
| Power           | Optimized       | None        |
| Rational        | Random          | None        |
| Sum of Sine     | Optimized       | $b_i > 0$   |
| Weibull         | Random          | $a, b > 0$  |
| Sigmoidal       | Optimized       | $x/c > 0$   |

The **Sum of Sine** and **Fourier** fits are particularly sensitive to starting points, and the optimized values might be accurate for only a few terms in the associated equations.

### Specify Fit Options at the Command Line

Create the default fit options structure and set the option to center and scale the data before fitting:

```
options = fitoptions;
options.Normal = 'on';
options
options =

    basefitoptions with properties:

        Normalize: 'on'
        Exclude: []
        Weights: []
        Method: 'None'
```

Modifying the default fit options structure is useful when you want to set the `Normalize`, `Exclude`, or `Weights` fields, and then fit your data using the same options with different fitting methods. For example:

```
load census
f1 = fit(cdate,pop,"poly3",options);
f2 = fit(cdate,pop,"expl",options);
f3 = fit(cdate,pop,"cubicsp",options);
```

Data-dependent fit options are returned in the third output argument of the `fit` function. For example, the smoothing parameter for smoothing spline is data-dependent:

```
[f,gof,out] = fit(cdate,pop,"smooth");
smoothparam = out.p
smoothparam =
    0.0089
```

Use fit options to modify the default smoothing parameter for a new fit:

```
options = fitoptions("Method","Smooth","SmoothingParam",0.0098);  
[f,gof,out] = fit(cdate,pop,"smooth",options);
```

For more details on using fit options, see the `fitoptions` function.

## See Also

### Apps

Curve Fitter

### Functions

`fit` | `fitoptions`

## Related Examples

- “Create Multiple Fits in Curve Fitter App” on page 2-15
- “List of Library Models for Curve and Surface Fitting” on page 4-10
- “Curve and Surface Fitting” on page 3-2

## List of Library Models for Curve and Surface Fitting

### In this section...

“Use Library Models to Fit Data” on page 4-10

“Library Model Types” on page 4-10

“Model Names and Equations” on page 4-11

### Use Library Models to Fit Data

You can use the Curve Fitting Toolbox library of models for data fitting with the `fit` function. You use library model names as input arguments in the `fit`, `fitoptions`, and `fittype` functions.

### Library Model Types

The following tables describe the library model types for curves and surfaces.

- Use the links in the table for examples and detailed information on each library type.
- If you want a quick reference of model names for input arguments to the `fit` function, see “Model Names and Equations” on page 4-11.

| Library Model Types for Curves | Description                                                                                                                                                 |
|--------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------|
| distribution                   | Distribution models such as Weibull. See “Weibull Distributions” on page 4-84.                                                                              |
| exponential                    | Exponential function and sum of two exponential functions. See “Exponential Models” on page 4-30.                                                           |
| fourier                        | Up to eight terms of Fourier series. See “Fit Fourier Models” on page 4-37.                                                                                 |
| gaussian                       | Sum of up to eight Gaussian models. See “Gaussian Models” on page 4-53.                                                                                     |
| interpolant                    | Interpolating models, including linear, nearest neighbor, cubic spline, and shape-preserving cubic spline. See “Nonparametric Fitting” on page 6-2.         |
| logarithmic                    | Logarithmic models, including natural log, log base 2, and log base 10. See “Fit Logarithmic Models” on page 4-57.                                          |
| polynomial                     | Polynomial models, up to degree nine. See “Polynomial Models” on page 4-15.                                                                                 |
| power                          | Power function and sum of two power functions. See “Power Series” on page 4-63.                                                                             |
| rational                       | Rational equation models, up to 5th degree/5th degree (i.e., up to degree 5 in both the numerator and the denominator). See “Rational Models” on page 4-67. |
| sin                            | Sum of up to eight sin functions. See “Sum of Sines Models” on page 4-74.                                                                                   |

| Library Model Types for Curves | Description                                                                                                       |
|--------------------------------|-------------------------------------------------------------------------------------------------------------------|
| sigmoidal                      | Sigmoidal models including logistic, 4-parameter logistic, and Gompertz. See “Fit Sigmoidal Models” on page 4-77. |
| spline                         | Cubic spline and smoothing spline models. See “Nonparametric Fitting” on page 6-2.                                |

| Library Model Types for Surfaces | Description                                                                                                                                                                          |
|----------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| interpolant                      | Interpolating models, including linear, nearest neighbor, cubic spline, biharmonic, and thin-plate spline interpolation. See “Interpolation with Curve Fitting Toolbox” on page 6-3. |
| lowess                           | Lowess smoothing models. See “Lowess Smoothing” on page 6-22.                                                                                                                        |
| polynomial                       | Polynomial models, up to degree five. See “Polynomial Models” on page 4-15.                                                                                                          |

## Model Names and Equations

To specify the model you want to fit, consult the following tables for a model name to use as an input argument to the `fit` function. For example, to specify a quadratic curve with model name “poly2” :

```
f = fit(x, y, 'poly2')
```

### Polynomial Model Names and Equations

| Examples of Polynomial Model Names for Curves | Equations                     |
|-----------------------------------------------|-------------------------------|
| poly1                                         | $Y = p1*x+p2$                 |
| poly2                                         | $Y = p1*x^2+p2*x+p3$          |
| poly3                                         | $Y = p1*x^3+p2*x^2+\dots+p4$  |
| ...etc., up to poly9                          | $Y = p1*x^9+p2*x^8+\dots+p10$ |

For polynomial surfaces, model names are 'polyij', where *i* is the degree in *x* and *j* is the degree in *y*. The maximum for both *i* and *j* is five. The degree of the polynomial is the maximum of *i* and *j*. The degree of *x* in each term will be less than or equal to *i*, and the degree of *y* in each term will be less than or equal to *j*. See the following table for some example model names and equations, of many potential examples.

| Examples of Polynomial Model Names for Surfaces | Equations                                                           |
|-------------------------------------------------|---------------------------------------------------------------------|
| poly21                                          | $Z = p00 + p10*x + p01*y + p20*x^2 + p11*x*y$                       |
| poly13                                          | $Z = p00 + p10*x + p01*y + p11*x*y + p02*y^2 + p12*x*y^2 + p03*y^3$ |
| poly55                                          | $Z = p00 + p10*x + p01*y + \dots + p14*x*y^4 + p05*y^5$             |

**Distribution Model Name and Equation**

| Distribution Model Names | Equations                       |
|--------------------------|---------------------------------|
| weibull                  | $Y = a*b*x^{(b-1)}*exp(-a*x^b)$ |

**Exponential Model Names and Equations**

| Exponential Model Names | Equations                   |
|-------------------------|-----------------------------|
| exp1                    | $Y = a*exp(b*x)$            |
| exp2                    | $Y = a*exp(b*x)+c*exp(d*x)$ |

**Fourier Series Model Names and Equations**

| Fourier Series Model Names | Equations                                                             |
|----------------------------|-----------------------------------------------------------------------|
| fourier1                   | $Y = a_0+a_1*cos(x*p)+b_1*sin(x*p)$                                   |
| fourier2                   | $Y = a_0+a_1*cos(x*p)+b_1*sin(x*p)+a_2*cos(2*x*p)+b_2*sin(2*x*p)$     |
| fourier3                   | $Y = a_0+a_1*cos(x*p)+b_1*sin(x*p)+...+a_3*cos(3*x*p)+b_3*sin(3*x*p)$ |
| ...etc., up to fourier8    | $Y = a_0+a_1*cos(x*p)+b_1*sin(x*p)+...+a_8*cos(8*x*p)+b_8*sin(8*x*p)$ |

Where  $p = 2*pi/(max(xdata) - min(xdata))$ .

**Gaussian Model Names and Equations**

| Gaussian Model Names  | Equations                                                     |
|-----------------------|---------------------------------------------------------------|
| gauss1                | $Y = a_1*exp(-((x-b_1)/c_1)^2)$                               |
| gauss2                | $Y = a_1*exp(-((x-b_1)/c_1)^2)+a_2*exp(-((x-b_2)/c_2)^2)$     |
| gauss3                | $Y = a_1*exp(-((x-b_1)/c_1)^2)+...+a_3*exp(-((x-b_3)/c_3)^2)$ |
| ...etc., up to gauss8 | $Y = a_1*exp(-((x-b_1)/c_1)^2)+...+a_8*exp(-((x-b_8)/c_8)^2)$ |

**Logarithmic Model Names and Equations**

| Logarithmic Model Names | Equations             |
|-------------------------|-----------------------|
| log                     | $Y = a*log(x)+b$      |
| log10                   | $Y = a*log_{10}(x)+b$ |
| log2                    | $Y = a*log_2(x)+b$    |

**Power Model Names and Equations**

| Power Model Names | Equations   |
|-------------------|-------------|
| power1            | $Y = a*x^b$ |



| Power Model Names | Equations     |
|-------------------|---------------|
| power2            | $Y = a*x^b+c$ |

### Rational Model Names and Equations

Rational models are polynomials over polynomials with the leading coefficient of the denominator set to 1. Model names are *ratij*, where *i* is the degree of the numerator and *j* is the degree of the denominator. The degrees go up to five for both the numerator and the denominator.

| Examples of Rational Model Names | Equations                              |
|----------------------------------|----------------------------------------|
| rat02                            | $Y = (p1)/(x^2+q1*x+q2)$               |
| rat21                            | $Y = (p1*x^2+p2*x+p3)/(x+q1)$          |
| rat55                            | $Y = (p1*x^5+\dots+p6)/(x^5+\dots+q5)$ |

### Sum of Sine Model Names and Equations

| Sum of Sine Model Names | Equations                                     |
|-------------------------|-----------------------------------------------|
| sin1                    | $Y = a1*\sin(b1*x+c1)$                        |
| sin2                    | $Y = a1*\sin(b1*x+c1)+a2*\sin(b2*x+c2)$       |
| sin3                    | $Y = a1*\sin(b1*x+c1)+\dots+a3*\sin(b3*x+c3)$ |
| ...etc., up to sin8     | $Y = a1*\sin(b1*x+c1)+\dots+a8*\sin(b8*x+c8)$ |

### Sigmoidal Model Names and Equations

| Sigmoidal Model Names | Equations                           |
|-----------------------|-------------------------------------|
| logistic              | $Y = a/(1+\exp(-b*(x-c)))$          |
| logistic4             | $Y = d+(a-d)/(1+(x/c)^b)$           |
| gompertz              | $Y = d+(a-d)*\exp(-\exp(-b*(x-c)))$ |

### Spline Model Names

Spline models are supported for curve fitting, not for surface fitting.

| Spline Model Names | Description                |
|--------------------|----------------------------|
| cubicspline        | Cubic interpolating spline |
| smoothingspline    | Smoothing spline           |

### Interpolant Model Names

| Type                | Interpolant Model Names | Description                    |
|---------------------|-------------------------|--------------------------------|
| Curves and Surfaces | linearinterp            | Linear interpolation           |
|                     | nearestinterp           | Nearest neighbor interpolation |
|                     | cubicinterp             | Cubic spline interpolation     |

| Type          | Interpolant Model Names | Description                                                    |
|---------------|-------------------------|----------------------------------------------------------------|
| Curves only   | pchipinterp             | Shape-preserving piecewise cubic Hermite (pchip) interpolation |
| Surfaces only | biharmonicinterp        | Biharmonic (MATLAB griddata) interpolation                     |
|               | thinplateinterp         | Thin-plate spline interpolation                                |

**Lowess Model Names**

Lowess models are supported for surface fitting, not for curve fitting.

| Lowess Model Names | Description                |
|--------------------|----------------------------|
| lowess             | Local linear regression    |
| loess              | Local quadratic regression |

# Polynomial Models

## In this section...

“About Polynomial Models” on page 4-15

“Fit Polynomial Models Interactively” on page 4-16

“Fit Polynomials Using the Fit Function” on page 4-17

“Polynomial Model Fit Options” on page 4-27

“Defining Polynomial Terms for Polynomial Surface Fits” on page 4-28

## About Polynomial Models

Polynomial models for curves are given by

$$y = \sum_{i=1}^{n+1} p_i x^{n+1-i}$$

where  $n + 1$  is the *order* of the polynomial,  $n$  is the *degree* of the polynomial, and  $1 \leq n \leq 9$ . The order gives the number of coefficients to be fit, and the degree gives the highest power of the predictor variable.

In this guide, polynomials are described in terms of their degree. For example, a third-degree (cubic) polynomial is given by

$$y = p_1 x^3 + p_2 x^2 + p_3 x + p_4$$

Polynomials are often used when a simple empirical model is required. You can use the polynomial model for interpolation or extrapolation, or to characterize data using a global fit. For example, the temperature-to-voltage conversion for a Type J thermocouple in the 0 to 760° temperature range is described by a seventh-degree polynomial.

---

**Note** If you do not require a global parametric fit and want to maximize the flexibility of the fit, piecewise polynomials might provide the best approach. Refer to “Nonparametric Fitting” on page 6-2 for more information.

---


The main advantages of polynomial fits include reasonable flexibility for data that is not too complicated, and they are linear, which means the fitting process is simple. The main disadvantage is that high-degree fits can become unstable. Additionally, polynomials of any degree can provide a good fit within the data range, but can diverge wildly outside that range. Therefore, exercise caution when extrapolating with polynomials.

When you fit with high-degree polynomials, the fitting procedure uses the predictor values as the basis for a matrix with very large values, which can result in scaling problems. To handle this, you should normalize the data by centering it at zero mean and scaling it to unit standard deviation. Normalize data by selecting the **Center and scale** check box in the Curve Fitter app.


## Fit Polynomial Models Interactively

- 1 Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.
- 2 In the Curve Fitter app, select curve or surface data. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. Select data variables in the dialog box.
  - If you select curve data (**X data** and **Y data**, or just **Y data** against an index), the Curve Fitter app creates the default curve fit, which is a **Polynomial** fit.
  - If you select surface data (**X data**, **Y data**, and **Z data**), the Curve Fitter app creates the default surface fit, which is an **Interpolant** fit. Click the arrow in the **Fit Type** section to open the gallery, and click **Polynomial** in the **Regression Models** group.

For curve data, the app creates a **Polynomial** fit for X.



For surface data, the app creates a **Polynomial** fit for X and Y.



You can specify the following options in the **Fit Options** pane:

- The degree for the X and Y variables:
  - For curve data, the degree of X can be up to 9.
  - For surface data, the degree of X and Y can be up to 5. The degree of the **Polynomial** fit is the maximum of X and Y degrees. For more information, see “Defining Polynomial Terms for Polynomial Surface Fits” on page 4-28.
- The robust linear least-squares fitting method to use (*Off*, *LAR*, or *Bisquare*). For details, see the **Robust** name-value argument of the `fitoptions` function.
- Set bounds or exclude terms. You can exclude any term by setting its bounds to 0. Look in the **Results** pane to see the model terms, the values of the coefficients, and the goodness-of-fit statistics.

---

**Tip** If your data variables have very different scales, select and clear the **Center and scale** check box to see the difference in the fit. The app displays messages in the **Results** pane when scaling the data can improve the fit.

---

For an example comparing various polynomial fits, see “Compare Fits in Curve Fitter App” on page 2-19.

## Fit Polynomials Using the Fit Function

This example shows how to use the `fit` function to fit polynomials to data. The steps fit and plot polynomial curves and a surface, specify fit options, return goodness of fit statistics, calculate predictions, and show confidence intervals.

The polynomial library model is an input argument to the `fit` and `fitype` functions. Specify the model type `poly` followed by the degree in `x` (up to 9), or `x` and `y` (up to 5). For example, you specify a quadratic curve with `'poly2'`, or a cubic surface with `'poly33'`.

### Create and Plot a Quadratic Polynomial Curve

Load some data and fit a quadratic polynomial. Specify a quadratic, or second-degree polynomial, with the string `'poly2'`.


```
load census;
fitpoly2=fit(cdate,pop,'poly2')
% Plot the fit with the plot method.
plot(fitpoly2,cdate,pop)
% Move the legend to the top left corner.
legend('Location','NorthWest');
```

```
fitpoly2 =
```

```
Linear model Poly2:
fitpoly2(x) = p1*x^2 + p2*x + p3
Coefficients (with 95% confidence bounds):
p1 =    0.006541 (0.006124, 0.006958)
p2 =   -23.51 (-25.09, -21.93)
p3 =  2.113e+04 (1.964e+04, 2.262e+04)
```



### Create a Cubic Curve


Fit a cubic polynomial 'poly3'.

```
fitpoly3=fit(cdate,pop,'poly3')
plot(fitpoly3,cdate,pop)
```

Warning: Equation is badly conditioned. Remove repeated data points or try centering and scaling.

```
fitpoly3 =
```

```
Linear model Poly3:
fitpoly3(x) = p1*x^3 + p2*x^2 + p3*x + p4
Coefficients (with 95% confidence bounds):
p1 =  3.855e-06  (-4.078e-06, 1.179e-05)
p2 =  -0.01532  (-0.06031, 0.02967)
p3 =   17.78    (-67.2, 102.8)
p4 =  -4852    (-5.834e+04, 4.863e+04)
```



### Specify Fit Options


The cubic fit warns that the equation is badly conditioned, so you should try centering and scaling by specifying the 'Normalize' option. Fit the cubic polynomial with both center and scale and robust fitting options. Robust 'on' is a shortcut equivalent to 'Bisquare', the default method for robust linear least-squares fitting method.

```
fit3=fit(cdate, pop, 'poly3', 'Normalize', 'on', 'Robust', 'on')
plot(fit3, cdate, pop)
```

```
fit3 =
```

```
Linear model Poly3:
fit3(x) = p1*x^3 + p2*x^2 + p3*x + p4
  where x is normalized by mean 1890 and std 62.05
Coefficients (with 95% confidence bounds):
p1 =    -0.4619  (-1.895, 0.9707)
p2 =     25.01  (23.79, 26.22)
p3 =     77.03  (74.37, 79.7)
p4 =     62.81  (61.26, 64.37)
```





To find out what parameters you can set for the library model 'poly3', use the fitoptions function.

```
fitoptions poly3
```

```
ans =
```

```
llsqoptions with properties:
    Lower: []
    Upper: []
    Robust: 'Off'
    Normalize: 'off'
    Exclude: []
    Weights: []
    Method: 'LinearLeastSquares'
```

### Get Goodness of Fit Statistics

Specify the 'gof' output argument to get the goodness-of-fit statistics for the cubic polynomial fit.

```
[fit4, gof]=fit(cdate, pop,'poly3','Normalize','on');
gof
```


```
gof =
```

```
struct with fields:
    sse: 149.7687
    rsquare: 0.9988
    dfe: 17
    adjrsquare: 0.9986
    rmse: 2.9682
```

### Plot the Residuals to Evaluate the Fit

To plot residuals, specify 'residuals' as the plot type in the plot method.


```
plot(fit4, cdate, pop, 'residuals');
```



### Examine a Fit Beyond the Data Range

By default, the fit is plotted over the range of the data. To plot a fit over a different range, set the x-limits of the axes before plotting the fit. For example, to see values extrapolated from the fit, set the upper x-limit to 2050.


```
plot( cdate, pop, 'o' );
xlim( [1900, 2050] );
hold on
plot( fit4 );
hold off
```



### Plot Prediction Bounds


To plot prediction bounds, use 'predobs' or 'predfun' as the plot type.

```
plot(fit4, cdate, pop, 'predobs')
```



Plot prediction bounds for the cubic polynomial up to year 2050.

```
plot( cdate, pop, 'o' );  
xlim( [1900, 2050] )  
hold on  
plot( fit4, 'predobs' );  
hold off
```



### Get Confidence Bounds at New Query Points

Evaluate the fit for some new query points.

```
cdateFuture = (2000:10:2020).';
popFuture = fit4( cdateFuture )
```

```
popFuture =
```

```
276.9632
305.4420
335.5066
```

Compute 95% confidence bounds on the prediction for the population in the future, using the `predint` method.

```
ci = predint( fit4, cdateFuture, 0.95, 'observation' )
```

```
ci =
```


```
267.8589 286.0674
294.3070 316.5770
321.5924 349.4208
```

Plot the predicted future population, with confidence intervals, against the fit and data.

```

plot(cdate, pop, 'o');
xlim([1900, 2040])
hold on
plot(fit4)
h = errorbar(cdateFuture,popFuture,popFuture-ci(:,1),ci(:,2)-popFuture, '.');
hold off
legend('cdate v pop','poly3','prediction','Location','NorthWest')

```



### Fit and Plot a Polynomial Surface

Load some surface data and fit a fourth-degree polynomial in x and y.

```

load franke;
fitsurface=fit([x,y],z, 'poly44','Normalize','on')
plot(fitsurface, [x,y],z)

```

Linear model Poly44:

$$\text{fitsurface}(x,y) = p_{00} + p_{10}x + p_{01}y + p_{20}x^2 + p_{11}xy + p_{02}y^2 + p_{30}x^3 + p_{21}x^2y + p_{12}xy^2 + p_{03}y^3 + p_{40}x^4 + p_{31}x^3y + p_{22}x^2y^2 + p_{13}xy^3 + p_{04}y^4$$

where x is normalized by mean 1982 and std 868.6

and where y is normalized by mean 0.4972 and std 0.2897

Coefficients (with 95% confidence bounds):

```


p00 =    0.3471    (0.3033, 0.3909)
p10 =   -0.1502   (-0.1935, -0.107)
p01 =   -0.4203   (-0.4637, -0.377)
p20 =    0.2165    (0.1514, 0.2815)

```

```

p11 = 0.1717 (0.1175, 0.2259)
p02 = 0.03189 (-0.03351, 0.09729)
p30 = 0.02778 (0.00749, 0.04806)
p21 = 0.01501 (-0.002807, 0.03283)
p12 = -0.03659 (-0.05439, -0.01879)
p03 = 0.1184 (0.09812, 0.1387)
p40 = -0.07661 (-0.09984, -0.05338)
p31 = -0.02487 (-0.04512, -0.004624)
p22 = 0.0007464 (-0.01948, 0.02098)
p13 = -0.02962 (-0.04987, -0.009366)
p04 = -0.02399 (-0.0474, -0.0005797)

```



## Polynomial Model Fit Options

All fitting methods have the default properties `Normalize`, `Exclude`, `Weights`, and `Method`. For an example, see “Specify Fit Options at the Command Line” on page 4-8.

Polynomial models have the `Method` property value `LinearLeastSquares`, and the additional fit options properties shown in the next table. For details on all fit options, see the `fitoptions` reference page.

| Property | Description                                                                                                                                                                                                                                                                                                  |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Robust   | Specifies the robust linear least-squares fitting method to use. Values are 'on', 'off', 'LAR', or 'Bisquare'. The default is 'off'. 'LAR' specifies the least absolute residual method and 'Bisquare' specifies the bisquare weights method. 'on' is equivalent to 'Bisquare', the default method.          |
| Lower    | A vector of lower bounds on the coefficients to be fitted. The default value is an empty vector, indicating that the fit is unconstrained by lower bounds. If bounds are specified, the vector length must equal the number of coefficients. Individual unconstrained lower bounds can be specified by -Inf. |
| Upper    | A vector of upper bounds on the coefficients to be fitted. The default value is an empty vector, indicating that the fit is unconstrained by upper bounds. If bounds are specified, the vector length must equal the number of coefficients. Individual unconstrained upper bounds can be specified by Inf.  |

## Defining Polynomial Terms for Polynomial Surface Fits

You can control the terms to include in the polynomial surface model by specifying the degrees for the x and y inputs. If  $i$  is the degree in x and  $j$  is the degree in y, the total degree of the polynomial is the maximum of  $i$  and  $j$ . The degree of x in each term is less than or equal to  $i$ , and the degree of y in each term is less than or equal to  $j$ . The maximum for both  $i$  and  $j$  is five.

For example:

$$\text{poly21 } Z = p_{00} + p_{10}x + p_{01}y + p_{20}x^2 + p_{11}xy$$

$$\text{poly13 } Z = p_{00} + p_{10}x + p_{01}y + p_{11}xy + p_{02}y^2 + p_{12}xy^2 + p_{03}y^3$$

$$\text{poly55 } Z = p_{00} + p_{10}x + p_{01}y + \dots + p_{14}xy^4 + p_{05}y^5$$

For example, if you specify an x degree of 3 and a y degree of 2, the model name is poly32. The model terms follow the form in this table.

| Degree of Term | 0     | 1      | 2      |
|----------------|-------|--------|--------|
| 0              | 1     | y      | $y^2$  |
| 1              | x     | xy     | $xy^2$ |
| 2              | $x^2$ | $x^2y$ | N/A    |
| 3              | $x^3$ | N/A    | N/A    |

The total degree of the polynomial cannot exceed the maximum of  $i$  and  $j$ . In this example, terms such as  $x^3y$  and  $x^2y^2$  are excluded because their degrees sum to more than 3. In both cases, the total degree is 4.



## See Also

### Apps

Curve Fitter

### Functions

fit | fitttype | fitoptions

## Related Examples

- Compare Polynomial Fits Interactively on page 2-19
- “Polynomial Curve Fitting” on page 12-2
- Polynomial Curve Fitting in MATLAB
- “Polynomial Model Names and Equations” on page 4-11

## Exponential Models

### In this section...

“About Exponential Models” on page 4-30

“Fit Exponential Models Interactively” on page 4-30

“Fit Exponential Models Using the fit Function” on page 4-32

### About Exponential Models

The toolbox provides a one-term and a two-term exponential model as given by

$$y = ae^{bx}$$

$$y = ae^{bx} + ce^{dx}$$

Exponentials are often used when the rate of change of a quantity is proportional to the initial amount of the quantity. If the coefficient associated with  $b$  and/or  $d$  is negative,  $y$  represents exponential decay. If the coefficient is positive,  $y$  represents exponential growth.


For example, a single radioactive decay mode of a nuclide is described by a one-term exponential.  $a$  is interpreted as the initial number of nuclei,  $b$  is the decay constant,  $x$  is time, and  $y$  is the number of remaining nuclei after a specific amount of time passes. If two decay modes exist, then you must use the two-term exponential model. For the second decay mode, you add another exponential term to the model.

Examples of exponential growth include contagious diseases for which a cure is unavailable, and biological populations whose growth is uninhibited by predation, environmental factors, and so on.

### Fit Exponential Models Interactively

- 1 Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.
- 2 In the Curve Fitter app, select curve data. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the **Select Fitting Data** dialog box, select **X data** and **Y data**, or just **Y data** against an index.
- 3 Click the arrow in the **Fit Type** section to open the gallery, and click **Exponential** in the **Regression Models** group.

The **Fit Options** pane for the single-term **Exponential** fit is shown here.



You can specify the following options in the **Fit Options** pane:

- Choose one or two terms to fit  $\exp_1$  or  $\exp_2$ . Look in the **Results** pane to see the model terms, values of the coefficients, and goodness-of-fit statistics.
- Optionally, in the **Advanced Options** section, specify coefficient starting values and constraint bounds appropriate for your data, or change algorithm settings. The coefficient starting values and constraints shown here are for the census data.

The app calculates optimized start points for **Exponential** fits, based on the data set. You can override the start points and specify your own values in the **Fit Options** pane. For an example specifying starting values appropriate to the data, see “Gaussian Fitting with an Exponential Background” on page 5-32.

**Fit Options**

**Advanced Options**

Method: NonlinearLeastSquares

Robust: Off

Algorithm: Trust-Region

DiffMinChange: 1e-8

DiffMaxChange: 0.1

MaxFunEvals: 600

MaxIter: 400

TolFun: 1e-6

TolX: 1e-6

**Coefficient Constraints**

| Coefficients | StartPoint | Lower | Upper |
|--------------|------------|-------|-------|
| a            | 0.2362     | 0     | Inf   |
| b            | 0.1194     | 0     | Inf   |
|              |            |       |       |

[Read about fit options](#)

For more information on the settings, see “Specify Fit Options and Optimized Starting Points” on page 4-5.

## Fit Exponential Models Using the fit Function

This example shows how to fit an exponential model to data using the `fit` function.

The exponential library model is an input argument to the `fit` and `fittype` functions. Specify the model type 'exp1' or 'exp2'.

### Fit a Single-Term Exponential Model


Generate data with an exponential trend and then fit the data using a single-term exponential. Plot the fit and data.

```
x = (0:0.2:5)';
y = 2*exp(-0.2*x) + 0.1*randn(size(x));
f = fit(x,y,'exp1')
```

f =

```
General model Exp1:
f(x) = a*exp(b*x)
Coefficients (with 95% confidence bounds):
a = 2.021 (1.89, 2.151)
b = -0.1812 (-0.2104, -0.152)
```

```
plot(f,x,y)
```




### Fit a Two-Term Exponential Model

```
f2 = fit(x,y,'exp2')
```

```
f2 =
```

```
General model Exp2:
f2(x) = a*exp(b*x) + c*exp(d*x)
Coefficients (with 95% confidence bounds):
a =      537.7  (-1.307e+10, 1.307e+10)
b =     -0.2573  (-4112, 4112)
c =     -535.7  (-1.307e+10, 1.307e+10)
d =     -0.2576  (-4131, 4130)
```

```
plot(f2,x,y)
```



### Set Start Points

The toolbox calculates optimized start points for exponential fits based on the current data set. You can override the start points and specify your own values.


Find the order of the entries for coefficients in the first model (  $f$  ) by using the `coeffnames` function.

```
coeffnames(f)
ans = 2x1 cell
      {'a'}
      {'b'}
```

If you specify start points, choose values appropriate to your data. Set arbitrary start points for coefficients **a** and **b** for example purposes.

```
f = fit(x,y,'exp1','StartPoint',[1,2])
f =
  General model Exp1:
  f(x) = a*exp(b*x)
  Coefficients (with 95% confidence bounds):
    a =      2.021 (1.89, 2.151)
    b =     -0.1812 (-0.2104, -0.152)

plot(f,x,y)
```



### Examine Exponential Fit Options

Examine the fit options if you want to modify fit options such as coefficient starting values and constraint bounds appropriate for your data, or change algorithm settings. For details on these options, see the table of properties for `NonlinearLeastSquares` on the `fitoptions` reference page.

```
fitoptions('expl')
```

```
ans =
```

```
  nlsqoptions with properties:
```

```

  StartPoint: []
    Lower: []
    Upper: []
  Algorithm: 'Trust-Region'
DiffMinChange: 1.0000e-08
DiffMaxChange: 0.1000
    Display: 'Notify'
MaxFunEvals: 600
    MaxIter: 400
    TolFun: 1.0000e-06
    TolX: 1.0000e-06
    Robust: 'Off'
  Normalize: 'off'
    Exclude: []
    Weights: []
```

Method: 'NonlinearLeastSquares'

## **See Also**

### **Apps**

Curve Fitter

### **Functions**

fit | fitype | fitoptions

## **Related Examples**

- “Gaussian Fitting with an Exponential Background” on page 5-32
- “Specify Fit Options and Optimized Starting Points” on page 4-5



## Fit Fourier Models

### In this section...

“About Fourier Series Models” on page 4-37

“Fit Fourier Model Interactively in Curve Fitter App” on page 4-37

“Fit Fourier Model at the Command Line” on page 4-42

### About Fourier Series Models

A Fourier series describes a periodic function as a sum of sine and cosine functions. You can separate an arbitrary periodic function into simple components by using a Fourier series. These components are easy to integrate, differentiate, and analyze. For this reason, Fourier series are often used to approximate periodic signals.

Fourier series are represented in several forms. Curve Fitting Toolbox uses the trigonometric Fourier series form

$$y = a_0 + \sum_{i=1}^n a_i \cos(iwx) + b_i \sin(iwx)$$

where  $a_0$  models a constant (intercept) term in the data and is associated with the  $i = 0$  cosine term,  $w$  is the fundamental frequency of the signal, and  $n$  is the number of terms (harmonics). Curve Fitting Toolbox supports Fourier series regression for  $1 \leq n \leq 8$ .

For more information about Fourier series, refer to “Fourier Analysis and Filtering”.

### Fit Fourier Model Interactively in Curve Fitter App

This example shows how to use the Curve Fitter app to fit a Fourier model to data.

Load the sound signal sample data.

```
load gong.mat
```

The variables `y` and `Fs` contain sound signal and frequency data for a gong ring, respectively. Create a sound clip by storing the first 1000 elements of `y` in a vector named `gongClip`.

```
gongClip = y(1:1000);
```

To calculate the time corresponding to each element in `gongClip`, divide the index of the elements by `Fs`.


```
t = [1:1000] ./ Fs;
```

Open the Curve Fitter app from the command line.


```
curveFitter
```

Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click **Curve Fitter**.


In the Curve Fitter app, select the data variables for the fit. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select **t** as the **X data** value and **gongClip** as the **Y data** value.



The app plots the data points as you select variables. By default, the app fits a polynomial to the data. To fit a Fourier model, click **Fourier** in the **Fit Type** section of the Curve Fitter tab.




The app fits a single-term Fourier model.



The fitted one-term Fourier model is a periodic function with a simple oscillatory behavior. The **Results** panel displays the general equation for the model, fitted coefficient estimates with 95% confidence intervals, fundamental frequency, and goodness-of-fit statistics.


| Results                                                  |            |            |            |
|----------------------------------------------------------|------------|------------|------------|
| Fit Name: untitled fit 1                                 |            |            |            |
| <b>Fourier Curve Fit (fourier1)</b>                      |            |            |            |
| $f(x) = a_0 + a_1 \cos(x \cdot w) + b_1 \sin(x \cdot w)$ |            |            |            |
| <b>Coefficients and 95% Confidence Bounds</b>            |            |            |            |
|                                                          | Value      | Lower      | Upper      |
| a0                                                       | 0.0014     | -0.0110    | 0.0138     |
| a1                                                       | -0.0675    | -0.0959    | -0.0392    |
| b1                                                       | -0.0721    | -0.0993    | -0.0448    |
| w                                                        | 2.1191e+03 | 2.1140e+03 | 2.1241e+03 |
| <b>Goodness of Fit</b>                                   |            |            |            |
|                                                          | Value      |            |            |
| SSE                                                      | 39.6998    |            |            |
| R-square                                                 | 0.1097     |            |            |
| DFE                                                      | 996.0000   |            |            |
| Adj R-sq                                                 | 0.1070     |            |            |
| RMSE                                                     | 0.1996     |            |            |

The fitted one-term Fourier model has a root mean square error (RMSE) of 0.1996. To compare the one-term Fourier model with a Fourier model that has four terms, select 4 for **Number of terms** in the **Fit Options** panel. The app fits a Fourier model with four terms to the data.



The fitted four-term Fourier model has more complex oscillatory behavior than the one-term Fourier model. An RMSE of 0.1685 for the four-term model indicates that four terms predict the sound data more accurately than one. However, the plot shows that some of the data points in `gongClip` are outside of the range of the four-term model.

Export the fitted four-term Fourier model to the workspace by clicking **Export** in the **Export** section and then selecting **Export to Workspace**. In the dialog box, uncheck the second and third options. Store the fit in the variable name in the box next to the first option.



You can listen to the sound data in `gongClip` by using the function `sound`.

```
sound(gongClip,Fs)
pause(2)    % Allow gongClip to play before executing next line
```

To get the sound data for the Fourier model approximation of `gongClip`, use `feval` to evaluate `gongFourierModel` at the times in `t`. Play the approximated sound data.

```
gongClipApprox = feval(gongFourierModel,t);
sound(gongClipApprox,Fs)
```

The two clips have the same approximate average tone. However, the approximated sound data does not have as many fluctuations in tone as the sound data in `gongClip`.

### Fit Fourier Model at the Command Line

This example shows how to fit a Fourier model to data using the `fit` function.

#### Fit Two-Term Fourier Model


Load the El Niño-Southern Oscillation (ENSO) data.

```
load enso;
```

The variable `pressure` contains data for the averaged atmospheric pressure difference between Easter Island, Chile and Darwin, Australia. The variable `month` contains data for the month in which each pressure difference occurred.

Plot `pressure` against `month`.

```
plot(month,pressure)
```



The pressure data oscillates between 0 and 18, which indicates that it can be described by a Fourier series.

Fit a two-term Fourier model by using the Fourier library model. Specify the model type as `fourier` followed by the number of terms. Save the goodness-of-fit statistics for later comparison.

```
[f2,gof2] = fit(month,pressure,"fourier2")
```

```
f2 =
General model Fourier2:
f2(x) = a0 + a1*cos(x*w) + b1*sin(x*w) +
        a2*cos(2*x*w) + b2*sin(2*x*w)
Coefficients (with 95% confidence bounds):
a0 =      10.63  (10.23, 11.03)
a1 =       2.923 (2.27, 3.576)
b1 =       1.059 (0.01593, 2.101)
a2 =      -0.5052 (-1.086, 0.07532)
b2 =       0.2187 (-0.4202, 0.8576)
w =       0.5258 (0.5222, 0.5294)
```

```
gof2 = struct with fields:
    sse: 1.1230e+03
    rsquare: 0.4279
    dfe: 162
    adjrsquare: 0.4103
    rmse: 2.6329
```

`f2` is a `cfi` object containing the general formula, coefficient estimates with 95% confidence bounds, and fundamental frequency for the fit `w`. The confidence bounds on `a2` and `b2` cross zero, so not enough evidence exists to conclude that they differ from zero or that the fitted model differs from a one-term Fourier model. The root mean square error (RMSE) of 2.6329 is useful for comparing the accuracy of `f2` to the accuracy of other fits.

To calculate the period from the fundamental frequency, use the formula  $T = 2\pi/w$ .

```
w = f2.w
```

```
w = 0.5258
```

```
T = 2*pi/w
```


```
T = 11.9497
```

The period of the fitted two-term Fourier model is approximately 12 months, or one year.

Plot `f2` with a scatter plot of the data.

```
plot(f2,month,pressure)
```





The shape of `f2` is similar to the shape of a one-term Fourier model, and the oscillation peaks approximately once every 12 months.

### Fit Seven-Term Fourier Model

Fit a seven-term Fourier model to the data. Save the goodness-of-fit statistics.

```
[f7,gof7] = fit(month,pressure,"fourier7")
```

```
f7 =
```

```
General model Fourier7:
```

```
f7(x) =
```

$$a_0 + a_1 \cos(x*w) + b_1 \sin(x*w) + a_2 \cos(2*x*w) + b_2 \sin(2*x*w) + a_3 \cos(3*x*w) + b_3 \sin(3*x*w) + a_4 \cos(4*x*w) + b_4 \sin(4*x*w) + a_5 \cos(5*x*w) + b_5 \sin(5*x*w) + a_6 \cos(6*x*w) + b_6 \sin(6*x*w) + a_7 \cos(7*x*w) + b_7 \sin(7*x*w)$$

```
Coefficients (with 95% confidence bounds):
```

```
a0 = 10.63 (10.28, 10.97)
a1 = 0.5669 (0.08285, 1.051)
b1 = 0.1969 (-0.29, 0.6838)
a2 = -1.203 (-1.687, -0.7189)
```

```
b2 = -0.8085 (-1.307, -0.31)
a3 = 0.9323 (0.4325, 1.432)
b3 = 0.7599 (0.2622, 1.258)
a4 = -0.6653 (-1.149, -0.1817)
b4 = -0.2038 (-0.6995, 0.292)
a5 = -0.02913 (-0.5129, 0.4547)
b5 = -0.3701 (-0.8566, 0.1164)
a6 = -0.04841 (-0.5437, 0.4469)
b6 = -0.1367 (-0.6286, 0.3552)
a7 = 2.812 (2.19, 3.433)
b7 = 1.333 (0.4017, 2.264)
w = 0.07527 (0.07478, 0.07576)
```

```
gof7 = struct with fields:
    sse: 768.3656
    rsquare: 0.6086
    dfe: 152
    adjrsquare: 0.5700
    rmse: 2.2483
```

f7 contains several coefficients with confidence bounds that cross zero, so not enough evidence exists to conclude that their corresponding terms increase the accuracy of the fitted Fourier model. The RMSE of 2.2483 is smaller than the RMSE error of f2, which confirms that the seven-term Fourier model predicts the pressure more accurately than the two-term Fourier model.

To calculate the period from the fundamental frequency, use the formula  $T = 2\pi/w$  to calculate the period.

```
w = f7.w
```

```
w = 0.0753
```

```
T = (2*pi)/w
```

```
T = 83.4745
```

The period of the fitted seven-term Fourier model is approximately 83 months, or roughly seven years. The amplitude of the fitted coefficients determines which terms contribute most to the predicted value of the pressure difference.

The period of a sinusoid of the form  $\sin(Ax)$  or  $\cos(Ax)$  is given by the formula  $T = 2\pi/|A|$ . a7 and b7 are the largest coefficients.

```
T = 2*pi/(w*7)
```

```
T = 11.9249
```

The period of the terms corresponding to a7 and b7 is approximately 12 months, indicating that the annual cycle is the strongest.

Use the same formula to calculate the periods of the following terms:


- The terms a1 and b1 have a period of 7 years each.
- The terms a2 and b2 have a period of 3.5 (7/2) years each. The a2 and b2 coefficients have larger magnitude than a1 and b1, so the 3.5-year cycle contributes more to the predicted value of the pressure difference than the 7-year cycle.

- The terms  $a_3$  and  $b_3$  are strong, indicating 2.3-year (7/3) cycle.

Smaller terms such as  $a_6$ ,  $b_6$ ,  $a_5$ , and  $b_5$  are less important for the fit.

Plot  $f_7$  with a scatter plot of the data.

```
plot(f7,month,pressure)
```



The seven-term Fourier model oscillates in a more complex pattern and captures a wider range of values in the pressure difference than the one-term Fourier model. The cycle repeats approximately every 84 months, or 7 years. Typically, the El Niño warming happens at irregular intervals of two to seven years, and lasts nine months to two years. The average period length is five years. The model results reflect some of these periods.

### Set Start Points

The `fit` function uses the `data` input argument to calculate optimized start points for the coefficient and fundamental frequency calculations. Fourier series models are particularly sensitive to start points, and the optimized values might be accurate for only a few terms in the associated equations. You can override the optimized start points by specifying the `StartPoint` name-value argument.

The extreme values in the scatter plot of the data suggest that a four-year cycle might be present. To confirm this suggestion, set the start point of the fundamental frequency to the value corresponding to a period of eight years, or 96 months. An eight-year period for the fitted Fourier model increases the period of the terms  $a_2$  and  $b_2$  from 3.5 to 4.

```
w_8 = (2*pi)/96
```

```
w_8 = 0.0654
```

Find the index of the fundamental frequency in the cell vector of  $f_7$  coefficient names by using the `coeffnames` function.

```
coeffnames(f7)
```

```
ans = 16x1 cell
    {'a0'}
    {'a1'}
    {'b1'}
    {'a2'}
    {'b2'}
    {'a3'}
    {'b3'}
    {'a4'}
    {'b4'}
    {'a5'}
    {'b5'}
    {'a6'}
    {'b6'}
    {'a7'}
    {'b7'}
    {'w' }
```

The fundamental frequency is in the last entry of the vector of coefficient names. Create a vector of coefficient values from the coefficients of  $f_7$ , and replace the value for the fundamental frequency with the value corresponding to an eight-year period.

```
coeffs = coeffvalues(f7);
coeffs(:,end) = w_8
```

```
coeffs = 1x16
```

```
    10.6262    0.5669    0.1969   -1.2031   -0.8085    0.9323    0.7599   -0.6653   -0.2038   -0.0000
```

Fit a seven-term Fourier model to the pressure difference data using the coefficients with the new value for the fundamental frequency as the start point. Save the goodness-of-fit statistics.

```
[f7_8,gof7_8] = fit(month,pressure,"fourier7",StartPoint=coeffs)
```


```
f7_8 =
    General model Fourier7:
    f7_8(x) =
        a0 + a1*cos(x*w) + b1*sin(x*w) +
        a2*cos(2*x*w) + b2*sin(2*x*w) + a3*cos(3*x*w) + b3*sin(3*x*w) +
        a4*cos(4*x*w) + b4*sin(4*x*w) + a5*cos(5*x*w) + b5*sin(5*x*w) +
        a6*cos(6*x*w) + b6*sin(6*x*w) + a7*cos(7*x*w) + b7*sin(7*x*w)
    Coefficients (with 95% confidence bounds):
```

```
a0 =      10.58 (10.05, 11.1)
a1 =      0.3286 (-0.4339, 1.091)
b1 =     -0.05917 (-0.7884, 0.6701)
a2 =     -0.8667 (-1.738, 0.004258)
b2 =      1.094 (0.2819, 1.906)
a3 =     -0.4524 (-1.232, 0.3272)
b3 =     -0.3117 (-1.099, 0.4753)
a4 =      0.181 (-0.7949, 1.157)
b4 =      0.5806 (-0.1796, 1.341)
a5 =      0.03263 (-0.7174, 0.7827)
b5 =     -0.2299 (-0.9767, 0.5169)
a6 =      0.3726 (-0.39, 1.135)
b6 =     -0.2745 (-1.165, 0.6161)
a7 =      0.4309 (-0.491, 1.353)
b7 =     -0.3547 (-1.316, 0.6062)
w =      0.06795 (0.06519, 0.0707)
```

```
gof7_8 = struct with fields:
  sse: 1.6851e+03
  rsquare: 0.1416
  dfe: 152
  adjrsquare: 0.0568
  rmse: 3.3296
```

The coefficients of `f7_8` are slightly shifted from the `f7` coefficients. The higher RMSE for `f7_8` indicates that `f7` is a better fit for the data. Plot both fits to visually compare the models.

```
plot(f7_8, month, pressure)
hold on
plot(f7, 'b')
hold off
legend("Data", "f7_8", "f7")
```



The plot shows that `f7` captures the variation in the pressure difference data more accurately than `f7_8`.

### Display Fourier Fit Iterations

An alternative to specifying additional options using name-value arguments is to pass a `fitoptions` object to the `fit` function. To view the available options for a Fourier model fit, pass the model name as an input argument to the `fitoptions` function.

```
fitoptions("fourier7")
```

```
ans =
```

```

    Normalize: 'off'
    Exclude: []
    Weights: []
    Method: 'NonlinearLeastSquares'
    Robust: 'Off'
    StartPoint: [1×0 double]
    Lower: [1×0 double]
    Upper: [1×0 double]

```

```

    Algorithm: 'Trust-Region'
    DiffMinChange: 1.0000e-08
    DiffMaxChange: 0.1000
    Display: 'Notify'
    MaxFunEvals: 600
    MaxIter: 400
    TolFun: 1.0000e-06
    TolX: 1.0000e-06

```

Create a `fitoptions` object, and specify to display the output after each iteration.

```
optionsf7 = fitoptions("fourier7",Display="iter")
```

```
options =
```

```

    Normalize: 'off'
    Exclude: []
    Weights: []
    Method: 'NonlinearLeastSquares'
    Robust: 'Off'
    StartPoint: [1×0 double]
    Lower: [1×0 double]
    Upper: [1×0 double]
    Algorithm: 'Trust-Region'
    DiffMinChange: 1.0000e-08
    DiffMaxChange: 0.1000
    Display: 'Iter'
    MaxFunEvals: 600
    MaxIter: 400
    TolFun: 1.0000e-06
    TolX: 1.0000e-06

```

`optionsf7` is a `fitoptions` object that contains the options for a seven-term Fourier model fit.

To view the iteration steps involved in creating `f7`, fit another seven-term Fourier model using the options in `optionsf7`.

```
f7_iter = fit(month,pressure,"fourier7",optionsf7)
```

| Iteration | Func-count | f(x)    | Norm of step | First-order optimality | CG-iterations |
|-----------|------------|---------|--------------|------------------------|---------------|
| 0         | 2          | 768.41  |              | 1.93e+03               |               |
| 1         | 4          | 768.366 | 2.2176e-05   | 69.1                   | 0             |
| 2         | 6          | 768.366 | 7.94962e-07  | 2.48                   | 0             |

Success, but fitting stopped because change in residuals less than tolerance (TolFun).

```
f7_iter =
```

```
General model Fourier7:
```

```
f7_iter(x) =
```

$$\begin{aligned}
 & a_0 + a_1 \cos(x*w) + b_1 \sin(x*w) + \\
 & a_2 \cos(2*x*w) + b_2 \sin(2*x*w) + a_3 \cos(3*x*w) + b_3 \sin(3*x*w) + \\
 & a_4 \cos(4*x*w) + b_4 \sin(4*x*w) + a_5 \cos(5*x*w) + b_5 \sin(5*x*w) + \\
 & a_6 \cos(6*x*w) + b_6 \sin(6*x*w) + a_7 \cos(7*x*w) + b_7 \sin(7*x*w)
 \end{aligned}$$

```
Coefficients (with 95% confidence bounds):
```

```

a0 =    10.63    (10.28, 10.97)
a1 =     0.5669 (0.08285, 1.051)
b1 =     0.1969 (-0.29, 0.6838)
a2 =    -1.203 (-1.687, -0.7189)
b2 =    -0.8085 (-1.307, -0.31)

```

```
a3 =      0.9323 (0.4325, 1.432)
b3 =      0.7599 (0.2622, 1.258)
a4 =     -0.6653 (-1.149, -0.1817)
b4 =     -0.2038 (-0.6995, 0.292)
a5 =     -0.02913 (-0.5129, 0.4547)
b5 =     -0.3701 (-0.8566, 0.1164)
a6 =     -0.04841 (-0.5437, 0.4469)
b6 =     -0.1367 (-0.6286, 0.3552)
a7 =          2.812 (2.19, 3.433)
b7 =          1.333 (0.4017, 2.264)
w =      0.07527 (0.07478, 0.07576)
```

To investigate the Fourier model fit further, you can experiment with specifying different options available for the `NonlinearLeastSquares` fitting algorithm. See `fitoptions` for more information.

### See Also

#### Apps

Curve Fitter

#### Functions

`fit` | `fitttype` | `fitoptions`

### Related Examples

- “Fourier Analysis and Filtering”
- “Custom Nonlinear ENSO Data Analysis” on page 5-23
- “Specify Fit Options and Optimized Starting Points” on page 4-5



## Gaussian Models

### In this section...

“About Gaussian Models” on page 4-53

“Fit Gaussian Models Interactively” on page 4-53

“Fit Gaussian Models Using the fit Function” on page 4-54

### About Gaussian Models

The Gaussian model fits peaks, and is given by


$$y = \sum_{i=1}^n a_i e^{-\left(\frac{x-b_i}{c_i}\right)^2}$$

where  $a$  is the amplitude,  $b$  is the centroid (location),  $c$  is related to the peak width,  $n$  is the number of peaks to fit, and  $1 \leq n \leq 8$ .

Gaussian peaks are encountered in many areas of science and engineering. For example, Gaussian peaks can describe line emission spectra and chemical concentration assays.

### Fit Gaussian Models Interactively

- 1 Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.
- 2 In the Curve Fitter app, select curve data. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the **Select Fitting Data** dialog box, select **X data** and **Y data**, or just **Y data** against an index.
- 3 Click the arrow in the **Fit Type** section to open the gallery, and click **Gaussian** in the **Regression Models** group.



You can specify the following options in the **Fit Options** pane:

- Specify the number of terms as a positive integer in the range [1 8]. Look in the **Results** pane to see the model terms, values of the coefficients, and goodness-of-fit statistics.
- Optionally, in the **Advanced Options** section, specify coefficient starting values and constraint bounds, or change algorithm settings. The app calculates optimized start points for **Gaussian** fits, based on the data set. You can override the start points and specify your own values in the **Fit Options** pane.

Gaussian fits have the width parameter  $c1$  constrained with a lower bound of 0. The default lower bounds for most library models are  $-\text{Inf}$ , which indicates that the coefficients are unconstrained.

For more information on the settings, see “Specify Fit Options and Optimized Starting Points” on page 4-5.

## Fit Gaussian Models Using the fit Function

This example shows how to use the `fit` function to fit a Gaussian model to data.

The Gaussian library model is an input argument to the `fit` and `fittype` functions. Specify the model type `gauss` followed by the number of terms, e.g., `'gauss1'` through `'gauss8'`.


### Fit a Two-Term Gaussian Model

Load some data and fit a two-term Gaussian model.

```
[x,y] = titanium;
f = fit(x.',y.', 'gauss2')

f =
General model Gauss2:
f(x) = a1*exp(-((x-b1)/c1)^2) + a2*exp(-((x-b2)/c2)^2)
Coefficients (with 95% confidence bounds):
a1 =      1.47 (1.426, 1.515)
b1 =     897.7 (897, 898.3)
c1 =     27.08 (26.08, 28.08)
a2 =    0.6994 (0.6821, 0.7167)
b2 =     810.8 (790, 831.7)
c2 =     592.9 (500.1, 685.7)

plot(f,x,y)
```



## See Also

### Apps

Curve Fitter

### Functions

fit | fitttype | fitoptions

### **Related Examples**

- “Gaussian Fitting with an Exponential Background” on page 5-32
- “Specify Fit Options and Optimized Starting Points” on page 4-5

## Fit Logarithmic Models

### About Logarithmic Models

A logarithmic model has a steep initial period of growth before continuing to grow at a slower rate. Logarithmic models are used in a variety of applications, such as studies of population growth and signal processing. Curve Fitting Toolbox supports the logarithmic models described in the following table.

| Logarithmic Model | Base | Equation                       |
|-------------------|------|--------------------------------|
| Natural Log       | $e$  | $Y = a \cdot \log(x) + b$      |
| Common Log        | 10   | $Y = a \cdot \log_{10}(x) + b$ |
| Binary Log        | 2    | $Y = a \cdot \log_2(x) + b$    |

In the above equations,  $a$  is a scaling parameter and  $b$  is the value for  $Y$  when  $x = 1$ . You can convert between the different logarithmic models using the change of base formula  $\log_j(x) = \frac{\log_i(x)}{\log_i(j)}$ , where  $j$  is the base of the model to convert to, and  $i$  is the base of the model being converted. The logarithmic model you use to fit to your data depends on the type of problem you are solving.

### Fit Logarithmic Models Using Curve Fitter

Generate some noisy data by using the `linspace`, `log2`, and `randn` functions.


```
rng(0, "twister") % For reproducibility
x = linspace(0.01, 3, 100)';
y = log2(x) + 0.2*randn(100, 1);
```

Open the Curve Fitter app from the command line.


```
curveFitter
```

Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click **Curve Fitter**.


In the Curve Fitter app, select the data variables for the fit. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select  $x$  as the **X data** value and  $y$  as the **Y data** value.



The app plots the data points as you select variables. By default, the app fits a polynomial to the data. To fit a logarithmic model, click **Logarithmic** in the **Fit Type** section of the Curve Fitter tab.




The app fits a natural log model.



The fitted natural log model increases relatively quickly for small values of  $x$ . The **Results** panel shows the formula for the natural log model and the fitted coefficients with 95% intervals. The **Table of Fits** shows that the fitted model has a sum of squares error (SSE) of approximately 5.2, and an R-square value of approximately 0.97.


To compare the natural log model with a binary log model, select 2 for **Base of log** in the **Fit Options** panel. The app fits a binary log model to the data.



The **Table of Fits** shows that the fitted natural log model and the fitted binary log model have the same SSE and R-square values. The plot also indicates that the fitted models are the same. The only differences between the models are the base of the logarithmic model and the values and confidence bounds for the coefficient **a**. You can manually convert between the natural log model and the binary log model by using the equations  $\log_2(x) = \frac{\log(x)}{\log(2)}$  and  $\log(x) = \frac{\log_2(x)}{\log_2(e)}$ .

By default, the app uses linear least-squares fitting to calculate the fitted coefficients. You can select a robust fitting method from the **Robust** menu in the **Fit Options** panel. For example, to use the bisquare-weights method, select **Bisquare**.





The **Table of Fits** shows that the SSE for the binary log model is slightly smaller with bisquare-weights fitting than with linear least-squares fitting, and that the R-square value is slightly larger.

## Fit Logarithmic Models from Command Line

Generate some noisy data by using the `linspace`, `log10`, and `randn` functions.

```
rng(0, "twister") % For reproducibility
x = linspace(0.01, 3, 100)';
y = log10(x) + 0.1*randn(100, 1);
```

Fit a common log model to the data.


```
f = fit(x, y, "log10")

f =
Linear model Log10:
f(x) = a*log10(x) + b
Coefficients (with 95% confidence bounds):
a =      0.9561 (0.9039, 1.008)
b =      0.01415 (-0.008812, 0.03712)
```

`f` is a `cf` object that contains the results of fitting the common log model to the data. The output displays the formula for the common log model and the fitted coefficients with 95% confidence bounds.

Plot `f` and the data.

```
plot(f,x,y)
```



The plot shows that `f` follows the bulk of the data.

## See Also

### Apps

Curve Fitter

### Functions

`fit` | `fitttype` | `fitoptions`

## Related Examples

- “List of Library Models for Curve and Surface Fitting” on page 4-10

## Power Series

### In this section...

“About Power Series Models” on page 4-63

“Fit Power Series Models Interactively” on page 4-63

“Fit Power Series Models Using the fit Function” on page 4-64

### About Power Series Models

The toolbox provides a one-term and a two-term power series model as given by


$$y = ax^b$$

$$y = ax^b + c$$

Power series models describe a variety of data. For example, the rate at which reactants are consumed in a chemical reaction is generally proportional to the concentration of the reactant raised to some power.

### Fit Power Series Models Interactively

- 1 Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.
- 2 In the Curve Fitter app, select curve data. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the **Select Fitting Data** dialog box, select **X data** and **Y data**, or just **Y data** against an index.
- 3 Click the arrow in the **Fit Type** section to open the gallery, and click **Power** in the **Regression Models** group.



You can specify the following options in the **Fit Options** pane:

- Specify the number of terms as 1 or 2. Look in the **Results** pane to see the model terms, values of the coefficients, and goodness-of-fit statistics.
- Optionally, in the **Advanced Options** section, specify coefficient starting values and constraint bounds, or change algorithm settings. The app calculates optimized start points for **Power** fits, based on the data set. You can override the start points and specify your own values in the **Fit Options** pane.

For more information on the settings, see “Specify Fit Options and Optimized Starting Points” on page 4-5.

## Fit Power Series Models Using the fit Function

This example shows how to use the `fit` function to fit power series models to data.

The power series library model is an input argument to the `fit` and `fittype` functions. Specify the model type 'power1' or 'power2'.


### Fit a Single-Term Power Series Model

```
load hahn1;
f = fit(temp,thermex,'power1')

f =
    General model Power1:
```

```
f(x) = a*x^b
Coefficients (with 95% confidence bounds):
a =      1.46 (1.224, 1.695)
b =      0.4094 (0.3825, 0.4363)
```

```
plot(f,temp,thermex)
```




### Fit a Two-Term Power Series Model

```
f = fit(temp,thermex,'power2')
```

```
f =
General model Power2:
f(x) = a*x^b+c
Coefficients (with 95% confidence bounds):
a =      -78.61 (-80.74, -76.48)
b =      -0.2349 (-0.271, -0.1989)
c =       36.9 (33.09, 40.71)
```

```
plot(f,temp,thermex)
```



## See Also

### Apps

Curve Fitter

### Functions

fit | fitype | fitoptions

## Related Examples

- “Specify Fit Options and Optimized Starting Points” on page 4-5

## Rational Models

### In this section...

“Fit Rational Models Interactively” on page 4-67

“Selecting a Rational Fit at the Command Line” on page 4-68

“Example: Rational Fit” on page 4-68

*Rational models*, sometimes called *rational functions*, are ratios of polynomials given by

$$y = \frac{\sum_{i=1}^{n+1} p_i x^{n+1-i}}{x^m + \sum_{i=1}^m q_i x^{m-i}}$$

where  $n$  is the degree of the numerator polynomial, and  $m$  is the degree of the denominator polynomial. Curve Fitting Toolbox supports rational models with  $0 \leq n \leq 5$  and  $1 \leq m \leq 5$ . The coefficient associated with  $x^m$  is always 1, which makes the numerator and denominator unique when the polynomial degrees are the same.


Here rationals are described in terms of the degree of the numerator/the degree of the denominator. For example, a quadratic/cubic rational equation is given by

$$y = \frac{p_1 x^2 + p_2 x + p_3}{x^3 + q_1 x^2 + q_2 x + q_3}$$

Like polynomials, rationals are often used when a simple empirical model is required. The main advantage of rationals is their flexibility with data that has a complicated structure. The main disadvantage is that they become unstable when the denominator is around 0. For an example that uses rational polynomials of various degrees, see “Example: Rational Fit” on page 4-68.

### Fit Rational Models Interactively

- 1 Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.
- 2 In the Curve Fitter app, select curve data. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the **Select Fitting Data** dialog box, select **X data** and **Y data**, or just **Y data** against an index.
- 3 Click the arrow in the **Fit Type** section to open the gallery, and click **Rational** in the **Regression Models** group.



You can specify the following options in the **Fit Options** pane:

- Specify the numerator degree as a nonnegative integer in the range [0 5] and the denominator degree as a positive integer in the range [1 5]. Look in the **Results** pane to see the model terms, values of the coefficients, and goodness-of-fit statistics.
- Optionally, in the **Advanced Options** section, specify coefficient starting values and constraint bounds, or change algorithm settings. The app calculates random start points for rational models, defined on the interval [0 1]. You can override the start points and specify your own values in the **Fit Options** pane.

For more information on the settings, see “Specify Fit Options and Optimized Starting Points” on page 4-5.

## Selecting a Rational Fit at the Command Line

Specify the model type `ratij`, where  $i$  is the degree of the numerator polynomial and  $j$  is the degree of the denominator polynomial. For example, 'rat02', 'rat21' or 'rat55'.

For example, to load some data and fit a rational model:

```
load hahn1;
f = fit( temp, thermex, 'rat32')
plot(f,temp,thermex)
```

See “Example: Rational Fit” on page 4-68 to fit this example interactively with various rational models.

If you want to modify fit options such as coefficient starting values and constraint bounds appropriate for your data, or change algorithm settings, see the table of additional properties with `NonlinearLeastSquares` on the `fitoptions` reference page.

## Example: Rational Fit

This example fits thermal expansion data using a rational fit. The data describes the coefficient of thermal expansion for copper as a function of temperature in kelvin.

A rational fit is defined as the ratio of polynomials given by:



$$y = \frac{p_1x^n + p_2x^{n-1} + \dots + p_{n+1}}{x^m + q_1x^{m-1} + \dots + q_m}$$

where  $n$  is the degree of the numerator polynomial and  $m$  is the degree of the denominator polynomial. The rational equations are not associated with physical parameters of the data. Instead, they provide a simple and flexible empirical model that you can use for interpolation and extrapolation.

- 1 Load the thermal expansion data in `hahn1`. The data set contains a vector of temperatures in kelvin (`temp`) and a vector of thermal expansion coefficients for copper (`thermex`).


```
load hahn1
```

- 2 Open the Curve Fitter app.


```
curveFitter
```

Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.

- 3 In the Curve Fitter app, select curve data. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, specify **X data** as `temp` and **Y data** as `thermex`. The Curve Fitter app fits and plots the curve data.
- 4 Click the arrow in the **Fit Type** section to open the gallery, and click **Rational** in the **Regression Models** group.
- 5 Try a quadratic/quadratic rational fit. In the **Fit Options** pane, select 2 for both **Numerator degree** and **Denominator degree**.



- 6 Rename the fit. In the **Table Of Fits** pane, double-click the **Fit Name** value and enter `rat22`.
- 7 In the **Visualization** section, select **Residuals Plot**. Examine the data, fit, and residuals. Observe that the fit misses the data for the smallest and largest predictor values. Additionally, the residuals show a strong pattern for the entire data set. These observations indicate that a better fit is possible.




- 8 Try a cubic/cubic rational fit. First duplicate the current fit. On the **Curve Fitter** tab, in the **File** section, click **Duplicate**. Name the new fit **rat33**.
- 9 In the **Fit Options** pane, select 3 for both **Numerator degree** and **Denominator degree**. Examine the data, fit, and residuals.

---

**Note** Your results depend on random start points and might vary from those shown. The fit can exhibit discontinuities around the zeros of the denominator.

---




- 10** Look at the **Results** pane. The message and numerical results indicate that the fit did not converge.

| Results                                                             |             |             |            |
|---------------------------------------------------------------------|-------------|-------------|------------|
| Fit Name: rat33                                                     |             |             |            |
| Rational Curve Fit (rat33)                                          |             |             |            |
| $f(x) = (p1*x^3 + p2*x^2 + p3*x + p4) / (x^3 + q1*x^2 + q2*x + q3)$ |             |             |            |
| Coefficients and 95% Confidence Bounds                              |             |             |            |
|                                                                     | Value       | Lower       | Upper      |
| p1                                                                  | 43.3257     | -76.4357    | 163.0870   |
| p2                                                                  | 1.0873e+05  | -5.5246e+05 | 7.6992e+05 |
| p3                                                                  | -3.9306e+06 | -2.8042e+07 | 2.0181e+07 |
| p4                                                                  | 2.8391e+07  | -1.5185e+08 | 2.0863e+08 |
| q1                                                                  | 6.0397e+03  | -2.9736e+04 | 4.1815e+04 |
| q2                                                                  | 2.7419e+04  | -2.0126e+05 | 2.5609e+05 |
| q3                                                                  | 9.2971e+06  | -4.2374e+07 | 6.0968e+07 |
| Goodness of Fit                                                     |             |             |            |
|                                                                     | Value       |             |            |
| SSE                                                                 | 18.1746     |             |            |
| R-square                                                            | 0.9977      |             |            |
| DFE                                                                 | 229.0000    |             |            |
| Adj R-sq                                                            | 0.9976      |             |            |
| RMSE                                                                | 0.2817      |             |            |

Although the message in the **Results** pane indicates that you might improve the fit if you increase the maximum number of iterations, a better choice at this stage of the fitting process is to use a different rational equation.

- 11 Try a cubic/quadratic rational fit. First duplicate the current fit. On the **Curve Fitter** tab, in the **File** section, click **Duplicate**. Name the new fit rat32.
- 12 In the **Fit Options** pane, select 3 and 2 for **Numerator degree** and **Denominator degree**, respectively.
- 13 The data variables have very different scales, so select the **Center and scale** check box. The data, fit, and residuals are shown here.



The fit behaves well over the entire data range, and the residuals are randomly scattered about zero. Therefore, you can confidently use this fit for further analysis.

## See Also

### Apps

Curve Fitter

### Functions

fit | fitype | fitoptions

## Related Examples

- “Specify Fit Options and Optimized Starting Points” on page 4-5

## Sum of Sines Models

### In this section...

“About Sum of Sines Models” on page 4-74

“Fit Sum of Sine Models Interactively” on page 4-74

“Selecting a Sum of Sine Fit at the Command Line” on page 4-75

### About Sum of Sines Models


The sum of sines model fits periodic functions, and is given by

$$y = \sum_{i=1}^n a_i \sin(b_i x + c_i)$$

where  $a$  is the amplitude,  $b$  is the frequency, and  $c$  is the phase constant for each sine wave term.  $n$  is the number of terms in the series and  $1 \leq n \leq 8$ . This equation is closely related to the Fourier series described in “Fit Fourier Models” on page 4-37. The main difference is that the sum of sines equation includes the phase constant, and does not include a constant (intercept) term.

### Fit Sum of Sine Models Interactively

- 1 Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.
- 2 In the Curve Fitter app, select curve data. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the **Select Fitting Data** dialog box, select **X data** and **Y data**, or just **Y data** against an index.
- 3 Click the arrow in the **Fit Type** section to open the gallery, and click **Sum of Sine** in the **Regression Models** group.



You can specify the following options in **Fit Options** pane:

- Specify the number of terms as a positive integer in the range [1 8]. Look in the **Results** pane to see the model terms, values of the coefficients, and goodness-of-fit statistics.
- Optionally, in the **Advanced Options** section, specify coefficient starting values and constraint bounds, or change algorithm settings. The app calculates optimized start points for **Sum of Sine** fits, based on the data set. You can override the start points and specify your own values in the **Fit Options** pane.

The **Sum of Sine** fit has a lower bound constraint on  $b_1$  of  $\theta$ . The default lower bounds for most fits in the **Fit Type** section are  $-\text{Inf}$ .

For more information on the settings, see “Specify Fit Options and Optimized Starting Points” on page 4-5.

## Selecting a Sum of Sine Fit at the Command Line

Specify the model type `sin` followed by the number of terms, e.g., `'sin1'` to `'sin8'`.

For example, to load some periodic data and fit a six-term sum of sine model:

```
load enso;
f = fit( month, pressure, 'sin6')
plot(f,month,pressure)
```

If you want to modify fit options such as coefficient starting values and constraint bounds appropriate for your data, or change algorithm settings, see the table of additional properties with `NonlinearLeastSquares` on the `fitoptions` reference page.

### See Also

#### Apps

Curve Fitter

#### Functions

`fit` | `fitttype` | `fitoptions`

### Related Examples

- “Specify Fit Options and Optimized Starting Points” on page 4-5



## Fit Sigmoidal Models

*Sigmoidal models* are S-shaped curves that are commonly used to model dose-response curves and population dynamics. These models are also used in many artificial neural networks as activation functions. Curve Fitting Toolbox supports logistic, 4-parameter logistic, and Gompertz sigmoidal models with the following equations.

| Sigmoidal Model      | Equation                                                |
|----------------------|---------------------------------------------------------|
| Logistic             | $f(x) = \frac{a}{1 + e^{-b(x-c)}}$                      |
| 4-parameter logistic | $f(x) = d + \frac{a-d}{1 + \left(\frac{x}{c}\right)^b}$ |
| Gompertz             | $f(x) = d + (a-d)e^{-e^{-b(x-c)}}$                      |

In these equations,  $a$  and  $d$  are parameters for the horizontal asymptotes, and  $b$  is a growth rate parameter. For a 4-parameter logistic model, the input data  $x$  must contain all positive or all negative elements, and  $c$  is the midpoint between the horizontal asymptotes. For a Gompertz model,  $c$  is the inflection point for the curve. For a logistic model,  $c$  is both the midpoint and the inflection point.

### Fit Sigmoidal Model Using Curve Fitter App

Generate data with added noise by using the `linspace`, `exp`, and `randn` functions, and the standard logistic function  $p(x) = \frac{1}{1 + e^{-x}}$ .  $p$ , which is bounded between 0 and 1, represents the probability of an event occurring given the input  $x$ .


```
rng(0, "twister") % For reproducibility
x = linspace(-5,5,100)';
p = 1./(1+exp(-x)) + 0.02*randn(100,1);
p(p>1) = 1;
p(p<0) = 0;
```

Open the Curve Fitter app from the command line.


```
curveFitter
```

Alternatively, on the **Apps** tab, in the **Math, Statistics, and Optimization** group of the apps gallery, click **Curve Fitter**.


In the app, select the data variables for the fit. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select  $x$  as the **X data** value and  $p$  as the **Y data** value.



The app plots the data points as you select variables. By default, the app fits a linear polynomial to the data. To fit a sigmoidal model, click **Sigmoidal** in the **Fit Type** gallery of the Curve Fitter tab.




By default, the app plots a logistic model.



The plot shows that the logistic fit follows the bulk of the data. The probability is small for negative values of  $x$ , then increases, and then plateaus around 1. The **Table of Fits** shows the goodness-of-fit statistics for the logistic model, including the sum of squares error (SSE) of approximately 0.048, and the R-square value of approximately 1. The **Results** pane also displays the model equation and the fitted coefficients with 95% confidence bounds.

To use a different model equation, select a different model name from the **Model** menu in the **Fit Options** pane. For example, you can select a Gompertz model.



The plot shows that the lower asymptote for the Gompertz curve is greater than zero. The **Table of Fits** shows that this fit has a larger SSE value and a slightly smaller R-square value compared to the logistic fit. This result is due to the data being generated from a Gompertz function rather than a logistic function.

## Fit Sigmoidal Model at Command Line


Generate data with added noise by using the `linspace`, `tanh`, and `randn` functions.

```
rng(0, "twister") % For reproducibility
pts = linspace(-5,5,100)';
x = linspace(1,11,100)';
y = tanh(pts)+0.1*randn(100,1);
```

The vector `x` contains data for the independent variable, and the vector `y` contains data for the dependent variable.

Use the `scatter` function to create a scatter plot of the data in `x` and `y`.

```
scatter(x,y)
```



The scatter plot shows that  $y$  contains positive and negative values,  $x$  contains all positive values, and the data follows an S-shape.

Fit a 4-parameter logistic model to  $x$  and  $y$ .


```
f = fit(x,y,'logistic4')
```

```
f =
General model Logistic4:
f(x) = d + (a-d)/(1 + (x/c)^b)
Coefficients (with 95% confidence bounds):
a =   -0.9507  (-0.989, -0.9125)
b =    12.93  (11.14, 14.72)
c =     6.013  (5.94, 6.086)
d =     1.003  (0.9608, 1.046)
```

$f$  is a `cfits` object that contains the results of fitting a 4-parameter logistic model to the data.

Plot  $f$  together with  $x$  and  $y$ .

```
plot(f,x,y)
```



The plot shows that the fitted curve  $f$  follows the bulk of the data.

## References

- [1] Tjørve, Kathleen M. C., and Even Tjørve. "The Use of Gompertz Models in Growth Analyses, and New Gompertz-Model Approach: An Addition to the Unified-Richards Family." *PLOS ONE*, edited by Roeland M.H. Merks, vol. 12, no. 6, June 2017, p. e0178691. *DOI.org (Crossref)*, <https://doi.org/10.1371/journal.pone.0178691>.

## See Also

### Apps

Curve Fitter

### Functions

fit | fitttype | fitoptions

**Related Examples**

- “List of Library Models for Curve and Surface Fitting” on page 4-10

## Weibull Distributions

### In this section...

“About Weibull Distribution Models” on page 4-84

“Fit Weibull Models Interactively” on page 4-84

“Selecting a Weibull Fit at the Command Line” on page 4-85

### About Weibull Distribution Models

The Weibull distribution is widely used in reliability and life (failure rate) data analysis. The toolbox provides the two-parameter Weibull distribution

$$y = abx^{b-1}e^{-ax^b}$$

where  $a$  is the scale parameter and  $b$  is the shape parameter.

Note that there are other Weibull distributions, but you must create a custom equation to use these distributions:


- A three-parameter Weibull distribution with  $x$  replaced by  $x - c$  where  $c$  is the location parameter
- A one-parameter Weibull distribution where the shape parameter is fixed and only the scale parameter is fitted.

Curve Fitting Toolbox does not fit Weibull probability distributions to a sample of data. Instead, it fits curves to response and predictor data such that the curve has the same shape as a Weibull distribution.

### Fit Weibull Models Interactively

- 1 Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.
- 2 In the Curve Fitter app, select curve data. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the **Select Fitting Data** dialog box, select **X data** and **Y data**, or just **Y data** against an index.
- 3 Click the arrow in the **Fit Type** section to open the gallery, and click **Weibull** in the **Regression Models** group.





There are no fit settings to configure in the **Fit Options** pane.

Optionally, in the **Advanced Options** section, specify coefficient starting values and constraint bounds, or change algorithm settings. The app calculates random start points for **Weibull** fits, defined on the interval [0 1]. You can override the start points and specify your own values in the **Fit Options** pane.

For more information on the settings, see “Specify Fit Options and Optimized Starting Points” on page 4-5.

## Selecting a Weibull Fit at the Command Line

Specify the model type `weibull`.

For example, to load some example data measuring blood concentration of a compound against time, and fit and plot a Weibull model specifying a start point:

```
time = [ 0.1; 0.1; 0.3; 0.3; 1.3; 1.7; 2.1; ...
        2.6; 3.9; 3.9; ...
        5.1; 5.6; 6.2; 6.4; 7.7; 8.1; 8.2; ...
        8.9; 9.0; 9.5; ...
        9.6; 10.2; 10.3; 10.8; 11.2; 11.2; 11.2; ...
        11.7; 12.1; 12.3; ...
        12.3; 13.1; 13.2; 13.4; 13.7; 14.0; 14.3; ...
        15.4; 16.1; 16.1; ...
        16.4; 16.4; 16.7; 16.7; 17.5; 17.6; 18.1; ...
        18.5; 19.3; 19.7;];
```

```
conc = [0.01; 0.08; 0.13; 0.16; 0.55; 0.90; 1.11;...
        1.62; 1.79; 1.59; ...
        1.83; 1.68; 2.09; 2.17; 2.66; 2.08; 2.26;...
        1.65; 1.70; 2.39; ...
        2.08; 2.02; 1.65; 1.96; 1.91; 1.30; 1.62;...
        1.57; 1.32; 1.56; ...
        1.36; 1.05; 1.29; 1.32; 1.20; 1.10; 0.88;...
        0.63; 0.69; 0.69; ...
        0.49; 0.53; 0.42; 0.48; 0.41; 0.27; 0.36;...
        0.33; 0.17; 0.20;];

f=fit(time, conc/25, 'Weibull', ...
'StartPoint', [0.01, 2] )
plot(f,time,conc/25, 'o');
```

If you want to modify fit options such as coefficient starting values and constraint bounds appropriate for your data, or change algorithm settings, see the table of additional properties with `NonlinearLeastSquares` on the `fitoptions` reference page.

Appropriate start point values and scaling `conc/25` for the two-parameter Weibull model were calculated by fitting a 3 parameter Weibull model using this custom equation:

```
f=fit(time, conc, ' c*a*b*x^(b-1)*exp(-a*x^b)', 'StartPoint', [0.01, 2, 5] )
```

```
f =
General model:
f(x) = c*a*b*x^(b-1)*exp(-a*x^b)
Coefficients (with 95% confidence bounds):
a = 0.009854 (0.007465, 0.01224)
b = 2.003 (1.895, 2.11)
c = 25.65 (24.42, 26.89)
```

This Weibull model is defined with three parameters: the first scales the curve along the horizontal axis, the second defines the shape of the curve, and the third scales the curve along the vertical axis. Notice that while this curve has almost the same form as the Weibull probability density function, it is not a density because it includes the parameter `c`, which is necessary to allow the curve's height to adjust to data.

## See Also

### Apps

Curve Fitter

### Functions

`fit` | `fitttype` | `fitoptions`

## Related Examples

- “Specify Fit Options and Optimized Starting Points” on page 4-5

## Introduction to Least-Squares Fitting

### In this section...

“Calculating Residuals” on page 4-87  
 “Error Assumptions” on page 4-88  
 “Linear Least Squares” on page 4-88  
 “Weighted Least Squares” on page 4-89  
 “Robust Least Squares” on page 4-90  
 “Nonlinear Least Squares” on page 4-91

A regression model relates response data to predictor data with one or more coefficients. A *fitting method* is an algorithm that calculates the model coefficients given a set of input data. Curve Fitting Toolbox uses least-squares fitting methods to estimate the coefficients of a regression model.

Curve Fitting Toolbox supports the following least-squares fitting methods:

- Linear least-squares
- Weighted least-squares
- Robust least-squares
- Nonlinear least-squares

The type of regression model and the properties of the input data determine which least-squares method is most appropriate for estimating model coefficients.

### Calculating Residuals

A *residual* for a data point is the difference between the value of the observed response and the response estimate returned by the fitted model. The formula for calculating the vector of estimated responses is

$$\hat{y} = f(X, b)$$

where

- $\hat{y}$  is an  $n$ -by-1 vector of response estimates
- $f$  is the general form of the regression model.
- $X$  is an  $n$ -by- $m$  design matrix.
- $b$  is an  $m$ -by-1 vector of fitted model coefficients.

A *least-squares fitting method* calculates model coefficients that minimize the sum of squared errors (SSE), which is also called the residual sum of squares. Given a set of  $n$  data points, the residual for the  $i$ th data point  $r_i$  is calculated with the formula

$$r_i = y_i - \hat{y}_i$$

where  $y_i$  is the  $i$ th observed response value and  $\hat{y}_i$  is the  $i$ th fitted response value. The SSE is given by

$$SSE = \sum_{i=1}^n r_i^2 = \sum_{i=1}^n (y_i - \hat{y}_i)^2$$

## Error Assumptions

The difference between the observed and true values for a data point is called the *error*. Because it cannot be observed directly, the error for a data point is approximated with the data point's residual.

Least-squares fitting methods are most accurate for data sets that do not contain a large number of random errors with extreme values. Statistical results, such as confidence and prediction bounds, assume that errors are normally distributed. Data fitting techniques typically make two important assumptions about the error in data containing random variations:

- The error exists only in the response data, and not in the predictor data.
- The errors are random and follow a normal distribution with zero mean and constant variance.

Data fitting techniques assume that errors are normally distributed because the normal distribution often provides an adequate approximation to the distribution of many measured quantities. Although the least-squares fitting method does not assume normally distributed errors when calculating parameter estimates, the method works best for data that does not contain a large number of random errors with extreme values. The normal distribution is one of the probability distributions in which extreme random errors are uncommon. However, statistical results, such as confidence and prediction bounds require normally distributed errors for their validity.

If the mean of the residuals is nonzero, check whether the residuals are influenced by the choice of model or predictor variables. For fitting methods other than weighted least squares, Curve Fitting Toolbox additionally assumes that the errors have constant variance across the values of the predictor variables. Residuals that do not have a constant variance indicate that the fit might be influenced by poor quality data.

## Linear Least Squares

Curve Fitting Toolbox uses the linear least-squares method to fit a linear model to data. A *linear model* is defined as an equation that is linear in its coefficients. Use the linear least-squares fitting method when the data contains few extreme values, and the variance of the error is constant across predictor variables.

A linear model of degree  $m - 1$  has the matrix form

$$y = X\beta + \varepsilon$$

where

- $y$  is an  $n$ -by-1 vector of response data.
- $\beta$  is an  $m$ -by-1 vector of unknown coefficients.
- $X$  is an  $n$ -by- $m$  design matrix containing  $m - 1$  predictor columns. Each predictor variable corresponds to a column in  $X$ . The last column in  $X$  is a column of ones representing the model's constant term.
- $\varepsilon$  is an  $n$ -by-1 vector of unknown errors.

For example, a first-degree polynomial of the form

$$y = p_1x + p_2$$

is given by

$$\begin{bmatrix} y_1 \\ y_2 \\ y_3 \\ \vdots \\ \vdots \\ y_n \end{bmatrix} = \begin{bmatrix} x_1 & 1 \\ x_2 & 1 \\ x_3 & 1 \\ \vdots & \vdots \\ \vdots & \vdots \\ x_n & 1 \end{bmatrix} \times \begin{bmatrix} p_1 \\ p_2 \end{bmatrix}$$

You cannot calculate  $\beta$  directly because  $\varepsilon$  is unknown. The linear least-squares fitting method approximates  $\beta$  by calculating a vector of coefficients  $b$  that minimizes the SSE. Curve Fitting Toolbox calculates  $b$  by solving a system of equations called the normal equations. The normal equations are given by the formula

$$(X^T X)b = X^T y$$

where  $X^T$  is the transpose of the matrix  $X$ . The formula for  $b$  is then

$$b = (X^T X)^{-1} X^T y$$

To solve the system of simultaneous linear equations for unknown coefficients, use the MATLAB backslash operator (`mldivide`). Because inverting  $X^T X$  can lead to unacceptable rounding errors, the backslash operator uses QR decomposition with pivoting, which is a stable algorithm numerically. See “Arithmetic Operations” for more information about the backslash operator and QR decomposition. To calculate the vector of fitted response values  $\hat{y}$ , substitute  $b$  into the model formula.

$$\hat{y} = Xb$$

For an example of fitting a polynomial model using the linear least-squares fitting method, see “Fit Polynomial Model to Data” on page 12-173.

## Weighted Least Squares

If the response data error does not have constant variance across the values of the predictor data, the fit can be influenced by poor quality data. The weighted least-squares fitting method uses scaling factors called *weights* to influence the effect of a response value on the calculation of model coefficients. Use the weighted least-squares fitting method if the weights are known, or if the weights follow a particular form.

The weighted least-squares fitting method introduces weights in the formula for the SSE, which becomes

$$SSE = \sum_{i=1}^n w_i (y_i - \hat{y}_i)^2$$

where  $w_i$  are the weights. The weights you supply should transform the response variances to a constant value. If you know the variances  $\sigma_i^2$  of the measurement errors in your data, then the weights are given by  $w_i = \frac{1}{\sigma_i^2}$ . Alternatively, you can use the residuals to estimate the error in the calculation of the  $\sigma_i^2$ .

The weighted formula for the *SSE* yields the formula for  $b$

$$b = (X^T W X)^{-1} X^T W y$$

where  $W$  is a diagonal matrix such that  $W_{ii} = w_i$ .

For an example of fitting a polynomial model using the weighted least-squares fitting method, see “Improve Model Fit with Weights” on page 12-175.

## Robust Least Squares

Extreme values in the response data are called *outliers*. Linear least-squares fitting is sensitive to outliers because squaring the residuals magnifies the effects of these data points in the *SSE* calculation. Use the robust least-squares fitting method if your data contains outliers.

Curve Fitting Toolbox provides the following robust least-squares fitting methods:

- Least absolute residuals (LAR) — This method finds a curve that minimizes the absolute residuals rather than the squared differences. Therefore, extreme values have less influence on the fit.
- Bisquare weights — This method minimizes a weighted sum of squares, where the weight given to each data point depends on how far the point is from a fitted curve. Points near the fitted curve get full weight. Points farther from the curve get reduced weight. Points that are farther from the curve than expected by random chance get zero weight.

The bisquare weights method is often preferred over LAR because it simultaneously seeks to find a curve that fits the bulk of the data using the least-squares approach while minimizing the effect of outliers.

Robust bisquare weights fitting uses the iteratively reweighted least-squares algorithm, which follows these steps:

- 1 Fit the model by weighted least squares. For the first iteration, the algorithm uses weights equal to one unless you specify the weights.
- 2 Calculate the adjusted residuals and standardize them. The adjusted residuals are given by

$$r_{adj} = \frac{r_i}{\sqrt{1 - h_i}}$$

where  $h_i$  are parameters that reduce the weight of data points that are far from the fitted curve. The standardized adjusted residuals are given by

$$u = \frac{r_{adj}}{Ks}$$

where  $K=4.685$  is a tuning constant, and  $s$  is the robust standard deviation given by dividing the median absolute deviation (MAD) of the residuals by 0.6745.

Calculate the robust weights as a function of  $u$ . The bisquare weights are given by

$$w_i = \begin{cases} (1 - (u_i)^2)^2 & |u_i| < 1 \\ 0 & |u_i| \geq 1 \end{cases}$$

- 3 If the fit converges, exit the iteration process. Otherwise, perform the next iteration of the bisquare weights fitting method by returning to step 1.

Instead of minimizing the effects of outliers by using robust least-squares fitting, you can mark data points to be excluded from the fit. See “Remove Outliers” on page 7-8 for more information.

For an example of fitting a polynomial model using the robust least-squares fitting method, see “Compare Robust Fitting Methods” on page 12-179.

## Nonlinear Least Squares

Curve Fitting Toolbox uses the nonlinear least-squares method to fit a nonlinear model to data. A *nonlinear model* is defined as an equation that is nonlinear in the coefficients, or has a combination of linear and nonlinear coefficients. Exponential, Fourier, and Gaussian models are nonlinear, for example.

A nonlinear model has the matrix form

$$y = f(X, \beta) + \varepsilon$$

where

- $y$  is an  $n$ -by-1 vector of response data.
- $\beta$  is an  $m$ -by-1 vector of coefficients.
- $X$  is the  $n$ -by- $m$  design matrix.
- $f$  is a nonlinear function of  $\beta$  and  $X$ .
- $\varepsilon$  is an  $n$ -by-1 vector of unknown errors.

In a nonlinear model, unlike a linear model, the approximate coefficients  $b$  cannot be calculated using matrix techniques. Curve Fitting Toolbox uses the following iterative approach to calculate the coefficients:

- 1 Initialize the coefficient values. For some nonlinear models, the toolbox provides a heuristic approach for calculating initial values. For other models, the coefficients are initialized with random values in the interval  $[0,1]$ .
- 2 Calculate the fitted curve for the current set of coefficients. The fitted response value  $\hat{y}$  is given by  $\hat{y} = f(X, b)$  and is calculated using the Jacobian of  $f(X, \beta)$ . The Jacobian of  $f(X, \beta)$  is defined as a matrix of partial derivatives taken with respect to the coefficients in  $\beta$ .
- 3 Adjust the coefficients using one of these nonlinear least-squares algorithms:
  - Trust-region — This algorithm is the default. You must use the trust-region algorithm if you specify coefficient constraints. The trust-region algorithm can solve difficult nonlinear problems more efficiently than other algorithms and is an improvement over the popular Levenberg-Marquardt algorithm.
  - Levenberg-Marquardt — If the trust-region algorithm does not produce a reasonable fit, and you do not have coefficient constraints, use the Levenberg-Marquardt algorithm.
- 4 If the fit satisfies the specified convergence criteria, exit the iteration. Otherwise, return to step 2.

Curve Fitting Toolbox supports the use of weights and robust fitting to calculate the SSE for nonlinear models.

The accuracy of a nonlinear model's predictions depends on the type of the model, the convergence criteria, the data set, and the initial values assigned to the coefficients. If the default options do not yield a reasonable fit, experiment with different starting values for the model coefficients, nonlinear least-squares algorithms, and convergence criteria. In general, begin by modifying the coefficient starting values, because nonlinear model fits are particularly sensitive to the starting values for the model coefficients. See “Specify Fit Options and Optimized Starting Points” on page 4-5 for more information about modifying the default options.

For an example of fitting an exponential model using the nonlinear least-squares fitting method, see “Fit Exponential Model to Data” on page 12-185.

## References

- [1] DuMouchel, W. H., and F. L. O'Brien. “Integrating a Robust Option into a Multiple Regression Computing Environment.” *Computer Science and Statistics: Proceedings of the 21st Symposium on the Interface*. Alexandria, VA: American Statistical Association, 1989.
- [2] Holland, P. W., and R. E. Welsch. “Robust Regression Using Iteratively Reweighted Least-Squares.” *Communications in Statistics: Theory and Methods*, A6, 1977, pp. 813-827.

## See Also

### Apps

Curve Fitter

### Functions

fit | fitoptions

## More About

- “Specify Fit Options and Optimized Starting Points” on page 4-5
- “Remove Outliers” on page 7-8
- “Fit Polynomial Model to Data” on page 12-173
- “Improve Model Fit with Weights” on page 12-175
- “Compare Robust Fitting Methods” on page 12-179
- “Fit Exponential Model to Data” on page 12-185



# Custom Linear and Nonlinear Regression

---

- “Custom Models” on page 5-2
- “Custom Linear Fitting” on page 5-7
- “Custom Nonlinear Census Fitting” on page 5-20
- “Custom Nonlinear ENSO Data Analysis” on page 5-23
- “Gaussian Fitting with an Exponential Background” on page 5-32
- “Surface Fitting to Biopharmaceutical Data” on page 5-35

## Custom Models

### In this section...

“Custom Models vs. Library Models” on page 5-2

“Selecting a Custom Equation Fit Interactively” on page 5-2

“Selecting a Custom Equation Fit at the Command Line” on page 5-5

### Custom Models vs. Library Models

If the Curve Fitting Toolbox library does not contain a desired parametric equation, you can create your own custom equation. Library models, however, offer the best chance for rapid convergence. This is because:

- For most library models, the toolbox calculates optimal default coefficient starting points. For custom models, the toolbox chooses random default starting points on the interval [0,1]. You need to find suitable start points for custom models.
- Library models use an analytic Jacobian. Custom models use finite differencing.

### Linear and Nonlinear Fitting

You can create custom general equations with the Custom Equation fit type. General models are nonlinear combinations of (perhaps nonlinear) terms. They are defined by equations that might be nonlinear in the parameters. The custom equation fit uses the nonlinear least-squares fitting procedure.


You can define a custom linear equation using the Custom Equation fit type, though the nonlinear fitting is less efficient and usually slower than linear least-squares fitting.

- If you don't know if your equation can be expressed as a set of linear functions, then choose **Custom Equation**. You might need to search for suitable start points.
- If you need linear least-squares fitting for custom equations, choose the **Linear Fitting** model type instead. See “Custom Linear Fitting” on page 5-7.


### Selecting a Custom Equation Fit Interactively

In the Curve Fitter app, on the **Curve Fitter** tab, in the **Fit Type** section, click the arrow to open the gallery. In the fit gallery, click **Custom Equation** in the **Custom** group.

In the **Fit Options** pane, use the custom equation fit to define your own equations. An example custom equation appears when you click **Custom Equation**, as shown here for curve data.



If you have surface data, the example custom equation uses both x and y.



- 1 You can edit x, y, and z to any valid variable names.
- 2 In the lower box, edit the example to define your own custom equation. You can enter any valid MATLAB expression in terms of your variable names. You can specify a function or script name (see “Fitting a Curve Defined by a File in the Curve Fitter App” on page 5-4).
- 3 Click **Advanced Options** if you want to specify start points or bounds. By default, the starting values are randomly selected on the interval [0,1] and are unconstrained. You might need to search for suitable start points and bounds. For an example, see “Custom Nonlinear ENSO Data Analysis” on page 5-23.

If you set fit options and then alter other fit settings, the app remembers your choices for lower and upper bounds and start points, if possible. For custom equations, the Curve Fitter app always remembers user values. However, for many library models, if you change fit settings, then the app automatically calculates new best values for start points or lower bounds.

You can save your custom equations as part of your saved Curve Fitter app sessions.

Your function can execute a number of times, both during fitting and during preprocessing before fitting. Be aware this may be time-consuming if you are using functions with side effects such as writing data to a file, or displaying diagnostic information to the Command Window.

For examples, see:

- “Custom Nonlinear ENSO Data Analysis” on page 5-23
- “Gaussian Fitting with an Exponential Background” on page 5-32
- “Surface Fitting to Biopharmaceutical Data” on page 5-35
- “Custom Linear Fitting” on page 5-7

### Fitting a Curve Defined by a File in the Curve Fitter App

This example shows how to provide a function or script name as the fitting model in the Curve Fitter app. Define a function in a file and use it to fit a curve.

- 1 Define a function in a MATLAB file.

```
function y = piecewiseLine(x,a,b,c,d,k)
% PIECEWISELINE  A line made of two pieces
% that is not continuous.

y = zeros(size(x));

% This example includes a for-loop and if statement
% purely for example purposes.
for i = 1:length(x)
    if x(i) < k
        y(i) = a + b.* x(i);
    else
        y(i) = c + d.* x(i);
    end
end
end
```

Save the file on the MATLAB path.

- 2 Define some data and open the Curve Fitter app.

```
x = [0.81;0.91;0.13;0.91;0.63;0.098;0.28;0.55; ...
     0.96;0.96;0.16;0.97;0.96];
y = [0.17;0.12;0.16;0.0035;0.37;0.082;0.34;0.56; ...
     0.15;-0.046;0.17;-0.091;-0.071];


curveFitter
```

- 3 In the Curve Fitter app, on the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select **x** and **y** in the **X data** and **Y data** lists, respectively. Enter **Piecewise Function** as the fit name.

- 4 Use your `piecewiseLine` function in the Curve Fitter app. On the **Curve Fitter** tab, in the **Fit Type** section, click the arrow to open the gallery. In the fit gallery, click **Custom Equation** in the **Custom** group. In the **Fit Options** pane, enter your function expression in the custom equation text box. The function takes `x` data and some parameters for fitting.

```
piecewiseLine(x,a,b,c,d,k)
```

The Curve Fitter app creates a fit using your function.



**Tip** If you want to use the same function for fitting at the command line, use the same expression as an input to `fittype`, and then use the `fittype` as an input to `fit`:

```
ft = fittype("piecewiseLine(x,a,b,c,d,k)");
f = fit(x,y,ft)
```

For more examples, see the `fit` function.

## Selecting a Custom Equation Fit at the Command Line

To fit custom models, either:

- Supply a custom model to the `fit` function in the `fitType` input argument. You can use a MATLAB expression (including any `.m` file), a cell array or string array of linear model terms, or an anonymous function.
- Create a `fittype` object with the `fittype` function to use as an input argument for the `fit` function.

This example loads some data and uses a custom equation defining a Weibull model as an input to the `fit` function:

```
time = [ 0.1; 0.1; 0.3; 0.3; 1.3; 1.7; 2.1; 2.6; 3.9; 3.9; ...
        5.1; 5.6; 6.2; 6.4; 7.7; 8.1; 8.2; 8.9; 9.0; 9.5; ...
        9.6; 10.2; 10.3; 10.8; 11.2; 11.2; 11.2; 11.7; 12.1; 12.3; ...
```

```
12.3; 13.1; 13.2; 13.4; 13.7; 14.0; 14.3; 15.4; 16.1; 16.1; ...
16.4; 16.4; 16.7; 16.7; 17.5; 17.6; 18.1; 18.5; 19.3; 19.7;];
conc = [0.01; 0.08; 0.13; 0.16; 0.55; 0.90; 1.11; 1.62; 1.79; 1.59; ...
1.83; 1.68; 2.09; 2.17; 2.66; 2.08; 2.26; 1.65; 1.70; 2.39; ...
2.08; 2.02; 1.65; 1.96; 1.91; 1.30; 1.62; 1.57; 1.32; 1.56; ...
1.36; 1.05; 1.29; 1.32; 1.20; 1.10; 0.88; 0.63; 0.69; 0.69; ...
0.49; 0.53; 0.42; 0.48; 0.41; 0.27; 0.36; 0.33; 0.17; 0.20;];

f = fit(time,conc,"c*a*b*x^(b-1)*exp(-a*x^b)","StartPoint",[0.01 2 5])
plot(f,time,conc)
```

To define a custom model using `fittype`, use the form:

```
f = fittype(expr)
```

which constructs a custom model `fittype` object for the MATLAB expression contained in the character vector, string scalar, cell array, string array, or anonymous function `expr`.

See the `fittype` reference page for details on:

- Specifying dependent and independent variables, problem parameters, and coefficients using `fittype`.
- Specifying a cell array or string array of terms to use a linear fitting algorithm for your custom equation. If `expr` is a string or anonymous function, then the toolbox uses a nonlinear fitting algorithm.

For more details on linear fitting, see “Selecting Linear Fitting at the Command Line” on page 5-8.

- Examples of linear and nonlinear custom models.

For a step-by-step example, see “Custom Nonlinear Census Fitting” on page 5-20.

## Custom Linear Fitting

### In this section...

“About Custom Linear Models” on page 5-7

“Selecting a Linear Fitting Custom Fit Interactively” on page 5-7

“Selecting Linear Fitting at the Command Line” on page 5-8

“Fit Custom Linear Legendre Polynomials” on page 5-9

### About Custom Linear Models

In the Curve Fitter app, you can use the **Custom Equation** fit to define your own linear or nonlinear equations. The custom equation fit uses the nonlinear least-squares fitting procedure.

You can define a custom linear equation in **Custom Equation**, but the nonlinear fitting is less efficient and usually slower than linear least-squares fitting. If you need linear least-squares fitting for custom equations, select **Linear Fitting** instead. Linear models are linear combinations of (perhaps nonlinear) terms. They are defined by equations that are linear in the parameters.

---

**Tip** If you need linear least-squares fitting for custom equations, choose **Linear Fitting**. If you don't know if your equation can be expressed as a set of linear functions, then choose **Custom Equation** instead. See “Selecting a Custom Equation Fit Interactively” on page 5-2.

---


### Selecting a Linear Fitting Custom Fit Interactively

- 1 In the Curve Fitter app, select some curve data. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select **X data** and **Y data** values.

Curve Fitter creates a default polynomial fit.

- 2 Change the model type. On the **Curve Fitter** tab, in the **Fit Type** section, click the arrow to open the gallery. In the gallery, click **Linear Fitting** in the **Custom** group.

In the **Fit Options** pane, an example equation appears when you click **Linear Fitting**.



- 3 You can change  $x$  and  $y$  to any valid variable names.
- 4 The lower box displays the example equation. Change the **Coefficients** and **Terms** entries to change the example terms and define your own equation.

For an example, see “Fit Custom Linear Legendre Polynomials in Curve Fitter App” on page 5-9.

## Selecting Linear Fitting at the Command Line

To use a linear fitting algorithm, specify a cell array or string array of model terms as an input to the `fit` or `fittype` functions. Do not include coefficients in the expressions for the terms. If there is a constant term, use '1' as the corresponding expression in the array.

To specify a linear model of the following form:

$$\text{coeff1} * \text{term1} + \text{coeff2} * \text{term2} + \text{coeff3} * \text{term3} + \dots$$

where no coefficient appears within any of `term1`, `term2`, etc., use a cell array or string array where each term, without coefficients, is specified as a separate element. For example:

```
LinearModelTerms = {'term1', 'term2', 'term3', ... }
```

- 1 Identify the linear model terms you need to input to `fittype`. For example, the model

$$a * \log(x) + b * x + c$$

is linear in  $a$ ,  $b$ , and  $c$ . It has three terms  $\log(x)$ ,  $x$ , and 1 (because  $c=c*1$ ). To specify this model you use these terms: `LinearModelTerms = {'log(x)', 'x', '1'}`.

- 2 Use the cell array or string array of linear model terms as the input to the `fittype` function:



```
linearfittype = fittype({'log(x)', 'x', '1'})
linearfittype =
    Linear model:
    linearfittype(a,b,c,x) = a*log(x) + b*x + c
```

- 3 Load some data and use the `fittype` as an input to the `fit` function.

```
load census
f = fit(cdate, pop, linearfittype)

f =
    Linear model:
    f(x) = a*log(x) + b*x + c
    Coefficients (with 95% confidence bounds):
    a = -4.663e+04 (-4.973e+04, -4.352e+04)
    b = 25.9 (24.26, 27.55)
    c = 3.029e+05 (2.826e+05, 3.232e+05)
```

Alternatively, you can specify the cell array or string array of linear model terms as an input to the `fit` function:

```
f = fit(x,z,{'log(x)', 'x', '1'})
```

- 4 Plot the fit and data.

```
plot(f, cdate, pop)
```


For an example, see “Fit Custom Linear Legendre Polynomials at the Command Line” on page 5-18.

## Fit Custom Linear Legendre Polynomials

### Fit Custom Linear Legendre Polynomials in Curve Fitter App

This example shows how to fit data using several custom linear equations. The data is generated, and is based on the nuclear reaction  $^{12}\text{C}(e, e'\alpha)^8\text{Be}$ . The equations use sums of Legendre polynomial terms.

Consider an experiment in which 124 MeV electrons are scattered from  $^{12}\text{C}$  nuclei. In the subsequent reaction, alpha particles are emitted and produce the residual nuclei  $^8\text{Be}$ . By analyzing the number of alpha particles emitted as a function of angle, you can deduce certain information regarding the nuclear dynamics of  $^{12}\text{C}$ . The reaction kinematics are shown next.



$e$  is the incident electron.

$^{12}\text{C}$  is the carbon target.

$q$  is the momentum transferred to  $^8\text{Be}$ .

$e'$  is the scattered electron.

$\alpha$  is the emitted alpha particle.

$\theta_{e'}$  is the electron scattering angle.

$\theta_{\alpha}$  is the alpha scattering angle.

The data is collected by placing solid state detectors at values of  $\Theta_\alpha$  ranging from  $10^\circ$  to  $240^\circ$  in  $10^\circ$  increments.

It is sometimes useful to describe a variable expressed as a function of angle in terms of Legendre polynomials

$$y(x) = \sum_{n=0}^{\infty} a_n P_n(x)$$

where  $P_n(x)$  is a Legendre polynomial of degree  $n$ ,  $x$  is  $\cos(\Theta_\alpha)$ , and  $a_n$  are the coefficients of the fit. For information about generating Legendre polynomials, see the [Legendre function](#).

For the alpha-emission data, you can directly associate the coefficients with the nuclear dynamics by invoking a theoretical model. Additionally, the theoretical model introduces constraints for the infinite sum shown above. In particular, by considering the angular momentum of the reaction, a fourth-degree Legendre polynomial using only even terms should describe the data effectively.

You can generate Legendre polynomials with Rodrigues' formula:

$$P_n(x) = \frac{1}{2^n n!} \left( \frac{d}{dx} \right)^n (x^2 - 1)^n$$

### Legendre Polynomials Up to Fourth Degree

| n | $P_n(x)$                   |
|---|----------------------------|
| 0 | 1                          |
| 1 | x                          |
| 2 | $(1/2)(3x^2 - 1)$          |
| 3 | $(1/2)(5x^3 - 3x)$         |
| 4 | $(1/8)(35x^4 - 30x^2 + 3)$ |

This example shows how to fit the data using a fourth-degree Legendre polynomial with only even terms:

$$y_1(x) = a_0 + a_2 \left( \frac{1}{2} \right) (3x^2 - 1) + a_4 \left( \frac{1}{8} \right) (35x^4 - 30x^2 + 3)$$

- 1 Load the  $^{12}\text{C}$  alpha-emission data.

```
load carbon12alpha
```

The workspace now contains two new variables:


- `angle` is a vector of angles (in radians) ranging from  $10^\circ$  to  $240^\circ$  in  $10^\circ$  increments.
- `counts` is a vector of raw alpha particle counts that correspond to the emission angles in `angle`.

- 2 Open the Curve Fitter app.

```
curveFitter
```

- 3 In the Curve Fitter app, on the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select `angle` and `counts` as the **X data** and **Y data** values, respectively, to create a default polynomial fit to the two variables.

- 4 Change the fit type to a default custom linear fit. On the **Curve Fitter** tab, in the **Fit Type** section, click the arrow to open the gallery. In the gallery, click **Linear Fitting** in the **Custom** group.



Use **Linear Fitting** instead of the **Custom Equation** fit type because the Legendre polynomials depend only on the predictor variable and constants. The equation you will specify for the model is  $y_1(x)$  (that is, the equation given at the beginning of this procedure). Because **angle** is given in radians, the argument of the Legendre terms is given by  $\cos(\Theta_\alpha)$ .

- 5 In the **Fit Options** pane, change the equation terms.
- Change the **Coefficients** names to **a2**, **a4**, and **a0**.
  - Change the **Terms** value for **a2** to the following:

$$(1/2)*(3*\cos(x)^2-1)$$

The Curve Fitter app updates the fit as you edit the terms.

- Change the **Terms** value for **a4** to the following:

$$(1/8)*(35*\cos(x)^4-30*\cos(x)^2+3)$$

**Fit Options**

**Linear Fitting**

y = f( x )

$a2*((1/2)*(3*\cos(x)^2-1))+a4*((1/8)*(35*\cos(x)^4-30*\cos(x)^2+3))+a0*(1)$

=


| Coefficients | Terms                                   |   |   |
|--------------|-----------------------------------------|---|---|
| a2           | * ( (1/2)*(3*cos(x)^2-1) )              | - | + |
| a4           | * ( (1/8)*(35*cos(x)^4-30*cos(x)^2+3) ) | - | + |
| a0           | * ( 1 )                                 | - | + |

► **Advanced Options**


[Read about fit options](#)

The fit appears in the Curve Fitter app.

- In the **Table Of Fits** pane, double-click the **Fit name** value and change it to Leg4Even.




- 7 Display the residuals. On the **Curve Fitter** tab, in the **Visualization** section, click **Residuals Plot**.



The fit appears to follow the trend of the data well, while the residuals appear to be randomly distributed and do not exhibit any systematic behavior.

- 8 Examine the numerical fit results in the **Results** pane. Look at each coefficient value and its confidence bounds in parentheses. The 95% confidence bounds indicate that the coefficients associated with  $a_0(x)$  and  $a_4(x)$  are known fairly accurately, but that the  $a_2(x)$  coefficient has a relatively large uncertainty.

▼ Results

Fit Name: Leg4Even 

**Custom Linear Curve Fit**

$$f(x) = a_2 * ((1/2) * (3 * \cos(x)^2 - 1)) + a_4 * ((1/8) * (35 * \cos(x)^4 - 30 * \cos(x)^2 + 3)) + a_0$$

**Coefficients and 95% Confidence Bounds**

|    | Value    | Lower    | Upper    |
|----|----------|----------|----------|
| a2 | 23.8626  | 4.4365   | 43.2886  |
| a4 | 201.8882 | 180.1734 | 223.6029 |
| a0 | 102.8745 | 93.2133  | 112.5357 |

**Goodness of Fit**

|          | Value      |
|----------|------------|
| SSE      | 7.9681e+03 |
| R-square | 0.9668     |
| DFE      | 21         |
| Adj R-sq | 0.9637     |
| RMSE     | 19.4790    |

- 9 To confirm the theoretical argument that the alpha-emission data is best described by a fourth-degree Legendre polynomial with only even terms, next fit the data using both even and odd terms:

$$y_2(x) = y_1(x) + a_1x + a_3\left(\frac{1}{2}\right)(5x^3 - 3x)$$

First, make a copy of the Legendre polynomial fit to modify. On the **Curve Fitter** tab, in the **File** section, click **Duplicate**. The duplicated fit appears in a new tab in the **Fits** pane.

- 10 In the **Table Of Fits** pane, rename the new fit to Leg4EvenOdd.
- 11 In the **Fit Options** pane, change the equation terms.

Edit the terms as follows to fit the model given by  $y_2(x)$ :

- a Click the last + button twice, to add the odd Legendre terms.
- b Change the new coefficient names to **a1** and **a3**.
- c Change the **Terms** value for **a1** to the following:

$$\cos(x)$$

- d Change the **Terms** value for **a3** to the following:

$$(1/2) * (5 * \cos(x)^3 - 3 * \cos(x))$$

**Fit Options**

**Linear Fitting**

y = f( x )

$$a2*((1/2)*(3*\cos(x)^2-1))+a4*((1/8)*(35*\cos(x)^4-30*\cos(x)^2+3))+a0*(1)+a1*(\cos(x))+a3*((1/2)*(5*\cos(x)^3-3*\cos(x)))$$

=

| Coefficients | Terms                                  |   |   |
|--------------|----------------------------------------|---|---|
| a2           | *( (1/2)*(3*cos(x)^2-1) )              | - | + |
| a4           | *( (1/8)*(35*cos(x)^4-30*cos(x)^2+3) ) | - | + |
| a0           | *( 1 )                                 | - | + |
| a1           | *( cos(x) )                            | - | + |
| a3           | *( (1/2)*(5*cos(x)^3-3*cos(x)) )       | - | + |

▶ **Advanced Options**

[Read about fit options](#)

- 12 Observe the new fit plotted in the Curve Fitter app, and examine the numerical results in the **Results** pane.



▼ Results

Fit Name: Leg4EvenOdd

Custom Linear Curve Fit

$$f(x) = a_2 \left( \frac{1}{2} (3 \cos(x)^2 - 1) \right) + a_4 \left( \frac{1}{8} (35 \cos(x)^4 - 30 \cos(x)^2 + 3) \right) + a_0 + a_1 \cos(x) + a_3 \left( \frac{1}{2} (5 \cos(x)^3 - 3 \cos(x)) \right)$$

Coefficients and 95% Confidence Bounds


|    | Value    | Lower    | Upper    |
|----|----------|----------|----------|
| a2 | 24.1933  | 3.2914   | 45.0952  |
| a4 | 201.5304 | 177.5797 | 225.4810 |
| a0 | 103.1450 | 92.7129  | 113.5771 |
| a1 | 1.8365   | -12.8882 | 16.5612  |
| a3 | -1.2102  | -22.5199 | 20.0995  |

Goodness of Fit


|          | Value      |
|----------|------------|
| SSE      | 7.9396e+03 |
| R-square | 0.9669     |
| DFE      | 19         |
| Adj R-sq | 0.9600     |
| RMSE     | 20.4419    |

Note that the odd Legendre coefficients (a1 and a3) are likely candidates for removal to simplify the fit because their values are small and their confidence bounds contain zero. These results indicate that the odd Legendre terms do not contribute significantly to the fit, and the even Legendre terms are essentially unchanged from the previous fit. This confirms that the initial model choice in the Leg4Even fit is the best one.

- Compare the fits side by side. Click the Document Actions button located to the far right of the fit figure tabs. Select the Tile All option and specify a 1-by-2 layout.



You can display only the plots by dragging and hiding the **Fit Options**, **Results**, and **Table Of Fits** panes.



### Fit Custom Linear Legendre Polynomials at the Command Line

Fit the same model at the command line that you created in the Curve Fitter app.

- 1 To use a linear fitting algorithm, specify a cell array or string array of model terms as an input to the `fittype` function. Use the same **Terms** you entered in the Curve Fitter app for the `Leg4Even` fit, and do not specify any coefficients.

```
linearft = fittype({'(1/2)*(3*cos(x)^2-1)', ...
                  '(1/8)*(35*cos(x)^4-30*cos(x)^2+3)', '1'})
```

```
linearft =
```

```
Linear model:
linearft(a,b,c,x) = a*((1/2)*(3*cos(x)^2-1))...
+ b*((1/8)*(35*cos(x)^4-30*cos(x)^2+3)) + c
```

- 2 Load the `angle` and `counts` variables in the workspace.

```
load carbon12alpha
```

- 3 Use the `fittype` as an input to the `fit` function, and specify the `angle` and `counts` variables in the workspace.

```
f = fit(angle,counts,linearft)
```

```
f =
```

```
Linear model:
f(x) = a*((1/2)*(3*cos(x)^2-1))...
```

```
+ b*((1/8)*(35*cos(x)^4-30*cos(x)^2+3)) + c
Coefficients (with 95% confidence bounds):
a =      23.86 (4.436, 43.29)
b =     201.9 (180.2, 223.6)
c =     102.9 (93.21, 112.5)
```

**4** Plot the fit and data.

```
plot(f,angle,counts)
```


For more details on linear model terms, see the `fittype` function.

## Custom Nonlinear Census Fitting

This example shows how to fit a custom equation to census data, specifying bounds, coefficients, and a problem-dependent parameter.

Load and plot the data in census.mat:

```
load census
plot(cdate,pop,'o')
hold on
```



Create a fit options structure and a fitype object for the custom nonlinear model  $y = a(x-b)^n$ , where  $a$  and  $b$  are coefficients and  $n$  is a problem-dependent parameter. See the fitype function page for more details on problem-dependent parameters.

```
s = fitoptions('Method','NonlinearLeastSquares',...
              'Lower',[0,0],...
              'Upper',[Inf,max(cdate)],...
              'Startpoint',[1 1]);
f = fitype('a*(x-b)^n','problem','n','options',s);
```

Fit the data using the fit options and a value of  $n = 2$ :

```
[c2,gof2] = fit(cdate,pop,f,'problem',2)
```

```
c2 =
    General model:
```

```
c2(x) = a*(x-b)^n
Coefficients (with 95% confidence bounds):
  a = 0.006092 (0.005743, 0.006441)
  b = 1789 (1784, 1793)
Problem parameters:
  n = 2
```

```
gof2 = struct with fields:
  sse: 246.1543
  rsquare: 0.9980
  dfe: 19
  adjrsquare: 0.9979
  rmse: 3.5994
```

Fit the data using the fit options and a value of  $n = 3$ :


```
[c3,gof3] = fit(cdate,pop,f,'problem',3)
```

```
c3 =
General model:
c3(x) = a*(x-b)^n
Coefficients (with 95% confidence bounds):
  a = 1.359e-05 (1.245e-05, 1.474e-05)
  b = 1725 (1718, 1731)
Problem parameters:
  n = 3
```

```
gof3 = struct with fields:
  sse: 232.0058
  rsquare: 0.9981
  dfe: 19
  adjrsquare: 0.9980
  rmse: 3.4944
```

Plot the fit results and the data:

```
plot(c2,'m')
plot(c3,'c')
legend('data','fit with n=2','fit with n=3')
```



## Custom Nonlinear ENSO Data Analysis

This example fits the ENSO data using several custom nonlinear equations. The ENSO data consists of monthly averaged atmospheric pressure differences between Easter Island and Darwin, Australia. This difference drives the trade winds in the southern hemisphere.

The ENSO data is clearly periodic, which suggests it can be described by a Fourier series:

$$y(x) = a_0 + \sum_{i=1}^{\infty} a_i \cos\left(2\pi \frac{x}{c_i}\right) + b_i \sin\left(2\pi \frac{x}{c_i}\right)$$

where  $a_i$  and  $b_i$  are the amplitudes, and  $c_i$  are the periods (cycles) of the data. Determine how many cycles exist.

As a first attempt, assume a single cycle and fit the data using one cosine term and one sine term.

$$y_1(x) = a_0 + a_1 \cos\left(2\pi \frac{x}{c_1}\right) + b_1 \sin\left(2\pi \frac{x}{c_1}\right)$$

If the fit does not describe the data well, add additional cosine and sine terms with unique period coefficients until a good fit is obtained.

The equation is nonlinear because an unknown coefficient  $c_1$  is included as part of the trigonometric function arguments.

### Load Data and Fit Library and Custom Fourier Models


- 1 Load the data and open the Curve Fitter app.

```
load enso
curveFitter
```

- 2 The app includes the Fourier series as a nonlinear library equation. However, the library equation does not meet the needs of this example because its terms are defined as fixed multiples of the fundamental frequency  $w$ . Refer to “Fit Fourier Models” on page 4-37 for more information. Create the built-in library Fourier fit to compare with your custom equations:

- a In the app, on the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select **month** as the **X data** value and **pressure** as the **Y data** value.
- b On the **Curve Fitter** tab, in the **Fit Type** section, click the arrow to open the gallery. In the fit gallery, click **Fourier** in the **Regression Models** group.
- c In the **Table Of Fits** pane, double-click the **Fit name** value and enter **Fourier**.
- d In the **Fit Options** pane, change the number of terms to **8**.

Observe the library model fit. In the next steps, you will create custom equations to compare.



- 3 Duplicate your fit. Right-click your fit in the **Table Of Fits** pane and select **Duplicate "Fourier"**.
- 4 Name the new fit **Enso1Period**.
- 5 On the **Curve Fitter** tab, in the **Fit Type** section, open the fit type gallery and click **Custom Equation** in the **Custom** group.
- 6 In the **Fit Options** pane, replace the example text in the equation edit box with the following:

$$a0 + a1*\cos(2*\pi*x/c1) + b1*\sin(2*\pi*x/c1)$$



▼ Fit Options
⊙

✚
Custom Equation


$y = f(x)$

$$a_0 + a_1 \cos(2\pi x / c_1) + b_1 \sin(2\pi x / c_1)$$

▶ Advanced Options
[Read about fit options](#)

The app applies the fit to the enso data.

The graphical and numerical results shown here indicate that the fit does not describe the data well. In particular, the fitted value for  $c_1$  is unreasonably small. Your initial fit results might differ from these results because the starting points are randomly selected.



**Results**

Fit Name: Enso1Period

**Custom Curve Fit**  
 $f(x) = a_0 + a_1 \cos(2\pi x/c_1) + b_1 \sin(2\pi x/c_1)$

**Coefficients and 95% Confidence Bounds**

|    | Value   | Lower   | Upper   |
|----|---------|---------|---------|
| a0 | 10.6378 | 10.1116 | 11.1640 |
| a1 | -0.0342 | -1.5305 | 1.4621  |
| b1 | 0.2892  | -0.4678 | 1.0462  |
| c1 | 0.0497  | 0.0496  | 0.0497  |

**Goodness of Fit**

|          | Value      |
|----------|------------|
| SSE      | 1.9559e+03 |
| R-square | 0.0036     |
| DFE      | 164        |
| Adj R-sq | -0.0146    |
| RMSE     | 3.4534     |

By default, the coefficients are unbounded and have random starting values from 0 to 1. The data include a periodic component with a period of about 12 months. However, with  $c_1$  unconstrained and with a random starting point, this fit failed to find that cycle.

### Use Fit Options to Constrain a Coefficient

- 1 To assist the fitting procedure, constrain  $c_1$  to a value from 10 to 14. In the **Fit Options** pane, click **Advanced Options** to expand the section and view the constraints for the coefficients. Observe that by default the coefficients are unbounded (bounds of  $-\infty$  and  $\infty$ ).
- 2 In the **Coefficient Constraints** table, change the **Lower** and **Upper** bounds for  $c_1$  to constrain the cycle from 10 to 14 months, as shown next.

**Fit Options**

**Advanced Options**

Method: NonlinearLeastSquares

Robust: Off

Algorithm: Trust-Region

DiffMinChange: 1e-08

DiffMaxChange: 0.1

MaxFunEvals: 600

MaxIter: 400

TolFun: 1e-06

TolX: 1e-06


**Coefficient Constraints**

| Coefficients | StartPoint | Lower | Upper |
|--------------|------------|-------|-------|
| a0           | 0.1839     | -Inf  | Inf   |
| a1           | 0.2400     | -Inf  | Inf   |
| b1           | 0.4173     | -Inf  | Inf   |
| c1           | 0.0497     | 10    | 14    |

[Read about fit options](#)

The Curve Fitter app updates the fit.

- 3 Observe the new fit and the residuals plot. If necessary, click **Residuals Plot** in the **Visualization** section of the **Curve Fitter** tab.



The fit appears to be reasonable for some data points but clearly does not describe the entire data set very well. As predicted, the numerical results in the **Results** pane ( $c_1=11.94$ ) indicate a cycle of approximately 12 months. However, the residuals show a systematic periodic distribution, indicating that at least one more cycle exists. There are additional cycles that you should include in the fit equation.

## Create Second Custom Fit with Additional Terms and Constraints

To refine your fit, you need to add an additional sine and cosine term to  $y_1(x)$  as follows:

$$y_2(x) = y_1(x) + a_2 \cos\left(2\pi \frac{x}{c_2}\right) + b_2 \sin\left(2\pi \frac{x}{c_2}\right)$$

and constrain the upper and lower bounds of  $c_2$  to be roughly twice the bounds used for  $c_1$ .


- 1 Duplicate your fit by right-clicking it in the **Table Of Fits** pane and selecting **Duplicate "Enso1Period"**.
- 2 Name the new fit Enso2Period.
- 3 In the **Fit Options** pane, add two terms to the end of the previous equation so that the equation box displays the following terms:

$$a_0 + a_1 \cos(2\pi x/c_1) + b_1 \sin(2\pi x/c_1) + a_2 \cos(2\pi x/c_2) + b_2 \sin(2\pi x/c_2)$$

- 4 Click **Advanced Options** to expand the section. In the **Coefficient Constraints** table, observe the **Lower** and **Upper** bounds for  $c_1$ , which constrain the cycle from 10 to 14 months. Add more coefficient constraints.
  - a Change the **Lower** and **Upper** bounds for  $c_2$  to be roughly twice the bounds used for  $c_1$  ( $20 < c_2 < 30$ ).

- b** Change the **StartPoint** value for  $a_0$  to 5.

As you change each setting, the Curve Fitter app updates the fit. You can observe the fit plot and the residuals plot.



The fit appears reasonable for most data points. However, the residuals indicate that you should include another cycle to the fit equation.

## Create a Third Custom Fit with Additional Terms and Constraints

As a third attempt, add an additional sine and cosine term to  $y_2(x)$

$$y_3(x) = y_2(x) + a_3 \cos\left(2\pi \frac{x}{c_3}\right) + b_3 \sin\left(2\pi \frac{x}{c_3}\right)$$

and constrain the lower bound of  $c_3$  to be roughly triple the value of  $c_1$ .

- 1 Duplicate your fit by right-clicking it in the **Table Of Fits** pane and selecting **Duplicate "Enso2Period"**.
- 2 Name the new fit **Enso3Period**.
- 3 In the **Fit Options** pane, add two terms to the end of the previous equation so that the equation box displays the following terms:

$$a_0 + a_1 \cos(2\pi x/c_1) + b_1 \sin(2\pi x/c_1) + a_2 \cos(2\pi x/c_2) + b_2 \sin(2\pi x/c_2) + a_3 \cos(2\pi x/c_3) + b_3 \sin(2\pi x/c_3)$$

- 4 Click **Advanced Options** to expand the section. Observe that your previous fit options are still present.
- 5 In the **Coefficient Constraints** table, change the **Lower** bound for  $c_3$  to 36, which is roughly triple the value of  $c_1$ .

**Fit Options**

▼ **Advanced Options**

Method: NonlinearLeastSquares

Robust: Off

Algorithm: Trust-Region

DiffMinChange: 1e-08

DiffMaxChange: 0.1

MaxFunEvals: 600

MaxIter: 400

TolFun: 1e-06


ToX: 1e-06

**Coefficient Constraints**

| Coefficients | StartPoint | Lower | Upper |
|--------------|------------|-------|-------|
| a0           | 0.3097     | -Inf  | Inf   |
| b1           | 0.4173     | -Inf  | Inf   |
| b2           | 0.3377     | -Inf  | Inf   |
| b3           | 0.2417     | -Inf  | Inf   |
| c1           | 0.0497     | 10    | 14    |
| c2           | 0.9001     | 20    | 30    |
| c3           | 0.4039     | 36    | Inf   |

[Read about fit options](#)

As you change each setting, the Curve Fitter app updates the fit. You can observe the fit plot and the residuals plot.



The fit is an improvement over the previous two fits, and appears to account for most of the cycles in the ENSO data set. The residuals appear random for most of the data, although a pattern is still visible indicating that additional cycles might be present, or you can improve the fitted amplitudes.

In conclusion, Fourier analysis of the data reveals three significant cycles. The annual cycle is the strongest, but cycles with periods of approximately 44 and 22 months are also present. These cycles correspond to El Niño and the Southern Oscillation (ENSO).

## Gaussian Fitting with an Exponential Background

This example fits two poorly resolved Gaussian peaks on a decaying exponential background using a general (nonlinear) custom model.

Fit the data using this equation

$$y(x) = ae^{-bx} + a_1e^{-\left(\frac{x-b_1}{c_1}\right)^2} + a_2e^{-\left(\frac{x-b_2}{c_2}\right)^2}$$

where  $a_i$  are the peak amplitudes,  $b_i$  are the peak centroids, and  $c_i$  are related to the peak widths. Because unknown coefficients are part of the exponential function arguments, the equation is nonlinear.

- 1 Load the data and open the Curve Fitter app.

```
load gauss3
curveFitter
```

The workspace contains two new variables:

- `xpeak` is a vector of predictor values.
- `ypeak` is a vector of response values.

- 2 In the Curve Fitter app, on the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select `xpeak` as the **X data** value and `ypeak` as the **Y data** value. Enter `Gauss2exp1` as the **Fit name** value.
- 3 On the **Curve Fitter** tab, in the **Fit Type** section, click the arrow to open the gallery. In the fit gallery, click **Custom Equation** in the **Custom** group.
- 4 In the **Fit Options** pane, replace the example text in the equation edit box with these terms:

```
a*exp(-b*x) + a1*exp(-((x-b1)/c1)^2) + a2*exp(-((x-b2)/c2)^2)
```

The fit is poor (or incomplete) at this point because the starting points are randomly selected and no coefficients have bounds.

- 5 Specify reasonable coefficient starting points and constraints. Deducing the starting points is particularly easy for the current model because the Gaussian coefficients have a straightforward interpretation and the exponential background is well defined. Additionally, as the peak amplitudes and widths cannot be negative, constrain  $a_1$ ,  $a_2$ ,  $c_1$ , and  $c_2$  to be greater than 0.
  - a In the **Fit Options** pane, click **Advanced Options**.
  - b In the **Coefficient Constraints** table, change the **Lower** bound for  $a_1$ ,  $a_2$ ,  $c_1$ , and  $c_2$  to 0, as the peak amplitudes and widths cannot be negative.
  - c Enter the **StartPoint** values as shown for the specified coefficients.

| Coefficients | Start Point |
|--------------|-------------|
| a            | 100         |
| a1           | 100         |
| a2           | 80          |
| b            | 0.1         |



| Coefficients | Start Point |
|--------------|-------------|
| b1           | 110         |
| b2           | 140         |
| c1           | 20          |
| c2           | 20          |

▼ Fit Options
⌵

▼ **Advanced Options**

Method: NonlinearLeastSquares

Robust:

Algorithm:

DiffMinChange:

DiffMaxChange:

MaxFunEvals:

MaxIter:

TolFun:

TolX:


**Coefficient Constraints**

| Coefficients | StartPoint | Lower | Upper |
|--------------|------------|-------|-------|
| a            | 100.0000   | -Inf  | Inf   |
| a1           | 100.0000   | 0     | Inf   |
| a2           | 80.0000    | 0     | Inf   |
| b            | 0.1000     | -Inf  | Inf   |
| b1           | 110.0000   | -Inf  | Inf   |
| b2           | 140.0000   | -Inf  | Inf   |
| c1           | 20.0000    | 0     | Inf   |
| c2           | 20.0000    | 0     | Inf   |

[Read about fit options](#)

As you change the fit options, the Curve Fitter app updates the fit.

- 6 Observe the fit and residuals plots. To create a residuals plot, click **Residuals Plot** in the **Visualization** section of the **Curve Fitter** tab.



## Surface Fitting to Biopharmaceutical Data

Curve Fitting Toolbox software provides some example data for an anesthesia drug interaction study. You can use the Curve Fitter app to fit response surfaces to this data to analyze drug interaction effects. Response surface models provide a good method for understanding the pharmacodynamic interaction behavior of drug combinations. This data is based on the results in [1].

Anesthesia is typically at least a two-drug process, consisting of an opioid and a sedative hypnotic. This example uses Propofol and Remifentanyl as drug class prototypes. Their interaction is measured by four different measures of the analgesic and sedative response to the drug combination. Algometry, Tetany, Sedation, and Laryngoscopy comprise the four measures of surrogate drug effects at various concentration combinations of Propofol and Remifentanyl.

To interactively create response surfaces for this drug combination:

- 1 Use the Current Folder browser to locate and view the folder `matlab\toolbox\curvefit\curvefit`.
- 2 Right-click the file `OpioidHypnoticSynergy.txt`, and select **Import Data**. The Import Tool appears.
  - a On the **Import** tab, in the **Delimiters** section, leave the default **Column delimiters** value as Tab.
 

Review the six variables selected for import: Propofol, Remifentanyl, Algometry, Tetany, Sedation, and Laryngoscopy.
  - b In the **Import** section, click **Import Selection** and select **Import Data** to import the dose-response data into the MATLAB workspace. Close the Import Tool.

Alternatively, you can import the data programmatically. Enter the following code to read the dose-response data from the file into the MATLAB workspace.


```
data = importdata("OpioidHypnoticSynergy.txt");
OpioidHypnoticSynergy = array2table(data.data, ...
    "VariableNames",data.textdata);
```

- 3 To create response surfaces, you must select two drugs as x and y inputs, and one of the four effects as the z output. After you load the variables into your workspace, you open the Curve Fitter app and then select variables interactively. Alternatively, you can specify the initial fit variables when using the `curveFitter` function.


For this example, open the Curve Fitter app.

```
curveFitter
```

- 4 In the Curve Fitter app, on the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, first select the `OpioidHypnoticSynergy` table from the **X data**, **Y data**, and **Z data** drop-down lists. Then select the `Propofol`, `Remifentanyl`, and `Algometry` variables from the new drop-down lists.



The app creates a new response surface for the **Algometry** data. The default fit is an interpolating surface that passes through the data points.



- 5 Create a copy of the current surface fit by either:
  - a Selecting the **Duplicate** button in the **File** section of the **Curve Fitter** tab.
  - b Right-clicking a fit in the **Table Of Fits** pane, and selecting **Duplicate "untitled fit 1"**.

- 6 Define your own equation to fit the data. On the **Curve Fitter** tab, in the **Fit Type** section, click the arrow to open the gallery. In the gallery, click **Custom Equation** in the **Custom** group.
- 7 In the **Fit Options** pane, select and delete the example custom equation text in the edit box.

You can use the custom equation edit box to enter MATLAB code to define your model. The equation that defines the model must depend on the data variables  $x$  and  $y$  and a list of fixed parameters, estimable parameters, or both.

The model from the paper is:

$$E = \frac{E_{\max} \cdot \left( \frac{C_A}{IC50_A} + \frac{C_B}{IC50_B} + \alpha \cdot \frac{C_A}{IC50_A} \cdot \frac{C_B}{IC50_B} \right)^n}{1 + \left( \frac{C_A}{IC50_A} + \frac{C_B}{IC50_B} + \alpha \cdot \frac{C_A}{IC50_A} \cdot \frac{C_B}{IC50_B} \right)^n}$$

where  $C_A$  and  $C_B$  are the drug concentrations, and  $IC50_A$ ,  $IC50_B$ ,  $\alpha$ , and  $n$  are the coefficients to be estimated.

You can define this in MATLAB code as:


```
Effect = Emax*(CA/IC50A + CB/IC50B + ...
    alpha*(CA/IC50A).*(CB/IC50B)).^n ./ ...
    (1 + (CA/IC50A + CB/IC50B + ...
    alpha*(CA/IC50A ).*(CB/IC50B)).^n);
```

Telling the app which variables to fit and which parameters to estimate requires rewriting the variable names  $CA$  and  $CB$  as  $x$ , and  $y$ . You must include  $x$  and  $y$  when you enter a custom equation in the edit box. Assume  $E_{\max} = 1$  because the effect output is normalized.

- 8 Enter the following text in the custom equation edit box.

```
(x/IC50A + y/IC50B + alpha*(x/IC50A).*(y/IC50B)).^n ./
(1 + (x/IC50A + y/IC50B + alpha*(x/IC50A).*(y/IC50B)).^n)
```

The Curve Fitter app fits a surface to the data using the custom equation model.



- 9 In the **Fit Options** pane, change some of the fit options. Click **Advanced Options** to expand the section.
- Set the **Robust** value to LAR.
  - In the **Coefficient Constraints** table, for the **alpha** coefficient, set the **StartPoint** value to 1 and the **Lower** bound to  $-5$ .

Fit Options
⌵

**Custom Equation**

$$z = f(x, y)$$

$$= \frac{(x/IC50A + y/IC50B + \alpha \cdot (x/IC50A) \cdot (y/IC50B))^n}{(1 + (x/IC50A + y/IC50B + \alpha \cdot (x/IC50A) \cdot (y/IC50B))^n)}$$

**Advanced Options**

Method: NonlinearLeastSquares

Robust: LAR

Algorithm: Trust-Region

DiffMinChange: 1e-8

DiffMaxChange: 0.1

MaxFunEvals: 600

MaxIter: 400

TolFun: 1e-6

TolX: 1e-6

**Coefficient Constraints**

| Coefficients | StartPoint | Lower | Upper |
|--------------|------------|-------|-------|
| IC50A        | 0.1112     | -Inf  | Inf   |
| IC50B        | 0.7803     | -Inf  | Inf   |
| alpha        | 1.0000     | -5    | Inf   |
| n            | 0.2417     | -Inf  | Inf   |


[Read about fit options](#)

The app updates the fit with your new options.

**10** Review the **Results** pane. View any of these results:

- The model equation
- The values of the estimated coefficients
- The goodness-of-fit statistics

**11** Display the residuals plot to check the distribution of points relative to the surface. On the **Curve Fitter** tab, in the **Visualization** section, click **Residuals Plot**.



- 12** Generate code for the currently selected fit and its open plots in your Curve Fitter app session. On the **Curve Fitter** tab, in the **Export** section, click **Export** and select **Generate Code**.

The Curve Fitter app generates code from your session and displays the file in the MATLAB Editor. The file includes the fit selected in your current session and its open plots.

- 13** Save the file with the default name, `createFit.m`.
- 14** You can recreate your fit and its plots by calling the file from the command line with your original data or new data as input arguments.

In this case, because your original data still appears in the workspace, you can run the function with the original data variables.

```
[fitresult,gof] = createFit(OpioidHypnoticSynergy.Propofol, ...
    OpioidHypnoticSynergy.Remifentanil, ...
    OpioidHypnoticSynergy.Algometry)
```

The function creates a figure window for the fit you selected in your session. The custom fit figure shows both the surface and residuals plots that you created interactively in the Curve Fitter app.

- 15** Create a new fit to the Tetany response instead of Algometry.

```
[fitresult,gof] = createFit(OpioidHypnoticSynergy.Propofol, ...
    OpioidHypnoticSynergy.Remifentanil, ...
    OpioidHypnoticSynergy.Tetany)
```



You need to edit the file if you want the new response label on the plots. You can use the generated code as a starting point to change the surface fits and plots to meet your needs. For a list of methods you can use, see `sfit`.

To see how to programmatically fit surfaces to the same example problem, see “Surface Fitting with Custom Equations to Biopharmaceutical Data” on page 12-14.

## References

- [1] Kern, Steven E., Guoming Xie, Julia L. White, and Talmage D. Egan. “A Response Surface Analysis of Propofol-Remifentanyl Pharmacodynamic Interaction in Volunteers.” *Anesthesiology* 100, no. 6 (June 1, 2004): 1373-81. <https://doi.org/10.1097/00000542-200406000-00007>.



# Interpolation and Smoothing

---

- “Nonparametric Fitting” on page 6-2
- “Interpolation with Curve Fitting Toolbox” on page 6-3
- “Extrapolation for Interpolant Fit Types” on page 6-8
- “Smoothing Splines” on page 6-14
- “Lowess Smoothing” on page 6-22
- “Fit Smooth Surfaces to Investigate Fuel Efficiency” on page 6-26
- “Filtering and Smoothing Data” on page 6-34

## Nonparametric Fitting

In some cases, you are not concerned about extracting or interpreting fitted parameters. Instead, you might simply want to draw a smooth curve through your data. Fitting of this type is called *nonparametric fitting*. The Curve Fitting Toolbox software supports these nonparametric fitting methods:

- “Interpolation with Curve Fitting Toolbox” on page 6-3 — Estimate values that lie between known data points.
- “Smoothing Splines” on page 6-14 — Create a smooth curve through the data. You adjust the level of smoothness by varying a parameter that changes the curve from a least-squares straight-line approximation to a cubic spline interpolant.
- “Lowess Smoothing” on page 6-22 — Create a smooth surface through the data using locally weighted linear regression to smooth data.

For details about interpolation, see “Interpolation”.

You can also use smoothing techniques on response data. See “Filtering and Smoothing Data” on page 6-34.

To view all available model types, see “List of Library Models for Curve and Surface Fitting” on page 4-10.

### See Also

#### Related Examples

- “Selecting an Interpolant Fit” on page 6-4
- “Smoothing Splines” on page 6-14
- “Lowess Smoothing” on page 6-22
- “Filtering and Smoothing Data” on page 6-34

## Interpolation with Curve Fitting Toolbox

### In this section...

“About Interpolation Methods” on page 6-3

“Selecting an Interpolant Fit” on page 6-4

*Interpolation* is a process for estimating values that lie between known data points.

Interpolation involves creating of a function  $f$  that matches given data values  $y_i$  at given data sites  $x_i$  where  $f(x_i) = y_i$ , for all  $i$ .

Most interpolation methods create the interpolant  $f$  as the unique function of the formula

$$f(x) = \sum_j f_j(x) a_j,$$

where the form of the functions  $f_j$  depends on the interpolation method.

For spline interpolation, the  $f_j$  are the  $n$  consecutive B-splines  $B_j(x) = B(x|t_j, \dots, t_{j+k})$ ,  $j = 1:n$ , of order  $k$  for a knot sequence  $t_1 \leq t_2 \leq \dots \leq t_{n+k}$ .

### About Interpolation Methods


Curve Fitting Toolbox supports the interpolation methods described in the following table.

| Method                   | Description                                                                                                                                                          |
|--------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Linear                   | Linear interpolation. This method fits a different linear polynomial between each pair of data points for curves, or between sets of three points for surfaces.      |
| Nearest neighbor         | Nearest neighbor interpolation. This method sets the value of an interpolated point to the value of the nearest data point.                                          |
| Cubic spline             | Cubic spline interpolation. This method fits a different cubic polynomial between each pair of data points for curves, or between sets of three points for surfaces. |
| Shape-preserving (PCHIP) | Piecewise cubic Hermite interpolation (PCHIP). This method preserves monotonicity and the shape of the data (for curves only).                                       |
| Biharmonic (v4)          | MATLAB 4 <code>griddata</code> method. This method fits surfaces that also extrapolate well (for surfaces only).                                                     |
| Thin-plate spline        | Thin-plate spline interpolation. This method fits smooth surfaces that also extrapolate well (for surfaces only).                                                    |

Interpolant surface fits use the MATLAB function `scatteredInterpolant` for the linear and nearest neighbor methods, and the MATLAB function `griddata` for the cubic spline and biharmonic methods. The thin-plate spline method uses the `tpaps` function.

The interpolant method you use depends on several factors, including the characteristics of the data being fit, the required smoothness of the curve, speed considerations, and post-fit analysis requirements. The linear and nearest neighbor methods fit models efficiently, and the resulting curves are not very smooth. The cubic spline, shape-preserving, and biharmonic methods take longer to fit models, and the resulting curves are very smooth.

For example, the following plot shows a nearest neighbor interpolant fit and a shape-preserving (PCHIP) interpolant fit for the nuclear reaction data from the `carbon12alpha.mat` sample data set. The nearest neighbor interpolant is not as smooth as the shape-preserving interpolant.




---

**Note** Goodness-of-fit statistics, prediction bounds, and weights are not defined for interpolants. Additionally, the fit residuals are always 0 (within computer precision) because interpolants pass through the data points.

---

Biharmonic interpolant fits consist of radial basis function interpolants. All other interpolants supported by Curve Fitting Toolbox are *piecewise polynomials* and consist of multiple polynomials defined between data points. For cubic spline and PCHIP interpolation, four coefficients describe each piece. Curve Fitting Toolbox uses a cubic (third-degree) polynomial to calculate the four coefficients. Refer to the following for more information:

- `spline` for cubic spline interpolation
- `pchip` for shape-preserving (PCHIP) interpolation, and for a comparison of PCHIP and cubic spline interpolation
- `scatteredInterpolant`, `griddata`, and `tpaps` for surface interpolation

It is possible to fit a single polynomial interpolant to data, with a degree one less than the number of data points. However, the behavior of such fits is unpredictable between data points. Piecewise polynomials with lower-order segments do not diverge significantly from the fitting data domain, so they are useful for analyzing a wider range of data sets.

## Selecting an Interpolant Fit


- “Select Interpolant Fit Interactively” on page 6-5
- “Fit Linear Interpolant Model Using the fit Function” on page 6-5

## Select Interpolant Fit Interactively

Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.

On the **Curve Fitter** tab, in the **Fit Type** section, select an **Interpolant** fit. The app fits an interpolating curve or surface that passes through every data point.

In the **Fit Options** pane, you can specify the **Interpolation method** value.



For curve data, you can set **Interpolation method** to Linear, Nearest neighbor, Cubic Spline, or Shape-preserving (PCHIP). For surface data, you can set **Interpolation method** to Nearest neighbor, Linear, Cubic Spline, Biharmonic (v4), or Thin-plate spline.

For surfaces, the **Interpolant** fit uses the `scatteredInterpolant` function for the Linear and Nearest neighbor methods, the `griddata` function for the Cubic Spline and Biharmonic (v4) methods, and the `tpaps` function for the Thin-plate spline method. Try the Thin-plate spline method when you require both smooth surface interpolation and good extrapolation properties.

---

**Tip** If your data variables have very different scales, select and clear the **Center and scale** check box to see the difference in the fit. Normalizing the inputs can influence the results of the piecewise Linear and Cubic Spline interpolation, and Nearest neighbor surface interpolation methods.

---

## Fit Linear Interpolant Model Using the fit Function


Load the census sample data set.

```
load census
```

The variables `pop` and `cdate` contain data for the population size and the year the census was taken, respectively.

You can use the `fit` function to fit any of the interpolant models described in “Interpolant Model Names” on page 4-13. In this case, fit a linear interpolant model using the `'linearinterp'` option, and then plot the result.

```
f = fit(cdate,pop,'linearinterp');
plot(f,cdate,pop);
```



### Compare Linear Interpolant Models

Load the `carbon12alpha` sample data set. Create both nearest neighbor and PCHIP interpolant fits using the `'nearestinterp'` and `'pchip'` options.


```
load carbon12alpha
f1 = fit(angle,counts,'nearestinterp');
f2 = fit(angle,counts,'pchip');
```

Compare the fitted curves `f1` and `f2` by plotting them in the same figure.

```
p1 = plot(f1,angle,counts);
xlim([min(angle),max(angle)])
hold on

p2 = plot(f2,'b');
hold off
legend([p1;p2], 'Counts per Angle', 'Nearest Neighbor', 'PCHIP', ...
        'Location', 'northwest')
```





## See Also

### Apps

Curve Fitter

### Functions

fit

## Related Examples

- “Introducing Spline Fitting” on page 8-2
- “Extrapolation for Interpolant Fit Types” on page 6-8

## Extrapolation for Interpolant Fit Types

*Extrapolation* is a process for estimating dependent variable values for independent variable values outside of the fitting data domain. Many different methods perform extrapolation. Given fitting data  $X$  for the independent variables and  $Y$  for the dependent variable, an extrapolation method creates a function

$$y = f(X, Y, u),$$

where  $u$  is a vector of independent variable values outside of the basic interval, and  $y$  is the corresponding estimate for the dependent variable.

Curve Fitting Toolbox supports extrapolation for interpolant curve and surface fits. For more information about interpolation, see “Interpolation with Curve Fitting Toolbox” on page 6-3. The following table describes the supported extrapolation methods in Curve Fitting Toolbox.

| Extrapolation Method                                     | Description                                                                                                                                                                             | Supported Interpolation Methods                                                           |
|----------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------|
| None                                                     | No extrapolation                                                                                                                                                                        | Curve fits — PCHIP<br>Curve and surface fits — cubic spline, linear, and nearest neighbor |
| Linear                                                   | This method fits a linear polynomial at each data point on the boundary of the fitting data's convex hull. Each linear polynomial follows the gradient at the corresponding data point. | Surface fits — cubic spline and nearest neighbor<br>Curve and surface fits — linear       |
| Nearest neighbor                                         | This method evaluates to the value of the nearest point on the boundary of the fitting data's convex hull.                                                                              | Curve fits — PCHIP<br>Curve and surface fits — cubic spline, linear, and nearest neighbor |
| Thin-plate spline                                        | This method fits a thin-plate spline through the fitting data and extends it outside of the fitting data's convex hull.                                                                 | Surface fits — thin-plate spline                                                          |
| Biharmonic spline                                        | This method fits a biharmonic spline through the fitting data and extends it outside of the fitting data's convex hull.                                                                 | Surface fits — biharmonic (v4)                                                            |
| PCHIP (piecewise cubic Hermite interpolating polynomial) | This method fits a shape-preserving piecewise cubic hermite interpolating polynomial (PCHIP) through the fitting data and extends it outside of the fitting data's convex hull.         | Curve fits — PCHIP                                                                        |

| Extrapolation Method | Description                                                                                                                      | Supported Interpolation Methods |
|----------------------|----------------------------------------------------------------------------------------------------------------------------------|---------------------------------|
| Cubic spline         | This method fits a cubic interpolating spline through the fitting data and extends it outside of the fitting data's convex hull. | Curve fits — cubic spline       |


Thin-plate spline extrapolation uses the `tpaps` function, and PCHIP extrapolation uses the `pchip` function. Interpolant surface fits use the MATLAB function `scatteredInterpolant` function for none, linear, and nearest neighbor extrapolation, and the MATLAB function `griddata` for biharmonic extrapolation.

## Selecting an Extrapolation Method

Curve Fitting Toolbox allows you to choose an extrapolation method for surface fits that use linear, nearest neighbor, or cubic spline interpolation. The extrapolation method you use depends on several factors, including the characteristics of the data being fit, the required smoothness of the curve, and post-fit analysis requirements. You can specify extrapolation methods interactively using the Curve Fitter app, or from the command line using the `fit` and `fitoptions` functions.

### Select Extrapolation Method Interactively

- 1 Generate data or load data into the workspace.
- 2 Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.
- 3 In the Curve Fitter app, select curve data. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the **Select Fitting Data** dialog box, select **X data**, **Y data** and **Z data**.
- 4 Click the arrow in the **Fit Type** section to open the gallery, and click **Interpolant** in the **Interpolation** group.



You can specify the interpolation method by using the Interpolation method menu in the **Fit Options** pane. If the interpolation method supports multiple extrapolation methods, you can specify the extrapolation method using the Extrapolation method menu.

### Specify Extrapolation Method from Command Line


Generate some noisy data using the `membrane` and `randn` functions.

```
n = 41;
M = membrane(1,20)+0.02*randn(n);
[X,Y] = meshgrid(1:n);
```

The matrix  $M$  contains data for the L-shaped membrane with added noise. The matrices  $X$  and  $Y$  contain the row and column index values, respectively, for the corresponding elements in  $M$ .

Display a surface plot of the data.

```
surf(X,Y,M)
```



The plot shows a wrinkled L-shaped membrane. The wrinkles in the membrane are caused by the noise in the data.

### Specify Extrapolation Method Using `fit` Function

Use the `fit` function to fit a surface through the wrinkled membrane using linear interpolation. Specify the extrapolation method as nearest neighbor.

```
linfit = fit([X(:),Y(:)],M(:),"linearinterp",ExtrapolationMethod="nearest")
```

Linear interpolant:

```
linfit(x,y) = piecewise linear surface computed from p
with nearest neighbor extrapolation
```

Coefficients:


```
p = coefficient structure
```

The output confirms that the function uses linear interpolation and nearest neighbor extrapolation to fit a surface through the data.

Evaluate the fit beyond the X and Y data domain by using the `meshgrid` function. Plot the result using the `surf` function.

```
[Xq,Yq] = meshgrid(-10:50);
Zlin = linfit(Xq,Yq);

surf(Xq,Yq,Zlin);
```



The plot shows that the nearest neighbor extrapolation method uses the data on the convex hull to extend the surface in each direction. This method of extrapolation generates waves that mimic the convex hull.

### Specify Extrapolation Method Using `fitoptions` Function

Use the `fitoptions` function to generate fit options that use nearest neighbor interpolation and linear extrapolation.

```
fitOptions = fitoptions("nearestinterp",ExtrapolationMethod="linear")
```

```
fitOptions =
    nearestinteroptions with properties:
```

```
    ExtrapolationMethod: 'linear'
        Normalize: 'off'
```

```
Exclude: []  
Weights: []  
Method: 'NearestInterpolant'
```

`fitOptions` is a fit options object that specifies nearest neighbor interpolation and linear extrapolation.


Fit a surface through the wrinkled membrane using the options in `fitOptions`.

```
nearfit = fit([X(:),Y(:)],M(:),"nearestinterp",fitOptions)
```

```
Nearest neighbor interpolant:  
nearfit(x,y) = piecewise constant surface computed from p  
with linear extrapolation  
Coefficients:  
p = coefficient structure
```

Evaluate the fit beyond the X and Y data domain, and then plot the result.

```
Znear = nearfit(Xq,Yq);  
surf(Xq,Yq,Znear);
```



The plot shows that the linear extrapolation method generates spikes outside of the X and Y convex hull. The plane segments that form the spikes follow the gradient at data points on the convex hull border.

## **See Also**

### **Functions**

`fit` | `fitoptions` | `tpaps` | `pchip` | `griddata`

### **Objects**

`scatteredInterpolant`

## Smoothing Splines

### In this section...

“About Smoothing Splines” on page 6-14

“Select Smoothing Spline Fit Interactively” on page 6-15

“Fit Smoothing Spline Models Using the fit Function” on page 6-16

“Compare Cubic and Smoothing Spline Fit Using Curve Fitter” on page 6-18

### About Smoothing Splines

If your data is noisy, you might want to fit it using a smoothing spline. Alternatively, you can use one of the smoothing methods described in “Filtering and Smoothing Data” on page 6-34.

The smoothing spline  $s$  is constructed for the specified *smoothing parameter*  $p$  and the specified weights  $w_i$ . The smoothing spline minimizes

$$p \sum_i w_i (y_i - s(x_i))^2 + (1 - p) \int \left( \frac{d^2 s}{dx^2} \right)^2 dx$$

If the weights are not specified, they are assumed to be 1 for all data points.

$p$  is defined between 0 and 1.  $p = 0$  produces a least-squares straight-line fit to the data, while  $p = 1$  produces a cubic spline interpolant. If you do not specify the smoothing parameter, it is automatically selected in the “interesting range.” The interesting range of  $p$  is often near  $1/(1+h^3/6)$  where  $h$  is the average spacing of the data points, and it is typically much smaller than the allowed range of the parameter. Because smoothing splines have an associated smoothing parameter, you might consider these fits to be parametric in that sense. However, smoothing splines are also piecewise polynomials like cubic spline or shape-preserving interpolants and are considered a nonparametric fit type in this guide.


---

**Note** The smoothing spline algorithm is based on the `csaps` function.

---

The nuclear reaction data from the file `carbon12alpha.mat` is shown here with three smoothing spline fits. The default smoothing parameter ( $p = 0.99$ ) produces the smoothest curve. The cubic spline curve ( $p = 1$ ) goes through all the data points, but is not quite as smooth. The third curve ( $p = 0.95$ ) misses the data by a wide margin and illustrates how small the “interesting range” of  $p$  can be.





## Select Smoothing Spline Fit Interactively

- 1 Load the data at the MATLAB command line.


```
load carbon12alpha
```

- 2 Open the Curve Fitter app.

```
curveFitter
```

Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.

- 3 On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the **Select Fitting Data** dialog box, select **angle** as the **X data** value and **counts** as the **Y data** value. For details, see “Select Data to Fit in Curve Fitter App” on page 2-11.
- 4 On the **Curve Fitter** tab, in the **Fit Type** section, click the arrow to open the gallery, and click **Smoothing Spline** in the **Smoothing** group.
- 5 In the **Fit Options** pane, you can specify the **Smoothing Parameter** value.



The default **Smoothing Parameter** value is close to 1. The app tries to select a default value appropriate for your data. You can change the **Smoothing Parameter** value by doing one of the following:

- To create a smoother fit further from the data, click the **< Smoother** button repeatedly until the plot shows the smoothness you want.
- To create a rougher fit closer to the data, click the **Rougher >** button until you are satisfied with the plot.
- Alternatively, specify any value from 0 to 1 for the smoothing parameter. A value of 0 produces a linear polynomial fit (a least-squares straight-line fit to the data), while 1 produces a piecewise cubic polynomial fit that passes through all the data points (a cubic spline interpolant). For the carbon12alpha data set, try **Smoothing Parameter** values 1 and 0.95.
- Click **Default** to return to the initial value.


## Fit Smoothing Spline Models Using the fit Function

This example shows how to use the `fit` function to fit a smoothing spline model to data.

### Fit a Smoothing Spline Model

Load data and fit a smoothing spline model by specifying `'smoothingspline'` when calling the `fit` function.

```
load ensu
f = fit(month,pressure,'smoothingspline');
plot(f,month,pressure)
```



### View Calculated Smoothing Parameter

Create the model again and use the third output argument to view the calculated smoothing parameter. The smoothing parameter is the  $p$  value in the out structure. The default value depends on the data set.

```
[f,gof,out] = fit(month,pressure,'smoothingspline');
```


```
out.p
```

```
ans = 0.9000
```

### Specify Smoothing Parameter using 'SmoothingParam'

Specify the smoothing parameter for a new fit with the 'SmoothingParam' option. Its value must be between 0 and 1.

```
f = fit(month,pressure,'smoothingspline','SmoothingParam',0.07);
plot(f,month,pressure)
```



### Specify Smoothing Parameter using fitoptions

Alternatively, use `fitoptions` to specify a smoothing parameter before fitting.

```
options = fitoptions('Method','Smooth','SmoothingParam',0.07);
[f,gof,out] = fit(month,pressure,'smooth',options);
out.p
```

```
ans = 0.0700
```

For an alternative to `'smoothingspline'`, you can use the `csaps` cubic smoothing spline function or other spline functions that allow greater control over what you can create. See “Introducing Spline Fitting” on page 8-2.

### Compare Cubic and Smoothing Spline Fit Using Curve Fitter

This example compares a cubic spline interpolant fit and a smoothing spline fit using the Curve Fitter app.

- 1 Create the data `x` and `y`.


```
x = (4*pi)*[0 1 rand(1,25)];
y = sin(x) + .2*(rand(size(x))- .5);
```

- 2 Open the Curve Fitter app.

```
curveFitter
```

Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.

- 3 On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the **Select Fitting Data** dialog box, select  $x$  as the **X data** value and  $y$  as the **Y data** value.
- 4 On the **Curve Fitter** tab, in the **Fit Type** section, click the arrow to open the gallery, and click **Interpolant** in the **Interpolation** group.
- 5 In the **Fit Options** pane, specify the **Interpolation Method** as Cubic spline. The Curve Fitter app fits and plots the cubic spline interpolant.



- 6 Rename the fit. In the **Table Of Fits** pane, double-click the **Fit Name** value and enter CubicSplineFit.
- 7 View the **Results** pane. Some goodness-of-fit statistics, such as RMSE, are not defined for **Interpolant** fits and their value is NaN.

**Results**

Fit Name: CubicSplineFit

**Interpolating Curve Fit (cubicinterp)**  
 $f(x)$  = piecewise polynomial with cubic extrapolation  
 $x$  is normalized by mean 6.213 and std 3.827

**Coefficients**  
Coefficient structure for  $f$


**Goodness of Fit**

|          | Value  |
|----------|--------|
| SSE      | 0.0000 |
| R-square | 1.0000 |
| DFE      | 0      |
| Adj R-sq | NaN    |
| RMSE     | NaN    |

A cubic spline interpolation is defined as a piecewise polynomial that results in a structure of coefficients ( $p$ ). The number of “pieces” in the structure is one less than the number of fitted data points, and the number of coefficients for each piece is four because the polynomial degree is three. You can examine the coefficient structure  $p$  if you export your fit to the workspace by entering `CubicSplineFit.p`. For more information on the coefficient structure, see “Constructing and Working with ppform Splines” on page 10-10.

- 8 Create another fit to compare. Right-click the existing fit `CubicSplineFit` on the **Table Of Fits** tab and select **Duplicate "CubicSplineFit"**. Rename the new fit to `SmoothingSplineFit`.
- 9 On the **Curve Fitter** tab, in the **Fit Type** section, select a Smoothing Spline fit.

**Fit Options**

 **Smoothing Spline**

Smoothing Parameter

Default

Specify

< 0.9998104750010401 >


Center and scale

[Read about fit options](#)

In the **Fit Options** pane, the **Smoothing Parameter** defines the level of smoothness. The app calculates the **Smoothing Parameter** depending on the data set. For this data set, the default **Smoothing Parameter** is close to 1, indicating that the smoothing spline is nearly cubic and comes very close to passing through each data point.

You can change the level of smoothing by specifying **Smoothing Parameter** as a nonnegative scalar in the range [0 1]. Specify **Smoothing Parameter** as 0 to create a linear polynomial fit. Specify **Smoothing Parameter** as 1 to create a piecewise cubic polynomial fit that passes through all the data points.

- 10 See the **Results** pane for numerical results of the smoothing spline fit.



|          | Value  |
|----------|--------|
| SSE      | 0.0000 |
| R-square | 1.0000 |
| DFE      | 0      |
| Adj R-sq | NaN    |
| RMSE     | NaN    |

- 11 Compare the plots for the two fits (cubic spline interpolant fit and smoothing spline fit), which you created. The two fits are similar for interior points, but diverge at the end points.

---

**Note** Your results depend on random start points and may vary from those described.

---

## See Also

### Apps

Curve Fitter

### Functions

fit

## Related Examples

- “Nonparametric Fitting” on page 6-2
- “Filtering and Smoothing Data” on page 6-34

## Lowess Smoothing

| In this section...                                      |
|---------------------------------------------------------|
| “About Lowess Smoothing” on page 6-22                   |
| “Select Lowess Fit Interactively” on page 6-22          |
| “Fit Lowess Models Using the fit Function” on page 6-23 |

### About Lowess Smoothing

Use Lowess models to fit smooth surfaces to your data. The names “lowess” and “loess” are derived from the term “locally weighted scatter plot smooth,” as both methods use locally weighted linear regression to smooth data. The process is *weighted* because the toolbox defines a regression weight function for the data points contained within the span. In addition to the regression weight function, the **Robust** option is a weight function that can make the process resistant to outliers.

For more information on these two types of smoothing fit, see “Local Regression Smoothing” on page 6-36.


### Select Lowess Fit Interactively

Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter.

On the **Curve Fitter** tab, in the **Fit Type** section, select a **Lowess** fit. The app uses locally weighted linear regression to smooth the data.

In the **Fit Options** pane, you can try different fit options.





- You can set the regression **Polynomial** model to **Linear** or **Quadratic**.
- You can use **Span** to set the span as a percentage of the total number of data points in the data set. The app uses neighboring data points defined within the span to determine each smoothed value. This smoothing process is called “local.”

---

**Tip** Increase the span to make the surface smoother. Reduce the span to make the surface follow the data more closely.

---

- You can set the **Robust** linear least-squares fitting method to **Off**, **LAR**, or **Bisquare**. The local regression uses the **Robust** option. Using the **Robust** weight function can make the smoothing resistant to outliers. For details, see the **Robust** name-value argument of the `fitoptions` function.

---

**Tip** If your data variables have very different scales, select and clear the **Center and scale** check box to see the difference in the fit. Normalizing the variables can strongly influence the results of a lowess fit.

---

For an example on how to create a lowess fit interactively, see “Surface Fitting to Franke Data” on page 2-32.

## Fit Lowess Models Using the fit Function


This example shows how to use the `fit` function to fit a Lowess model to data.

Load some data and fit a Lowess model by specifying 'lowess' when calling the fit function.

```
load franke
f = fit([x y],z,'lowess')

Locally weighted smoothing linear regression:
  f(x,y) = lowess (linear) smoothing regression computed from p
Coefficients:
  p = coefficient structure

plot(f,[x y],z)
```



For a command-line example fitting a Lowess model, see “Fit Smooth Surfaces to Investigate Fuel Efficiency” on page 6-26.

## See Also

**Apps**  
Curve Fitter

**Functions**  
fit

**Related Examples**

- “Nonparametric Fitting” on page 6-2
- “Fit Smooth Surfaces to Investigate Fuel Efficiency” on page 6-26
- “Filtering and Smoothing Data” on page 6-34
- “Surface Fitting to Franke Data” on page 2-32

## Fit Smooth Surfaces to Investigate Fuel Efficiency

This example shows how to use Curve Fitting Toolbox™ to fit a response surface to some automotive data to investigate fuel efficiency.

The toolbox provides sample data generated from a GTPOWER predictive combustion engine model. The model emulates a naturally aspirated spark-ignition, 2-liter, inline 4-cylinder engine. You can fit smooth lowess surfaces to this data to find minimum fuel consumption.

The data set includes the required variables to model response surfaces:

- Speed is in revolutions per minute (rpm) units.
- Load is the normalized cylinder air mass (the ratio of cylinder aircharge to maximum naturally aspirated cylinder aircharge at standard temperature and pressure).
- BSFC is the brake-specific fuel consumption in g/KWh. That is, the energy flow in, divided by mechanical power out (fuel efficiency).

The aim is to model a response surface to find the minimum BSFC as a function of speed and load. You can use this surface as a table, included as part of a hybrid vehicle optimization algorithm combining the use of a motor and your engine. To operate the engine as fuel efficiently as possible, the table must operate the engine near the bottom of the BSFC bowl.

### Load and Preprocess Data

Load the data from the XLS spreadsheet. Use the 'basic' command option for non-Windows® platforms.

Create a variable `n` that has all the numeric data in one array.

```
n = xlsread( 'Engine_Data_SI_NA_2L_I4.xls', 'SI NA 2L I4', '', 'basic' );
```

Extract from the variable `n` the columns of interest.

```
SPEED = n(:,2);
LOAD_CMD = n(:,3);
LOAD = n(:,8);
BSFC = n(:,22);
```

Process the data before fitting, to pick out the minimum BSFC values from each sweep. The data points are organized in sweeps on speed/load.

Get a list of the speed/load sites:

```
SL = unique( [SPEED, LOAD_CMD], 'rows' );
nRuns = size( SL, 1 );
```

For each speed/load site, find the data at the site and extract the actual measured load and the minimum BSFC.

```
minBSFC = zeros( nRuns, 1 );
Load     = zeros( nRuns, 1 );
Speed    = zeros( nRuns, 1 );
for i = 1:nRuns
    idx = SPEED == SL(i,1) & LOAD_CMD == SL(i,2);
```

```

minBSFC(i) = min( BSFC(idx) );
Load(i)    = mean( LOAD(idx) );
Speed(i)   = mean( SPEED(idx) );
end

```

### Fit a Surface

Fit a surface of fuel efficiency to the preprocessed data.

```
f1 = fit( [Speed, Load], minBSFC, 'Lowess', 'Normalize', 'on' )
```


Locally weighted smoothing linear regression:  
 $f_1(x,y)$  = lowess (linear) smoothing regression computed from  $p$   
 where  $x$  is normalized by mean 3407 and std 1214  
 and where  $y$  is normalized by mean 0.5173 and std 0.1766  
 Coefficients:  
 $p$  = coefficient structure

### Plot Fit

```

plot( f1, [Speed, Load], minBSFC );
xlabel( 'Speed [RPM]' );
ylabel( 'Load [%]' );
zlabel( 'Minimum BSFC [g/Kwh]' );

```



### Remove Problem Points

Review the resulting plot.

There are points where BSFC is negative because this data is generated by an engine simulation.


Remove those problem data points by keeping points in the range [0, Inf].

```
out = excludedata( Speed, minBSFC, 'Range', [0, Inf] );
f2 = fit( [Speed, Load], minBSFC, 'Lowess', ...
         'Normalize', 'on', 'Exclude', out )
```

Locally weighted smoothing linear regression:  
 $f_2(x,y)$  = lowess (linear) smoothing regression computed from  $p$   
 where  $x$  is normalized by mean 3443 and std 1187  
 and where  $y$  is normalized by mean 0.521 and std 0.175  
 Coefficients:  
 $p$  = coefficient structure

Plot the new fit. Note that the excluded points are plotted as red crosses.


```
plot( f2, [Speed, Load], minBSFC, 'Exclude', out );
xlabel( 'Speed [RPM]' );
ylabel( 'Load [%]' );
zlabel( 'Minimum BSFC [g/Kwh]' );
```



### Zoom In


Zoom in on the part of the z-axis of interest.

```
zlim([0, max( minBSFC )])
```



You want to operate the engine efficiently, so create a contour plot to see the region where the BSFC is low. Use the plot function, and specify the name/value parameter pair 'style', 'Contour'.

```
plot( f2, [Speed, Load], minBSFC, 'Exclude', out, 'Style', 'Contour' );  
xlabel( 'Speed [RPM]' );  
ylabel( 'Load [%]' );  
colorbar
```



### Create a Table from the Surface

Generate a table by evaluating the model `f2` over a grid of points.

Create variables for the table breakpoints.

```
speedbreakpoints = linspace( 1000, 5500, 17 );
loadbreakpoints = linspace( 0.2, 0.8, 13 );
```

To generate values for the table, evaluate the model over a grid of points.

```
[tSpeed, tLoad] = meshgrid( speedbreakpoints, loadbreakpoints );
tBSFC = f2( tSpeed, tLoad );
```

Examine the rows and columns of the table at the command line.

```
tBSFC(1:2:end,1:2:end)
```

```
ans =
```

```
Columns 1 through 7
```

```
722.3280 766.7608 779.4296 757.4574 694.5378 624.4095 576.5235
503.9880 499.9201 481.7240 458.2803 427.7338 422.1099 412.1624
394.7579 364.3421 336.1811 330.1550 329.1635 328.1810 329.1144
333.7740 307.7736 295.1777 291.2068 290.3637 290.0173 287.8672
295.9729 282.7567 273.8287 270.8869 269.8485 271.0547 270.5502
```



|          |          |          |          |          |          |          |
|----------|----------|----------|----------|----------|----------|----------|
| 273.7512 | 264.5167 | 259.7631 | 257.9215 | 256.9350 | 258.3228 | 258.6638 |
| 251.5652 | 247.6746 | 247.2747 | 247.4699 | 247.3570 | 248.2433 | 248.8139 |


Columns 8 through 9

|          |          |
|----------|----------|
| 532.1533 | 466.9610 |
| 396.3209 | 398.0199 |
| 335.3871 | 346.3882 |
| 286.3077 | 291.0075 |
| 269.6837 | 272.2054 |
| 258.0298 | 260.5269 |
| 249.0083 | 250.4165 |

### Plot the Table Against the Original Model

The grid on the model surface shows the table breakpoints.

```
h = plot( f2 );
h.EdgeColor = 'none';
hold on
mesh( tSpeed, tLoad, tBSFC, ...
      'LineStyle', '-', 'LineWidth', 2, 'EdgeColor', 'k', ...
      'FaceColor', 'none', 'FaceAlpha', 1 );
hold off
xlabel( 'Speed [RPM]' );
ylabel( 'Load [%]' );
zlabel( 'Minimum BSFC [g/Kwh]' );
```




### Check the Table Accuracy

View the difference between the model and the table by plotting the difference between them on a finer grid. Then, use this difference in prediction accuracy between the table and the model to determine the most efficient table size for your accuracy requirements.

The following code evaluates the model over a finer grid and plots the difference between the model and the table.

```
[tfSpeed, tfLoad] = meshgrid( ...
    linspace( 1000, 5500, 8*17+1 ), ...
    linspace( 0.2, 0.8, 8*13+1 ) );
tfBSFC_model = f2( tfSpeed, tfLoad );
tfBSFC_table = interp2( tSpeed, tLoad, tBSFC, tfSpeed, tfLoad, 'linear' );
tfDiff = tfBSFC_model - tfBSFC_table;

surf( tfSpeed, tfLoad, tfDiff, 'LineStyle', 'none' );
hold on
mesh( tSpeed, tLoad, zeros( size( tBSFC ) ), ...
    'LineStyle', '-', 'LineWidth', 2, 'EdgeColor', 'k', ...
    'FaceColor', 'none', 'FaceAlpha', 1 );
hold off
axis tight
xlabel( 'Speed [RPM]' );
ylabel( 'Load [%]' );
zlabel( 'Difference between model and table [g/Kwh]' );
title( sprintf( 'Max difference: %g', max( abs( tfDiff(:) ) ) ) );
```



### Create a Table Array Including Breakpoint Values

After creating a table by evaluating a model fit over a grid of points, it can be useful to export your table data from MATLAB. Before exporting, create a table array that includes the breakpoint values in the first row and column. The following command reshapes your data to this table format:

- X (speedbreakpoints) is a (1 x M) vector
- Y (loadbreakpoints) is an (N x 1) vector
- Z (tBSFC) is an (M x N) matrix

```
table = [
    {'Load\Speed'}, num2cell(speedbreakpoints(:).') )
    num2cell(loadbreakpoints (:) ), num2cell( tBSFC )
];
```

### Export Table to Spreadsheet File

You can use the `xlswrite` function to export your table data to a new Excel Spreadsheet. Execute the following command to create a spreadsheet file.

```
xlswrite( 'tabledata.xlsx', table )
```

### Create a Lookup Table Block

If you have Simulink® software, you can create a Look Up Table block as follows. Execute the following code to try it out.

1. Create a model with a 2-D Lookup Table block.

```
simulink
new_system( 'my_model' )
open_system( 'my_model' )
add_block( 'simulink/Lookup Tables/2-D Lookup Table', 'my_model/surfaceblock' )
```

2. Populate the Lookup Table with speed breakpoints, load breakpoints, and a lookup table.

```
set_param( 'my_model/surfaceblock', ...
    'BreakpointsForDimension1', 'loadbreakpoints', ...
    'BreakpointsForDimension2', 'speedbreakpoints', ...
    'Table', 'tBSFC' );
```

3. Examine the populated Lookup Table block.

## Filtering and Smoothing Data

### In this section...

“About Data Filtering and Smoothing” on page 6-34

“Moving Average Filtering” on page 6-34

“Savitzky-Golay Filtering” on page 6-35

“Local Regression Smoothing” on page 6-36

“Example: Smoothing Data” on page 6-40

“Example: Smoothing Data Using Loess and Robust Loess” on page 6-41

### About Data Filtering and Smoothing

This topic explains how to smooth response data using this function. With the `smooth` function, you can use optional methods for moving average, Savitzky-Golay filters, and local regression with and without weights and robustness (`lowess`, `loess`, `rloess` and `rloess`). See `smoothdata` for more functionality, including support for matrices, tables, and timetables, as well as moving median and Gaussian methods.

### Moving Average Filtering

A moving average filter smooths data by replacing each data point with the average of the neighboring data points defined within the span. This process is equivalent to lowpass filtering with the response of the smoothing given by the difference equation

$$y_s(i) = \frac{1}{2N+1}(y(i+N) + y(i+N-1) + \dots + y(i-N))$$

where  $y_s(i)$  is the smoothed value for the  $i$ th data point,  $N$  is the number of neighboring data points on either side of  $y_s(i)$ , and  $2N+1$  is the span.

The moving average smoothing method used by Curve Fitting Toolbox follows these rules:

- The span must be odd.
- The data point to be smoothed must be at the center of the span.
- The span is adjusted for data points that cannot accommodate the specified number of neighbors on either side.
- The end points are not smoothed because a span cannot be defined.


Note that you can use `filter` function to implement difference equations such as the one shown above. However, because of the way that the end points are treated, the toolbox moving average result will differ from the result returned by `filter`. Refer to Difference Equations and Filtering for more information.

For example, suppose you smooth data using a moving average filter with a span of 5. Using the rules described above, the first four elements of  $y_s$  are given by

$$\begin{aligned} y_s(1) &= y(1) \\ y_s(2) &= (y(1)+y(2)+y(3))/3 \\ y_s(3) &= (y(1)+y(2)+y(3)+y(4)+y(5))/5 \\ y_s(4) &= (y(2)+y(3)+y(4)+y(5)+y(6))/5 \end{aligned}$$

Note that  $y_s(1)$ ,  $y_s(2)$ , ...,  $y_s(\text{end})$  refer to the order of the data after sorting, and not necessarily the original order.

The smoothed values and spans for the first four data points of a generated data set are shown below.



Plot (a) indicates that the first data point is not smoothed because a span cannot be constructed. Plot (b) indicates that the second data point is smoothed using a span of three. Plots (c) and (d) indicate that a span of five is used to calculate the smoothed value.

## Savitzky-Golay Filtering

Savitzky-Golay filtering can be thought of as a generalized moving average. You derive the filter coefficients by performing an unweighted linear least-squares fit using a polynomial of a given degree. For this reason, a Savitzky-Golay filter is also called a digital smoothing polynomial filter or a least-squares smoothing filter. Note that a higher degree polynomial makes it possible to achieve a high level of smoothing without attenuation of data features.


The Savitzky-Golay filtering method is often used with frequency data or with spectroscopic (peak) data. For frequency data, the method is effective at preserving the high-frequency components of the signal. For spectroscopic data, the method is effective at preserving higher moments of the peak such as the line width. By comparison, the moving average filter tends to filter out a significant portion of the signal's high-frequency content, and it can only preserve the lower moments of a peak such as the centroid. However, Savitzky-Golay filtering can be less successful than a moving average filter at rejecting noise.

The Savitzky-Golay smoothing method used by Curve Fitting Toolbox software follows these rules:

- The span must be odd.
- The polynomial degree must be less than the span.
- The data points are not required to have uniform spacing.

Normally, Savitzky-Golay filtering requires uniform spacing of the predictor data. However, the Curve Fitting Toolbox algorithm supports nonuniform spacing. Therefore, you are not required to perform an additional filtering step to create data with uniform spacing.

The plot shown below displays generated Gaussian data and several attempts at smoothing using the Savitzky-Golay method. The data is very noisy and the peak widths vary from broad to narrow. The span is equal to 5% of the number of data points.



Plot (a) shows the noisy data. To more easily compare the smoothed results, plots (b) and (c) show the data without the added noise.

Plot (b) shows the result of smoothing with a quadratic polynomial. Notice that the method performs poorly for the narrow peaks. Plot (c) shows the result of smoothing with a quartic polynomial. In general, higher degree polynomials can more accurately capture the heights and widths of narrow peaks, but can do poorly at smoothing wider peaks.

## Local Regression Smoothing

- “Lowess and Loess” on page 6-37
- “The Local Regression Method” on page 6-37
- “Robust Local Regression” on page 6-39

## Lowess and Loess

The names “lowess” and “loess” are derived from the term “locally weighted scatter plot smooth,” as both methods use locally weighted linear regression to smooth data.

The smoothing process is considered local because, like the moving average method, each smoothed value is determined by neighboring data points defined within the span. The process is weighted because a regression weight function is defined for the data points contained within the span. In addition to the regression weight function, you can use a robust weight function, which makes the process resistant to outliers. Finally, the methods are differentiated by the model used in the regression: lowess uses a linear polynomial, while loess uses a quadratic polynomial.

The local regression smoothing methods used by Curve Fitting Toolbox software follow these rules:

- The span can be even or odd.
- You can specify the span as a percentage of the total number of data points in the data set. For example, a span of 0.1 uses 10% of the data points.

### The Local Regression Method

The local regression smoothing process follows these steps for each data point:

- 1 Compute the *regression weights* for each data point in the span. The weights are given by the tricube function shown below.



$$w_i = \left(1 - \left|\frac{x - x_i}{d(x)}\right|^3\right)^3$$

$x$  is the predictor value associated with the response value to be smoothed,  $x_i$  are the nearest neighbors of  $x$  as defined by the span, and  $d(x)$  is the distance along the abscissa from  $x$  to the most distant predictor value within the span. The weights have these characteristics:


- The data point to be smoothed has the largest weight and the most influence on the fit.
  - Data points outside the span have zero weight and no influence on the fit.
- 2 A weighted linear least-squares regression is performed. For lowess, the regression uses a first degree polynomial. For loess, the regression uses a second degree polynomial.
  - 3 The smoothed value is given by the weighted regression at the predictor value of interest.

If the smooth calculation involves the same number of neighboring data points on either side of the smoothed data point, the weight function is symmetric. However, if the number of neighboring points is not symmetric about the smoothed data point, then the weight function is not symmetric. Note that unlike the moving average smoothing process, the span never changes. For example, when you smooth the data point with the smallest predictor value, the shape of the weight function is truncated by one half, the leftmost data point in the span has the largest weight, and all the neighboring points are to the right of the smoothed value.

The weight function for an end point and for an interior point is shown below for a span of 31 data points.



Using the lowess method with a span of five, the smoothed values and associated regressions for the first four data points of a generated data set are shown below.



Notice that the span does not change as the smoothing process progresses from data point to data point. However, depending on the number of nearest neighbors, the regression weight function might



not be symmetric about the data point to be smoothed. In particular, plots (a) and (b) use an asymmetric weight function, while plots (c) and (d) use a symmetric weight function.

For the loess method, the graphs would look the same except the smoothed value would be generated by a second-degree polynomial.

### Robust Local Regression

If your data contains outliers, the smoothed values can become distorted, and not reflect the behavior of the bulk of the neighboring data points. To overcome this problem, you can smooth the data using a robust procedure that is not influenced by a small fraction of outliers. For a description of outliers, refer to “Residual Analysis” on page 7-46.

Curve Fitting Toolbox software provides a robust version for both the lowess and loess smoothing methods. These robust methods include an additional calculation of robust weights, which is resistant to outliers. The robust smoothing procedure follows these steps:

- 1 Calculate the residuals from the smoothing procedure described in the previous section.
- 2 Compute the *robust weights* for each data point in the span. The weights are given by the bisquare function,

$$w_i = \begin{cases} \left(1 - (r_i/6MAD)^2\right)^2, & |r_i| < 6MAD, \\ 0, & |r_i| \geq 6MAD, \end{cases}$$


where  $r_i$  is the residual of the  $i$ th data point produced by the regression smoothing procedure, and  $MAD$  is the median absolute deviation of the residuals,

$$MAD = \text{median}(|r|).$$

The median absolute deviation is a measure of how spread out the residuals are. If  $r_i$  is small compared to  $6MAD$ , then the robust weight is close to 1. If  $r_i$  is greater than  $6MAD$ , the robust weight is 0 and the associated data point is excluded from the smooth calculation.

- 3 Smooth the data again using the robust weights. The final smoothed value is calculated using both the local regression weight and the robust weight.
- 4 Repeat the previous two steps for a total of five iterations.

The smoothing results of the lowess procedure are compared below to the results of the robust lowess procedure for a generated data set that contains a single outlier. The span for both procedures is 11 data points.



Plot (a) shows that the outlier influences the smoothed value for several nearest neighbors. Plot (b) suggests that the residual of the outlier is greater than six median absolute deviations. Therefore, the robust weight is zero for this data point. Plot (c) shows that the smoothed values neighboring the outlier reflect the bulk of the data.

### Example: Smoothing Data

Load the data in `count.dat`:

```
load count.dat
```

The 24-by-3 array `count` contains traffic counts at three intersections for each hour of the day.

First, use a moving average filter with a 5-hour span to smooth all of the data at once (by linear index):

```
c = smooth(count(:));
C1 = reshape(c,24,3);
```

Plot the original data and the smoothed data:

```
subplot(3,1,1)
plot(count,':');
hold on
plot(C1,'-');
title('Smooth C1 (All Data)')
```

Second, use the same filter to smooth each column of the data separately:

```
C2 = zeros(24,3);
for I = 1:3,
```

```

    C2(:,I) = smooth(count(:,I));
end

```

Again, plot the original data and the smoothed data:

```

subplot(3,1,2)
plot(count,':');
hold on
plot(C2,'-');
title('Smooth C2 (Each Column)')


```

Plot the difference between the two smoothed data sets:

```

subplot(3,1,3)
plot(C2 - C1,'o-')
title('Difference C2 - C1')

```



Note the additional end effects from the 3-column smooth.

## Example: Smoothing Data Using Loess and Robust Loess

Create noisy data with outliers:

```

x = 15*rand(150,1);
y = sin(x) + 0.5*(rand(size(x))-0.5);
y(ceil(length(x)*rand(2,1))) = 3;

```

Smooth the data using the `loess` and `rloess` methods with a span of 10%:

```

yy1 = smooth(x,y,0.1,'loess');
yy2 = smooth(x,y,0.1,'rloess');

```

Plot original data and the smoothed data.

```


[xx,ind] = sort(x);
subplot(2,1,1)
plot(xx,y(ind),'b.',xx,yy1(ind),'r-')
set(gca,'YLim',[-1.5 3.5])

```

```

legend('Original Data','Smoothed Data Using ''loess''',...
      'Location','NW')
subplot(2,1,2)
plot(xx,y(ind),'b.',xx,yy2(ind),'r-')
set(gca,'YLim',[-1.5 3.5])
legend('Original Data','Smoothed Data Using ''rloess''',...
      'Location','NW')

```



Note that the outliers have less influence on the robust method.

## See Also

[smooth](#) | [smoothdata](#)

## Related Examples

- “Nonparametric Fitting” on page 6-2
- “Smoothing Splines” on page 6-14
- “Lowess Smoothing” on page 6-22

# Fit Postprocessing

---

- “Explore and Customize Plots” on page 7-2
- “Remove Outliers” on page 7-8
- “Select Validation Data” on page 7-12
- “Generate Code and Export Fits to the Workspace” on page 7-13
- “Evaluate Curve Fit” on page 7-16
- “Evaluate Surface Fit” on page 7-24
- “Compare Fits Programmatically” on page 7-30
- “Evaluating Goodness of Fit” on page 7-42
- “Residual Analysis” on page 7-46
- “Confidence and Prediction Bounds” on page 7-50
- “Differentiating and Integrating a Fit” on page 7-58

## Explore and Customize Plots

### In this section...

“Displaying Fit and Residual Plots” on page 7-2

“Viewing Surface Plots and Contour Plots” on page 7-3

“Using Zoom, Pan, Data Cursor, and Outlier Exclusion” on page 7-5

“Customizing the Fit Display” on page 7-5


“Print to MATLAB Figures” on page 7-6

### Displaying Fit and Residual Plots

In the Curve Fitter app, within each fit figure, you can display up to three plots simultaneously to examine the fit. Use the buttons in the **Visualization** section of the **Curve Fitter** tab to select the type of plot to display.


- Click **Fit Plot** to show the curve or surface fit.
- Click **Residuals Plot** to show the errors between your fit and your data.
- Click **Contour Plot** to show a contour map of a surface fit (not available for curve fits).

This example shows two plots: a plot with a curve fit and prediction bounds and a residuals plot.



When you select **Prediction Bounds** in the **Visualization** section of the **Curve Fitter** tab, two additional curves (or surfaces) are plotted to show the prediction bounds on both sides of your model fit.


Choose which bounds to display: **None**, **90%**, **95%**, **99%**, or **Custom**. The **Custom** option opens the **Set Prediction Bounds** dialog box, where you can enter the required confidence level.



See also “Customizing the Fit Display” on page 7-5.

### Residuals Plot

On the residuals plot, you can view the errors between your fit and your data, and you can remove outliers. See “Remove Outliers” on page 7-8. This example shows a residuals plot with some excluded outliers.



### Viewing Surface Plots and Contour Plots

If you fit a surface, then the fit plot shows your surface fit. Click-and-drag rotation is the default mouse mode for surface plots in the Curve Fitter app. Rotate mode in the Curve Fitter app is the same as using the Rotate 3D button in the axes toolbar of MATLAB figures. You can change the mouse mode for manipulating plots just as for curve plots. See “Using Zoom, Pan, Data Cursor, and Outlier Exclusion” on page 7-5.


---

**Tip** To return to rotate mode, turn off any other mouse mode.

---

If you turn on a mouse mode for zoom, pan, data cursor, or exclude outliers, turn the mode off again to return to rotate mode. For example, click the Zoom in button on the axes toolbar a second time to clear it and return to rotate mode.

If you have a surface fit, use the contour plot to examine a contour map of your surface. Contour plots are not available for curve fits. On a surface fit, a contour plot makes it easier to see points that have the same height.



For polynomial and custom fits, you also can display prediction bounds. On the **Curve Fitter** tab, in the **Visualization** section, select a value from the **Prediction Bounds** list. When you display prediction bounds, two additional surfaces are plotted to show the prediction bounds on both sides of your model fit. The previous example shows prediction bounds. You can see three surfaces on the plot. The top and bottom surfaces show the prediction bounds at the specified confidence level on either side of your model fit surface.

You can also switch your surface plot to a 2-D plot. Your plot cursor must be in rotate mode. Clear any other mouse mode, if necessary. Then, right-click the plot to select **Go to X-Y view**, **Go to X-Z view**, **Go to Y-Z view**, or **Rotate Options**. All these context menu options are standard MATLAB 3-D plot tools. For more information, see "Interactively Explore Plotted Data".



## Using Zoom, Pan, Data Cursor, and Outlier Exclusion

You can change mouse mode for manipulating plots. Use the plot axes toolbar to switch to zoom in, zoom out, pan, data cursor, or exclude outliers modes. The Curve Fitter app remembers your selected mouse mode in each fit figure within a session.

Use the axes toolbar to toggle mouse mode in your plots:

- The Zoom in, Zoom out, Pan, and Data cursor buttons are similar to standard MATLAB axes toolbar options.

On surfaces, turn all these modes off to return to rotation mode. For surface plots, rotation is the default mouse mode in the Curve Fitter app. See “Viewing Surface Plots and Contour Plots” on page 7-3.

- Clicking the Data cursor button enables data cursor mode, where you can click points to display data tips.
- Clicking the Exclude outliers button enables exclude outliers mode, where you can click points to remove or include in your fit. See “Remove Outliers” on page 7-8.

## Customizing the Fit Display

To customize your plot display, use the plot axes toolbar, the options in the **Visualization** section of the **Curve Fitter** tab, or the Document Actions button located to the far right of the fit figure tabs. See also “Create Multiple Fits in Curve Fitter App” on page 2-15.

### Axes Toolbar

Use the plot axes toolbar buttons to change the display of the plot legend and grid marks.

- The Legend button toggles the display of the legend on all plots in the currently selected fit tab.
- The Grid button toggles the display of the grid on all plots in the currently selected fit tab.

### Visualization Section


Use the options in the **Visualization** section of the **Curve Fitter** tab to customize the display of plots and prediction bounds.

- **Fit Plot** toggles the display of the fit plot in the currently selected fit figure. This button is disabled if the fit plot is the only displayed plot.
- **Residuals Plot** toggles the display of the residuals plot in the currently selected fit tab. This button is disabled if the residuals plot is the only displayed plot.
- **Contour Plot** toggles the display of the contour plot in the currently selected fit tab. This button is disabled if the contour plot is the only displayed plot.
- The **Prediction Bounds** list lets you choose which bounds to display: None, 90%, 95%, 99%, or Custom. The custom option opens a dialog box where you can enter the required confidence level.

### Document Actions Button

To compare plots and see multiple fits simultaneously, you can drag and drop the fit figure tabs. Alternatively, you can click the Document Actions button located to the far right of the fit figure tabs. For example, select the **Tile All** option and specify the number and position of tiles you want to display.

**Tip** For more space to view and compare plots, as shown next, you can drag and drop the **Fit Options**, **Results**, and **Table Of Fits** panes.



See also “Displaying Multiple Fits Simultaneously” on page 2-15.

## Print to MATLAB Figures

In the Curve Fitter app, you can produce MATLAB figures from the results of curve fitting. On the **Curve Fitter** tab, in the **Export** section, click **Export** and select **Export to Figure**. The app creates a figure containing all plots for the current fit. You can then use the interactive plotting tools to edit and export the figures in different formats.

## See Also

### Related Examples

- “Remove Outliers” on page 7-8
- “Compare Fits in Curve Fitter App” on page 2-19
- “Create Multiple Fits in Curve Fitter App” on page 2-15
- “Generate Code and Export Fits to the Workspace” on page 7-13
- “Compare Fits Programmatically” on page 7-30

## Remove Outliers

### In this section...


“Remove Outliers Interactively” on page 7-8

“Exclude Data Ranges” on page 7-8

“Remove Outliers Programmatically” on page 7-8

### Remove Outliers Interactively

To remove outliers in the Curve Fitter app, follow these steps:

- 1 In the plot axes toolbar, click the Exclude outliers button .

When you move the mouse cursor to the plot, it changes to a cross-hair to show that you are in outlier selection mode.

- 2 Click a point that you want to exclude in the fit plot or residuals plot. Alternatively, click and drag to define a rectangle and remove all enclosed points.

A removed plot point becomes a red cross in the plots. If you have **Auto** fitting selected in the **Fit** section of the **Curve Fitter** tab, the Curve Fitter app refits the surface without the point. Otherwise, if you have **Manual** fitting selected, you can click **Fit** to refit.

- 3 Repeat the process for all points you want to exclude.

When removing outliers from surface fits, it can be helpful to display a 2-D residuals plot for examining and removing outliers. With your plot cursor in rotation mode, right-click the plot to select **Go to X-Y view**, **Go to X-Z view**, or **Go to Y-Z view**.

To replace individual excluded points in the fit, click an excluded point again in outlier selection mode (that is, with the Exclude outliers button toggled on in the axes toolbar). To replace all excluded points in the fit, right-click and select **Clear all exclusions**.

In surface plots, to return to rotation mode, click the Exclude outliers button again to turn off outlier selection mode.

### Exclude Data Ranges

To exclude sections of data by range in the Curve Fitter app, follow these steps:

- 1 On the **Curve Fitter** tab, in the **Data** section, click **Exclusion Rules**.
- 2 In the Exclusion Rules dialog box, specify data to exclude. Enter numbers in any of the boxes to define beginning or ending intervals to exclude in the X, Y, or Z data.

The Curve Fitter app displays shaded pink areas on the plots to show excluded ranges. Excluded points become red.


### Remove Outliers Programmatically

This example shows how to remove outliers when curve fitting programmatically, using the 'Exclude' name/value pair argument with the fit or fitoptions functions. You can plot excluded data by supplying an Exclude or outliers argument with the plot function.

### Exclude Data Using a Simple Rule

For a simple example, load data and fit a Gaussian distribution, excluding some data with an expression. Then plot the fit, data and the excluded points.

```
[x, y] = titanium;
f1 = fit(x',y', 'gauss2', 'Exclude', x<800);
plot(f1,x,y,x<800)
```



### Exclude Data by Distance from the Model

It can be useful to exclude outliers by distance from the model, using standard deviations. The following example shows how to identify outliers using distance greater than 1.5 standard deviations from the model, and compares with a robust fit which gives lower weight to outliers.

Create a baseline sinusoidal signal:

```
xdata = (0:0.1:2*pi)';
y0 = sin(xdata);
```

Add noise to the signal with non-constant variance:

```
% Response-dependent Gaussian noise
gnoise = y0.*randn(size(y0));
```

```
% Salt-and-pepper noise
spnoise = zeros(size(y0));
p = randperm(length(y0));
sppoints = p(1:round(length(p)/5));
spnoise(sppoints) = 5*sign(y0(sppoints));

ydata = y0 + gnoise + spnoise;
```

Fit the noisy data with a baseline sinusoidal model:

```
f = fittype('a*sin(b*x)');
fit1 = fit(xdata,ydata,f,'StartPoint',[1 1]);
```

Identify outliers as points at a distance greater than 1.5 standard deviations from the baseline model, and refit the data with the outliers excluded:

```
fdata = feval(fit1,xdata);
I = abs(fdata - ydata) > 1.5*std(ydata);
outliers = excludedata(xdata,ydata,'indices',I);


fit2 = fit(xdata,ydata,f,'StartPoint',[1 1],...
          'Exclude',outliers);
```

Compare the effect of excluding the outliers with the effect of giving them lower bisquare weight in a robust fit:

```
fit3 = fit(xdata,ydata,f,'StartPoint',[1 1],'Robust','on');
```

Plot the data, the outliers, and the results of the fits:

```
plot(fit1,'r-',xdata,ydata,'k.',outliers,'m*')
hold on
plot(fit2,'c--')
plot(fit3,'b:')
xlim([0 2*pi])
```



## See Also

`fit | excludedata`

## Related Examples

- “Explore and Customize Plots” on page 7-2

## Select Validation Data

To specify validation data for the currently selected fit in the Curve Fitter app, follow these steps:

- 1** On the **Curve Fitter** tab, in the **Data** section, click **Validation Data**. The app opens the Select Validation Data dialog box.
- 2** In the dialog box, select variables for **X data** and **Y data** (and **Z data** for surfaces).

When you select two or three variables, depending on whether your data is for a curve or a surface, the app calculates validation statistics (SSE and RMSE) and displays them in the **Results** and **Table Of Fits** panes. For definitions of these statistics, see “Using the Statistics in the Table of Fits” on page 2-17. The app displays the validation data points on the fit plot and the residuals plot along with the original data.

- 3** Close the dialog box.



## Generate Code and Export Fits to the Workspace

### In this section...

“Generating Code from the Curve Fitter App” on page 7-13

“Exporting a Fit to the Workspace” on page 7-14

### Generating Code from the Curve Fitter App

You can generate and use MATLAB code from an interactive session in the Curve Fitter app. In this way, you can transform your interactive analysis into reusable functions for batch processing of multiple data sets. You can use the generated file without modification, or you can edit and customize the file as needed.

To generate code for the currently selected fit and its opened plots in your Curve Fitter app session, follow these steps:

- 1 On the **Curve Fitter** tab, in the **Export** section, click **Export** and select **Generate Code**.

The Curve Fitter app generates code from your session and displays the file in the MATLAB Editor. The file includes the currently selected fit in your session and its opened plots. The file captures the following information:

- Name of the fit and its variables
- Fit settings and options
- Plots
- Curve or surface fitting object and the function used to create the fit:
  - `cfit` or `sfit` object representing the fit
  - A structure with goodness-of-fit information

- 2 Save the file.

To recreate your fit and its plots, call the file from the command line with your original data as input arguments. You also can call the file with new data.

For example, enter the following code, where `a`, `b`, and `c` are the variable names and `myFileName` is the file name.

```
[fitresult,gof] = myFileName(a,b,c)
```

Calling the file from the command line does not recreate your Curve Fitter app session. When you call the file, you get the same plots you had in your Curve Fitter app session in a standard MATLAB figure window. For example, if your fit in the Curve Fitter app session displayed fit, residuals, and contour plots, all three plots appear in a single figure window.

### Curve Fitting Functions

The curve and surface fit objects (`cfit` and `sfit`) store the results from a fitting operation, making it easy to plot and analyze fits at the command line.


To learn about available functions for working with fits, see “Curve and Surface Fitting” on page 3-2.

## Exporting a Fit to the Workspace

To export a fit to the MATLAB workspace, follow these steps:

- 1 Select a fit and save it to the MATLAB workspace using one of these methods:
  - Right-click the fit in the **Table Of Fits** pane, and select **Save "myfitname" to Workspace**.
  - On the **Curve Fitter** tab, in the **Export** section, click **Export** and select **Export to Workspace**.

The app opens the Save Fit to MATLAB Workspace dialog box.



- 2 Edit the names as appropriate. If you previously exported fits, the app automatically adds a numbered suffix to the default names to avoid overwriting existing names.
- 3 Choose which options you want to export by selecting the check boxes. Check box options are as follows:
  - **Save fit to MATLAB object named** — This option creates a `cf` or `sfit` object, that encapsulates the result of fitting a curve or surface to data. You can examine the fit coefficients at the command line.

```
fittedmodel
```

```
Linear model Poly22:
fittedmodel(x,y) = p00 + p10*x + p01*y + p20*x^2 + p11*x*y + p02*y^2
  where x is normalized by mean 1982 and std 868.6
  and where y is normalized by mean 0.4972 and std 0.2897
Coefficients (with 95% confidence bounds):
p00 =    0.4227   (0.3837, 0.4616)
p10 =   -0.137   (-0.1579, -0.1161)
p01 =   -0.1913   (-0.2122, -0.1705)
p20 =    0.0234   (-2.895e-05, 0.04682)
p11 =    0.067   (0.04613, 0.08787)
p02 =   -0.02946  (-0.05288, -0.006043)
```

You also can treat the `cf` or `sfit` object as a function to make predictions or evaluate the fit at values of X (or X and Y). See `cf` and `sfit`.

- **Save goodness of fit to MATLAB struct named** — This option creates a structure that contains statistical information about the fit.

```
goodness
```

```
goodness =
```

```
struct with fields:
```

```
    sse: 9.4302
   rsquare: 0.6565
    dfe: 287
  adjrsquare: 0.6505
    rmse: 0.1813
```

- **Save fit output to MATLAB struct named** — This option creates a structure that contains information such as number of observations, number of parameters, residuals, and so on.

```
output
```

```
output =
```

```
struct with fields:
```

```
    numobs: 293
   numparam: 6
  residuals: [293×1 double]
   Jacobian: [293×6 double]
   exitflag: 1
  algorithm: 'QR factorization and solve'
  iterations: 1
```

---

**Note** The goodness-of-fit and output structures are outputs of the `fit` function.

---

- 4 Click **OK** to save the fit options to the workspace.

After you save your fit to the workspace, you can use fit postprocessing functions. For an example, see “Analyzing Best Fit in the Workspace” on page 2-27. For more information and a list of functions, see “Fit Postprocessing”.

## See Also

### Related Examples

- “Evaluate Curve Fit” on page 7-16
- “Evaluate Surface Fit” on page 7-24

## Evaluate Curve Fit

This example shows how to work with a curve fit.


### Load Data and Fit a Polynomial Curve

```
load census
curvefit = fit(cdate,pop,'poly3','normalize','on')
curvefit =
  Linear model Poly3:
  curvefit(x) = p1*x^3 + p2*x^2 + p3*x + p4
  where x is normalized by mean 1890 and std 62.05
  Coefficients (with 95% confidence bounds):
  p1 =      0.921  (-0.9743, 2.816)
  p2 =     25.18  (23.57, 26.79)
  p3 =     73.86  (70.33, 77.39)
  p4 =     61.74  (59.69, 63.8)
```

The output displays the fitted model equation, the fitted coefficients, and the confidence bounds for the fitted coefficients.


### Plot the Fit, Data, Residuals, and Prediction Bounds

```
plot(curvefit,cdate,pop)
```




Plot the residuals fit.

```
plot(curvefit,cdate,pop, 'Residuals')
```



Plot the prediction bounds on the fit.

```
plot(curvefit,cdate,pop, 'predfunc')
```



### Evaluate the Fit at a Specified Point

Evaluate the fit at a specific point by specifying a value for  $x$ , using this form:  $y = \text{fittedmodel}(x)$ .

```
curvefit(1991)
ans = 252.6690
```

### Evaluate the Fit Values at Many Points

Evaluate the model at a vector of values to extrapolate to the year 2050.

```
xi = (2000:10:2050).';
curvefit(xi)
ans = 6x1

    276.9632
    305.4420
    335.5066
    367.1802
    400.4859
    435.4468
```

Get prediction bounds on those values.

```
ci = predint(curvefit,xi)
```

```

ci = 6x2

    267.8589    286.0674
    294.3070    316.5770
    321.5924    349.4208
    349.7275    384.6329
    378.7255    422.2462
    408.5919    462.3017


```

Plot the fit and prediction intervals across the extrapolated fit range. By default, the fit is plotted over the range of the data. To see values extrapolated from the fit, set the upper x-limit of the axes to 2050 before plotting the fit. To plot prediction intervals, use `predobs` or `predfun` as the plot type.

```

plot(cdate,pop,'o')
xlim([1900,2050])
hold on
plot(curvefit,'predobs')
hold off

```



### Get the Model Equation

Enter the fit name to display the model equation, the fitted coefficients, and the confidence bounds for the fitted coefficients.

```
curvefit
```

```

curvefit =
  Linear model Poly3:
  curvefit(x) = p1*x^3 + p2*x^2 + p3*x + p4
  where x is normalized by mean 1890 and std 62.05
  Coefficients (with 95% confidence bounds):
  p1 =      0.921  (-0.9743, 2.816)
  p2 =      25.18  (23.57, 26.79)
  p3 =      73.86  (70.33, 77.39)
  p4 =      61.74  (59.69, 63.8)

```

To get only the model equation, use `formula`.

```

formula(curvefit)

ans =
'p1*x^3 + p2*x^2 + p3*x + p4'

```

### Get Coefficient Names and Values

Specify a coefficient by name.

```

p1 = curvefit.p1

p1 = 0.9210

p2 = curvefit.p2

p2 = 25.1834

```

Get all the coefficient names. Look at the fit equation (for example,  $f(x) = p1*x^3 + \dots$ ) to see the model terms for each coefficient.

```

coeffnames(curvefit)

ans = 4x1 cell
    {'p1'}
    {'p2'}
    {'p3'}
    {'p4'}

```

Get all the coefficient values.

```

coeffvalues(curvefit)

ans = 1x4
    0.9210    25.1834    73.8598    61.7444

```

### Get Confidence Bounds on the Coefficients

Use confidence bounds on coefficients to help you evaluate and compare fits. The confidence bounds on the coefficients determine their accuracy. Bounds that are far apart indicate uncertainty. If the bounds cross zero for linear coefficients, this means you cannot be sure that these coefficients differ from zero. If some model terms have coefficients of zero, then they are not helping with the fit.

```

confint(curvefit)

```



```
ans = 2×4
    -0.9743    23.5736    70.3308    59.6907
     2.8163    26.7931    77.3888    63.7981
```

### Examine Goodness-of-Fit Statistics

To get goodness-of-fit statistics at the command line, you can either:

- Open the Curve Fitter app. On the **Curve Fitter** tab, in the **Export** section, click **Export** and select **Export to Workspace** to export your fit and goodness of fit to the workspace.
- Specify the `gof` output argument using the `fit` function.

Recreate the fit specifying the `gof` and output arguments to get goodness-of-fit statistics and fitting algorithm information.

```
[curvefit,gof,output] = fit(cdate,pop,'poly3','normalize','on')
```


```
curvefit =
    Linear model Poly3:
    curvefit(x) = p1*x^3 + p2*x^2 + p3*x + p4
    where x is normalized by mean 1890 and std 62.05
    Coefficients (with 95% confidence bounds):
    p1 =      0.921  (-0.9743, 2.816)
    p2 =     25.18  (23.57, 26.79)
    p3 =     73.86  (70.33, 77.39)
    p4 =     61.74  (59.69, 63.8)
```

```
gof = struct with fields:
    sse: 149.7687
    rsquare: 0.9988
    dfe: 17
    adjrsquare: 0.9986
    rmse: 2.9682
```

```
output = struct with fields:
    numobs: 21
    numparam: 4
    residuals: [21x1 double]
    Jacobian: [21x4 double]
    exitflag: 1
    algorithm: 'QR factorization and solve'
    iterations: 1
```


Plot a histogram of the residuals to look for a roughly normal distribution.

```
histogram(output.residuals,10)
```



**Plot the Fit, Data, and Residuals**

```
plot(curvefit,cdate,pop,'fit','residuals')  
legend Location SouthWest  
subplot(2,1,1)  
legend Location NorthWest
```



### Find Methods

List every method that you can use with the fit.

```
methods(curvefit)
```

Methods for class cfit:

```
argnames      category      cfit      coeffnames      coeffvalues      confint      depend
```

For more information on how to use a fit method, see `cfit`.

### See Also

```
fit | plot | predint | confint
```

## Evaluate Surface Fit

This example shows how to work with a surface fit.

### Load Data and Fit a Polynomial Surface

```
load franke;  
surffit = fit([x,y],z,'poly23','normalize','on')
```

Linear model Poly23:

```
surffit(x,y) = p00 + p10*x + p01*y + p20*x^2 + p11*x*y + p02*y^2 + p21*x^2*y  
              + p12*x*y^2 + p03*y^3
```

where x is normalized by mean 1982 and std 868.6

and where y is normalized by mean 0.4972 and std 0.2897


Coefficients (with 95% confidence bounds):

```
p00 =      0.4253 (0.3928, 0.4578)  
p10 =     -0.106 (-0.1322, -0.07974)  
p01 =     -0.4299 (-0.4775, -0.3822)  
p20 =      0.02104 (0.001457, 0.04062)  
p11 =      0.07153 (0.05409, 0.08898)  
p02 =     -0.03084 (-0.05039, -0.01129)  
p21 =      0.02091 (0.001372, 0.04044)  
p12 =     -0.0321 (-0.05164, -0.01255)  
p03 =      0.1216 (0.09929, 0.1439)
```

The output displays the fitted model equation, the fitted coefficients, and the confidence bounds for the fitted coefficients.


### Plot the Fit, Data, Residuals, and Prediction Bounds

```
plot(surffit,[x,y],z)
```




Plot the residuals fit.

```
plot(surffit,[x,y],z,'Style','Residuals')
```



Plot prediction bounds on the fit.

```
plot(surffit,[x,y],z,'Style','predfunc')
```



### Evaluate the Fit at a Specified Point

Evaluate the fit at a specific point by specifying a value for  $x$  and  $y$ , using this form:  $z = \text{fittedmodel}(x,y)$ .

```
surffit(1000,0.5)
```

```
ans = 0.5673
```

### Evaluate the Fit Values at Many Points

```
xi = [500;1000;1200];
```

```
yi = [0.7;0.6;0.5];
```

```
surffit(xi,yi)
```

```
ans = 3×1
```

```
0.3771
```

```
0.4064
```

```
0.5331
```

Get prediction bounds on those values.

```
[ci, zi] = predint(surffit,[xi,yi])
```

```
ci = 3×2
```

```

0.0713    0.6829
0.1058    0.7069
0.2333    0.8330

```

```
zi = 3×1
```

```

0.3771
0.4064
0.5331

```

### Get the Model Equation

Enter the fit name to display the model equation, fitted coefficients, and confidence bounds for the fitted coefficients.

```
surffit
```

```

Linear model Poly23:
surffit(x,y) = p00 + p10*x + p01*y + p20*x^2 + p11*x*y + p02*y^2 + p21*x^2*y
              + p12*x*y^2 + p03*y^3
  where x is normalized by mean 1982 and std 868.6
  and where y is normalized by mean 0.4972 and std 0.2897
Coefficients (with 95% confidence bounds):
p00 =    0.4253    (0.3928, 0.4578)
p10 =   -0.106    (-0.1322, -0.07974)
p01 =   -0.4299    (-0.4775, -0.3822)
p20 =    0.02104   (0.001457, 0.04062)
p11 =    0.07153   (0.05409, 0.08898)
p02 =   -0.03084   (-0.05039, -0.01129)
p21 =    0.02091   (0.001372, 0.04044)
p12 =   -0.0321    (-0.05164, -0.01255)
p03 =    0.1216    (0.09929, 0.1439)

```

To get only the model equation, use `formula`.

```
formula(surffit)
```

```

ans =
'p00 + p10*x + p01*y + p20*x^2 + p11*x*y + p02*y^2 + p21*x^2*y + p12*x*y^2 + p03*y^3'

```

### Get Coefficient Names and Values

Specify a coefficient by name.

```
p00 = surffit.p00
```

```
p00 = 0.4253
```

```
p03 = surffit.p03
```

```
p03 = 0.1216
```

Get all the coefficient names. Look at the fit equation (for example,  $f(x,y) = p00 + p10*x \dots$ ) to see the model terms for each coefficient.

```
coeffnames(surffit)
```

```

ans = 9×1 cell
      {'p00'}

```



```
{'p10'}
{'p01'}
{'p20'}
{'p11'}
{'p02'}
{'p21'}
{'p12'}
{'p03'}
```

Get all the coefficient values.

```
coeffvalues(surffit)
```

```
ans = 1×9
```

```
0.4253 -0.1060 -0.4299 0.0210 0.0715 -0.0308 0.0209 -0.0321 0.1216
```

### Get Confidence Bounds on the Coefficients

Use confidence bounds on coefficients to help you evaluate and compare fits. The confidence bounds on the coefficients determine their accuracy. Bounds that are far apart indicate uncertainty. If the bounds cross zero for linear coefficients, this means you cannot be sure that these coefficients differ from zero. If some model terms have coefficients of zero, then they are not helping with the fit.

```
confint(surffit)
```

```
ans = 2×9
```

```
0.3928 -0.1322 -0.4775 0.0015 0.0541 -0.0504 0.0014 -0.0516 0.0993
0.4578 -0.0797 -0.3822 0.0406 0.0890 -0.0113 0.0404 -0.0126 0.1439
```

### Find Methods

List every method that you can use with the fit.

```
methods(surffit)
```

```
Methods for class sfit:
```

```
argnames category coeffnames coeffvalues confint dependnames differ
```

For more information on how to use a fit method, see `sfit`.

### See Also

```
fit | plot | predint | confint
```

## Compare Fits Programmatically

This example shows how to fit and compare polynomials up to sixth degree using Curve Fitting Toolbox™, fitting some census data. It also shows how to fit a single-term exponential equation and compare this to the polynomial models.

The steps show how to:

- Load data and create fits using different library models.
- Search for the best fit by comparing graphical fit results, and by comparing numerical fit results including the fitted coefficients and goodness of fit statistics.

### Load and Plot the Data

The data for this example is the file census.mat.


```
load census
```

The workspace contains two new variables:

- cdate is a column vector containing the years 1790 to 1990 in 10-year increments.
- pop is a column vector with the U.S. population figures that correspond to the years in cdate.

```
whos cdate pop  
plot(cdate,pop,'o')
```

| Name  | Size | Bytes | Class  | Attributes |
|-------|------|-------|--------|------------|
| cdate | 21x1 | 168   | double |            |
| pop   | 21x1 | 168   | double |            |




### Create and Plot a Quadratic

Use the fit function to fit a polynomial to data. You specify a quadratic, or second-degree polynomial, using 'poly2'. The first output from fit is the polynomial, and the second output, gof, contains the goodness of fit statistics you will examine in a later step.

```
[population2,gof] = fit(cdate,pop,'poly2');
```

To plot the fit, use the plot method.

```
plot(population2,cdate,pop);  
% Move the legend to the top left corner.  
legend('Location','NorthWest');
```



### Create and Plot a Selection of Polynomials

To fit polynomials of different degrees, change the `fitype`, e.g., for a cubic or third-degree polynomial use `'poly3'`. The scale of the input, `cdate`, is quite large, so you can obtain better results by centering and scaling the data. To do this, use the `'Normalize'` option.


```
population3 = fit(cdate,pop,'poly3','Normalize','on');
population4 = fit(cdate,pop,'poly4','Normalize','on');
population5 = fit(cdate,pop,'poly5','Normalize','on');
population6 = fit(cdate,pop,'poly6','Normalize','on');
```

A simple model for population growth tells us that an exponential equation should fit this census data well. To fit a single term exponential model, use `'exp1'` as the `fitype`.

```
populationExp = fit(cdate,pop,'exp1');
```

Plot all the fits at once, and add a meaningful legend in the top left corner of the plot.


```
hold on
plot(population3,'b');
plot(population4,'g');
plot(population5,'m');
plot(population6,'b--');
plot(populationExp,'r--');
hold off
legend('cdate v pop','poly2','poly3','poly4','poly5','poly6','exp1',...
      'Location','NorthWest');
```



### Plot the Residuals to Evaluate the Fit


To plot residuals, specify 'residuals' as the plot type in the plot method.

```
plot(population2,cdate,pop,'residuals');
```



The fits and residuals for the polynomial equations are all similar, making it difficult to choose the best one. If the residuals display a systematic pattern, it is a clear sign that the model fits the data poorly.

```
plot(populationExp,cdate,pop,'residuals');
```




The fit and residuals for the single-term exponential equation indicate it is a poor fit overall. Therefore, it is a poor choice and you can remove the exponential fit from the candidates for best fit.

### Examine Fits Beyond the Data Range

Examine the behavior of the fits up to the year 2050. The goal of fitting the census data is to extrapolate the best fit to predict future population values. By default, the fit is plotted over the range of the data. To plot a fit over a different range, set the x-limits of the axes before plotting the fit. For example, to see values extrapolated from the fit, set the upper x-limit to 2050.

```
plot(cdate,pop, 'o');
xlim([1900, 2050]);
hold on
plot(population6);
hold off
```




Examine the plot. The behavior of the sixth-degree polynomial fit beyond the data range makes it a poor choice for extrapolation and you can reject this fit.

### Plot Prediction Intervals

To plot prediction intervals, use 'predobs' or 'predfun' as the plot type. For example, to see the prediction bounds for the fifth-degree polynomial for a new observation up to year 2050:


```
plot(cdate,pop,'o');  
xlim([1900, 2050])  
hold on  
plot(population5,'predobs');  
hold off
```





Plot prediction intervals for the cubic polynomial up to year 2050.

```
plot(cdate,pop,'o');  
xlim([1900, 2050])  
hold on  
plot(population3,'predobs')  
hold off
```



### Examine Goodness-of-Fit Statistics

The struct `gof` shows the goodness-of-fit statistics for the 'poly2' fit. When you created the 'poly2' fit with the fit function in an earlier step, you specified the `gof` output argument.

`gof`

`gof =`

```
struct with fields:
    sse: 159.0293
    rsquare: 0.9987
    dfe: 18
    adjrsquare: 0.9986
    rmse: 2.9724
```

Examine the sum of squares due to error (SSE) and the adjusted R-square statistics to help determine the best fit. The SSE statistic is the least-squares error of the fit, with a value closer to zero indicating a better fit. The adjusted R-square statistic is generally the best indicator of the fit quality when you add additional coefficients to your model.

The large SSE for 'exp1' indicates it is a poor fit, which you already determined by examining the fit and residuals. The lowest SSE value is associated with 'poly6'. However, the behavior of this fit

beyond the data range makes it a poor choice for extrapolation, so you already rejected this fit by examining the plots with new axis limits.

The next best SSE value is associated with the fifth-degree polynomial fit, 'poly5', suggesting it might be the best fit. However, the SSE and adjusted R-square values for the remaining polynomial fits are all very close to each other. Which one should you choose?

### Compare the Coefficients and Confidence Bounds to Determine the Best Fit

Resolve the best fit issue by examining the coefficients and confidence bounds for the remaining fits: the fifth-degree polynomial and the quadratic.

Examine population2 and population5 by displaying the models, the fitted coefficients, and the confidence bounds for the fitted coefficients:

```
population2
```

```
population5
```

```
population2 =
```

```
Linear model Poly2:
population2(x) = p1*x^2 + p2*x + p3
Coefficients (with 95% confidence bounds):
  p1 =    0.006541 (0.006124, 0.006958)
  p2 =   -23.51 (-25.09, -21.93)
  p3 =   2.113e+04 (1.964e+04, 2.262e+04)
```

```
population5 =
```

```
Linear model Poly5:
population5(x) = p1*x^5 + p2*x^4 + p3*x^3 + p4*x^2 + p5*x + p6
  where x is normalized by mean 1890 and std 62.05
Coefficients (with 95% confidence bounds):
  p1 =    0.5877 (-2.305, 3.48)
  p2 =    0.7047 (-1.684, 3.094)
  p3 =   -0.9193 (-10.19, 8.356)
  p4 =    23.47 (17.42, 29.52)
  p5 =    74.97 (68.37, 81.57)
  p6 =    62.23 (59.51, 64.95)
```

You can also get the confidence intervals by using confint.

```
ci = confint(population5)
```

```
ci =
```

```
-2.3046  -1.6841  -10.1943  17.4213  68.3655  59.5102
 3.4801   3.0936   8.3558  29.5199  81.5696  64.9469
```

The confidence bounds on the coefficients determine their accuracy. Check the fit equations (e.g.  $f(x)=p1*x+p2*x...$ ) to see the model terms for each coefficient. Note that p2 refers to the  $p2*x$  term in 'poly2' and the  $p2*x^4$  term in 'poly5'. Do not compare normalized coefficients directly with non-normalized coefficients.

The bounds cross zero on the p1, p2, and p3 coefficients for the fifth-degree polynomial. This means you cannot be sure that these coefficients differ from zero. If the higher order model terms may have coefficients of zero, they are not helping with the fit, which suggests that this model over fits the census data.

The fitted coefficients associated with the constant, linear, and quadratic terms are nearly identical for each normalized polynomial equation. However, as the polynomial degree increases, the coefficient bounds associated with the higher degree terms cross zero, which suggests over fitting.

However, the small confidence bounds do not cross zero on p1, p2, and p3 for the quadratic fit, indicating that the fitted coefficients are known fairly accurately.

Therefore, after examining both the graphical and numerical fit results, you should select the quadratic population2 as the best fit to extrapolate the census data.

### Evaluate the Best Fit at New Query Points

Now you have selected the best fit, population2, for extrapolating this census data, evaluate the fit for some new query points.

```
cdateFuture = (2000:10:2020).';
popFuture = population2(cdateFuture)
```

```
popFuture =
```

```
    274.6221
    301.8240
    330.3341
```

To compute 95% confidence bounds on the prediction for the population in the future, use the predint method:


```
ci = predint(population2,cdateFuture,0.95,'observation')
```

```
ci =
```

```
    266.9185    282.3257
    293.5673    310.0807
    321.3979    339.2702
```

Plot the predicted future population, with confidence intervals, against the fit and data.

```
plot(cdate,pop,'o');
xlim([1900, 2040])
hold on
plot(population2)
h = errorbar(cdateFuture,popFuture,popFuture-ci(:,1),ci(:,2)-popFuture,'.');
hold off
legend('cdate v pop','poly2','prediction','Location','NorthWest')
```



## Evaluating Goodness of Fit

|                                                |
|------------------------------------------------|
| <b>In this section...</b>                      |
| “How to Evaluate Goodness of Fit” on page 7-42 |
| “Goodness-of-Fit Statistics” on page 7-43      |

### How to Evaluate Goodness of Fit

After fitting data with one or more models, you should evaluate the goodness of fit. A visual examination of the fitted curve displayed in the Curve Fitter app should be your first step. Beyond that, the toolbox provides these methods to assess goodness of fit for both linear and nonlinear parametric fits:

- “Goodness-of-Fit Statistics” on page 7-43
- “Residual Analysis” on page 7-46
- “Confidence and Prediction Bounds” on page 7-50

As is common in statistical literature, the term *goodness of fit* is used here in several senses: A “good fit” might be a model

- that your data could reasonably have come from, given the assumptions of least-squares fitting
- in which the model coefficients can be estimated with little uncertainty
- that explains a high proportion of the variability in your data, and is able to predict new observations with high certainty

A particular application might dictate still other aspects of model fitting that are important to achieving a good fit, such as a simple model that is easy to interpret. The methods described here can help you determine goodness of fit in all these senses.

These methods group into two types: graphical and numerical. Plotting residuals and prediction bounds are graphical methods that aid visual interpretation, while computing goodness-of-fit statistics and coefficient confidence bounds yield numerical measures that aid statistical reasoning.

Generally speaking, graphical measures are more beneficial than numerical measures because they allow you to view the entire data set at once, and they can easily display a wide range of relationships between the model and the data. The numerical measures are more narrowly focused on a particular aspect of the data and often try to compress that information into a single number. In practice, depending on your data and analysis requirements, you might need to use both types to determine the best fit.

Note that it is possible that none of your fits can be considered suitable for your data, based on these methods. In this case, it might be that you need to select a different model. It is also possible that all the goodness-of-fit measures indicate that a particular fit is suitable. However, if your goal is to extract fitted coefficients that have physical meaning, but your model does not reflect the physics of the data, the resulting coefficients are useless. In this case, understanding what your data represents and how it was measured is just as important as evaluating the goodness of fit.

## Goodness-of-Fit Statistics

After using graphical methods to evaluate the goodness of fit, you should examine the goodness-of-fit statistics. Curve Fitting Toolbox software supports these goodness-of-fit statistics for parametric models:

- The sum of squares due to error (SSE)
- R-square
- Degrees of freedom for error (DFE)
- Adjusted R-square
- Root mean squared error (RMSE)

For the current fit, these statistics are displayed in the **Results** pane in the Curve Fitter app. For all fits in the current curve-fitting session, you can compare the goodness-of-fit statistics in the **Table Of Fits** pane.

To examine goodness-of-fit statistics at the command line, either:

- In the Curve Fitter app, export your fit and goodness of fit to the workspace. On the **Curve Fitter** tab, in the **Export** section, click **Export** and select **Export to Workspace**.
- Specify the `gof` output argument with the `fit` function.

### Sum of Squares Due to Error

This statistic measures the total deviation of the response values from the fit to the response values. It is also called the summed square of residuals and is usually labeled as *SSE*.

$$SSE = \sum_{i=1}^n w_i (y_i - \hat{y}_i)^2$$

A value closer to 0 indicates that the model has a smaller random error component, and that the fit will be more useful for prediction.

### R-Square

This statistic measures how successful the fit is in explaining the variation of the data. Put another way, R-square is the square of the correlation between the response values and the predicted response values. It is also called the square of the multiple correlation coefficient and the coefficient of multiple determination.

R-square is defined as the ratio of the sum of squares of the regression (*SSR*) and the total sum of squares (*SST*). *SSR* is defined as

$$SSR = \sum_{i=1}^n w_i (\hat{y}_i - \bar{y})^2$$

*SST* is also called the sum of squares about the mean, and is defined as

$$SST = \sum_{i=1}^n w_i (y_i - \bar{y})^2$$

where  $SST = SSR + SSE$ . Given these definitions, R-square is expressed as

$$\text{R-square} = \frac{SSR}{SST} = 1 - \frac{SSE}{SST}$$

R-square can take on any value between 0 and 1, with a value closer to 1 indicating that a greater proportion of variance is accounted for by the model. For example, an R-square value of 0.8234 means that the fit explains 82.34% of the total variation in the data about the average.

If you increase the number of fitted coefficients in your model, R-square will increase although the fit may not improve in a practical sense. To avoid this situation, you should use the degrees of freedom adjusted R-square statistic described below.

Note that it is possible to get a negative R-square for equations that do not contain a constant term. Because R-square is defined as the proportion of variance explained by the fit, if the fit is actually worse than just fitting a horizontal line then R-square is negative. In this case, R-square cannot be interpreted as the square of a correlation. Such situations indicate that a constant term should be added to the model.

### Degrees of Freedom Adjusted R-Square

This statistic uses the R-square statistic defined above, and adjusts it based on the residual degrees of freedom. The residual degrees of freedom is defined as the number of response values  $n$  minus the number of fitted coefficients  $m$  estimated from the response values.

$$v = n - m$$

$v$  indicates the number of independent pieces of information involving the  $n$  data points that are required to calculate the sum of squares. Note that if parameters are bounded and one or more of the estimates are at their bounds, then those estimates are regarded as fixed. The degrees of freedom is increased by the number of such parameters.

The adjusted R-square statistic is generally the best indicator of the fit quality when you compare two models that are *nested* — that is, a series of models each of which adds additional coefficients to the previous model.

$$\text{adjusted R-square} = 1 - \frac{SSE(n-1)}{SST(v)}$$

The adjusted R-square statistic can take on any value less than or equal to 1, with a value closer to 1 indicating a better fit. Negative values can occur when the model contains terms that do not help to predict the response.

### Root Mean Squared Error

This statistic is also known as the fit standard error and the standard error of the regression. It is an estimate of the standard deviation of the random component in the data, and is defined as

$$RMSE = s = \sqrt{MSE}$$

where  $MSE$  is the mean square error or the residual mean square

$$MSE = \frac{SSE}{v}$$

Just as with  $SSE$ , an  $MSE$  value closer to 0 indicates a fit that is more useful for prediction.



**See Also**

fit

**Related Examples**

- “Generate Code and Export Fits to the Workspace” on page 7-13
- “Evaluate Curve Fit” on page 7-16
- “Evaluate Surface Fit” on page 7-24

## Residual Analysis

### Plotting and Analysing Residuals

The residuals from a fitted model are defined as the differences between the response data and the fit to the response data at each predictor value.

$$\text{residual} = \text{data} - \text{fit}$$


You can display the residuals in the Curve Fitter app by clicking **Residuals Plot** in the **Visualization** section of the **Curve Fitter** tab.

Mathematically, the residual for a specific predictor value is the difference between the response value  $y$  and the predicted response value  $\hat{y}$ .

$$r = y - \hat{y}$$


Assuming the model you fit to the data is correct, the residuals approximate the random errors. Therefore, if the residuals appear to behave randomly, it suggests that the model fits the data well. However, if the residuals display a systematic pattern, it is a clear sign that the model fits the data poorly. Always bear in mind that many results of model fitting, such as confidence bounds, will be invalid should the model be grossly inappropriate for the data.

A graphical display of the residuals for a first-degree polynomial fit is shown below. The top plot shows that the residuals are calculated as the vertical distance from the data point to the fitted curve. The bottom plot displays the residuals relative to the fit, which is the zero line.



The residuals appear randomly scattered around zero indicating that the model describes the data well.

A graphical display of the residuals for a second-degree polynomial fit is shown below. The model includes only the quadratic term, and does not include a linear or constant term.




The residuals are systematically positive for much of the data range indicating that this model is a poor fit for the data.

## Example: Residual Analysis

This example fits several polynomial models to generated data and evaluates how well those models fit the data and how precisely they can predict. The data is generated from a cubic curve, and there is a large gap in the range of the x variable where no data exist.

```
x = [1:0.1:3 9:0.1:10]';
c = [2.5 -0.5 1.3 -0.1];
y = c(1) + c(2)*x + c(3)*x.^2 + c(4)*x.^3 + (rand(size(x))-0.5);
```

Fit the data in the Curve Fitter app using a cubic polynomial and a fifth-degree polynomial. The data, fits, and residuals are shown below. You can display residuals in the Curve Fitter app by clicking **Residuals Plot** in the **Visualization** section of the **Curve Fitter** tab.




Both models appear to fit the data well, and the residuals appear to be randomly distributed around zero. Therefore, a graphical evaluation of the fits does not reveal any obvious differences between the two equations.

Look at the numerical fit results in the **Results** pane and compare the confidence bounds for the coefficients.

The results show that the cubic fit coefficients are accurately known (bounds are small), while the quintic fit coefficients are not accurately known. As expected, the fit results for `poly3` are reasonable because the generated data follows a cubic curve. The 95% confidence bounds on the fitted coefficients indicate that they are acceptably precise. However, the 95% confidence bounds for `poly5` indicate that the fitted coefficients are not known precisely.

The goodness-of-fit statistics are shown in the **Table Of Fits** pane. By default, the adjusted R-square and RMSE statistics are displayed in the table. The statistics do not reveal a substantial difference between the two equations. To choose statistics to display or hide, right-click the column headers.

The 95% nonsimultaneous prediction bounds for new observations are shown below. To display prediction bounds in the Curve Fitter app, select 95% from the **Prediction Bounds** list in the **Visualization** section of the **Curve Fitter** tab.



The prediction bounds for `poly3` indicate that new observations can be predicted with a small uncertainty throughout the entire data range. This is not the case for `poly5`. It has wider prediction bounds in the area where no data exist, apparently because the data does not contain enough information to estimate the higher degree polynomial terms accurately. In other words, a fifth-degree polynomial overfits the data.

The 95% prediction bounds for the fitted function using `poly5` are shown below. As you can see, the uncertainty in predicting the function is large in the center of the data. Therefore, you would conclude that more data must be collected before you can make precise predictions using a fifth-degree polynomial.

In conclusion, you should examine all available goodness-of-fit measures before deciding on the fit that is best for your purposes. A graphical examination of the fit and residuals should always be your initial approach. However, some fit characteristics are revealed only through numerical fit results, statistics, and prediction bounds.

## Confidence and Prediction Bounds

### In this section...

“About Confidence and Prediction Bounds” on page 7-50

“Confidence Bounds on Coefficients” on page 7-50

“Prediction Bounds on Fits” on page 7-51

“Calculate Prediction Intervals from the Command Line” on page 7-53

“Calculate Prediction Bounds Using Curve Fitter App” on page 7-54

### About Confidence and Prediction Bounds

Curve Fitting Toolbox software lets you calculate confidence bounds for the fitted coefficients, and prediction bounds for new observations or for the fitted function. Additionally, for prediction bounds, you can calculate simultaneous bounds, which take into account all predictor values, or you can calculate nonsimultaneous bounds, which take into account only individual predictor values. The coefficient confidence bounds are presented numerically, while the prediction bounds are displayed graphically and are also available numerically.

The available confidence and prediction bounds are summarized below.

#### Types of Confidence and Prediction Bounds

| Interval Type       | Description                                              |
|---------------------|----------------------------------------------------------|
| Fitted coefficients | Confidence bounds for the fitted coefficients            |
| New observation     | Prediction bounds for a new observation (response value) |
| New function        | Prediction bounds for a new function value               |

**Note** Prediction bounds are also often described as confidence bounds because you are calculating a confidence interval for a predicted response.

Confidence and prediction bounds define the lower and upper values of the associated interval, and define the width of the interval. The width of the interval indicates how uncertain you are about the fitted coefficients, the predicted observation, or the predicted fit. For example, a very wide interval for the fitted coefficients can indicate that you should use more data when fitting before you can say anything very definite about the coefficients.

The bounds are defined with a level of certainty that you specify. The level of certainty is often 95%, but it can be any value such as 90%, 99%, 99.9%, and so on. For example, you might want to take a 5% chance of being incorrect about predicting a new observation. Therefore, you would calculate a 95% prediction interval. This interval indicates that you have a 95% chance that the new observation is actually contained within the lower and upper prediction bounds.

### Confidence Bounds on Coefficients

The confidence bounds for fitted coefficients are given by

$$C = b \pm t\sqrt{S}$$

where  $b$  are the coefficients produced by the fit,  $t$  depends on the confidence level, and is computed using the inverse of Student's  $t$  cumulative distribution function, and  $S$  is a vector of the diagonal elements from the estimated covariance matrix of the coefficient estimates,  $(X^T X)^{-1} s^2$ . In a linear fit,  $X$  is the design matrix, while for a nonlinear fit  $X$  is the Jacobian of the fitted values with respect to the coefficients.  $X^T$  is the transpose of  $X$ , and  $s^2$  is the mean squared error.

The confidence bounds are displayed in the **Results** pane in the Curve Fitter app using the following format.

```
p1 = 1.275 (1.113, 1.437)
```

The fitted value for the coefficient p1 is 1.275, the lower bound is 1.113, the upper bound is 1.437, and the interval width is 0.324. By default, the confidence level for the bounds is 95%.

You can calculate confidence intervals at the command line with the `confint` function.

## Prediction Bounds on Fits

As mentioned previously, you can calculate prediction bounds for the fitted curve. The prediction is based on an existing fit to the data. Additionally, the bounds can be simultaneous and measure the confidence for all predictor values, or they can be nonsimultaneous and measure the confidence only for a single predetermined predictor value. If you are predicting a new observation, nonsimultaneous bounds measure the confidence that the new observation lies within the interval given a single predictor value. Simultaneous bounds measure the confidence that a new observation lies within the interval regardless of the predictor value.

| Bound Type      | Observation                 | Functional            |
|-----------------|-----------------------------|-----------------------|
| Simultaneous    | $y \pm f\sqrt{s^2 + xSx^T}$ | $y \pm f\sqrt{xSx^T}$ |
| Nonsimultaneous | $y \pm t\sqrt{s^2 + xSx^T}$ | $y \pm t\sqrt{xSx^T}$ |

Where:

- $s^2$  is the mean squared error
- $t$  depends on the confidence level, and is computed using the inverse of Student's  $t$  cumulative distribution function
- $f$  depends on the confidence level, and is computed using the inverse of the  $F$  cumulative distribution function.
- $S$  is the covariance matrix of the coefficient estimates,  $(X^T X)^{-1} s^2$ .
- $x$  is a row vector of the design matrix or Jacobian evaluated at a specified predictor value.

You can graphically display prediction bounds using the Curve Fitter app. In the Curve Fitter app, you can display nonsimultaneous prediction bounds for new observations. On the **Curve Fitter** tab, in the **Visualization** section, select a level of certainty from the **Prediction Bounds** list. You can change this level to any value by selecting **Custom** from the list.

You can display numerical prediction bounds of any type at the command line with the `predint` function.

To understand the quantities associated with each type of prediction interval, recall that the data, fit, and residuals are related through the formula

$$data = fit + residuals$$

where the fit and residuals terms are estimates of terms in the formula

$$data = model + random\ error$$

Suppose you plan to take a new observation at the predictor value  $x_{n+1}$ . Call the new observation  $y_{n+1}(x_{n+1})$  and the associated error  $\varepsilon_{n+1}$ . Then

$$y_{n+1}(x_{n+1}) = f(x_{n+1}) + \varepsilon_{n+1}$$

where  $f(x_{n+1})$  is the true but unknown function you want to estimate at  $x_{n+1}$ . The likely values for the new observation or for the estimated function are provided by the nonsimultaneous prediction bounds.

If instead you want the likely value of the new observation to be associated with any predictor value, the previous equation becomes

$$y_{n+1}(x) = f(x) + \varepsilon$$

The likely values for this new observation or for the estimated function are provided by the simultaneous prediction bounds.


The types of prediction bounds are summarized below.

### Types of Prediction Bounds

| Type of Bound | Simultaneous or Nonsimultaneous | Associated Equation        |
|---------------|---------------------------------|----------------------------|
| Observation   | Nonsimultaneous                 | $y_{n+1}(x_{n+1})$         |
|               | Simultaneous                    | $y_{n+1}(x)$ , for all $x$ |
| Function      | Nonsimultaneous                 | $f(x_{n+1})$               |
|               | Simultaneous                    | $f(x)$ , for all $x$       |

The nonsimultaneous and simultaneous prediction bounds for a new observation and the fitted function are shown below. Each graph contains three curves: the fit, the lower confidence bounds, and the upper confidence bounds. The fit is a single-term exponential to generated data and the bounds reflect a 95% confidence level. Note that the intervals associated with a new observation are wider than the fitted function intervals because of the additional uncertainty in predicting a new response value (the curve plus random errors).





## Calculate Prediction Intervals from the Command Line

Calculate and plot observation and functional prediction intervals for a fit to noisy data.

Generate noisy data with an exponential trend.

```
x = (0:0.2:5)';
y = 2*exp(-0.2*x) + 0.5*randn(size(x));
```

Fit a curve to the data using a single-term exponential.

```
fitresult = fit(x,y,'exp1');
```

Compute 95% observation and functional prediction intervals, both simultaneous and nonsimultaneous. Nonsimultaneous bounds are for individual elements of  $x$ ; simultaneous bounds are for all elements of  $x$ .

```
p11 = predint(fitresult,x,0.95,'observation','off');
p12 = predint(fitresult,x,0.95,'observation','on');
p21 = predint(fitresult,x,0.95,'functional','off');
p22 = predint(fitresult,x,0.95,'functional','on');
```

Plot the data, fit, and prediction intervals. Observation bounds are wider than functional bounds because they measure the uncertainty of predicting the fitted curve plus the random variation in the new observation.

```
subplot(2,2,1)
plot(fitresult,x,y), hold on, plot(x,p11,'m--'), xlim([0 5]), ylim([-1 5])
title('Nonsimultaneous Observation Bounds','FontSize',9)
legend off
```

```
subplot(2,2,2)
plot(fitresult,x,y), hold on, plot(x,p12,'m--'), xlim([0 5]), ylim([-1 5])
```


```

title('Simultaneous Observation Bounds','FontSize',9)
legend off

subplot(2,2,3)
plot(fitresult,x,y), hold on, plot(x,p21,'m--'), xlim([0 5]), ylim([-1 5])
title('Nonsimultaneous Functional Bounds','FontSize',9)
legend off

subplot(2,2,4)
plot(fitresult,x,y), hold on, plot(x,p22,'m--'), xlim([0 5]), ylim([-1 5])
title('Simultaneous Functional Bounds','FontSize',9)
legend({'Data','Fitted curve','Prediction intervals'},...
       'FontSize',8,'Location','northeast')

```



## Calculate Prediction Bounds Using Curve Fitter App

Load the census data set.


```
load census
```

The variables `cdate` and `pop` contain data for the date and population when the census was taken.


Open the Curve Fitter app.

```
curveFitter
```

In the app, select the data variables for the fit. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select **cdate** as the **X data** value and **pop** as the **Y data** value.





The app plots the data points as you select the variables.





The plot shows the census data and the linear fit for the data.

Plot the 95% prediction bounds for the fit. In the **Visualization** section of the Curve Fitter tab, select 95% for **Prediction Bounds**.



The plot now shows the 95% prediction intervals in addition to the census data and linear fit.

To plot the 60% prediction bounds for the fit, you must specify a custom confidence level. In the **Visualization** section of the Curve Fitter tab, select Custom for **Prediction Bounds**. In the **Set Prediction Bounds** dialog box, type 60 in Confidence level (%) box, and click **OK**.



The plot now shows the 60% prediction intervals in addition to the census data and linear fit. Together, the two plots show that the 60% prediction intervals lie closer to the linear fit than the 95% prediction intervals.

## Differentiating and Integrating a Fit

This example shows how to find the first and second derivatives of a fit, and the integral of the fit, at the predictor values.

Create a baseline sinusoidal signal:

```
xdata = (0:.1:2*pi)';  
y0 = sin(xdata);
```

Add noise to the signal:

```
noise = 2*y0.*randn(size(y0)); % Response-dependent noise  
ydata = y0 + noise;
```

Fit the noisy data with a custom sinusoidal model:


```
f = fittype('a*sin(b*x)');  
fit1 = fit(xdata,ydata,f,'StartPoint',[1 1]);
```

Find the derivatives of the fit at the predictors:

```
[d1,d2] = differentiate(fit1,xdata);
```


Plot the data, the fit, and the derivatives:

```
subplot(3,1,1)  
plot(fit1,xdata,ydata) % cfit plot method  
subplot(3,1,2)  
plot(xdata,d1,'m') % double plot method  
grid on  
legend('1st derivative')  
subplot(3,1,3)  
plot(xdata,d2,'c') % double plot method  
grid on  
legend('2nd derivative')
```



Note that derivatives can also be computed and plotted directly with the `cfit` plot method, as follows. The plot method, however, does not return data on the derivatives.

```
plot(fit1,xdata,ydata,{'fit','deriv1','deriv2'})
```




Find the integral of the fit at the predictors:

```
int = integrate(fit1,xdata,0);
```

Plot the data, the fit, and the integral:


```
subplot(2,1,1)
plot(fit1,xdata,ydata) % cfit plot method
subplot(2,1,2)
plot(xdata,int,'m') % double plot method
grid on
legend('integral')
```





Note that integrals can also be computed and plotted directly with the `cfits` plot method, as follows. The plot method, however, does not return data on the integral.

```
plot(fit1,xdata,ydata,{'fit','integral'})
```



# Spline Fitting



# About Splines

---

- “Introducing Spline Fitting” on page 8-2
- “Curve Fitting Toolbox Splines and MATLAB Splines” on page 8-4

## Introducing Spline Fitting

### In this section...

“Spline Overview” on page 8-2

“Interactive Spline Fitting” on page 8-2

“Programmatic Spline Fitting” on page 8-3

### Spline Overview

The Curve Fitting Toolbox spline functions are a collection of tools for creating, viewing, and analyzing spline approximations of data. Splines are smooth piecewise polynomials that you can use to represent functions over large intervals, where it would be impractical to use a single approximating polynomial.

The spline functionality includes a tool that provides easy access to functions for creating, visualizing, and manipulating splines. The toolbox also contains functions that enable you to evaluate, plot, combine, differentiate, and integrate splines. Because all toolbox functions are implemented in the open MATLAB language, you can inspect the algorithms, modify the source code, and create your own custom functions.

Key spline features:

- Tools that let you create, view, and manipulate splines and manage and compare spline approximations
- Functions for advanced spline operations, including differentiation, integration, break/knot manipulation, and optimal knot placement
- Support for piecewise polynomial form (ppform) and basis form (B-form) splines
- Support for tensor-product splines and rational splines (including NURBS)

In Curve Fitting Toolbox you can fit splines interactively or programmatically.

### Interactive Spline Fitting

Use the Curve Fitter app or the Spline Tool to interactively create spline fits.

Open the Curve Fitter app by entering `curveFitter` at the MATLAB command line. Alternatively, on the **Apps** tab, in the **Math, Statistics and Optimization** group, click Curve Fitter. The Curve Fitter app supports the same spline fitting options as the `fit` function.

Open the Spline Tool by entering `splinetool` at the command line. The Spline Tool supports all spline functions. Use the tool to do the following:

- Vary spline parameters and tolerances.
- View and modify data, breaks, knots, and weights.
- View the error of the spline, or the spline's first or second derivative.
- Observe the toolbox commands that generated your spline.
- Create and import data, including built-in instructive data sets, and save splines to the workspace.

For more information, see `splinetool`.

## Programmatic Spline Fitting

Use the `fit` function to do the following:

- Fit cubic spline interpolants to curves or surfaces.
- Fit smoothing splines and shape-preserving cubic spline interpolants only to curves.
- Fit thin-plate splines only to surfaces.

Curve Fitting Toolbox also provides specific splines functions that allow more control and flexibility when you fit splines. For example, use the `csapi` function, instead of `fit` with `fitType` set to `"cubicinterp"`, if you want to do one of the following:

- Combine the results with other splines, for example, by addition.
- Create vector-valued splines. You can use `csapi` with scalars, vectors, matrices, and ND-arrays. The `fit` function supports only scalar-valued splines.
- Create other types of splines such as `ppform`, B-form, tensor-product, rational, and `stform` thin-plate splines.
- Create splines without data.
- Specify breaks, optimize knot placement, and use specialized functions for spline manipulation such as differentiation and integration.

For more information on how to create splines including B-form, tensor-product, NURBs, and other rational splines, see “Spline Construction”.

## See Also

### Apps

Curve Fitter

### Functions

`splinetool` | `fit` | `csapi`

## Curve Fitting Toolbox Splines and MATLAB Splines

### In this section...

“Curve Fitting Toolbox Splines” on page 8-4

“Splines” on page 8-5

“MATLAB Splines” on page 8-5

“Expected Background” on page 8-6

“Vector Data Type Support” on page 8-6

“Spline Function Naming Conventions” on page 8-6

“Arguments for Curve Fitting Toolbox Spline Functions” on page 8-7

“Acknowledgments” on page 8-7

### Curve Fitting Toolbox Splines

Curve Fitting Toolbox spline functions contain versions of the essential MATLAB programs of the B-spline package (extended to handle also *vector*-valued splines) as described in *A Practical Guide to Splines*, (Applied Math. Sciences Vol. 27, Springer Verlag, New York (1978), xxiv + 392p; revised edition (2001), xviii+346p), hereafter referred to as *PGS*. The toolbox makes it easy to create and work with piecewise-polynomial functions.

The typical use envisioned for this toolbox involves the construction and subsequent use of a piecewise-polynomial approximation. This construction would involve data fitting, but there is a wide range of possible data that could be fit. In the simplest situation, one is given points  $(t_i, y_i)$  and is looking for a piecewise-polynomial function  $f$  that satisfies  $f(t_i) = y_i$ , all  $i$ , more or less. An exact fit would involve *interpolation*, an approximate fit might involve *least-squares approximation* or the *smoothing spline*. But the function to be approximated may also be described in more implicit ways, for example as the solution of a differential or integral equation. In such a case, the data would be of the form  $(Af)(t_i)$ , with  $A$  some differential or integral operator. On the other hand, one might want to construct a spline *curve* whose exact location is less important than is its overall shape. Finally, in all of this, one might be looking for functions of more than one variable, such as *tensor product splines*.

Care has been taken to make this work as painless and intuitive as possible. In particular, the user need not worry about just how splines are constructed or stored for later use, nor need the casual user worry about such items as “breaks” or “knots” or “coefficients”. It is enough to know that each function constructed is just another variable that is freely usable as input (where appropriate) to many of the commands, including all commands beginning with `fn`, which stands for `function`. At times, it may be also useful to know that, internal to the toolbox, splines are stored in different forms, with the command `fn2fm` available to convert between forms.

At present, the toolbox supports two major forms for the representation of piecewise-polynomial functions, because each has been found to be superior to the other in certain common situations. The B-form is particularly useful during the construction of a spline, while the `ppform` is more efficient when the piecewise-polynomial function is to be evaluated extensively. These two forms are almost exactly the B-representation and the `pp` representation used in *A Practical Guide to Splines*.

But, over the years, the Curve Fitting Toolbox spline functions have gone beyond the programs in *A Practical Guide to Splines*. The toolbox now supports the ‘scattered translates’ form, or `stform`, in order to handle the construction and use of bivariate thin-plate splines, and also two ways to represent rational splines, the `rBform` and the `rpform`, in order to handle NURBS.



Splines can be very effective for data fitting because the linear systems to be solved for this are banded, hence the work needed for their solution, done properly, grows only linearly with the number of data points. In particular, the MATLAB sparse matrix facilities are used in the Curve Fitting Toolbox spline functions when that is more efficient than the toolbox's own equation solver, `slvblk`, which relies on the fact that some of the linear systems here are even almost block diagonal.

All polynomial spline construction commands are equipped to produce bivariate (or even multivariate) piecewise-polynomial functions as tensor products of the univariate functions used here, and the various `fn . . .` commands also work for these multivariate functions.

There are various examples, all accessible through the Help browser. You are strongly urged to have a look at some of them, or at the `splinetool`, to help you work with splines.

## Splines

Consider the set

$$S: = \Pi_{\xi, k}^{\mu}$$

of all (scalar-valued) piecewise-polynomials of order  $k$  with breaks  $\xi_1 < \dots < \xi_{l+1}$  that, for  $i = 2 \dots l$ , may have a jump across  $\xi_i$  in its  $\mu_i$ th derivative but have no jump there in any lower order derivative. This set is a linear space, in the sense that any scalar multiple of a function in  $S$  is again in  $S$ , as is the sum of any two functions in  $S$ .

Accordingly,  $S$  contains a basis (in fact, infinitely many bases), that is, a sequence  $f_1, \dots, f_n$  so that every  $f$  in  $S$  can be written *uniquely* in the form

$$f(x) = \sum_{j=1}^n f_j(x) a_j,$$

for suitable coefficients  $a_j$ . The number  $n$  appearing here is the *dimension* of the linear space  $S$ . The coefficients  $a_j$  are often referred to as the *coordinates* of  $f$  with respect to this basis.

In particular, according to the Curry-Schoenberg Theorem, our space  $S$  has a basis consisting of B-splines, namely the sequence of all B-splines of the form  $B(\cdot | t_j, \dots, t_{j+k})$ ,  $j = 1 \dots n$ , with the knot sequence  $t$  obtained from the break sequence  $\xi$  and the sequence  $\mu$  by the following conditions:

- Have both  $\xi_1$  and  $\xi_{l+1}$  occur in  $t$  exactly  $k$  times
- For each  $i = 2:l$ , have  $\xi_i$  occur in  $t$  exactly  $k - \mu_i$  times
- Make sure the sequence is nondecreasing and only contains elements from  $\xi$

Note the correspondence between the multiplicity of a knot and the smoothness of the spline across that knot. In particular, at a simple knot, that is a knot that appears exactly once in the knot sequence, only the  $(k - 1)$ st derivative may be discontinuous.

## MATLAB Splines

The MATLAB technical computing environment provides spline approximation via the command `spline`. If called in the form `cs = spline(x, y)`, it returns the ppform of the cubic spline with break sequence  $x$  that takes the value  $y(i)$  at  $x(i)$ , all  $i$ , and satisfies the not-a-knot end condition. In other words, the command `cs = spline(x, y)` gives the same result as the command `cs =`

`csapi(x,y)` available in the Curve Fitting Toolbox spline functions. But only the latter also works when  $x,y$  describe multivariate gridded data. In MATLAB, cubic spline interpolation to multivariate gridded data is provided by the command `interp(x1,...,xd,v,y1,...,yd,'spline')` which returns values of the interpolating tensor product cubic spline at the grid specified by  $y_1,\dots,y_d$ .

Further, any of the Curve Fitting Toolbox spline `fn...` commands can be applied to the output of the MATLAB `spline(x,y)` command, with simple versions of the Curve Fitting Toolbox spline commands `fnval`, `ppmak`, `fnbrk` available directly in MATLAB, as the commands `ppval`, `mkpp`, `unmkpp`, respectively.

## Expected Background

The Curve Fitting Toolbox spline functions started out as an extension of the MATLAB environment of interest to experts in spline approximation, to aid them in the construction and testing of new methods of spline approximation. These experts should know the material covered in *A Practical Guide to Splines*.

However, the basic commands for constructing and using spline approximations are set up to be usable with no more knowledge than it takes to understand what it means to, say, construct an interpolant or a least squares approximant to some data, or what it means to differentiate or integrate a function.

With that in mind, there are sections, like “Cubic Spline Interpolation” on page 9-2, that are meant even for the novice, while sections devoted to a detailed example, like the one on constructing a Chebyshev spline or on constructing and using tensor products, are meant for users interested in developing their own spline commands.

## Vector Data Type Support

The Curve Fitting Toolbox spline functions can handle *vector*-valued splines, i.e., splines whose values lie in  $R^d$ . Since MATLAB started out with just one variable type, that of a matrix, there is even now some uncertainty about how to deal with vectors, i.e., lists of numbers. MATLAB sometimes stores such a list in a matrix with just one row, and other times in a matrix with just one column. In the first instance, such a *1-row matrix* is called a row-vector; in the second instance, such a *1-column matrix* is called a column-vector. Either way, these are merely different ways for *storing* vectors, not different *kinds* of vectors.

In this toolbox, *vectors*, i.e., lists of numbers, may also end up stored in a 1-row matrix or in a 1-column matrix, but with the following agreements.

A point in  $R^d$ , i.e., a *d*-vector, is always stored as a column vector. In particular, if you want to supply an *n*-list of *d*-vectors to one of the commands, you are expected to provide that list as the *n* columns of a matrix of size  $[d, n]$ .

While other lists of numbers (e.g., a knot sequence or a break sequence) may be stored internally as row vectors, you may supply such lists as you please, as a row vector or a column vector.

## Spline Function Naming Conventions

Most of the spline commands in this toolbox have names that follow one of the following patterns:

`cs...` commands construct cubic splines (in `ppform`)

`sp...` commands construct splines in B-form  
`fn...` commands operate on spline functions  
`..2...` commands convert something  
`..api` commands construct an approximation by interpolation  
`..aps` commands construct an approximation by smoothing  
`..ap2` commands construct a least-squares approximation  
`...knt` commands construct (part of) a particular knot sequence  
`...dem` commands are examples.

## Arguments for Curve Fitting Toolbox Spline Functions

For ease of use, most Curve Fitting Toolbox spline functions have default arguments. In the reference entry under Syntax, we usually first list the function with all *necessary* input arguments and then with all *possible* input arguments. When there is more than one optional argument, then, sometimes, but not always, their exact order is immaterial. When their order does matter, you have to specify every optional argument preceding the one(s) you are interested in. In this situation, you can specify the default value for an optional argument by using `[]` (the empty matrix) as the input for it. The description in the reference page tells you the default value for each optional input argument.

As in MATLAB, only the output arguments explicitly specified are returned to the user.

## Acknowledgments

MathWorks® would like to acknowledge the contributions of **Carl de Boor** to the Curve Fitting Toolbox spline functions. Professor de Boor authored the Spline Toolbox™ from its first release until Version 3.3.4 (2008).

Professor de Boor received the John von Neumann Prize in 1996 and the National Medal of Science in 2003. He is a member of both the American Academy of Arts and Sciences and the National Academy of Sciences. He is the author of *A Practical Guide to Splines* (Springer, 2001).

Some of the spline function naming conventions are the result of a discussion with Jörg Peters, then a graduate student in Computer Sciences at the University of Wisconsin-Madison.



# Simple Spline Examples

---

- “Cubic Spline Interpolation” on page 9-2
- “Vector-Valued Functions” on page 9-8
- “Fitting Values at N-D Grid with Tensor-Product Splines” on page 9-10
- “Fitting Values at Scattered 2-D Sites with Thin-Plate Smoothing Splines” on page 9-12
- “Postprocessing Splines” on page 9-13

## Cubic Spline Interpolation

| In this section...                                    |
|-------------------------------------------------------|
| “Cubic Spline Interpolant of Smooth Data” on page 9-2 |
| “Periodic Data” on page 9-3                           |
| “Other End Conditions” on page 9-4                    |
| “General Spline Interpolation” on page 9-4            |
| “Knot Choices” on page 9-5                            |
| “Smoothing” on page 9-5                               |
| “Least Squares” on page 9-7                           |

### Cubic Spline Interpolant of Smooth Data

Suppose you want to interpolate some smooth data, e.g., to

```
rng(6), x = (4*pi)*[0 1 rand(1,15)]; y = sin(x);
```


You can use the cubic spline interpolant obtained by

```
cs = csapi(x,y);
```

and plot the spline, along with the data, with the following code:

```
fnplt(cs);  
hold on  
plot(x,y,'o')  
legend('cubic spline','data')  
hold off
```

This produces a figure like the following.



### Cubic Spline Interpolant of Smooth Data

This is, more precisely, the cubic spline interpolant with the not-a-knot end conditions, meaning that it is the unique piecewise cubic polynomial with two continuous derivatives with breaks at all *interior* data sites except for the leftmost and the rightmost one. It is the same interpolant as produced by the MATLAB `spline(x,y)` command.

### Periodic Data

The sine function is  $2\pi$ -periodic. To check how well your interpolant does on that score, compute, e.g., the difference in the value of its first derivative at the two endpoints,

```
diff(fnval(fnder(cs),[0 4*pi]))
ans = -.0100
```

which is not so good. If you prefer to get an interpolant whose first and second derivatives at the two endpoints,  $0$  and  $4\pi$ , match, use instead the command `csape` which permits specification of many different kinds of end conditions, including periodic end conditions. So, use instead

```
pcs = csape(x,y,'periodic');
```

for which you get

```
diff(fnval(fnder(pcs),[0 4*pi]))
```

Output is `ans = 0` as the difference of end slopes. Even the difference in end second derivatives is small:

```
diff(fnval(fnder(pcs,2),[0 4*pi]))
```

Output is `ans = -4.6074e-015`.

## Other End Conditions

Other end conditions can be handled as well. For example,


```
cs = csape(x,[3,y,-4],[1 2]);
```

provides the cubic spline interpolant with breaks at the  $x(i)$  and with its slope at the leftmost data site equal to 3, and its second derivative at the rightmost data site equal to -4.

## General Spline Interpolation

If you want to interpolate at sites other than the breaks and/or by splines other than cubic splines with simple knots, then you use the `spapi` command. In its simplest form, you would say `sp = spapi(k,x,y)`; in which the first argument, `k`, specifies the *order* of the interpolating spline; this is the number of coefficients in each polynomial piece, i.e., 1 more than the nominal degree of its polynomial pieces. For example, the next figure shows a linear, a quadratic, and a quartic spline interpolant to your data, as obtained by the statements

```
sp2 = spapi(2,x,y); fnplt(sp2,2), hold on
sp3 = spapi(3,x,y); fnplt(sp3,2,'k--'),
sp5 = spapi(5,x,y); fnplt(sp5,2,'r-.'), plot(x,y,'o')
legend('linear','quadratic','quartic','data'), hold off
```




## Spline Interpolants of Various Orders of Smooth Data

Even the cubic spline interpolant obtained from `spapi` is different from the one provided by `csapi` and `spline`. To emphasize their difference, compute and plot their second derivatives, as follows:

```
fnplt(fnder(spapi(4,x,y),2)), hold on,
fnplt(fnder(csapi(x,y),2),2,'k--'),plot(x,zeros(size(x)), 'o')
legend('from spapi','from csapi','data sites'), hold off
```



This gives the following graph:



### Second Derivative of Two Cubic Spline Interpolants of the Same Smooth Data

Since the second derivative of a cubic spline is a broken line, with vertices at the breaks of the spline, you can see clearly that `csapi` places breaks at the data sites, while `spapi` does not.

### Knot Choices

It is, in fact, possible to specify explicitly just where the spline interpolant should have its breaks, using the command `sp = spapi(knots, x, y)`; in which the sequence `knots` supplies, in a certain way, the breaks to be used. For example, recalling that you had chosen `y` to be `sin(x)`, the command

```
ch = spapi(augknt(x,4,2), [x x], [y cos(x)]);
```

provides a cubic Hermite interpolant to the sine function, namely the piecewise cubic function, with breaks at all the `x(i)`'s, that matches the sine function in value *and* slope at all the `x(i)`'s. This makes the interpolant continuous with continuous first derivative but, in general, it has jumps across the breaks in its second derivative. Just how does this command know which part of the data value array `[y cos(x)]` supplies the values and which the slopes? Notice that the data site array here is given as `[x x]`, i.e., each data site appears twice. Also notice that `y(i)` is associated with the first occurrence of `x(i)`, and `cos(x(i))` is associated with the second occurrence of `x(i)`. The data value associated with the first appearance of a data site is taken to be a function value; the data value associated with the second appearance is taken to be a slope. If there were a third appearance of that data site, the corresponding data value would be taken as the second derivative value to be matched at that site. See "Constructing and Working with B-form Splines" on page 10-17 for a discussion of the command `augknt` used here to generate the appropriate "knot sequence".

### Smoothing

What if the data are noisy? For example, suppose that the given values are

```
noisy = y + .3*(rand(size(x))-.5);
```


Then you might prefer to approximate instead. For example, you might try the cubic smoothing spline, obtained by the command

```
scs = csaps(x,noisy);
```

and plotted by

```
fnplt(scs,2), hold on, plot(x,noisy,'o'),
legend('smoothing spline','noisy data'), hold off
```

This produces a figure like this:




### Cubic Smoothing Spline of Noisy Data

If you don't like the level of smoothing done by `csaps(x,y)`, you can change it by specifying the smoothing parameter, `p`, as an optional third argument. Choose this number anywhere between 0 and 1. As `p` changes from 0 to 1, the smoothing spline changes, correspondingly, from one extreme, the least squares straight-line approximation to the data, to the other extreme, the "natural" cubic spline interpolant to the data. Since `csaps` returns the smoothing parameter actually used as an optional second output, you could now experiment, as follows:

```
[scs,p] = csaps(x,noisy); fnplt(scs,2), hold on
fnplt(csaps(x,noisy,p/2),2,'k--'),
fnplt(csaps(x,noisy,(1+p)/2),2,'r:'), plot(x,noisy,'o')
legend('smoothing spline','more smoothed','less smoothed',...
'noisy data'), hold off
```

This produces the following picture.



### Noisy Data More or Less Smoothed

At times, you might prefer simply to get the smoothest cubic spline `sp` that is within a specified tolerance `tol` of the given data in the sense that  $\text{norm}(\text{noisy} - \text{fnval}(\text{sp}, x))^2 \leq \text{tol}$ . You create this spline with the command `sp = spaps(x, noisy, tol)` for your defined tolerance `tol`.

### Least Squares

If you prefer a least squares approximant, you can obtain it by the statement `sp = spap2(knots, k, x, y)`; in which both the knot sequence `knots` and the order `k` of the spline must be provided.

The popular choice for the order is 4, and that gives you a cubic spline. If you have no clear idea of how to choose the knots, simply specify the number of polynomial pieces you want used. For example,

```
sp = spap2(3, 4, x, y);
```

gives a cubic spline consisting of three polynomial pieces. If the resulting error is uneven, you might try for a better knot distribution by using `newknt` as follows:


```
sp = spap2(newknt(sp), 4, x, y);
```

## Vector-Valued Functions

Curve Fitting Toolbox™ supports *vector-valued* splines. For example, if you want a spline *curve* through given planar points  $(x(i), y(i))$ ,  $i = 1, \dots, n$ , then the following code defines some data and then creates and plots such a spline curve, using chord-length parameterization and cubic spline interpolation with the not-a-knot end condition.

```
x = [19 43 62 88 114 120 130 129 113 76 135 182 232 298 ...
     348 386 420 456 471 485 463 444 414 348 275 192 106 ...
     30 48 83 107 110 109 92 66 45 23 22 30 40 55 55 52 34 20 16];
y = [306 272 240 215 218 237 275 310 368 424 425 427 428 ...
     397 353 302 259 200 148 105 77 47 28 17 10 12 23 41 43 ...
     77 96 133 155 164 157 148 142 162 181 187 192 202 217 245 266 303];

xy = [x;y];
df = diff(xy,1,2);
t = cumsum([0,sqrt([1 1]*(df.*df))]);
cv = csapi(t,xy);
fnplt(cv)
hold on
plot(x,y,"o")
hold off
```



If you then wanted to know the area enclosed by this curve, you would want to evaluate the integral  $\int y(t)dx(t) = \int y(t)Dx(t)dt$ , with  $(x(t), y(t))$  the point on the curve corresponding to the parameter

value  $t$ . For the spline curve in  $cv$  just constructed, this can be done exactly in one (somewhat complicated) command:

```
area = diff(fnval(fnint( ...
    fncmb(fncmb(cv,[0 1]),"*",fnder(fncmb(cv,[1 0]))), ...
    fnbrk(cv,"interval"))));
```

To explain,  $y = \text{fncmb}(cv, [0 \ 1])$  picks out the second component of the curve in  $cv$ ,  $Dx = \text{fnder}(\text{fncmb}(cv, [1 \ 0]))$  provides the derivative of the first component, and  $yDx = \text{fncmb}(y, "*", Dx)$  constructs their pointwise product. Then  $IyDx = \text{fnint}(yDx)$  constructs the indefinite integral of  $yDx$  and, finally,  $\text{diff}(\text{fnval}(IyDx, \text{fnbrk}(cv, "interval")))$  evaluates that indefinite integral at the endpoints of the basic interval and then takes the difference of the second from the first value, thus getting the definite integral of  $yDx$  over its basic interval. Depending on whether the enclosed area is to the right or to the left as the curve point travels with increasing parameter, the resulting number is either positive or negative.

Further, all the values  $Y$  (if any) for which the point  $(X, Y)$  lies on the spline curve in  $cv$  just constructed can be obtained by the following (somewhat complicated) command:

```
X = 250; % Define a value of X
Y = fnval(fncmb(cv,[0 1]), ...
    mean(fnzeros(fncmb(fncmb(cv,[1 0]),"-",X))))
```

```
Y = 1x2
```

```
423.4902    9.4812
```

To explain:  $x = \text{fncmb}(cv, [1 \ 0])$  picks out the first component of the curve in  $cv$ ;  $xmX = \text{fncmb}(x, "-", X)$  translates that component by  $X$ ;  $t = \text{mean}(\text{fnzeros}(xmX))$  provides all the parameter values for which  $xmX$  is zero, that is, for which the first component of the curve equals  $X$ ;  $y = \text{fncmb}(cv, [0 \ 1])$  picks out the second component of the curve in  $cv$ ; and, finally,  $Y = \text{fnval}(y, t)$  evaluates that second component at those parameter sites at which the first component of the curve in  $cv$  equals  $X$ .


As another example of the use of vector-valued functions, suppose that you have solved the equations of motion of a particle in some specified force field in the plane, obtaining, at discrete times  $t_j = t(j)$ ,  $j = 1:n$ , the position  $(x(t_j), y(t_j))$  as well as the velocity  $(\dot{x}(t_j), \dot{y}(t_j))$  stored in the 4-vector  $z(:, j)$ , as you would if, in the standard way, you had solved the equivalent first-order system numerically. Then the following statement, which uses cubic Hermite interpolation, will produce a plot of the particle path: `fnplt(spapi(augknt(t,4,2),t,reshape(z,2,2*n)))`.

## Fitting Values at N-D Grid with Tensor-Product Splines

Vector-valued splines are also used in the approximation to *gridded data*, in any number of variables, using *tensor-product* splines. The same spline-construction commands are used, only the form of the input differs. For example, if  $x$  is an  $m$ -vector,  $y$  is an  $n$ -vector, and  $z$  is an array of size  $[m, n]$ , then `cs = csapi({x,y},z)`; describes a bicubic spline  $f$  satisfying  $f(x(i), y(j)) = z(i, j)$  for  $i = 1:m, j = 1:n$ . Such a multivariate spline can be vector-valued. For example, the following gives a perfectly acceptable sphere.

```
x = 0:4;
y = -2:2;
s2 = 1/sqrt(2);
z(3, :, :) = [0 1 s2 0 -s2 -1 0].'*[1 1 1 1 1];
z(2, :, :) = [1 0 s2 1 s2 0 -1].'*[0 1 0 -1 0];
z(1, :, :) = [1 0 s2 1 s2 0 -1].'*[1 0 -1 0 1];
sph = csape({x,y},z,["clamped","periodic"]);
fnplt(sph)
axis equal
axis off
title("Sphere Made by 3-D-Valued " + ...
      "Bivariate Tensor Product Spline")
```

**Sphere Made by 3-D-Valued Bivariate Tensor Product Spline**




The sphere's projection onto the  $(x,z)$ -plane is plotted by the following.

```
fnplt(fncmb(sph,[1 0 0; 0 0 1]))
axis equal
```

```
axis off  
title("Planar Projection of Spline Sphere")
```

**Planar Projection of Spline Sphere**



## Fitting Values at Scattered 2-D Sites with Thin-Plate Smoothing Splines

Tensor-product splines are good for gridded (bivariate and even multivariate) data. For work with scattered bivariate data, the toolbox provides the thin-plate smoothing spline. Suppose you have given data values  $y(j)$  at scattered data sites  $x(:, j)$ ,  $j=1:N$ , in the plane. To give a specific example,

```
n = 65; t = linspace(0,2*pi,n+1);
x = [cos(t);sin(t)]; x(:,end) = [0;0];
```

provides 65 sites, namely 64 points equally spaced on the unit circle, plus the center of that circle. Here are corresponding data values, namely noisy values of the very nice function

$$g(x) = (x(1)+1/2)^2 + (x(2)+1/2)^2.$$

```
y = (x(1,:)+.5).^2 + (x(2,:)+.5).^2;
noisy = y + (rand(size(y))-0.5)/3;
```


Then you can compute a reasonable approximation to these data by

```
st = tpaps(x,noisy);
```

and plot the resulting approximation along with the noisy data by

```
fnplt(st); hold on
plot3(x(1,:),x(2,:),noisy,'wo','markerfacecolor','k')
hold off
```

and so produce the following picture:



**Thin-Plate Smoothing Spline Approximation to Noisy Data**



## Postprocessing Splines

You can use the following commands with any example spline, such as the `cs`, `ch` and `sp` examples constructed in the section “Cubic Spline Interpolation” on page 9-2.

First construct a spline, for example:

```
sp = spmak(1:6,0:2)
```

To display a plot of the spline:

```
fnplt(sp)
```

To get the value at `a`, use the syntax `fnval(f,a)`, for example:

```
fnval(sp,4)
```

To construct the spline's second derivative:

```
DDf = fnder(fnder(sp))
```

An alternative way to construct the second derivative:

```
DDf = fnder(sp,2);
```

To obtain the spline's definite integral over an interval `[a..b]`, in this example from 2 to 5:

```
diff(fnval(fnint(sp),[2;5]))
```

To compute the difference between two splines, use the form `fncmb(sp1,'-',sp2)`, for example:

```
fncmb(sp,'-',DDf);
```



# Types of Splines

---

- “Types of Splines: ppform and B-form” on page 10-2
- “B-Splines and Smoothing Splines” on page 10-4
- “Multivariate and Rational Splines” on page 10-6
- “The ppform” on page 10-8
- “Constructing and Working with ppform Splines” on page 10-10
- “The B-form” on page 10-13
- “Constructing and Working with B-form Splines” on page 10-17
- “Multivariate Tensor Product Splines” on page 10-21
- “NURBS and Other Rational Splines” on page 10-23
- “Constructing and Working with Rational Splines” on page 10-25
- “Constructing and Working with stform Splines” on page 10-28

## Types of Splines: ppform and B-form

### In this section...

“Polynomials vs. Splines” on page 10-2

“ppform” on page 10-2

“B-form” on page 10-2

“Knot Multiplicity” on page 10-3

### Polynomials vs. Splines

Polynomials are the approximating functions of choice when a smooth function is to be approximated locally. For example, the truncated Taylor series

$$\sum_{i=0}^n (x-a)^i D^i f(a)/i!$$

provides a satisfactory approximation for  $f(x)$  if  $f$  is sufficiently smooth and  $x$  is sufficiently close to  $a$ . But if a function is to be approximated on a larger interval, the degree,  $n$ , of the approximating polynomial may have to be chosen unacceptably large. The alternative is to subdivide the interval  $[a..b]$  of approximation into sufficiently small intervals  $[\xi_j.. \xi_{j+1}]$ , with  $a = \xi_1 < \dots < \xi_{l+1} = b$ , so that, on each such interval, a polynomial  $p_j$  of relatively low degree can provide a good approximation to  $f$ . This can even be done in such a way that the polynomial pieces blend smoothly, i.e., so that the resulting patched or composite function  $s(x)$  that equals  $p_j(x)$  for  $x \in [\xi_j \xi_{j+1}]$ , all  $j$ , has several continuous derivatives. Any such smooth piecewise polynomial function is called a *spline*. I.J. Schoenberg coined this term because a twice continuously differentiable cubic spline with sufficiently small first derivative approximates the shape of a draftsman's spline.

There are two commonly used ways to represent a polynomial spline, the ppform and the B-form. In this toolbox, a spline in ppform is often referred to as a piecewise polynomial, while a piecewise polynomial in B-form is often referred to as a spline. This reflects the fact that piecewise polynomials and (polynomial) splines are just two different views of the same thing.

### ppform

The *ppform* of a polynomial spline of order  $k$  provides a description in terms of its *breaks*  $\xi_1.. \xi_{l+1}$  and the *local polynomial coefficients*  $c_{ji}$  of its  $l$  pieces.

$$p_j(x) = \sum_{i=1}^k (x - \xi_j)^{k-i} c_{ji}, \quad j = 1:l$$

For example, a cubic spline is of order 4, corresponding to the fact that it requires four coefficients to specify a cubic polynomial. The ppform is convenient for the evaluation and other *uses* of a spline.

### B-form

The *B-form* has become the standard way to represent a spline during its *construction*, because the B-form makes it easy to build in smoothness requirements across breaks and leads to banded linear systems. The B-form describes a spline as a weighted sum

$$\sum_{j=1}^n B_{j,k} a_j$$

of B-splines of the required order  $k$ , with their number,  $n$ , at least as big as  $k-1$  plus the number of polynomial pieces that make up the spline. Here,  $B_{j,k} = B(\cdot | t_j, \dots, t_{j+k})$  is the  $j$ th B-spline of order  $k$  for the knot sequence  $t_1 \leq t_2 \leq \dots \leq t_{n+k}$ . In particular,  $B_{j,k}$  is piecewise-polynomial of degree  $< k$ , with breaks  $t_j, \dots, t_{j+k}$ , is nonnegative, is zero outside the interval  $[t_j, t_{j+k}]$ , and is so normalized that

$$\sum_{j=1}^n B_{j,k}(x) = 1 \text{ on } [t_k, t_{n+1}]$$

## Knot Multiplicity

The multiplicity of the knots governs the smoothness, in the following way: If the number  $\tau$  occurs exactly  $r$  times in the sequence  $t_j, \dots, t_{j+k}$ , then  $B_{j,k}$  and its first  $k-r-1$  derivatives are continuous across the break  $\tau$ , while the  $(k-r)$ th derivative has a jump at  $\tau$ . You can experiment with all these properties of the B-spline in a very visual and interactive way using the command `bspligui`.

## See Also

### Related Examples

- “Constructing and Working with ppform Splines” on page 10-10
- “Constructing and Working with B-form Splines” on page 10-17

## B-Splines and Smoothing Splines

### In this section...

“B-Spline Properties” on page 10-4

“Variational Approach and Smoothing Splines” on page 10-4

The Cox-de Boor recursion definition of the  $j$ th B-spline  $B_{j,k}(x)$  with order  $k$  and nondecreasing knot sequence  $\mathbf{t} = (t_0, t_1, \dots, t_n)$  is given by the following formulas:

$$B_{j,1}(x) = \begin{cases} 1 & t_j \leq x < t_{j+1} \\ 0 & x < t_j, t_{j+1} \leq x \end{cases}$$

$$B_{j,k+1}(x) = \frac{x - t_j}{t_{j+k-1} - t_j} B_{j,k-1}(x) + \frac{t_{j+k} - x}{t_{j+k} - t_{j+1}} B_{j+1,k-1}(x)$$

The reference page for the `bspligui` interface lists some of the basic properties of the B-spline. You can use the interface to gain some experience with B-splines. The most important property of the B-spline is also the reason for the letter B in its name:

*Every space of (univariate) piecewise-polynomials of a given order has a Basis consisting of B-splines.*

### B-Spline Properties

Because  $B_{j,k}$  is nonzero only on the interval  $(t_j, t_{j+k})$ , the linear system for the B-spline coefficients is banded and easy to solve. For example, to construct a spline  $s$  of order  $k$  with knot sequence  $t_1 \leq t_2 \leq \dots \leq t_{n+k}$  so that  $s(x_i) = y_i$  for  $i = 1, \dots, n$ , use the linear system

$$\sum_{j=1}^n B_{j,k}(x_i) a_j = y_i \quad i = 1:n$$

for the unknown B-spline coefficients  $a_j$  in which each equation has at most  $k$  nonzero entries.

Also, many theoretical facts concerning splines are most easily stated or proved in terms of B-splines. For example, it is possible to match arbitrary data at sites  $x_1 < \dots < x_n$  uniquely by a spline of order  $k$  with knot sequence  $(t_1, \dots, t_{n+k})$  if and only if  $B_{j,k}(x_j) \neq 0$  for all  $j$  (Schoenberg-Whitney Conditions). Computations with B-splines are facilitated by their stable recurrence relations, which are also helpful in the conversion from B-form to pform. The dual functional

$$a_j(s) := \sum_{i < k} (-D)^{k-i-1} \Psi_j(\tau) D^i s(\tau)$$

provides a useful expression for the  $j$ th B-spline coefficient of the spline  $s$  in terms of its value and derivatives at an arbitrary site  $\tau$  between  $t_j$  and  $t_{j+k}$ , and with  $\Psi_j(t) := (t_{j+1} - t) \cdots (t_{j+k-1} - t) / (k-1)!$ . It can be used to show that  $a_j(s)$  is closely related to  $s$  on the interval  $[t_j, t_{j+k}]$ , and seems the most efficient means for converting from pform to B-form.

### Variational Approach and Smoothing Splines

The above *constructive* approach is not the only avenue to splines. In the *variational* approach, a spline is obtained as a *best interpolant*, e.g., as the function with smallest  $m$ th derivative among all

those matching prescribed function values at certain sites. As it turns out, among the many such splines available, only those that are piecewise-polynomials or, perhaps, piecewise-exponentials have found much use. Of particular practical interest is the *smoothing spline*  $s = s_p$  which, for given data  $(x_i, y_i)$  with  $x \in [a..b]$ , all  $i$ , and given corresponding positive weights  $w_i$ , and for given *smoothing parameter*  $p$ , minimizes

$$p \sum_i w_i |y_i - f(x_i)|^2 + (1 - p) \int_a^b |D^m f(t)|^2 dt$$

over all functions  $f$  with  $m$  derivatives. It turns out that the smoothing spline  $s$  is a spline of order  $2m$  with a break at every data site. The smoothing parameter,  $p$ , is chosen artfully to strike the right balance between wanting the *error measure*

$$E(s) = \sum_i w_i |y_i - s(x_i)|^2$$

small and wanting the *roughness measure*

$$F(D^m s) = \int_a^b |D^m s(t)|^2 dt$$

small. The hope is that  $s$  contains as much of the information, and as little of the supposed noise, in the data as possible. One approach to this (used in `spaps`) is to make  $F(D^m f)$  as small as possible subject to the condition that  $E(f)$  be no bigger than a prescribed tolerance. For computational reasons, `spaps` uses the (equivalent) smoothing parameter  $\rho = p/(1-p)$ , i.e., minimizes  $\rho E(f) + F(D^m f)$ . Also, it is useful at times to use the more flexible roughness measure

$$F(D^m s) = \int_a^b \lambda(t) |D^m s(t)|^2 dt$$

with  $\lambda$  a suitable positive weight function.

## See Also

## Related Examples

- “Constructing and Working with B-form Splines” on page 10-17

## Multivariate and Rational Splines

|                                     |
|-------------------------------------|
| <b>In this section...</b>           |
| “Multivariate Splines” on page 10-6 |
| “Rational Splines” on page 10-7     |

### Multivariate Splines

Multivariate splines can be obtained from univariate splines by the tensor product construct. For example, a trivariate spline in B-form is given by

$$f(x, y, z) = \sum_{u=1}^U \sum_{v=1}^V \sum_{w=1}^W B_{u,k}(x)B_{v,l}(y)B_{w,m}(z)a_{u,v,w}$$

with  $B_{u,k}, B_{v,l}, B_{w,m}$  univariate B-splines. Correspondingly, this spline is of order  $k$  in  $x$ , of order  $l$  in  $y$ , and of order  $m$  in  $z$ . Similarly, the pform of a tensor-product spline is specified by break sequences in each of the variables and, for each hyper-rectangle thereby specified, a coefficient array. Further, as in the univariate case, the coefficients may be vectors, typically 2-vectors or 3-vectors, making it possible to represent, e.g., certain surfaces in  $\mathfrak{R}^3$ .

A very different bivariate spline is the *thin-plate spline*. This is a function of the form

$$f(x) = \sum_{j=1}^{n-3} \Psi(x - c_j)a_j + x(1)a_{n-2} + x(2)a_{n-1} + a_n$$

with  $\psi(x)=|x|^2\log|x|^2$  the thin-plate spline basis function, and  $|x|$  denoting the Euclidean length of the vector  $x$ . Here, for convenience, denote the independent variable by  $x$ , but  $x$  is now a *vector* whose two components,  $x(1)$  and  $x(2)$ , play the role of the two independent variables earlier denoted  $x$  and  $y$ . Correspondingly, the sites  $c_j$  are points in  $\mathfrak{R}^2$ .

Thin-plate splines arise as bivariate *smoothing splines*, meaning a thin-plate spline minimizes

$$p \sum_{i=1}^{n-3} |y_i - fc_i|^2 + (1 - p) \int (|D_1D_1f|^2 + 2|D_1D_2f|^2 + |D_2D_2f|^2)$$

over all sufficiently smooth functions  $f$ . Here, the  $y_i$  are data values given at the data sites  $c_i$ ,  $p$  is the smoothing parameter, and  $D_jf$  denotes the partial derivative of  $f$  with respect to  $x(j)$ . The integral is taken over the entire  $\mathfrak{R}^2$ . The upper summation limit,  $n-3$ , reflects the fact that 3 degrees of freedom of the thin-plate spline are associated with its polynomial part.

Thin-plate splines are functions in stform, meaning that, up to certain polynomial terms, they are a weighted sum of arbitrary or scattered translates  $\Psi(\cdot - c)$  of one fixed function,  $\Psi$ . This so-called basis function for the thin-plate spline is special in that it is radially symmetric, meaning that  $\Psi(x)$  only depends on the Euclidean length,  $|x|$ , of  $x$ . For that reason, thin-plate splines are also known as RBFs or radial basis functions. See “Constructing and Working with stform Splines” on page 10-28 for more information.



## Rational Splines

A *rational spline* is any function of the form  $r(x) = s(x)/w(x)$ , with both  $s$  and  $w$  splines and, in particular,  $w$  a scalar-valued spline, while  $s$  often is vector-valued.

Rational splines are attractive because it is possible to describe various basic geometric shapes, like conic sections, exactly as the range of a rational spline. For example, a circle can so be described by a quadratic rational spline with just two pieces.

In this toolbox, there is the additional requirement that both  $s$  and  $w$  be of the same form and even of the same order, and with the same knot or break sequence. This makes it possible to store the rational spline  $r$  as the ordinary spline  $R$  whose value at  $x$  is the vector  $[s(x);w(x)]$ . Depending on whether the two splines are in B-form or ppform, such a representation is called here the rBform or the rpform of such a rational spline.

It is easy to obtain  $r$  from  $R$ . For example, if  $v$  is the value of  $R$  at  $x$ , then  $v(1:end-1)/v(end)$  is the value of  $r$  at  $x$ . As another example, consider getting derivatives of  $r$  from those of  $R$ . Because  $s = wr$ , Leibniz' rule tells us that

$$D^m s = \sum_{j=0}^m \binom{m}{j} D^j w D^{m-j} r$$

where  $D^m s$  is the  $m$ th derivative of  $s$ .

Hence, if  $v(:,j)$  contains  $D^{j-1}R(x)$ ,  $j = 1 \dots m + 1$ , then

$$\left( \left( v(1:end-1, m+1) - \sum_{j=1}^m \binom{m}{j} v(end, j+1) v(1:end-1, j+1) \right) / v(end, 1) \right)$$

provides the value of  $D^m R(x)$ .

## See Also

## Related Examples

- “Constructing and Working with Rational Splines” on page 10-25

## The ppform

### In this section...

“Introduction to ppform” on page 10-8

“Definition of ppform” on page 10-8

### Introduction to ppform

A univariate *piecewise polynomial*  $f$  is specified by its *break sequence*  $\text{breaks}$  and the *coefficient array*  $\text{coefs}$  of the local power form (see equation in “Definition of ppform” on page 10-8) of its polynomial pieces; see “Multivariate Tensor Product Splines” on page 10-21 for a discussion of multivariate piecewise-polynomials. The coefficients may be (column-)vectors, matrices, even ND-arrays. For simplicity, the present discussion deals only with the case when the coefficients are scalars.

The break sequence is assumed to be strictly increasing,

$$\begin{aligned} &\text{breaks}(1) \\ &< \text{breaks}(2) < \dots < \text{breaks}(l+1) \end{aligned}$$

with  $l$  the number of polynomial pieces that make up  $f$ .

While these polynomials may be of varying degrees, they are all recorded as polynomials of the same *order*  $k$ , i.e., the coefficient array  $\text{coefs}$  is of size  $[l, k]$ , with  $\text{coefs}(j, :)$  containing the  $k$  coefficients in the local power form for the  $j$ th polynomial piece, from the highest to the lowest power; see equation in “Definition of ppform” on page 10-8.

### Definition of ppform

The items  $\text{breaks}$ ,  $\text{coefs}$ ,  $l$ , and  $k$ , make up the *ppform* of  $f$ , along with the dimension  $d$  of its coefficients; usually  $d$  equals 1. The *basic interval* of this form is the interval  $[\text{breaks}(1) \dots \text{breaks}(l+1)]$ . It is the default interval over which a function in ppform is plotted by the plot command `fnplt`.

In these terms, the precise description of the piecewise-polynomial  $f$  is

$$f(t) = \text{polyval}(\text{coefs}(j, :), t - \text{breaks}(j)) \quad (10-1)$$

for  $\text{breaks}(j) \leq t < \text{breaks}(j+1)$ .

Here, `polyval(a,x)` is the MATLAB function; it returns the number

$$\sum_{j=1}^k a(j)x^{k-j} = a(1)x^{k-1} + a(2)x^{k-2} + \dots + a(k)x^0$$

This defines  $f(t)$  only for  $t$  in the half-open interval  $[\text{breaks}(1) \dots \text{breaks}(l+1)]$ . For any other  $t$ ,  $f(t)$  is defined by

$$f(t) = \text{polyval}(\text{coefs}(j, :), t - \text{breaks}(j)) \quad j = \begin{cases} 1, & t < \text{breaks}(1) \\ l, & t \geq \text{breaks}(l+1) \end{cases}$$

i.e., by extending the first, respectively last, polynomial piece. In this way, a function in ppform has possible jumps, in its value and/or its derivatives, only across the interior breaks, `breaks(2:l)`. The end breaks, `breaks([1, l+1])`, mainly serve to define the basic interval of the ppform.

## See Also

## Related Examples

- “Constructing and Working with ppform Splines” on page 10-10

## Constructing and Working with ppform Splines

### In this section...

“Constructing a ppform” on page 10-10

“Working With ppform Splines” on page 10-10

“Example ppform” on page 10-11

### Constructing a ppform

A piecewise-polynomial is usually constructed by some command, through a process of interpolation or approximation, or conversion from some other form e.g., from the B-form, and is output as a variable. But it is also possible to make one up from scratch, using the statement

```
pp
= ppmak(breaks,coefs)
```

For example, if you enter `pp=ppmak(-5:-1,-22:-11)`, or, more explicitly,

```
breaks = -5:-1;
coefs = -22:-11; pp = ppmak(breaks,coefs);
```

you specify the uniform break sequence `-5:-1` and the coefficient sequence `-22:-11`. Because this break sequence has 5 entries, hence 4 break intervals, while the coefficient sequence has 12 entries, you have, in effect, specified a piecewise-polynomial of order 3 (= 12/4). The command

```
fnbrk(pp)
```

prints out all the constituent parts of this piecewise-polynomial, as follows:

```
breaks(1:l+1)
   -5  -4  -3  -2  -1
coefficients(d*l,k)
   -22 -21 -20
   -19 -18 -17
   -16 -15 -14
   -13 -12 -11
pieces number l
     4
order k
     3
dimension d of target
     1
```

Further, `fnbrk` can be used to supply each of these parts separately. But the point of Curve Fitting Toolbox spline functionality is that you usually need not concern yourself with these details. You simply use `pp` as an argument to commands that evaluate, differentiate, integrate, convert, or plot the piecewise-polynomial whose description is contained in `pp`.

### Working With ppform Splines

Here are some functions for operations you can perform on a piecewise-polynomial.

|                                        |                                                                     |
|----------------------------------------|---------------------------------------------------------------------|
| <code>v = fnval(pp,x)</code>           | Evaluates                                                           |
| <code>dpp = fnder(pp)</code>           | Differentiates                                                      |
| <code>dirpp = fndir(pp,dir)</code>     | Differentiates in the direction <code>dir</code>                    |
| <code>ipp = fnint(pp)</code>           | Integrates                                                          |
| <code>fnmin(pp,[a,b])</code>           | Finds the minimum value in given interval                           |
| <code>fnzeros(pp,[a,b])</code>         | Finds the zeros in the given interval                               |
| <code>pj = fnbrk(pp,j)</code>          | Pulls out the <code>j</code> th polynomial piece                    |
| <code>pc = fnbrk(pp,[a b])</code>      | Restricts/extends to the interval <code>[a..b]</code>               |
| <code>po = fnxtr(pp,order)</code>      | Extends outside its basic interval by polynomial of specified order |
| <code>fnplt(pp,[a,b])</code>           | Plots on given interval                                             |
| <code>sp = fn2fm(pp,'B-')</code>       | Converts to B-form                                                  |
| <code>pr = fnrfn(pp,morebreaks)</code> | Inserts additional breaks                                           |

Inserting additional breaks comes in handy when you want to add two piecewise-polynomials with different breaks, as is done in the command `fncmb`.

## Example ppform

Execute the following commands to create and plot the particular piecewise-polynomial (ppform) described in the “Constructing a ppform” on page 10-10 section.

- 1 Create the piecewise-polynomial with break sequence `-5:-1` and coefficient sequence `-22:-11`:

```
pp=ppmak(-5:-1,-22:-11)
```

- 2 Create the basic plot:


```
x = linspace(-5.5,-.5,101);
plot(x, fnval(pp,x),'x')
```

- 3 Add the break lines to the plot:

```
breaks=fnbrk(pp,'b'); yy=axis; hold on
for j=1:fnbrk(pp,'l')+1
    plot(breaks([j j]),yy(3:4))
end
```

- 4 Superimpose the plot of the polynomial that supplies the third polynomial piece:

```
plot(x,fnval(fnbrk(pp,3),x),'linewidth',1.3)
set(gca,'ylim',[-60 -10]), hold off
```



### A Piecewise-Polynomial Function, Its Breaks, and the Polynomial Giving Its Third Piece

The figure above is the final picture. It shows the piecewise-polynomial as a sequence of points and, solidly on top of it, the polynomial from which its third polynomial piece is taken. It is quite noticeable that the value of a piecewise-polynomial at a break is its limit from the *right*, and that the value of the piecewise-polynomial outside its basic interval is obtained by extending its leftmost, respectively its rightmost, polynomial piece.

While the ppform of a piecewise-polynomial is efficient for evaluation, the *construction* of a piecewise-polynomial from some data is usually more efficiently handled by determining first its *B-form*, i.e., its representation as a linear combination of B-splines.

### See Also

#### More About

- “Types of Splines: ppform and B-form” on page 10-2
- “The ppform” on page 10-8

## The B-form

### In this section...

“Introduction to B-form” on page 10-13

“Definition of B-form” on page 10-13

“B-form and B-Splines” on page 10-13

“B-Spline Knot Multiplicity” on page 10-14

“Choice of Knots for B-form” on page 10-15

### Introduction to B-form

A univariate spline  $f$  is specified by its nondecreasing knot sequence  $\mathbf{t}$  and by its B-spline coefficient sequence  $\mathbf{a}$ . See “Multivariate Tensor Product Splines” on page 10-21 for a discussion of multivariate splines. The coefficients may be (column-)vectors, matrices, even ND-arrays. When the coefficients are 2-vectors or 3-vectors,  $f$  is a curve in  $\mathbb{R}^2$  or  $\mathbb{R}^3$  and the coefficients are called the *control points* for the curve.

Roughly speaking, such a spline is a piecewise-polynomial of a certain order and with breaks  $\mathbf{t}(i)$ . But knots are different from breaks in that they may be repeated, i.e.,  $\mathbf{t}$  need not be *strictly* increasing. The resulting knot *multiplicities* govern the smoothness of the spline across the knots, as detailed below.

With  $[d, n] = \text{size}(\mathbf{a})$ , and  $n+k = \text{length}(\mathbf{t})$ , the spline is of *order*  $k$ . This means that its polynomial pieces have degree  $< k$ . For example, a *cubic* spline is a spline of *order* 4 because it takes four coefficients to specify a cubic polynomial.

### Definition of B-form

These four items,  $\mathbf{t}$ ,  $\mathbf{a}$ ,  $n$ , and  $k$ , make up the B-form of the spline  $f$ .

This means, explicitly, that


$$f = \sum_{i=1}^n B_{i,k} a(:, i)$$

with  $B_{i,k} = B(\cdot | t(i:i+k))$  the  $i$ th B-spline of order  $k$  for the given knot sequence  $\mathbf{t}$ , i.e., the B-spline with knots  $t(i), \dots, t(i+k)$ . The basic interval of this B-form is the interval  $[t(1)..t(n+k)]$ . It is the default interval over which a spline in B-form is plotted by the command `fnplt`. Note that a spline in B-form is zero outside its basic interval while, after conversion to `ppform` via `fn2fm`, this is usually not the case because, outside its basic interval, a piecewise-polynomial is defined by extension of its first or last polynomial piece. In particular, a function in B-form may have jumps in value and/or one of its derivative not only across its interior knots, i.e., across  $t(i)$  with  $t(1) < t(i) < t(n+k)$ , but also across its end knots,  $t(1)$  and  $t(n+k)$ .

### B-form and B-Splines

The building blocks for the B-form of a spline are the B-splines. “A B-Spline of Order 4, and the Four Cubic Polynomials from Which It Is Made” on page 10-14 shows a picture of such a B-spline, the one

with the knot sequence  $[0 \ 1.5 \ 2.3 \ 4 \ 5]$ , hence of order 4, together with the polynomials whose pieces make up the B-spline. The information for that picture could be generated by the command `bspline([0 1.5 2.3 4 5])`



### A B-Spline of Order 4, and the Four Cubic Polynomials from Which It Is Made

To summarize: The B-spline with knots  $t(i) \leq \dots \leq t(i+k)$  is positive on the interval  $(t(i)..t(i+k))$  and is zero outside that interval. It is piecewise-polynomial of order  $k$  with breaks at the sites  $t(i), \dots, t(i+k)$ . These knots may coincide, and the precise *multiplicity* governs the smoothness with which the two polynomial pieces join there.

#### Definition of B-Splines

The shorthand

$$f \in S_{k,t}$$

is one of several ways to indicate that  $f$  is a spline of order  $k$  with knot sequence  $\mathbf{t}$ , i.e., a *linear combination of the B-splines* of order  $k$  for the knot sequence  $\mathbf{t}$ .


A word of caution: The term *B-spline* has been expropriated by the Computer-Aided Geometric Design (CAGD) community to mean what is called here a *spline in B-form*, with the unhappy result that, in any discussion between mathematicians/approximation theorists and people in CAGD, one now always has to check in what sense the term is being used.

### B-Spline Knot Multiplicity

The rule is

**knot multiplicity + condition multiplicity = order**





### All Third-Order B-Splines for a Certain Knot Sequence with Various Knot Multiplicities

For example, for a B-spline of order 3, a simple knot would mean two smoothness conditions, i.e., continuity of function and first derivative, while a double knot would only leave one smoothness condition, i.e., just continuity, and a triple knot would leave no smoothness condition, i.e., even the function would be discontinuous.

“All Third-Order B-Splines for a Certain Knot Sequence with Various Knot Multiplicities” on page 10-15 shows a picture of all the third-order B-splines for a certain mystery knot sequence  $\mathbf{t}$ . The breaks are indicated by vertical lines. For each break, try to determine its multiplicity in the knot sequence (it is 1,2,1,1,3), as well as its multiplicity as a knot in each of the B-splines. For example, the second break has multiplicity 2 but appears only with multiplicity 1 in the third B-spline and not at all, i.e., with multiplicity 0, in the last two B-splines. Note that only one of the B-splines shown has all its knots simple. It is the only one having three different nontrivial polynomial pieces. Note also that you can tell the knot-sequence multiplicity of a knot by the number of B-splines whose nonzero part begins or ends there. The picture is generated by the following MATLAB statements, which use the command `spcol` from this toolbox to generate the function values of all these B-splines at a fine net  $x$ .

```
t=[0,1,1,3,4,6,6,6]; x=linspace(-1,7,81);
c=spcol(t,3,x); [l,m]=size(c);
c=c+ones(l,1)*[0:m-1];
axis([-1 7 0 m]); hold on
for tt=t, plot([tt tt],[0 m],'-'), end
plot(x,c,'linew',2), hold off, axis off
```

Further illustrated examples are provided by the example “Construct and Work with the B-form”. You can also use the GUI `bspligui` to study the dependence of a B-spline on its knots experimentally.

### Choice of Knots for B-form

The rule “knot multiplicity + condition multiplicity = order” has the following consequence for the process of choosing a knot sequence for the B-form of a spline approximant. Suppose the spline  $s$  is to be of order  $k$ , with basic interval  $[a..b]$ , and with interior breaks  $\xi_2 < \dots < \xi_l$ . Suppose, further, that, at  $\xi_i$ , the spline is to satisfy  $\mu_i$  smoothness conditions, i.e.,

$$\text{jump}_{\xi_i} D^j s := D^j s(\xi_i^+) - D^j s(\xi_i^-) = 0, \quad 0 \leq j < \mu_i, \quad i = 2, \dots, l$$

Then, the appropriate knot sequence  $t$  should contain the break  $\xi_i$  exactly  $k - \mu_i$  times,  $i=2,\dots,l$ . In addition, it should contain the two endpoints,  $a$  and  $b$ , of the basic interval exactly  $k$  times. This last requirement can be relaxed, but has become standard. With this choice, there is exactly one way to write each spline  $s$  with the properties described as a weighted sum of the B-splines of order  $k$  with knots a segment of the knot sequence  $t$ . This is the reason for the  $B$  in *B-spline*: B-splines are, in Schoenberg's terminology, *basic* splines.

For example, if you want to generate the B-form of a cubic spline on the interval  $[1 .. 3]$ , with interior breaks 1.5, 1.8, 2.6, and with two continuous derivatives, then the following would be the appropriate knot sequence:

```
t = [1, 1, 1, 1, 1.5, 1.8, 2.6, 3, 3, 3, 3];
```

This is supplied by `augknt([1, 1.5, 1.8, 2.6, 3], 4)`. If you wanted, instead, to allow for a corner at 1.8, i.e., a possible jump in the first derivative there, you would triple the knot 1.8, i.e., use

```
t = [1, 1, 1, 1, 1.5, 1.8, 1.8, 1.8, 2.6, 3, 3, 3, 3];
```

and this is provided by the statement

```
t = augknt([1, 1.5, 1.8, 2.6, 3], 4, [1, 3, 1] );
```

## See Also

### Related Examples

- “Constructing and Working with B-form Splines” on page 10-17

## Constructing and Working with B-form Splines

### In this section...

“Construction of B-form” on page 10-17

“Working With B-form Splines” on page 10-17

“Example: B-form Spline Approximation to a Circle” on page 10-18

### Construction of B-form

Usually, a spline is constructed from some information, like function values and/or derivative values, or as the approximate solution of some ordinary differential equation. But it is also possible to make up a spline from scratch, by providing its knot sequence and its coefficient sequence to the command `spmak`.

For example, if you enter

```
sp = spmak(1:10,3:8);
```

you supply the uniform knot sequence `1:10` and the coefficient sequence `3:8`. Because there are 10 knots and 6 coefficients, the order must be  $4 (= 10 - 6)$ , i.e., you get a cubic spline. The command

```
fnbrk(sp)
```

prints out the constituent parts of the B-form of this cubic spline, as follows:

```
knots(1:n+k)
  1 2 3 4 5 6 7 8 9 10
coefficients(d,n)
  3 4 5 6 7 8
number n of coefficients
  6
order k
  4
dimension d of target
  1
```

Further, `fnbrk` can be used to supply each of these parts separately.

But the point of the Curve Fitting Toolbox spline functionality is that there shouldn't be any need for you to look up these details. You simply use `sp` as an argument to commands that evaluate, differentiate, integrate, convert, or plot the spline whose description is contained in `sp`.

### Working With B-form Splines

The following commands are available for spline work. There is `spmak` and `fnbrk` to make up a spline and take it apart again. Use `fn2fm` to convert from B-form to `ppform`. You can evaluate, differentiate, integrate, minimize, find zeros of, plot, refine, or selectively extrapolate a spline with the aid of `fnval`, `fnder`, `fndir`, `fnint`, `fnmin`, `fnzeros`, `fnplt`, `fnrfn`, and `fnxtr`.

There are five commands for generating knot sequences:

- `augknt` for providing boundary knots and also controlling the multiplicity of interior knots

- `brk2knt` for supplying a knot sequence with specified multiplicities
- `aptknt` for providing a knot sequence for a spline space of given order that is suitable for interpolation at given data sites
- `optknt` for providing an *optimal* knot sequence for interpolation at given sites
- `newknt` for a knot sequence perhaps more suitable for the function to be approximated

In addition, there is:

- `aveknt` to supply certain knot averages (the Greville sites) as recommended sites for interpolation
- `chbpnt` to supply such sites
- `knt2brk` and `knt2mlt` for extracting the breaks and/or their multiplicities from a given knot sequence

To display a spline *curve* with given two-dimensional coefficient sequence and a uniform knot sequence, use `spcrv`.

You can also write your own spline construction commands, in which case you will need to know the following. The construction of a spline satisfying some interpolation or approximation conditions usually requires a *collocation matrix*, i.e., the matrix that, in each row, contains the sequence of numbers  $D^r B_{j,k}(\tau)$ , i.e., the  $r$ th derivative at  $\tau$  of the  $j$ th B-spline, for all  $j$ , for some  $r$  and some site  $\tau$ . Such a matrix is provided by `spcol`. An optional argument allows for this matrix to be supplied by `spcol` in a space-saving spline-almost-block-diagonal-form or as a MATLAB sparse matrix. It can be fed to `slvblk`, a command for solving linear systems with an almost-block-diagonal coefficient matrix. If you are interested in seeing how `spcol` and `slvblk` are used in this toolbox, have a look at the commands `spapi`, `spap2`, and `spaps`.

In addition, there are routines for constructing *cubic* splines. `csapi` and `csape` provide the cubic spline interpolant at knots to given data, using the not-a-knot and various other end conditions, respectively. A parametric cubic spline curve through given points is provided by `cscvn`. The cubic *smoothing* spline is constructed in `csaps`.

## Example: B-form Spline Approximation to a Circle

As another simple example,

```
points = .95*[0 -1 0 1;1 0 -1 0];
sp = spmak(-4:8,[points points]);
```

provides a planar, quartic, spline curve whose middle part is a pretty good approximation to a circle, as the plot on the next page shows. It is generated by a subsequent

```
plot(points(1,:),points(2:,:), 'x'), hold on
fnplt(sp,[0,4]), axis equal square, hold off
```

Insertion of additional control points  $(\pm 0.95, \pm 0.95)/\sqrt{1.9}$  would make a visually perfect circle.

Here are more details. The spline curve generated has the form  $\sum_{j=1}^8 B_{j,5} a(:, j)$ , with `-4:8` the uniform knot sequence, and with its control points  $a(:, j)$  the sequence  $(0, \alpha), (-\alpha, 0), (0, -\alpha), (\alpha, 0), (0, \alpha), (-\alpha, 0), (0, -\alpha), (\alpha, 0)$  with  $\alpha=0.95$ . Only the curve part between the parameter values 0 and 4 is actually plotted.

To get a feeling for how close to circular this part of the curve actually is, compute its unsigned curvature. The curvature  $\kappa(t)$  at the curve point  $\gamma(t) = (x(t), y(t))$  of a space curve  $\gamma$  can be computed from the formula

$$\kappa = \frac{|x'y'' - y'x''|}{(x'^2 + y'^2)^{3/2}}$$

in which  $x'$ ,  $x''$ ,  $y'$ , and  $y''$  are the first and second derivatives of the curve with respect to the parameter used ( $t$ ). Treat the planar curve as a space curve in the  $(x,y)$ -plane, hence obtain the maximum and minimum of its curvature at 21 points as follows:


```
t = linspace(0,4,21);zt = zeros(size(t));
dsp = fnder(sp); dspt = fnval(dsp,t); ddspt = fnval(fnder(dsp),t);
kappa = abs(dspt(1,:).*ddspt(2,:)-dspt(2,:).*ddspt(1,:))./...
(sum(dspt.^2)).^(3/2);
[min(kappa),max(kappa)]
```

```
ans =
    1.6747    1.8611
```

So, while the curvature is not quite constant, it is close to  $1/\text{radius}$  of the circle, as you see from the next calculation:

```
1/norm(fnval(sp,0))
```

```
ans =
    1.7864
```



**Spline Approximation to a Circle; Control Points Are Marked x**

## **See Also**

### **More About**

- “Types of Splines: ppform and B-form” on page 10-2
- “The B-form” on page 10-13

## Multivariate Tensor Product Splines

### In this section...

“Introduction to Multivariate Tensor Product Splines” on page 10-21  
 “B-form of Tensor Product Splines” on page 10-21  
 “Construction With Gridded Data” on page 10-21  
 “ppform of Tensor Product Splines” on page 10-22  
 “Example: The Mobius Band” on page 10-22

### Introduction to Multivariate Tensor Product Splines

The toolbox provides (polynomial) spline functions in any number of variables, as tensor products of univariate splines. These multivariate splines come in both standard forms, the B-form and the ppform, and their construction and use parallels entirely that of the univariate splines discussed in previous sections, “Constructing and Working with ppform Splines” on page 10-10 and “Constructing and Working with B-form Splines” on page 10-17. The same commands are used for their construction and use.

For simplicity, the following discussion deals just with bivariate splines.

### B-form of Tensor Product Splines

The tensor-product idea is very simple. If  $f$  is a function of  $x$ , and  $g$  is a function of  $y$ , then their tensor-product  $p(x,y) := f(x)g(y)$  is a function of  $x$  and  $y$ , i.e., a bivariate function. More generally, with  $s = (s_1, \dots, s_{m+h})$  and  $t = (t_1, \dots, t_{n+k})$  knot sequences and  $a_{ij}$  ( $i = 1, \dots, m; j = 1, \dots, n$ ) a corresponding coefficient array, you obtain a bivariate spline as

$$f(x, y) = \sum_{i=1}^m \sum_{j=1}^n B(x | s_i, \dots, s_{i+h}) B(y | t_j, \dots, t_{j+k}) a_{ij}$$

The B-form of this spline comprises the cell array  $\{s, t\}$  of its knot sequences, the coefficient array  $a$ , the numbers vector  $[m, n]$ , and the orders vector  $[h, k]$ . The command

```
sp = spmak({s, t}, a);
```

constructs this form. Further, `fnplt`, `fnval`, `fnder`, `fndir`, `fnrfn`, and `fn2fm` can be used to plot, evaluate, differentiate and integrate, refine, and convert this form.

### Construction With Gridded Data

You are most likely to construct such a form by looking for an interpolant or approximant to gridded data. For example, if you know the values  $z(i,j) = g(x(i), y(j))$ ,  $i = 1:m, j = 1:n$ , of some function  $g$  at all the points in a rectangular grid, then, assuming that the strictly increasing sequence  $x$  satisfies the Schoenberg-Whitney conditions with respect to the above knot sequence  $s$ , and that the strictly increasing sequence  $y$  satisfies the Schoenberg-Whitney conditions with respect to the above knot sequence  $t$ , the command

```
sp = spapi({s, t}, [h, k], {x, y}, z);
```

constructs the unique bivariate spline of the above form that matches the given values. The command `fnplt(sp)` gives you a quick plot of this interpolant. The command `pp = fn2fm(sp, 'pp')` gives you the `ppform` of this spline, which is probably what you want when you want to evaluate the spline at a fine grid (`xx(i),yy(j)`) for `i=1:M`, `j=1:N`), by the command:

```
values = fnval(pp,{xx,yy});
```


## ppform of Tensor Product Splines

The `ppform` of such a bivariate spline comprises, analogously, a cell array of break sequences, a multidimensional coefficient array, a vector of number pieces, and a vector of polynomial orders. Fortunately, the toolbox is set up in such a way that there is usually no reason for you to concern yourself with these details of either form. You use interpolation, approximation, or smoothing to construct splines, and then use the `fn...` commands to make use of them.

## Example: The Möbius Band

Here is an example of a surface constructed as a 3-D-valued bivariate spline. The surface is the famous Möbius band, obtainable by taking a longish strip of paper and gluing its narrow ends together, but with a twist. The figure is obtained by the following commands:

```
x = 0:1; y = 0:4; h = 1/4; o2 = 1/sqrt(2); s = 2; ss = 4;
v(3, :, :) = h*[0, -1, -o2, 0, o2, 1, 0; 0, 1, o2, 0, -o2, -1, 0];
v(2, :, :) = [ss, 0, s-h*o2, 0, -s-h*o2, 0, ss; ...
              ss, 0, s+h*o2, 0, -s+h*o2, 0, ss];
v(1, :, :) = s*[0, 1, 0, -1+h, 0, 1, 0; 0, 1, 0, -1-h, 0, 1, 0];
cs = csape({x,y},v,{'variational','clamped'});
fnplt(cs), axis([-2 2 -2.5 2.5 -.5 .5]), shading interp
axis off, hold on
values = squeeze(fnval(cs,{1,linspace(y(1),y(end),51)}));
plot3(values(1,:), values(2,:), values(3,:), 'k', 'linewidth', 2)
view(-149,28), hold off
```



**A Möbius Band Made by Vector-Valued Bivariate Spline Interpolation**

## See Also

## More About

- “Types of Splines: `ppform` and B-form” on page 10-2



## NURBS and Other Rational Splines

### In this section...

"Introduction to Rational Splines" on page 10-23

"rsform: rpform, rBform" on page 10-23

### Introduction to Rational Splines

A rational spline is, by definition, any function that is the ratio of two splines:

$$r(x) = s(x)/w(x)$$

This requires  $w$  to be scalar-valued, but  $s$  is often chosen to be vector-valued. Further, it is desirable that  $w(x)$  be not zero for any  $x$  of interest.

Rational splines are popular because, in contrast to ordinary splines, they can be used to describe certain basic design shapes, like conic sections, exactly.

### rsform: rpform, rBform

The two splines,  $s$  and  $w$ , in the rational spline  $r(x)=s(x)/w(x)$  need not be related to one another. They could even be of different forms. But, in the context of this toolbox, it is convenient to restrict them to be of the same form, and even of the same order and with the same breaks or knots. For, under that assumption, you can represent such a rational spline by the (vector-valued) spline function

$$R(x) = [s(x); w(x)]$$

whose values are vectors with one more entry than the values of the rational spline  $r$ , and call this the *rsform* of the rational spline, or, more precisely, the *rpform* or *rBform*, depending on whether  $s$  and  $w$  are in *ppform* or in *B-form*. Internally, the only thing that distinguishes these rational forms from their corresponding ordinary spline forms, *rpform* and *B-form*, is their form part, i.e., the output obtained from `fnbrk(r, 'form')`. This is enough to alert the `fn...` commands to act appropriately on a function in one of the *rsforms*.

For example, as is done in `fnval`, it is very easy to obtain  $r(x)$  from  $R(x)$ . If  $v$  is the value of  $R$  at  $x$ , then  $v(1:end-1)/v(end)$  is the value of  $r$  at  $x$ . If, in addition,  $dv$  is  $DR(x)$ , then  $(dv(1:end-1) - dv(end)*v(1:end-1))/v(end)$  is  $Dr(x)$ . More generally, by Leibniz's formula,

$$D^j s = D^j(wr) = \sum_{i=0}^j \binom{j}{i} D^i w D^{j-i} r$$

Therefore,

$$D^j r = \left( D^j s - \sum_{i=1}^j \binom{j}{i} D^i w D^{j-i} r \right) / w$$

This shows that you can compute the derivatives of  $r$  inductively, using the derivatives of  $s$  and  $w$  (i.e., the derivatives of  $R$ ) along with the derivatives of  $r$  of order less than  $j$  to compute the  $j$ th derivative of  $r$ . This inductive scheme is used in `fntrlr` to provide the first so many derivatives of a rational spline. There is a corresponding formula for partial and directional derivatives for multivariate rational splines.

## **See Also**

### **Related Examples**

- “Constructing and Working with Rational Splines” on page 10-25

## Constructing and Working with Rational Splines

### In this section...

“Rational Spline Example: Circle” on page 10-25  
 “Rational Spline Example: Sphere” on page 10-26  
 “Functions for Working With Rational Splines” on page 10-26

### Rational Spline Example: Circle

For example,

```
circle = rsmak('circle');
```

provides a rational spline whose values on its basic interval trace out the unit circle, i.e., the circle of radius 1 with center at the origin, as the command

```
fnplt(circle), axis square
```

readily shows; the resulting output is the circle in the figure “A Circle and an Ellipse, Both Given by a Rational Spline” on page 10-25.


It is easy to manipulate this circle to obtain related shapes. For example, the next commands stretch the circle into an ellipse, rotate the ellipse 45 degrees, and translate it by (1,1), and then plot it on top of the circle.

```
ellipse = fncmb(circle,[2 0;0 1]);
s45 = 1/sqrt(2);
rtellipse = fncmb(fncmb(ellipse, [s45 -s45;s45 s45]), [1;1] );
hold on, fnplt(rtellipse), hold off
```

As a further example, the "circle" just constructed is put together from four pieces. To highlight the first such piece, use the following commands:

```
quarter = fnbrk(fn2fm(circle,'rp'),1);
hold on, fnplt(quarter,3), hold off
```

In the first command, `fn2fm` is used to change forms, from one based on the B-form to one based on the ppform, and then `fnbrk` is used to extract the first piece, and this piece is then plotted on top of the circle in “A Circle and an Ellipse, Both Given by a Rational Spline” on page 10-25, with linewidth 3 to make it stand out.



**A Circle and an Ellipse, Both Given by a Rational Spline**

## Rational Spline Example: Sphere

As a surface example, the command `rsmak('southcap')` provides a 3-vector valued rational bicubic polynomial whose values on the unit square  $[-1 \dots 1]^2$  fill out a piece of the unit sphere. Adjoin to it five suitable rotates of it and you get the unit sphere exactly. For illustration, the following commands generate two-thirds of that sphere, as shown in “Part of a Sphere Formed by Four Rotates of a Quartic Rational” on page 10-26.

```
southcap = rsmak('southcap'); fnplt(southcap)
xpcap = fncmb(southcap,[0 0 -1;0 1 0;1 0 0]);
ypcap = fncmb(xpcap,[0 -1 0; 1 0 0; 0 0 1]);
northcap = fncmb(southcap,-1);
hold on, fnplt(xpcap), fnplt(ypcap), fnplt(northcap)
axis equal, shading interp, view(-115,10), axis off, hold off
```



Part of a Sphere Formed by Four Rotates of a Quartic Rational

## Functions for Working With Rational Splines

Having chosen to represent the rational spline  $r = s/w$  in this way by the ordinary spline  $R=[s;w]$  makes it is easy to apply to a rational spline all the `fn...` commands in the Curve Fitting Toolbox spline functions, with the following exceptions. The integral of a rational spline need not be a rational spline, hence there is no way to extend `fnint` to rational splines. The derivative of a rational spline is again a rational spline but one of roughly twice the order. For that reason, `fnder` and `fndir` will not touch rational splines. Instead, there is the command `fntr` for computing the value at a given  $x$  of all derivatives up to a given order of a given function. If that function is rational, the needed calculation is based on the considerations given in the preceding paragraph.

The command `r = rsmak(shape)` provides rational splines in `rBform` that describe exactly certain standard geometric shapes, like 'circle', 'arc', 'cylinder', 'sphere', 'cone', 'torus'. The command `fncmb(r,trans)` can be used to apply standard transformations to the resulting shape. For example, if `trans` is a column-vector of the right length, the shape would be translated by that vector while, if `trans` is a suitable matrix like a rotation, the shape would be transformed by that matrix.

The command `r = rscvn(p)` constructs the quadratic `rBform` of a tangent-continuous curve made up of circular arcs and passing through the given sequence, `p`, of points in the plane.

A special rational spline form, called a NURBS, has become a standard tool in CAGD. A NURBS is, by definition, any rational spline for which both  $s$  and  $w$  are in the same B-form, with each coefficient for  $s$  containing explicitly the corresponding coefficient for  $w$  as a factor:

$$s = \sum_i B_i v(i) a(:, i), \quad w = \sum_i B_i v(i)$$

The normalized coefficients  $a(:, i)$  for the numerator spline are more readily used as control points than the unnormalized coefficients  $v(i)a(:, i)$  used in the `rbform`. Nevertheless, this toolbox provides no special NURBS form, but only the more general rational spline, but in both B-form (called `rbform` internally) and in ppform (called `rpform` internally).

The rational spline `circle` used earlier is put together in `rsmak` by code like the following.

```
x = [1 1 0 -1 -1 -1 0 1 1]; y = [0 1 1 1 0 -1 -1 -1 0];
s45 = 1/sqrt(2); w = [1 s45 1 s45 1 s45 1 s45 1];
circle = rsmak(augknt(0:4,3,2), [w.*x;w.*y;w]);
```

Note the appearance of the denominator spline as the last component. Also note how the coefficients of the denominator spline appear here explicitly as factors of the corresponding coefficients of the numerator spline. The normalized coefficient sequence `[x;y]` is very simple; it consists of the vertices and midpoints, in proper order, of the "unit square". The resulting control polygon is tangent to the circle at the places where the four quadratic pieces that form the circle abut.

For a thorough discussion of NURBS, see [G. Farin, *NURBS*, 2nd ed., AKPeters Ltd, 1999] or [Les Piegl and Wayne Tiller, *The NURBS Book*, 2nd ed., Springer-Verlag, 1997].

## See Also

## More About

- "Multivariate and Rational Splines" on page 10-6

## Constructing and Working with stform Splines

### In this section...

“Introduction to the stform” on page 10-28

“Construction and Properties of the stform” on page 10-28

“Working with the stform” on page 10-29

### Introduction to the stform

A multivariate function form quite different from the tensor-product construct is the scattered translates form, or stform for short. As the name suggests, it uses arbitrary or scattered translates  $\psi(\cdot - c_j)$  of one fixed function  $\psi$ , in addition to some polynomial terms. Explicitly, such a form describes a function

$$f(x) = \sum_{j=1}^{n-k} \psi(x - c_j) a_j + p(x)$$

in terms of the *basis function*  $\psi$ , a sequence  $(c_j)$  of sites called *centers* and a corresponding sequence  $(a_j)$  of  $n$  coefficients, with the final  $k$  coefficients,  $a_{n-k+1}, \dots, a_n$ , involved in the *polynomial part*,  $p$ .

When the basis function is radially symmetric, meaning that  $\psi(x)$  depends only on the Euclidean length  $|x|$  of its argument,  $x$ , then  $\psi$  is called a *radial basis function*, and, correspondingly,  $f$  is then often called an RBF.

At present, the toolbox works with just one kind of stform, namely a bivariate thin-plate spline and its first partial derivatives. For the thin-plate spline, the basis function is  $\psi(x) = \varphi(|x|^2)$ , with  $\varphi(t) = t \log t$ , i.e., a radial basis function. Its polynomial part is a linear polynomial, i.e.,  $p(x) = x(1) a_{n-2} + x(2) a_{n-1} + a_n$ . The first partial derivative with respect to its first argument uses, correspondingly, the basis function  $\psi(x) = \varphi(|x|^2)$ , with  $\varphi(t) = (D_1 t) \cdot (\log t + 1)$  and  $D_1 t = D_1 t(x) = 2x(1)$ , and  $p(x) = a_n$ .

### Construction and Properties of the stform

A function in stform can be put together from its center sequence `centers` and its coefficient sequence `coefs` by the command

```
f = stmak(centers, coefs, type);
```

where `type` can be specified as one of `'tp00'`, `'tp10'`, `'tp01'`, to indicate, respectively, a thin-plate spline, a first partial of a thin-plate spline with respect to the first argument, and a first partial of a thin-plate spline with respect to the second argument. There is one other choice, `'tp'`; it denotes a thin-plate spline without any polynomial part and is likely to be used only during the construction of a thin-plate spline, as in `tpaps`.

A function  $f$  in stform depends linearly on its coefficients, meaning that

$$f(x) = \sum_{j=1}^n \psi_j(x) a_j$$

with  $\psi_j$  either a translate of the basis function  $\Psi$  or else some polynomial. Suppose you wanted to determine these coefficients  $a_j$  so that the function  $f$  matches prescribed values at prescribed sites  $x_i$ .

Then you would need the collocation matrix ( $\psi_j(x_i)$ ). You can obtain this matrix by the command `stcol(centers,x,type)`. In fact, because the stform has  $a_j$  as the  $j$ th column, `coefs(:,j)`, of its coefficient array, it is worth noting that `stcol` can also supply the *transpose* of the collocation matrix. Thus, the command

```
values = coefs*stcol(centers,x,type,'tr');
```

would provide the values at the entries of `x` of the st function specified by `centers` and `type`.

The stform is attractive because, in contrast to piecewise polynomial forms, its complexity is the same in any number of variables. It is quite simple, yet, because of the complete freedom in the choice of centers, very flexible and adaptable.

On the negative side, the most attractive choices for a radial basis function share with the thin-plate spline that the evaluation at any site involves all coefficients. For example, plotting a scalar-valued thin-plate spline via `fnplt` involves evaluation at a 51-by-51 grid of sites, a nontrivial task when there are 1000 coefficients or more. The situation is worse when you want to determine these 1000 coefficients so as to obtain the stform of a function that matches function values at 1000 data sites, as this calls for solving a full linear system of order 1000, a task requiring  $O(10^9)$  flops if done by a direct method. Just the construction of the collocation matrix for this linear system (by `stcol`) takes  $O(10^6)$  flops.

The command `tpaps`, which constructs thin-plate spline interpolants and approximants, uses iterative methods when there are more than 728 data points, but convergence of such iteration may be slow.

## Working with the stform

After you have constructed an approximating or interpolating thin-plate spline `st` with the aid of `tpaps` (or directly via `stmak`), you can use the following commands:

- `fnbrk` to obtain its parts or change its basic interval,
- `fnval` to evaluate it
- `fnplt` to plot it
- `fnder` to construct its two first partial derivatives, but no higher order derivatives as they become infinite at the centers.

This is just one indication that the stform is quite different in nature from the other forms in this toolbox, hence other `fn...` commands by and large don't work with stforms. For example, it makes no sense to use `fnjmp`, and `fnmin` or `fnzeros` only work for univariate functions. It also makes no sense to use `fnint` on a function in stform because such functions cannot be integrated in closed form.

- The command `Ast = fncmb(st,A)` can be used on `st`, provided `A` is something that can be applied to the values of the function described by `st`. For example, `A` might be `'sin'`, in which case `Ast` is the stform of the function whose coefficients are the sine of the coefficients of `st`. In effect, `Ast` describes the function obtained by composing `A` with `st`. But, because of the singularities in the higher-order derivatives of a thin-plate spline, there seems little point to make `fndir` or `fntlr` applicable to such a `st`.





# Advanced Spline Examples

---

- “Least-Squares Approximation by Natural Cubic Splines” on page 11-2
- “Solving A Nonlinear ODE” on page 11-6
- “Chebyshev Spline Construction” on page 11-10
- “Approximation by Tensor Product Splines” on page 11-14

## Least-Squares Approximation by Natural Cubic Splines

The construction of a least-squares approximant usually requires that one have in hand a basis for the space from which the data are to be approximated. As the example of the space of “natural” cubic splines illustrates, the explicit construction of a basis is not always straightforward.

This section makes clear that an explicit basis is not actually needed; it is sufficient to have available some means of interpolating in some fashion from the space of approximants. For this, the fact that the Curve Fitting Toolbox spline functions support work with vector-valued functions is essential.

This section discusses these aspects of least-squares approximation by “natural” cubic splines.

- “Problem” on page 11-2
- “General Resolution” on page 11-2
- “Need for a Basis Map” on page 11-2
- “A Basis Map for “Natural” Cubic Splines” on page 11-3
- “The One-line Solution” on page 11-3
- “The Need for Proper Extrapolation” on page 11-3
- “The Correct One-Line Solution” on page 11-4
- “Least-Squares Approximation by Cubic Splines” on page 11-5

### Problem

You want to construct the least-squares approximation to given data  $(x,y)$  from the space  $S$  of “natural” cubic splines with given breaks  $b(1) < \dots < b(l+1)$ .

### General Resolution

If you know a basis,  $(f_1, f_2, \dots, f_m)$ , for the linear space  $S$  of all “natural” cubic splines with break sequence  $b$ , then you have learned to find the least-squares approximation in the form  $c(1)f_1 + c(2)f_2 + \dots + c(m)f_m$ , with the vector  $c$  the least-squares solution to the linear system  $A*c = y$ , whose coefficient matrix is given by

$$A(i, j) = f_j(x(i)), \quad i=1:\text{length}(x), \quad j=1:m .$$

In other words,  $c = A \backslash y$ .

### Need for a Basis Map

The general solution seems to require that you know a basis. However, in order to construct the coefficient sequence  $c$ , you only need to know the matrix  $A$ . For this, it is sufficient to have at hand a *basis map*, namely a function  $F$  say, so that  $F(c)$  returns the spline given by the particular weighted sum  $c(1)f_1 + c(2)f_2 + \dots + c(m)f_m$ . For, with that, you can obtain, for  $j=1:m$ , the  $j$ -th column of  $A$  as  $f_{\text{eval}}(F(e_j), x)$ , with  $e_j$  the  $j$ -th column of  $\text{eye}(m)$ , the identity matrix of order  $m$ .

Better yet, the Curve Fitting Toolbox spline functions can handle *vector-valued* functions, so you should be able to construct the basis map  $F$  to handle vector-valued coefficients  $c(i)$  as well. However, by agreement, in this toolbox, a vector-valued coefficient is a *column* vector, hence the

sequence  $c$  is necessarily a row vector of column vectors, i.e., a *matrix*. With that,  $F(\text{eye}(m))$  is the vector-valued spline whose  $i$ -th component is the basis element  $f_i$ ,  $i=1:m$ . Hence, assuming the vector  $x$  of data sites to be a row vector,  $\text{fnval}(F(\text{eye}(m)), x)$  is the matrix whose  $(i, j)$ -entry is the value of  $f_i$  at  $x(j)$ , i.e., the *transpose* of the matrix  $A$  you are seeking. On the other hand, as just pointed out, your basis map  $F$  expects the coefficient sequence  $c$  to be a row vector, i.e., the transpose of the vector  $A \setminus y$ . Hence, assuming, correspondingly, the vector  $y$  of data values to be a row vector, you can obtain the least-squares approximation from  $S$  to data  $(x, y)$  as

```
F(y/fnval(F(eye(m)),x))
```

To be sure, if you wanted to be prepared for  $x$  and  $y$  to be arbitrary vectors (of the same length), you would use instead

```
F(y(:).'/fnval(F(eye(m)),x(:).'))
```

## A Basis Map for “Natural” Cubic Splines

What exactly is required of a basis map  $F$  for the linear space  $S$  of “natural” cubic splines with break sequence  $b(1) < \dots < b(l+1)$ ? Assuming the dimension of this linear space is  $m$ , the map  $F$  should set up a linear one-to-one correspondence between  $m$ -vectors and elements of  $S$ . But that is exactly what `csape(b, ., 'var')` does.

To be explicit, consider the following function  $F$ :

```
function s = F(c)
s = csape(b,c,'var');
```

For given vector  $c$  (of the same length as  $b$ ), it provides the *unique* “natural” cubic spline with break sequence  $b$  that takes the value  $c(i)$  at  $b(i)$ ,  $i=1:l+1$ . The uniqueness is key. It ensures that the correspondence between the vector  $c$  and the resulting spline  $F(c)$  is one-to-one. In particular,  $m$  equals  $\text{length}(b)$ . More than that, because the value  $f(t)$  of a function  $f$  at a point  $t$  depends linearly on  $f$ , this uniqueness ensures that  $F(c)$  depends linearly on  $c$  (because  $c$  equals  $\text{fnval}(F(c), b)$  and the inverse of an invertible linear map is again a linear map).

## The One-line Solution

Putting it all together, you arrive at the following code

```
csape(b,y(:).'/fnval(csape(b,eye(length(b)),'var'),x(:).')),...
'var')
```

for the least-squares approximation by “natural” cubic splines with break sequence  $b$ .

## The Need for Proper Extrapolation

Let's try it on some data, the census data, say, which is provided in MATLAB by the command

```
load census
```

and which supplies the years, 1790:10:1990, as `cdate` and the values as `pop`. Use the break sequence 1810:40:1970.

```
b = 1810:40:1970;
s = csape(b, ...
```

```


pop(:)'/fnval(csape(b,eye(length(b)),'var'),cdate(:))','var');
fnplt(s, [1750,2050],2.2);
hold on
plot(cdate,pop,'or');
hold off

```

Have a look at “Least-Squares Approximation by “Natural” Cubic Splines With Three Interior Breaks” on page 11-4 which shows, in thick blue, the resulting approximation, along with the given data.

This looks like a good approximation, -- except that it doesn't look like a “natural” cubic spline. A “natural” cubic spline, to recall, must be linear to the left of its first break and to the right of its last break, and this approximation satisfies neither condition. This is due to the following facts.

The “natural” cubic spline interpolant to given data is provided by `csape` in `ppform`, with the interval spanned by the data sites its basic interval. On the other hand, evaluation of a `ppform` outside its basic interval is done, in MATLAB `ppval` or Curve Fitting Toolbox spline function `fnval`, by using the relevant polynomial end piece of the `ppform`, i.e., by full-order extrapolation. In case of a “natural” cubic spline, you want instead second-order extrapolation. This means that you want, to the left of the first break, the straight line that agrees with the cubic spline in value and slope at the first break. Such an extrapolation is provided by `fnxtr`. Because the “natural” cubic spline has zero second derivative at its first break, such an extrapolation is even third-order, i.e., it satisfies three matching conditions. In the same way, beyond the last break of the cubic spline, you want the straight line that agrees with the spline in value and slope at the last break, and this, too, is supplied by `fnxtr`.



## Least-Squares Approximation by “Natural” Cubic Splines With Three Interior Breaks

### The Correct One-Line Solution

The following one-line code provides the correct least-squares approximation to data  $(x,y)$  by “natural” cubic splines with break sequence `b`:

```

fnxtr(csape(b,y(:).'/ ...
      fnval(fnxtr(csape(b,eye(length(b)),'var')),x(:).'),'var'))

```

But it is, admittedly, a rather long line.

The following code uses this correct formula and plots, in a thinner, red line, the resulting approximation on top of the earlier plots, as shown in “Least-Squares Approximation by “Natural” Cubic Splines With Three Interior Breaks” on page 11-4.

```

ss = fnxtr(csape(b,pop(:)'/ ...
    fnval(fnxtr(csape(b,eye(length(b)),'var')),cdate(:)'),'var'));
hold on, fnplt(ss,[1750,2050],1.2,'r'),grid, hold off
legend('incorrect approximation','population', ...
'correct approximation')

```

## Least-Squares Approximation by Cubic Splines

The one-line solution works perfectly if you want to approximate by the space  $S$  of all cubic splines with the given break sequence  $b$ . You don't even have to use the Curve Fitting Toolbox spline functions for this because you can rely on the MATLAB `spline`. You know that, with  $c$  a sequence containing two more entries than does  $b$ , `spline(b,c)` provides the unique cubic spline with break sequence  $b$  that takes the value  $c(i+1)$  at  $b(i)$ , all  $i$ , and takes the slope  $c(1)$  at  $b(1)$ , and the slope  $c(\text{end})$  at  $b(\text{end})$ . Hence, `spline(b,.)` is a basis map for  $S$ .

More than that, you know that `spline(b,c,xi)` provides the value(s) at  $xi$  of this interpolating spline. Finally, you know that `spline` can handle vector-valued data. Therefore, the following one-line code constructs the least-squares approximation by cubic splines with break sequence  $b$  to data  $(x,y)$ :

```
spline(b,y(:)'/spline(b,eye(length(b)),x(:)'))
```

## Solving A Nonlinear ODE

This section discusses these aspects of a nonlinear ODE problem:

- “Problem” on page 11-6
- “Approximation Space” on page 11-6
- “Discretization” on page 11-6
- “Numerical Problem” on page 11-7
- “Linearization” on page 11-7
- “Linear System to Be Solved” on page 11-7
- “Iteration” on page 11-8

You can run this example: “Solving a Nonlinear ODE with a Boundary Layer by Collocation”.

### Problem

Consider the nonlinear singularly perturbed problem:

$$\varepsilon D^2 g(x) + (g(x))^2 = 1 \text{ on } [0..1]$$

$$Dg(0) = g(1) = 0$$

### Approximation Space

Seek an approximate solution by collocation from  $C^1$  piecewise cubics with a suitable break sequence; for instance,

```
breaks = (0:4)/4;
```

Because cubics are of order 4, you have

```
k = 4;
```

Obtain the corresponding knot sequence as

```
knots = augknt(breaks,k,2);
```

This gives a quadruple knot at both 0 and 1, which is consistent with the fact that you have cubics, i.e., have order 4.

This implies that you have

```
n = length(knots) - k;  
n = 10;
```

i.e., 10 degrees of freedom.

### Discretization

You collocate at two sites per polynomial piece, i.e., at eight sites altogether. This, together with the two side conditions, gives us 10 conditions, which matches the 10 degrees of freedom.

Choose the two Gaussian sites for each interval. For the *standard* interval  $[-0.5, 0.5]$  of length 1, these are the two sites

```
gauss = .5773502692*[-1/2; 1/2];
```

From this, you obtain the whole collection of collocation sites by

```
ninterv = length(breaks)-1;
temp = ((breaks(2:ninterv+1)+breaks(1:ninterv))/2);
temp = temp([1 1], :) + gauss*diff(breaks);
colsites = temp(:).';
```

## Numerical Problem

With this, the numerical problem you want to solve is to find  $y \in S_{4, knots}$  that satisfies the nonlinear system

$$\begin{aligned} Dy(0) &= 0 \\ (y + \varepsilon D^2 y(x) &= 1 \text{ for } x \in \text{colsites} \\ y(1) &= 0 \end{aligned}$$

## Linearization

If  $y$  is your current approximation to the solution, then the linear problem for the supposedly better solution  $z$  by Newton's method reads

$$\begin{aligned} Dz(0) &= 0 \\ w_0(x)z(x) + \varepsilon D^2 z(x) &= b(x) \text{ for } x \in \text{colsites} \\ z(1) &= 0 \end{aligned}$$

with  $w_0(x) = 2y(x)$ ,  $b(x) = (y(x))^2 + 1$ . In fact, by choosing

$$\begin{aligned} w_0(1) &= 1, \quad w_1(0) = 1 \\ w_1(x) &= 0, \quad w_2(x) = \varepsilon \text{ for } x \in \text{colsites} \end{aligned}$$

and choosing all other values of  $w_0, w_1, w_2, b$  not yet specified to be zero, you can give your system the uniform shape

$$w_0(x)z(x) + w_1(x)Dz(x) + w_2(x)D^2z(x) = b(x), \text{ for } x \in \text{sites}$$

with

```
sites = [0, colsites, 1];
```

## Linear System to Be Solved

Because  $z \in S_{4, knots}$ , convert this last system into a system for the B-spline coefficients of  $z$ . This requires the values, first, and second derivatives at every  $x \in \text{sites}$  and for all the relevant B-splines. The command `spcol` was expressly written for this purpose.

Use `spcol` to supply the matrix

```
colmat = ...
spcol(knots,k,brk2knt(sites,3));
```

From this, you get the collocation matrix by combining the row triple of `colmat` for  $x$  using the weights  $w_0(x), w_1(x), w_2(x)$  to get the row for  $x$  of the actual matrix. For this, you need a current approximation  $y$ . Initially, you get it by interpolating some reasonable initial guess from your piecewise-polynomial space at the `sites`. Use the parabola  $x^2-1$ , which satisfies the end conditions as the initial guess, and pick the matrix from the full matrix `colmat`. Here it is, in several cautious steps:

```
intmat = colmat([2 1+(1:(n-2))*3,1+(n-1)*3],:);
coefs = intmat\[0 colsites.*colsites-1 0].';
y = spmak(knots,coefs.');
```

Plot the initial guess, and turn hold on for subsequent plotting:

```
fnplt(y,'g');
legend('Initial Guess (x^2-1)', 'location', 'NW');
axis([-0.01 1.01 -1.01 0.01]);
hold on
```

## Iteration

You can now complete the construction and solution of the linear system for the improved approximate solution  $z$  from your current guess  $y$ . In fact, with the initial guess  $y$  available, you now set up an iteration, to be terminated when the change  $z-y$  is *small enough*. Choose a relatively mild  $\varepsilon = .1$ .

```
tolerance = 6.e-9;
epsilon = .1;
while 1
    vtau = fnval(y,colsites);
    weights=[0 1 0;
             [2*vtau.' zeros(n-2,1) repmat(epsilon,n-2,1)];
            1 0 0];
    colloc = zeros(n,n);
    for j=1:n
        colloc(j,:) = weights(j,:)*colmat(3*(j-1)+(1:3),:);
    end
    coefs = colloc\[0 vtau.*vtau+1 0].';
    z = spmak(knots,coefs.');
```

```
fnplt(z,'k');
maxdif = max(max(abs(z.coefs-y.coefs)));
fprintf('maxdif = %g\n',maxdif)
if (maxdif<tolerance), break, end
% now reiterate
y = z;
end
legend({'Initial Guess (x^2-1)' 'Iterates'}, 'location', 'NW');
```

The resulting printout of the errors is:

```
maxdif = 0.206695
maxdif = 0.01207
maxdif = 3.95151e-005
maxdif = 4.43216e-010
```



If you now decrease  $\varepsilon$ , you create more of a boundary layer near the right endpoint, and this calls for a nonuniform mesh.

Use `newknt` to construct an appropriate finer mesh from the current approximation:

```
knots = newknt(z, ninterv+1); breaks = knt2brk(knots);
knots = augknt(breaks,4,2);
n = length(knots)-k;
```

From the new break sequence, you generate the new collocation site sequence:

```
ninterv = length(breaks)-1;
temp = ((breaks(2:ninterv+1)+breaks(1:ninterv))/2);
temp = temp([1 1], :) + gauss*diff(breaks);
colpnts = temp(:).';
sites = [0,colpnts,1];
```

Use `spcol` to supply the matrix

```
colmat = spcol(knots,k,sort([sites sites sites]));
```

and use your current approximate solution `z` as the initial guess:

```
intmat = colmat([2 1+(1:(n-2))*3,1+(n-1)*3],:);
y = spmak(knots,[0 fnval(z,colpnts) 0]/intmat.');
```

Thus set up, divide  $\varepsilon$  by 3 and repeat the earlier calculation, starting with the statements

```
tolerance=1.e-9;
while 1
    vtau=fnval(y,colpnts);
    .
    .
    .
```

Repeated passes through this process generate a sequence of solutions, for  $\varepsilon = 1/10, 1/30, 1/90, 1/270, 1/810$ . The resulting solutions, ever flatter at 0 and ever steeper at 1, are shown in the example plot. The plot also shows the final break sequence, as a sequence of vertical bars. To view the plots, run the example “Solving a Nonlinear ODE with a Boundary Layer by Collocation”.

In this example, at least, `newknt` has performed satisfactorily.

## Chebyshev Spline Construction

This section discusses these aspects of the Chebyshev spline construction:

- “What Is a Chebyshev Spline?” on page 11-10
- “Choice of Spline Space” on page 11-10
- “Initial Guess” on page 11-10
- “Remez Iteration” on page 11-11

### What Is a Chebyshev Spline?

The *Chebyshev spline*  $C=C_t=C_{k,t}$  of order  $k$  for the knot sequence  $t=(t_i; i=1:n+k)$  is the unique element of  $S_{k,t}$  of max-norm 1 that maximally oscillates on the interval  $[t_k..t_{n+1}]$  and is positive near  $t_{n+1}$ . This means that there is a unique strictly increasing  $n$ -sequence  $\tau$  so that the function  $C=C_t \in S_{k,t}$  given by  $C(\tau_i)=(-1)^{n-i}$ , all  $i$ , has max-norm 1 on  $[t_k..t_{n+1}]$ . This implies that  $\tau_1=t_k, \tau_n=t_{n+1}$ , and that  $t_i < \tau_i < t_{k+i}$ , for all  $i$ . In fact,  $t_{i+1} \leq \tau_i \leq t_{i+k-1}$ , all  $i$ . This brings up the point that the knot sequence is assumed to make such an inequality possible, i.e., the elements of  $S_{k,t}$  are assumed to be continuous.

In short, the Chebyshev spline  $C$  looks just like the Chebyshev polynomial. It performs similar functions. For example, its extreme sites  $\tau$  are particularly good sites to interpolate at from  $S_{k,t}$  because the norm of the resulting projector is about as small as can be; see the toolbox command `chbpnt`.

You can run the example “Construct Chebyshev Spline” on page 12-156 to construct  $C$  for a particular knot sequence  $t$ .

### Choice of Spline Space

You deal with cubic splines, i.e., with order

```
k = 4;
```

and use the break sequence

```
breaks = [0 1 1.1 3 5 5.5 7 7.1 7.2 8];
lp1 = length(breaks);
```

and use simple interior knots, i.e., use the knot sequence

```
t = breaks([ones(1,k) 2:(lp1-1) lp1(:),ones(1,k))]);
n = length(t)-k;
```

Note the quadruple knot at each end. Because  $k = 4$ , this makes  $[0..8] = [\text{breaks}(1)..\text{breaks}(\text{lp1})]$  the interval  $[t_k..t_{n+1}]$  of interest, with  $n = \text{length}(t)-k$  the dimension of the resulting spline space  $S_{k,t}$ . The same knot sequence would have been supplied by

```
t=augknt(breaks,k);
```

### Initial Guess

As the initial guess for the  $\tau$ , use the knot averages

$$t_i = (t_{i+1} + \dots + t_{i+k-1}) / (k-1)$$


recommended as good interpolation site choices. These are supplied by

```
tau=aveknt(t,k);
```

Plot the resulting first approximation to  $C$ , i.e., the spline  $c$  that satisfies  $c(\tau_i) = (-1)^{n-i}$ , all  $i$ :

```
b = cumprod(repmat(-1,1,n)); b = b*b(end);
c = spapi(t,tau,b);
fnplt(c,'-.-')
grid
```

Here is the resulting plot.



### First Approximation to a Chebyshev Spline

### Remez Iteration

Starting from this approximation, you use the Remez algorithm to produce a sequence of splines converging to  $C$ . This means that you construct new  $\tau$  as the extrema of your current approximation  $c$  to  $C$  and try again. Here is the entire loop.

Find the new interior  $\tau_i$  as the zeros of  $Dc$ —that is, the first derivative of  $c$ . First, differentiate

```
Dc = fnder(c);
```

Take the zeros of  $Dc$  using the `fnzeros` function. The zeros represent the extrema of the current approximation  $c$ . The result is the new guess for  $\tau$ .

```
tau(2:n-1) = mean(fnzeros(Dc));
```

Then check the extrema values of your current approximation there:

```
extremes = abs(fnval(c, tau));
```

The difference

```
max(extremes)-min(extremes)
ans = 0.6906
```

is an estimate of how far you are from total leveling.


Construct a new spline corresponding to the new choice of  $\tau$  and plot it on top of the old:

```
c = spapi(t,tau,b);
sites = sort([tau (0:100)*(t(n+1)-t(k))/100]);
values = fnval(c,sites);
hold on, plot(sites,values)
```

The following code turns on the grid and plots the locations of the extrema.

```
grid on
plot(tau(2:end-1),zeros(size(tau(2:end-1))), 'o');
hold off
lgd = legend( 'Initial Guess', 'Current Guess', 'Extreme Locations',...
'location', 'NorthEastOutside' );
lgd.Location = 'south';
```

Following is the resulting figure (legend not shown).



### A More Nearly Level Spline

If this is not close enough, one simply reiterates the loop. For this example, the next iteration already produces  $C$  to graphic accuracy.

## Approximation by Tensor Product Splines

Because the toolbox can handle splines with *vector* coefficients, it is easy to implement interpolation or approximation to gridded data by tensor product splines, as the following illustration is meant to show. You can also run the example “Bivariate Tensor Product Splines”.

To be sure, most tensor product spline approximation to gridded data can be obtained directly with one of the spline construction commands, like `spapi` or `csape`, in this toolbox, without concern for the details discussed in this example. Rather, this example is meant to illustrate the theory behind the tensor product construction, and this will be of help in situations not covered by the construction commands in this toolbox.

This section discusses these aspects of the tensor product spline problem:

- “Choice of Sites and Knots” on page 11-14
- “Least Squares Approximation as Function of  $y$ ” on page 11-14
- “Approximation to Coefficients as Functions of  $x$ ” on page 11-16
- “The Bivariate Approximation” on page 11-19
- “Switch in Order” on page 11-17
- “Approximation to Coefficients as Functions of  $y$ ” on page 11-18
- “The Bivariate Approximation” on page 11-19
- “Comparison and Extension” on page 11-20

### Choice of Sites and Knots

Consider, for example, least squares approximation to given data  $z(i,j)=f(x(i),y(j)), i=1:N_x, j=1:N_y$ . You take the data from a function used extensively by Franke for the testing of schemes for surface fitting (see R. Franke, “A critical comparison of some methods for interpolation of scattered data,” *Naval Postgraduate School Techn. Rep. NPS-53-79-003*, March 1979). Its domain is the unit square. You choose a few more data sites in the  $x$ -direction than the  $y$ -direction; also, for a better definition, you use higher data density near the boundary.

```
x = sort([(0:10)/10, .03 .07, .93 .97]);
y = sort([(0:6)/6, .03 .07, .93 .97]);
[xx,yy] = ndgrid(x,y); z = franke(xx,yy);
```

### Least Squares Approximation as Function of $y$

Treat these data as coming from a vector-valued function, namely, the function of  $y$  whose value at  $y(j)$  is the vector  $z(:,j)$ , all  $j$ . For no particular reason, choose to approximate this function by a vector-valued parabolic spline, with three uniformly spaced interior knots. This means that you choose the spline order and the knot sequence for this vector-valued spline as

```
ky = 3; knotsy = augknt([0, .25, .5, .75, 1], ky);
```

and then use `spap2` to provide the least squares approximant to the data:

```
sp = spap2(knotsy, ky, y, z);
```

In effect, you are finding simultaneously the discrete least squares approximation from  $S_{k_y, \text{knots}_y}$  to each of the  $N_x$  data sets

$$(y(j), z(i, j))_{j=1}^{N_y}, i = 1:N_x$$

In particular, the statements


```
yy = -.1:.05:1.1;
vals = fnval(sp,yy);
```

provide the array `vals`, whose entry `vals(i, j)` can be taken as an approximation to the value  $f(x(i), yy(j))$  of the underlying function  $f$  at the mesh-point  $x(i), yy(j)$  because `vals(:, j)` is the value at  $yy(j)$  of the approximating spline curve in `sp`.

This is evident in the following figure, obtained by the command:

```
mesh(x,yy,vals. '), view(150,50)
```

Note the use of `vals. '`, in the `mesh` command, needed because of the MATLAB matrix-oriented view when plotting an array. This can be a serious problem in bivariate approximation because there it is customary to think of  $z(i, j)$  as the function value at the point  $(x(i), y(j))$ , while MATLAB thinks of  $z(i, j)$  as the function value at the point  $(x(j), y(i))$ .



### A Family of Smooth Curves Pretending to Be a Surface

Note that both the first two and the last two values on each smooth curve are actually zero because both the first two and the last two sites in `yy` are outside the basic interval for the spline in `sp`.

Note also the ridges. They confirm that you are plotting smooth curves in one direction only.

## Approximation to Coefficients as Functions of $x$

To get an actual surface, you now have to go a step further. Look at the coefficients `coefsy` of the spline in `sp`:

```
coefsy = fnbrk(sp, 'coefs');
```

Abstractly, you can think of the spline in `sp` as the function

$$y \Big| \rightarrow \sum_r \text{coefs}_y(:, r) B_{r, k_y}(y)$$

with the  $i$ th entry `coefsy(i, r)` of the vector coefficient `coefsy(:, r)` corresponding to  $x(i)$ , for all  $i$ . This suggests approximating each coefficient vector `coefsy(q, :)` by a spline of the same order `kx` and with the same appropriate knot sequence `knotsx`. For no particular reason, this time use *cubic* splines with *four* uniformly spaced interior knots:

```
kx = 4; knotsx = augknt([0:.2:1], kx);
sp2 = spap2(knotsx, kx, x, coefsy.');
```

Note that `spap2(knots, k, x, fx)` expects `fx(:, j)` to be the datum at  $x(j)$ , i.e., expects each *column* of `fx` to be a function value. To fit the datum `coefsy(q, :)` at  $x(q)$ , for all  $q$ , present `spap2` with the *transpose* of `coefsy`.

## The Bivariate Approximation

Now consider the transpose of the coefficients `cxy` of the resulting spline *curve*:

```
coefs = fnbrk(sp2, 'coefs').';
```

It provides the *bivariate* spline approximation

$$(x, y) \Big| \rightarrow \sum_q \sum_r \text{coefs}(q, r) B_{q, k_x}(x) B_{r, k_y}(y)$$

to the original data

$$(x(i), y(j)) \Big| \rightarrow z(x(i), y(j)), i = 1:N_x, j = 1:N_y$$

To plot this spline surface over a grid, e.g., the grid


```
xv = 0:.025:1; yv = 0:.025:1;
```

you can do the following:

```
values = spcol(knotsx, kx, xv) * coefs * spcol(knotsy, ky, yv).';
mesh(xv, yv, values. '), view(150, 50);
```

This results in the following figure.





### Spline Approximation to Franke's Function

This makes good sense because `spcol(knotsx, kx, xv)` is the matrix whose  $(i, q)$ th entry equals the value  $B_{q, kx}(xv(i))$  at  $xv(i)$  of the  $q$ th B-spline of order  $kx$  for the knot sequence `knotsx`.

Because the matrices `spcol(knotsx, kx, xv)` and `spcol(knotsy, ky, yv)` are banded, it may be more efficient, though perhaps more memory-consuming, for *large* `xv` and `yv` to make use of `fncval`, as follows:

```
value2 = ...
    fncval(spmak(knotsx, fncval(spmak(knotsy, coefs), yv) .'), xv) .';
```

This is, in fact, what happens internally when `fncval` is called directly with a tensor product spline, as in

```
value2 = fncval(spmak({knotsx, knotsy}, coefs), {xv, yv});
```

Here is the calculation of the relative error, i.e., the difference between the given data and the value of the approximation at those data sites as compared with the magnitude of the given data:

```
errors = z - spcol(knotsx, kx, x)*coefs*spcol(knotsy, ky, y) .';
disp( max(max(abs(errors)))/max(max(abs(z))) )
```

The output is `0.0539`, perhaps not too impressive. However, the coefficient array was only of size `8 6`

```
disp(size(coefs))
```

to fit a data array of size `15 11`.

```
disp(size(z))
```

### Switch in Order

The approach followed here seems *biased*, in the following way. First think of the given data `z` as describing a vector-valued function of `y`, and then treat the matrix formed by the vector coefficients of the approximating curve as describing a vector-valued function of `x`.

What happens when you take things in the opposite order, i.e., think of  $z$  as describing a vector-valued function of  $x$ , and then treat the matrix made up from the vector coefficients of the approximating curve as describing a vector-valued function of  $y$ ?

Perhaps surprisingly, the final approximation is the same, up to round-off. Here is the numerical experiment.

### Least Squares Approximation as Function of $x$

First, fit a spline curve to the data, but this time with  $x$  as the independent variable, hence it is the rows of  $z$  that now become the data values. Correspondingly, you must supply  $z.'$ , rather than  $z$ , to `spap2`,


```
spb = spap2(knotsx,kx,x,z.');
```

thus obtaining a spline approximation to all the curves ( $x ; z(:,j)$ ). In particular, the statement

```
valsb = fnval(spb,xv).';
```

provides the matrix `valsb`, whose entry `valsb(i, j)` can be taken as an approximation to the value  $f(xv(i),y(j))$  of the underlying function  $f$  at the mesh-point  $(xv(i),y(j))$ . This is evident when you plot `valsb` using `mesh`:

```
mesh(xv,y,valsb. '), view(150,50)
```



### Another Family of Smooth Curves Pretending to Be a Surface

Note the ridges. They confirm that you are, once again, plotting smooth curves in one direction only. But this time the curves run in the other direction.

### Approximation to Coefficients as Functions of $y$

Now comes the second step, to get the actual surface. First, extract the coefficients:

```
coefsx = fnbrk(spb,'coefs');
```

Then fit each coefficient vector `coefsx(r, :)` by a spline of the same order `ky` and with the same appropriate knot sequence `knotsy`:

```
spb2 = spap2(knotsy,ky,y,coefsx.');
```

Note that, once again, you need to transpose the coefficient array from `spb`, because `spap2` takes the columns of its last input argument as the data values.

Correspondingly, there is now no need to transpose the coefficient array `coefsb` of the resulting *curve*:

```
coefsb = fnbrk(spb2, 'coefs');
```

## The Bivariate Approximation

The claim is that `coefsb` equals the earlier coefficient array `coefs`, up to round-off, and here is the test:

```
disp( max(max(abs(coefs - coefsb))) )
```

The output is `1.4433e-15`.

The explanation is simple enough: The coefficients  $c$  of the spline  $s$  contained in `sp = spap2(knots, k, x, y)` depend *linearly* on the input values  $y$ . This implies, given that both  $c$  and  $y$  are 1-row matrices, that there is some matrix  $A = A_{\text{knots}, k, x}$  so that

$$c = yA_{\text{knots}, k, x}$$

for any data  $y$ . This statement even holds when  $y$  is a *matrix*, of size  $d$ -by- $N$ , say, in which case each datum  $y(:,j)$  is taken to be a point in  $R^d$ , and the resulting spline is correspondingly  $d$ -vector-valued, hence its coefficient array  $c$  is of size  $d$ -by- $n$ , with  $n = \text{length}(\text{knots}) - k$ .

In particular, the statements

```
sp = spap2(knotsy, ky, y, z);
coefsy = fnbrk(sp, 'coefs');
```

provide us with the matrix `coefsy` that satisfies

$$\text{coefsy} = z \cdot A_{\text{knotsy}, ky, y}$$

The subsequent computations

```
sp2 = spap2(knotsx, kx, x, coefsy. ');
coefs = fnbrk(sp2, 'coefs').';
```

generate the coefficient array `coefs`, which, taking into account the two transpositions, satisfies

$$\begin{aligned} \text{coefs} &= ((zA_{\text{knotsy}, ky, y})' \cdot A_{\text{knotsx}, kx, x})' \\ &= (A_{\text{knotsx}, kx, x})' \cdot z \cdot A_{\text{knotsy}, ky, y} \end{aligned}$$

In the second, alternative, calculation, you first computed

```
spb = spap2(knotsx, kx, x, z. ');
coefsx = fnbrk(spb, 'coefs');
```

hence `coefsx = z' \cdot A_{\text{knotsx}, kx, x}`. The subsequent calculation

```
spb2 = spap2(knotsy, ky, y, coefsx. ');
coefsb = fnbrk(spb2, 'coefs');
```

then provided

$$\text{coefsb} = \text{coefsx} \cdot A_{\text{knotsy}, \text{ky}, \text{y}} = (A_{\text{knotsx}, \text{kx}, \text{x}}) \cdot z \cdot A_{\text{knotsy}, \text{ky}, \text{y}}$$

Consequently,  $\text{coefsb} = \text{coefsb}$ .

## Comparison and Extension

The second approach is more symmetric than the first in that transposition takes place in each call to `spap2` and nowhere else. This approach can be used for approximation to gridded data in any number of variables.

If, for example, the given data over a *three*-dimensional grid are contained in some three-dimensional array  $v$  of size  $[N_x, N_y, N_z]$ , with  $v(i, j, k)$  containing the value  $f(x(i), y(j), z(k))$ , then you would start off with

```
coefb = reshape(v, Nx, Ny*Nz);
```

Assuming that  $n_j = \text{knotsj} - k_j$ , for  $j = x, y, z$ , you would then proceed as follows:

```
sp = spap2(knotsx, kx, x, coefb. ');
coefb = reshape(fnbrk(sp, 'coefb'), Ny, Nz*nx);
sp = spap2(knotsy, ky, y, coefb. ');
coefb = reshape(fnbrk(sp, 'coefb'), Nz, nx*ny);
sp = spap2(knotsz, kz, z, coefb. ');
coefb = reshape(fnbrk(sp, 'coefb'), nx, ny*nz);
```

See Chapter 17 of *PGS* or [C. de Boor, "Efficient computer manipulation of tensor products," *ACM Trans. Math. Software* 5 (1979), 173-182; Corrigenda, 525] for more details. The same references also make clear that there is nothing special here about using least squares approximation. Any approximation process, including spline interpolation, whose resulting approximation has coefficients that depend linearly on the given data, can be extended in the same way to a multivariate approximation process to gridded data.

This is exactly what is used in the spline construction commands `csapi`, `csape`, `spapi`, `spaps`, and `spap2`, when gridded data are to be fitted. It is also used in `fnval`, when a tensor product spline is to be evaluated on a grid.

# Examples

---

## Polynomial Curve Fitting

This example shows how to fit polynomials up to sixth degree to some census data using Curve Fitting Toolbox™. It also shows how to fit a single-term exponential equation and compare this to the polynomial models.

The steps show how to:

- Load data and create fits using different library models.
- Search for the best fit by comparing graphical fit results, and by comparing numerical fit results including the fitted coefficients and goodness of fit statistics.

### Load and Plot the Data

The data for this example is the file `census.mat`.

```
load census
```


The workspace contains two new variables:

- `cdate` is a column vector containing the years 1790 to 1990 in 10-year increments.
- `pop` is a column vector with the U.S. population figures that correspond to the years in `cdate`.

```
whos cdate pop
```

| Name               | Size | Bytes | Class  | Attributes |
|--------------------|------|-------|--------|------------|
| <code>cdate</code> | 21x1 | 168   | double |            |
| <code>pop</code>   | 21x1 | 168   | double |            |

```
plot(cdate,pop,'o')
```




### Create and Plot a Quadratic

Use the `fit` function to fit a polynomial to data. You specify a quadratic, or second-degree polynomial, using `'poly2'`. The first output from `fit` is the polynomial, and the second output, `gof`, contains the goodness of fit statistics you will examine in a later step.

```
[population2,gof] = fit(cdate,pop,'poly2');
```

To plot the fit, use the `plot` function. Add a legend in the top left corner.

```
plot(population2,cdate,pop);  
legend('Location','NorthWest');
```



### Create and Plot a Selection of Polynomials

To fit polynomials of different degrees, change the fit type, e.g., for a cubic or third-degree polynomial use 'poly3'. The scale of the input, `cdate`, is quite large, so you can obtain better results by centering and scaling the data. To do this, use the 'Normalize' option.

```
population3 = fit(cdate,pop,'poly3','Normalize','on');
population4 = fit(cdate,pop,'poly4','Normalize','on');
population5 = fit(cdate,pop,'poly5','Normalize','on');
population6 = fit(cdate,pop,'poly6','Normalize','on');
```


A simple model for population growth tells us that an exponential equation should fit this census data well. To fit a single term exponential model, use 'exp1' as the fittype.

```
populationExp = fit(cdate,pop,'exp1');
```

Plot all the fits at once, and add a meaningful legend in the top left corner of the plot.

```
hold on
plot(population3,'b');
plot(population4,'g');
plot(population5,'m');
plot(population6,'b--');
plot(populationExp,'r--');
hold off
legend('cdate v pop','poly2','poly3','poly4','poly5','poly6','exp1', ...
      'Location','NorthWest');
```






### Plot the Residuals to Evaluate the Fit

To plot residuals, specify 'residuals' as the plot type in the plot function.


```
plot(population2,cdate,pop,'residuals');
```



The fits and residuals for the polynomial equations are all similar, making it difficult to choose the best one.

If the residuals display a systematic pattern, it is a clear sign that the model fits the data poorly.

```
plot(populationExp, cdate, pop, 'residuals');
```




The fit and residuals for the single-term exponential equation indicate it is a poor fit overall. Therefore, it is a poor choice and you can remove the exponential fit from the candidates for best fit.

### Examine Fits Beyond the Data Range

Examine the behavior of the fits up to the year 2050. The goal of fitting the census data is to extrapolate the best fit to predict future population values.

By default, the fit is plotted over the range of the data. To plot a fit over a different range, set the x-limits of the axes before plotting the fit. For example, to see values extrapolated from the fit, set the upper x-limit to 2050.

```
plot(cdate,pop,'o');
xlim([1900, 2050]);
hold on
plot(population6);
hold off
```




Examine the plot. The behavior of the sixth-degree polynomial fit beyond the data range makes it a poor choice for extrapolation and you can reject this fit.

### Plot Prediction Intervals


To plot prediction intervals, use 'predobs' or 'predfun' as the plot type. For example, to see the prediction bounds for the fifth-degree polynomial for a new observation up to year 2050:

```
plot(cdate,pop,'o');  
xlim([1900,2050])  
hold on  
plot(population5,'predobs');  
hold off
```



Plot prediction intervals for the cubic polynomial up to year 2050:

```
plot(cdate,pop,'o');  
xlim([1900,2050])  
hold on  
plot(population3,'predobs')  
hold off
```



### Examine Goodness-of-Fit Statistics

The struct `gof` shows the goodness-of-fit statistics for the 'poly2' fit. When you created the 'poly2' fit with the `fit` function in an earlier step, you specified the `gof` output argument.

`gof`

```
gof = struct with fields:
    sse: 159.0293
    rsquare: 0.9987
    dfe: 18
    adjrsquare: 0.9986
    rmse: 2.9724
```

Examine the sum of squares due to error (SSE) and the adjusted R-square statistics to help determine the best fit. The SSE statistic is the least-squares error of the fit, with a value closer to zero indicating a better fit. The adjusted R-square statistic is generally the best indicator of the fit quality when you add additional coefficients to your model.

The large SSE for 'exp1' indicates it is a poor fit, which you already determined by examining the fit and residuals. The lowest SSE value is associated with 'poly6'. However, the behavior of this fit beyond the data range makes it a poor choice for extrapolation, so you already rejected this fit by examining the plots with new axis limits.

The next best SSE value is associated with the fifth-degree polynomial fit, 'poly5', suggesting it might be the best fit. However, the SSE and adjusted R-square values for the remaining polynomial fits are all very close to each other. Which one should you choose?

### Compare the Coefficients and Confidence Bounds to Determine the Best Fit

Resolve the best fit issue by examining the coefficients and confidence bounds for the remaining fits: the fifth-degree polynomial and the quadratic.

Examine `population2` and `population5` by displaying the models, the fitted coefficients, and the confidence bounds for the fitted coefficients:

`population2`

```
population2 =
Linear model Poly2:
population2(x) = p1*x^2 + p2*x + p3
Coefficients (with 95% confidence bounds):
p1 =    0.006541 (0.006124, 0.006958)
p2 =   -23.51 (-25.09, -21.93)
p3 =   2.113e+04 (1.964e+04, 2.262e+04)
```

`population5`

```
population5 =
Linear model Poly5:
population5(x) = p1*x^5 + p2*x^4 + p3*x^3 + p4*x^2 + p5*x + p6
where x is normalized by mean 1890 and std 62.05
Coefficients (with 95% confidence bounds):
p1 =    0.5877 (-2.305, 3.48)
p2 =    0.7047 (-1.684, 3.094)
p3 =   -0.9193 (-10.19, 8.356)
p4 =    23.47 (17.42, 29.52)
p5 =    74.97 (68.37, 81.57)
p6 =    62.23 (59.51, 64.95)
```

You can also get the confidence intervals by using `confint` :

```
ci = confint(population5)
```

```
ci = 2x6
```

```
-2.3046  -1.6841  -10.1943  17.4213  68.3655  59.5102
 3.4801   3.0936   8.3558  29.5199  81.5696  64.9469
```

The confidence bounds on the coefficients determine their accuracy. Check the fit equations (e.g.  $f(x)=p_1x+p_2x\dots$ ) to see the model terms for each coefficient. Note that `p2` refers to the  $p_2x$  term in 'poly2' and the  $p_2x^4$  term in 'poly5'. Do not compare normalized coefficients directly with non-normalized coefficients.

The bounds cross zero on the `p1`, `p2`, and `p3` coefficients for the fifth-degree polynomial. This means you cannot be sure that these coefficients differ from zero. If the higher order model terms may have coefficients of zero, they are not helping with the fit, which suggests that this model over fits the census data.

The fitted coefficients associated with the constant, linear, and quadratic terms are nearly identical for each normalized polynomial equation. However, as the polynomial degree increases, the coefficient bounds associated with the higher degree terms cross zero, which suggests over fitting.

However, the small confidence bounds do not cross zero on  $p_1$ ,  $p_2$ , and  $p_3$  for the quadratic fit, indicating that the fitted coefficients are known fairly accurately.

Therefore, after examining both the graphical and numerical fit results, you should select the quadratic `population2` as the best fit to extrapolate the census data.

### Evaluate the Best Fit at New Query Points

Now you have selected the best fit, `population2`, for extrapolating this census data, evaluate the fit for some new query points:

```
cdateFuture = (2000:10:2020).';
popFuture = population2(cdateFuture)
```

```
popFuture = 3×1
```

```
274.6221
301.8240
330.3341
```

To compute 95% confidence bounds on the prediction for the population in the future, use the `predint` method:

```
ci = predint(population2,cdateFuture,0.95,'observation')
```


```
ci = 3×2
```

```
266.9185 282.3257
293.5673 310.0807
321.3979 339.2702
```

Plot the predicted future population, with confidence intervals, against the fit and data.

```
plot(cdate,pop,'o');
xlim([1900,2040])
hold on
plot(population2)
h = errorbar(cdateFuture,popFuture,popFuture-ci(:,1),ci(:,2)-popFuture,'.');
hold off
legend('cdate v pop','poly2','prediction', ...
       'Location','NorthWest')
```





For more information, see "Polynomial Models" on page 4-15.

## Surface Fitting with Custom Equations to Biopharmaceutical Data

This example shows how to use Curve Fitting Toolbox™ to fit response surfaces to some anesthesia data to analyze drug interaction effects. Response surface models provide a good method for understanding the pharmacodynamic interaction behavior of drug combinations.

This data is based on the results in this paper: Kern SE, Xie G, White JL, Egan TD. Opioid-hypnotic synergy: A response surface analysis of propofol-remifentanyl pharmacodynamic interaction in volunteers. *Anesthesiology* 2004; 100: 1373-81.

Anesthesia is typically at least a two-drug process, consisting of an opioid and a sedative hypnotic. This example uses Propofol and Remifentanyl as drug class prototypes. Their interaction is measured by four different measures of the analgesic and sedative response to the drug combination. Algometry, Tetany, Sedation, and Laryngoscopy comprise the four measures of surrogate drug effects at various concentration combinations of Propofol and Remifentanyl.

The following code, using Curve Fitting Toolbox methods, reproduces the interactive surface building with the Curve Fitting Tool described in “Surface Fitting to Biopharmaceutical Data” on page 5-35.

### Load Data

Load the data from file.

```
data = importdata( 'OpioidHypnoticSynergy.txt' );
Propofol      = data.data(:,1);
Remifentanyl  = data.data(:,2);
Algometry     = data.data(:,3);
Tetany        = data.data(:,4);
Sedation      = data.data(:,5);
Laryngoscopy = data.data(:,6);
```

### Create the Model Fit Type

You can use the `fittype` function to define the model from the paper, where CA and CB are the drug concentrations, and IC50A, IC50B, alpha, and n are the coefficients to be estimated. Create the model fit type.

```
ft = fittype( 'Emax*( CA/IC50A + CB/IC50B + alpha*( CA/IC50A ) * ( CB/IC50B ) )^n /(( CA/IC50A +
'indepent', {'CA', 'CB'}, 'dependent', 'z', 'problem', 'Emax' )

ft =
General model:
ft(IC50A,IC50B,alpha,n,Emax,CA,CB) = Emax*( CA/IC50A + CB/IC50B + alpha*(
CA/IC50A ) * ( CB/IC50B ) )^n /(( CA/IC50A + CB/IC50B
+ alpha*( CA/IC50A ) * ( CB/IC50B ) )^n + 1 )
```

Assume  $E_{max} = 1$  because the effect output is normalized.

```
Emax = 1;
```

### Set Fit Options

Set fit options for robust fitting, bounds, and start points.

```

opts = fitoptions( ft );
opts.Lower = [0, 0, -5, -0];
opts.Robust = 'LAR';
opts.StartPoint = [0.0089, 0.706, 1.0, 0.746];

```

### Fit and Plot a Surface for Algometry

```

[f, gof] = fit( [Propofol, Remifentanil], Algometry, ft,...
  opts, 'problem', Emax )

```

Success, but fitting stopped because change in residuals less than tolerance (TolFun).

```

General model:
f(CA,CB) = Emax*( CA/IC50A + CB/IC50B + alpha*( CA/IC50A ) * ( CB/IC50B
  ) )^n /(( CA/IC50A + CB/IC50B + alpha*( CA/IC50A )
  * ( CB/IC50B ) )^n + 1 )
Coefficients (with 95% confidence bounds):
IC50A =      4.149 (4.123, 4.174)
IC50B =      9.045 (8.971, 9.118)
alpha =      8.502 (8.316, 8.688)
n =          8.288 (8.131, 8.446)
Problem parameters:
Emax =          1

```

```


gof = struct with fields:
  sse: 0.0842
  rsquare: 0.9991
  dfe: 393
  adjrsquare: 0.9991
  rmse: 0.0146

```

```

plot( f, [Propofol, Remifentanil], Algometry );

```



### Fit a Surface to Tetany

Reuse the same `fittype` to create a response surface for tetany.

```
[f, gof] = fit( [Propofol, Remifentani], Tetany, ft, opts, 'problem', Emax )
```

General model:

$$f(CA, CB) = Emax * ( CA/IC50A + CB/IC50B + alpha * ( CA/IC50A ) * ( CB/IC50B ) )^n / ( ( CA/IC50A + CB/IC50B + alpha * ( CA/IC50A ) * ( CB/IC50B ) )^n + 1 )$$

Coefficients (with 95% confidence bounds):

```
IC50A = 4.544 (4.522, 4.567)
IC50B = 21.22 (21.04, 21.4)
alpha = 14.94 (14.67, 15.21)
n = 6.132 (6.055, 6.209)
```


Problem parameters:

```
Emax = 1
```

`gof` = struct with fields:

```
sse: 0.0537
rsquare: 0.9993
dfe: 393
adjrsquare: 0.9993
rmse: 0.0117
```

```
plot( f, [Propofol, Remifentani], Tetany );
```



### Fit a Surface to Sedation

```
[f, gof] = fit( [Propofol, Remifentani], Sedation, ft, opts, 'problem', Emax )
```

General model:

$$f(CA, CB) = E_{\max} * \left( \frac{CA}{IC50A} + \frac{CB}{IC50B} + \alpha * \left( \frac{CA}{IC50A} \right) * \left( \frac{CB}{IC50B} \right) \right)^n / \left( \left( \frac{CA}{IC50A} + \frac{CB}{IC50B} + \alpha * \left( \frac{CA}{IC50A} \right) * \left( \frac{CB}{IC50B} \right) \right)^n + 1 \right)$$

Coefficients (with 95% confidence bounds):

IC50A = 1.843 (1.838, 1.847)

IC50B = 13.7 (13.67, 13.74)

alpha = 1.986 (1.957, 2.015)

n = 44.27 (42.56, 45.98)

Problem parameters:

Emax = 1

*gof = struct with fields:*

sse: 0.0574


rsquare: 0.9994

dfe: 393

adjrsquare: 0.9994

rmse: 0.0121

```
plot( f, [Propofol, Remifentani], Sedation );
```



### Fit a Surface to Laryngoscopy

```
[f, gof] = fit( [Propofol, Remifentani], Laryngoscopy, ft, opts, 'problem', Emax )
```

General model:

$$f(CA, CB) = E_{\max} * ( CA/IC50A + CB/IC50B + \alpha * ( CA/IC50A ) * ( CB/IC50B ) )^n / ( ( CA/IC50A + CB/IC50B + \alpha * ( CA/IC50A ) * ( CB/IC50B ) )^n + 1 )$$

Coefficients (with 95% confidence bounds):

```
IC50A =      5.192 (5.177, 5.207)
IC50B =     37.77 (37.58, 37.97)
alpha =     19.67 (19.48, 19.86)
n =        37 (35.12, 38.87)
```


Problem parameters:

```
Emax =      1
```

*gof = struct with fields:*

```
sse: 0.1555
rsquare: 0.9982
dfe: 393
adjrsquare: 0.9982
rmse: 0.0199
```

```
plot( f, [Propofol, Remifentani], Laryngoscopy );
```



## How to Construct Splines

This example shows how to construct splines in various ways using the spline functions in Curve Fitting Toolbox™.


### Interpolation

You can construct a *cubic spline interpolant* that matches the cosine function at the following sites  $x$ , using the `csapi` command.

```
x = 2*pi*[0 1 .1:.2:.9];  
y = cos(x);  
cs = csapi(x,y);
```

You can then view the interpolating spline by using `fnplt`.

```
fnplt(cs,2);  
axis([-1 7 -1.2 1.2])  
hold on  
plot(x,y,'o')  
hold off
```



### Checking the Interpolant


The cosine function is  $2\pi$ -periodic. How well does our cubic spline interpolant do in that regard? One way to check is to compute the difference in the first derivative at the two endpoints.



```
diff( fnval( fnder(cs), [0 2*pi] ) )
ans = -0.1375
```

To enforce periodicity, use `csape` instead of `csapi`.

```
csp = csape( x, y, 'periodic' );
hold on
fnplt(csp, 'g')
hold off
```



Now the check gives

```
diff( fnval( fnder(csp), [0 2*pi] ) )
ans = -2.2806e-17
```


Even the second derivative now matches at the endpoints.

```
diff( fnval( fnder(csp, 2), [0 2*pi] ) )
ans = -2.2204e-16
```

The *piecewise linear interpolant* to the same data is available via `spapi`. Here we add it to the previous plot, in red.

```
pl = spapi(2, x, y);
hold on
```


```
fnplt(pl, 'r', 2)
hold off
```



### Smoothing


If the data are noisy, you usually want to approximate rather than interpolate. For example, with these data

```
x = linspace(0,2*pi,51);
noisy_y = cos(x) + .2*(rand(size(x))-0.5);
plot(x,noisy_y,'x')
axis([-1 7 -1.2 1.2])
```



interpolation would give the wiggly interpolant shown below in blue.

```
hold on
fnplt( csapi(x, noisy_y) )
hold off
```




In contrast, smoothing with a proper tolerance

```
tol = (.05)^2*(2*pi)
```

```
tol = 0.0157
```

gives a smoothed approximation, shown below in red.

```
hold on  
fnplt( spaps(x, noisy_y, tol), 'r', 2 )  
hold off
```




The approximation is much worse near the ends of the interval, and is far from periodic. To enforce periodicity, approximate to periodically extended data, then restrict the approximation to the original interval.

```
noisy_y([1 end]) = mean( noisy_y([1 end]) );
lx = length(x);
lx2 = round(lx/2);
range = [lx2:lx 2:lx 2:lx2];
sps = spaps([x(lx2:lx)-2*pi x(2:lx) x(2:lx2)+2*pi],noisy_y(range),2*tol);
```

This gives the more nearly periodic approximation, shown in black.

```
hold on
fnplt(sps, [0 2*pi], 'k', 2)
hold off
```




### Least-Squares Approximation

Alternatively, you could use least-squares approximation to the noisy data by a spline with few degrees of freedom.

For example, you might try a cubic spline with just four pieces.


```
spl2 = spap2(4, 4, x, noisy_y);  
fnplt(spl2, 'b', 2);  
axis([-1 7 -1.2 1.2])  
hold on  
plot(x, noisy_y, 'x')  
hold off
```



### Knot Selection

When using `spapi` or `spap2`, you usually have to specify a particular spline space. This is done by specifying a *knot sequence* and an *order*, and this may be a bit of a problem. However, when doing spline interpolation to  $x, y$  data using a spline of order  $k$ , you can use the function `optknt` to supply a good knot sequence, as in the following example.


```
k = 5; % order 5, i.e., we are working with quartic splines
x = 2*pi*sort([0 1 rand(1,10)]);
y = cos(x);
sp = spapi( optknt(x,k), x, y );
fnplt(sp,2,'g');
hold on
plot(x,y,'o')
hold off
axis([-1 7 -1.1 1.1])
```



When doing least-squares approximation, you can use the current approximation to determine a possibly better knot selection with the aid of `newknt`. For example, the following approximation to the exponential function isn't all that good, as can be seen from its error, plotted in red.


```
x = linspace(0,10,101);  
y = exp(x);  
sp0 = spap2( augknt(0:2:10,4), 4, x, y );  
plot(x,y-fnval(sp0,x),'r','LineWidth',2)
```





However, you can use that initial approximation to create another one with the *same* number of knots, but which are better distributed. Its error is plotted in black.

```
sp1 = spap2( newknt(sp0), 4, x, y );  
hold on  
plot(x,y-fnval(sp1,x), 'k', 'LineWidth',2)  
hold off
```




### Gridded Data

All the spline interpolation and approximation commands in the Curve Fitting Toolbox can also handle gridded data, in any number of variables.


For example, here is a bicubic spline interpolant to the Mexican Hat function.

```
x = .0001+(-4:.2:4);
y = -3:.2:3;
[yy,xx] = meshgrid(y,x);
r = pi*sqrt(xx.^2+yy.^2);
z = sin(r)./r;
bcs = csapi({x,y}, z);
fnplt(bcs)
axis([-5 5 -5 5 -.5 1])
```



Here is the *least-squares* approximation to noisy values of that same function on the same grid.

```
knotsx = augknt(linspace(x(1), x(end), 21), 4);  
knotsy = augknt(linspace(y(1), y(end), 15), 4);  
bsp2 = spap2({knotsx,knotsy},[4 4], {x,y},z+.02*(rand(size(z))-.5));  
fnplt(bsp2)  
axis([-5 5 -5 5 -.5 1])
```




### Curves

Gridded data can be handled easily because Curve Fitting Toolbox can deal with *vector-valued* splines. This also makes it easy to work with parametric curves.


Here, for example, is an approximation to infinity, obtained by putting a cubic spline curve through the points marked in the following figure.

```
t = 0:8;
xy = [0 0;1 1; 1.7 0;1 -1;0 0; -1 1; -1.7 0; -1 -1; 0 0].';
infty = csape(t, xy, 'periodic');
fnplt(infty, 2)
axis([-2 2 -1.1 1.1])
hold on
plot(xy(1,:),xy(2,:), 'o')
hold off
```



Here is the same curve, but with motion in a third dimension.

```
roller = csape( t , [ xy ;0 1/2 1 1/2 0 1/2 1 1/2 0], 'periodic');  
fnplt( roller , 2, [0 4], 'b' )  
hold on  
fnplt( roller, 2, [4 8], 'r')  
plot3(0,0,0, 'o')  
hold off
```




The two halves of the curve are plotted in different colors and the origin is marked, as an aid to visualizing this two-winged space curve.

### Surfaces


Bivariate tensor-product splines with values in  $\mathbb{R}^3$  give surfaces. For example, here is a good approximation to a torus.

```
x = 0:4;
y = -2:2;
R = 4;
r = 2;
v = zeros(3,5,5);
v(3, :, :) = [0 (R-r)/2 0 (r-R)/2 0].'*[1 1 1 1 1];
v(2, :, :) = [R (r+R)/2 r (r+R)/2 R].'*[0 1 0 -1 0];
v(1, :, :) = [R (r+R)/2 r (r+R)/2 R].'*[1 0 -1 0 1];
dough0 = csape({x,y},v,'periodic');
fnplt(dough0)
axis equal, axis off
```



Here is a crown of normals to that surface.


```
nx = 43;
xy = [ones(1,nx); linspace(2,-2,nx)];
points = fnval(dough0,xy)';
ders = fnval(fndir(dough0,eye(2)),xy);
normals = cross(ders(4:6,:),ders(1:3,:));
normals = (normals./repmat(sqrt(sum(normals.*normals)),3,1))';
pn = [points;points+normals];
hold on
for j=1:nx
    plot3(pn([j,j+nx],1),pn([j,j+nx],2),pn([j,j+nx],3))
end
hold off
```



Finally, here is its projection onto the (x,y)-plane.

```
fnplt(fncmb(dough0, [1 0 0; 0 1 0]))  
axis([-5.25 5.25 -4.14 4.14]), axis off
```






### Scattered Data

It is also possible to interpolate to values given at ungridded data sites in the plane. Consider, for example, the task of mapping the unit square smoothly to the unit disk. We construct the data values, marked as circles, and the corresponding data sites, marked as x's. Each data site is connected to its associated value by an arrow.

```
n = 64;
t = linspace(0,2*pi,n+1); t(end) = [];
values = [cos(t); sin(t)];
plot(values(1,:),values(2:,:), 'or')
axis equal, axis off

sites = values./repmat(max(abs(values)),2,1);
hold on
plot(sites(1,:),sites(2:,:), 'xk')
quiver(sites(1,:),sites(2:,:), ...
       values(1:)-sites(1:), values(2:)-sites(2:))
hold off
```




Then use `tpaps` to construct a bivariate interpolating vector-valued thin-plate spline.

```
st = tpaps(sites, values, 1);
```

The spline does indeed map the unit square smoothly (approximately) to the unit disk, as its plot via `fnplt` indicates. The plot shows the image of a uniformly-spaced square grid under the spline map in `st`.

```
hold on  
fnplt(st)  
hold off
```



## Construct and Work with the B-form

This example shows how to construct and work with the B-form of a spline in Curve Fitting Toolbox™.

### Introduction

In Curve Fitting Toolbox, a piecewise polynomial, or pp, function in B-form is often called a *spline*.

The *B-form* of a (univariate) pp is specified by its (nondecreasing) *knot* sequence  $\mathbf{t}$  and by its B-spline *coefficient* sequence  $\mathbf{a}$ .

Given the knot sequence and coefficient sequence of a pp, the command `spmak` returns the corresponding B-form, for use in commands such as `fnval` (evaluate a function), `fnplt` (plot a function), `fnder` (differentiate a function), and other related commands.


The resulting spline is of *order*  $k := \text{length}(\mathbf{t}) - \text{size}(\mathbf{a}, 2)$ . This means that all its polynomial pieces have degree  $< k$ .

To say that a spline  $s$  has knots  $\mathbf{t}$  and coefficients  $\mathbf{a}$  means that

$$s(x) := \sum_{j=1}^n B_{\{j,k\}}(x) * a(:,j),$$

where  $B_{(j,k)} = B(\cdot | t_j, \dots, t_{j+k})$  is the  $j$ -th *B-spline* of *order*  $k$  for the given *knot sequence*  $\mathbf{t}$ , i.e., the B-spline with knots  $t_j, \dots, t_{j+k}$ . For example,

```
t = [.1 .4 .5 .8 .9];
a = 1;
fnplt(spmak(t,a),2.5);
tmp = repmat(t,3,1);
ty = repmat(.1*[1;-1;NaN],1,5);
hold on
plot(tmp(:),ty(:))
text(.65,.5,'B( \cdot | .1, .4, .5, .8, .9)', 'FontSize',12)
text(.05,1., 's(x) = \Sigma_j B(x | t_j, \dots, t_{j+k}) a(:,j)', ...
     'FontSize',16, 'Color', 'r')
axis([0 1 -.2 1.2])
title('A B-spline of Order 4')
hold off
```



### The Local Partition of Unity

The value of the spline

$$s(x) = \sum_j B_{\{j,k\}}(x) a(:,j)$$

$j$

at any  $x$  in the knot interval  $[t_i \dots t_{i+1}]$  is a *convex* combination of the  $k$  coefficients  $a(:,i-k+1), \dots, a(:,i)$  since, on that interval, only the  $k$  B-splines  $B_{\{i-k+1,k\}}, \dots, B_{\{i,k\}}$  are nonzero, and they are nonnegative there and sum to 1, as is illustrated in the next figure.


This is often summarized by saying that the B-splines provide a *local (nonnegative) partition of unity*.

```
k = 3;
n = 3;
t = [1 1.7 3.2 4.2 4.8 6];
tt = (10:60)/10;
vals = fnval(spmak(t,eye(k)),tt);
plot(tt.',vals. ');
hold on
ind = find(tt>=t(3)&tt<=t(4));
plot(tt(ind).',vals(:,ind).','LineWidth',3)
plot(t([3 4]),[1 1], 'k', 'LineWidth',3)
ty = repmat(.1*[1;-1;NaN],1,6);
plot([0 0 -.2 0 0 -.2 0 0],[-.5 0 0 0 1 1 1 1.5], 'k')
```

```

text(-.5,0,'0','FontSize',12)
text(-.5,1,'1','FontSize',12)
tmp = repmat(t,3,1);
plot(tmp(:),ty(:),'k');
yd = -.25;
text(t(1),yd,'t_{i-2}','FontSize',12);
text(t(3),yd,'t_i','FontSize',12);
text(t(4),yd,'t_{i+1}','FontSize',12);
text(1.8,.5,'B_{i-2,3}','FontSize',12);
text(5,.45,'B_{i,3}','FontSize',12);
axis([-5 7 -5 1.5])
title('B-splines Form a Local Partition of Unity')
axis off
hold off

```



### The Convex Hull Property and the Control Polygon

When the coefficients are points in the plane and, correspondingly, the spline

$$s(x) = \sum B_{j,k}(x) a(:,j)$$


$j$

traces out a curve, this means that the curve piece

$$\{ s(x) : t_i \leq x \leq t_{i+1} \}$$

highlighted in the figure below by a larger LineWidth, lies in the convex hull, shown in yellow in the figure below, of the  $k$  points  $a(:,i-k+1), \dots, a(:,i)$ .

```
t = 1:9;
c = [2 1.4;1 .5; 2 -.4; 5 1.4; 6 .5; 5 -.4].';
sp = spmak(t,c);
fill(c(1,3:5),c(2,3:5),'y','EdgeColor','y');
hold on
fnplt(sp,t([3 7]),1.5)
fnplt(sp,t([5 6]),3)
plot(c(1,:),c(2,:),'ok')
text(2,-.55,'a(:,i-2)','FontSize',12)
text(5,1.6,'a(:,i-1)','FontSize',12)
text(6.1,.5,'a(:,i)','FontSize',12)
title('The Convex-Hull Property')
axis([.5 7 -.8 1.8])
axis off
hold off
```



For a quadratic spline (i.e.,  $k = 3$ ), as shown here, it even means that the curve is tangent to the *control polygon* (shown as dotted lines). This is the broken line that connects the coefficients, which are called *control points* in this connection (shown here as open circles).

### The Control Polygon for Scalar-Valued Splines

We can think of the graph of the *scalar-valued* spline

$$s = \sum B_{\{j,k\}} * a(j)$$

j

as the curve  $x \mapsto (x, s(x))$ . Since

$$x = \sum_j B_{j,k}(x) t^*_j$$

j

for  $x$  in the interval  $[t_k \dots t_{n+1}]$ , where

$$t^*_i := (t_{i+1} + \dots + t_{i+k-1}) / (k-1) \text{ for } i = 1:n$$

are the knot averages obtainable using the `aveknt` command, the *control polygon* for a scalar-valued spline is the broken line with vertices  $(t^*_i, a(i))$ ,  $i=1:n$ .


The example below shows a *cubic* spline ( $k = 4$ ), with 4-fold end knots, hence

$$t^*_1 = t_1 \text{ and } t^*_n = t_{n+k}.$$

```
t = [0 .2 .35 .47 .61 .84 1]*(2*pi);
s = t([1 3 4 5 7]);
knots = augknt(s,4);
sp = spapi(knots,t,sin(t)+1.8);
fnplt(sp,2);
hold on
c = fnbrk(sp,'c');
ts = aveknt(knots,4);
plot(ts,c,':ok');
tt = [s;s;NaN(size(s))];
ty = repmat(.25*[-1;1;NaN], size(s));
plot(tt(:),ty(:),'r')
plot(ts(1,:),zeros(size(ts)),'*')
text(knots(5),-.5,'t_5','FontSize',12)
text(ts(2),-.45,'t^*_2','FontSize',12)
text(knots(1)-.28,-.5,'t_1=t_4','FontSize',12)
text(knots(end)-.65,-.45,'t_{n+1}=t^*_n=t_{n+4}','FontSize',12)
title('A Cubic Spline and its Control Polygon')
axis([-1.72 7 -.5 3.5])
axis off
hold off
```



### A Cubic Spline and its Control Polygon




```
savesp = sp;
```

The essential parts of the B-form are the knot sequence  $t$  and the B-spline coefficient sequence  $a$ . Other parts are the *number*  $n$  of the B-splines or coefficients involved, the *order*  $k$  of its polynomial pieces, and the *dimension*  $d$  of its coefficients  $a$ . In particular, `size(a)` equals  $[d, n]$ .

There is one more part, namely the *basic interval*,  $[t(1) \dots t(\text{end})]$ . It is used as the default interval when plotting the function. Also, a spline is taken to be continuous from the right everywhere except at the right endpoint of the basic interval, where it is taken to be continuous from the left. This is illustrated in the example below, for a spline created using `spmak`.

```
b = 0:3;
sp = spmak(augknt(b,3), [-1,0,1,0,-1]);
x = linspace(-1,4,51);
plot(x, fnval(sp,x), 'x')
hold on
axis([-2 5, -1.5, 1])
tx = repmat(b,3,1);
ty = repmat(.5*[1;-1;NaN],1,length(b));
plot(tx(:,),ty(:,), '-r')
legend({'Spline Values' 'Knots'})
hold off
title({'A Spline in B-form is Right(Left)-Continuous ';\dots
      'at Left(Right) Endpoint of its Basic Interval'})
```



`fnbrk` can be used to obtain any or all parts of a B-form. For example, here is the output provided by `fnbrk` for the B-form of the spline shown above.

```
fnbrk(sp)
```

```
The input describes a B- form
```

```
knots(1:n+k)
  0   0   0   1   2   3   3   3
```

```
coefficients(d,n)
 -1   0   1   0  -1
```

```
number n of coefficients
  5
```

```
order k
  3
```

```
dimension d of target
  1
```

However, there is usually *no need* to know any of these parts. Rather, you use commands like `spapi` or `spaps` to construct the B-form of a spline from some data, then use commands like `fnval`, `fnplt`, `fnder`, etc., to make use of the spline constructed, without any need to look at its various parts.

The following sections give more detailed information about the B-splines, in particular about the important role played by knot *multiplicity*.


## Knot Multiplicity

Here, for  $k = 2, 3,$  and  $4,$  are B-splines of order  $k,$  and below them their first and second (piecewise) derivatives, to illustrate some facts about B-splines. Try out the `bpspligui` tool if you want to experiment with examples of your own.

```

cl = ['g', 'r', 'b', 'k', 'k'];
v = 5.4; d1 = 2.5; d2 = 0; s1 = 1; s2 = .5;
t1 = [0 .8 2];
t2 = [3 4.4 5 6];
t3 = [7 7.9 9.2 10 11];
tt = [t1 t2 t3];
ext = tt([1 end])+[-.5 .5];
plot(ext([1 2]),[v v],cl(5))
hold on
plot(ext([1 2]),[d1 d1],cl(5))
plot(ext([1 2]),[d2 d2],cl(5))
ts = [tt;tt;NaN(size(tt))];
ty = repmat(.2*[-1;0;NaN],size(tt));
plot(ts(:),ty(:)+v,cl(5))
plot(ts(:),ty(:)+d1,cl(5))
plot(ts(:),ty(:)+d2,cl(5))
b1 = spmak(t1,1);
p1 = [t1;0 1 0];
db1 = fnder(b1);
p11 = fnplt(db1,'j');
p12 = fnplt(fnder(db1));
lw = 2;
plot(p1(1,:),p1(2,)+v,cl(2),'LineWidth',lw)
plot(p11(1,:),s1*p11(2,)+d1,cl(2),'LineWidth',lw)
plot(p12(1,:),s2*p12(2,)+d2,cl(2),'LineWidth',lw)
b1 = spmak(t2,1);
p1 = fnplt(b1);
db1 = fnder(b1);
p11 = [t2;fnval(db1,t2)];
p12 = fnplt(fnder(db1),'j');
plot(p1(1,:),p1(2,)+v,cl(3),'LineWidth',lw)
plot(p11(1,:),s1*p11(2,)+d1,cl(3),'LineWidth',lw)
plot(p12(1,:),s2*p12(2,)+d2,cl(3),'LineWidth',lw)
b1 = spmak(t3,1);
p1 = fnplt(b1);
db1 = fnder(b1);
p11 = fnplt(db1);
p12=[t3;fnval(fnder(db1),t3)];
plot(p1(1,:),p1(2,)+v,cl(4),'LineWidth',lw)
plot(p11(1,:),s1*p11(2,)+d1,cl(4),'LineWidth',lw)
plot(p12(1,:),s2*p12(2,)+d2,cl(4),'LineWidth',lw)
tey = v+1.5;
text(t1(2)-.5,tey,'linear','FontSize',12,'Color',cl(2))
text(t2(2)-.8,tey,'quadratic','FontSize',12,'Color',cl(3))
text(t3(3)-.5,tey,'cubic','FontSize',12,'Color',cl(4))
text(-2,v,'B','FontSize',12)
text(-2,d1,'DB','FontSize',12)
text(-2,d2,'D^2B')
axis([-1 12 -2 7.5])
title({'B-splines with Simple Knots and Their Derivatives'})
axis off
hold off

```



1. The B-spline  $B_{\{j,k\}} = B(\cdot | t_j, \dots, t_{\{j+k\}})$  is a pp of order  $k$  with breaks at  $t_j, \dots, t_{\{j+k\}}$  (and nowhere else). Actually, its nontrivial polynomial pieces are all of exact degree  $k-1$ .

For example, the rightmost B-spline above involves 5 knots, hence is of order 4, i.e., a *cubic* B-spline. Correspondingly, its second derivative is piecewise linear.

2.  $B_{\{j,k\}}$  is positive on the interval  $(t_j \dots t_{\{j+k\}})$  and is zero off that interval. It also vanishes at the endpoints of that interval, unless the endpoint is a knot of multiplicity  $k$  (see the rightmost example in the next figure).

3. Knot *multiplicity* determines the smoothness with which the two adjacent polynomials join across that knot. In shorthand, the rule is:

$$\text{knot multiplicity} + \text{number of smoothness conditions} = \text{order}$$


To illustrate this last point, the figure below shows four cubic B-splines and, below them, their first two derivatives. Each spline has a certain knot of multiplicity 1, 2, 3, 4, as indicated by the lengths of the knot lines.

```
d2 = -1;
t1 = [7 7.9 9.2 10 11]-7;
t2 = [7 7.9 7.9 9 10]-2;
t3 = [7 7.9 7.9 7.9 9]+2;
t4 = [7 7.9 7.9 7.9 7.9]+5;
[m,tt] = knt2mlt([t1 t2 t3 t4]);
```

```

ext = tt([1 end])+[-.5 .5];
plot(ext,[v v],cl(5))
hold on
plot(ext,[d1 d1],cl(5))
plot(ext,[d2 d2],cl(5))
ts = [tt;tt;NaN(size(tt))];
ty = .2*[-m-1;zeros(size(m));m];
plot(ts(:),ty(:)+v,cl(5))
plot(ts(:),ty(:)+d1,cl(5))
plot(ts(:),ty(:)+d2,cl(5))
b1 = spmak(t1,1);
p1 = fnplt(b1);
db1 = fnder(b1);
p11 = fnplt(db1);
p12 = [t1;fnval(fnder(db1),t1)];
plot(p1(1,:),p1(2,)+v,cl(1),'LineWidth',lw)
plot(p11(1,:),s1*p11(2,)+d1,cl(1),'LineWidth',lw)
plot(p12(1,:),s2*p12(2,)+d2,cl(1),'LineWidth',lw)
text(-2,v,'B'), text(-2,d1,'DB'), text(-2,d2,'D^2B')
b1 = spmak(t2,1);
p1 = fnplt(b1);
db1 = fnder(b1);
p11 = fnplt(db1);
p12 = fnplt(fnder(db1),'j');
plot(p1(1,:),p1(2,)+v,cl(2),'LineWidth',lw)
plot(p11(1,:),s1*p11(2,)+d1,cl(2),'LineWidth',lw)
plot(p12(1,:),s2*s2*p12(2,)+d2,cl(2),'LineWidth',lw)
b1 = spmak(t3,1);
p1 = fnplt(b1);
db1 = fnder(b1);
p11 = fnplt(db1,'j');
p12 = fnplt(fnder(db1),'j');
plot(p1(1,:),p1(2,)+v,cl(3),'LineWidth',lw)
plot(p11(1,:),s1*s2*p11(2,)+d1,cl(3),'LineWidth',lw)
plot(p12(1,:),s2*s2*p12(2,)+d2,cl(3),'LineWidth',lw)
b1 = spmak(t4,1);
p1 = fnplt(b1);
db1 = fnder(b1);
p11 = fnplt(db1);
p12 = fnplt(fnder(db1));
plot(p1(1,:),p1(2,)+v,cl(4),'LineWidth',lw)
plot(p11(1,:),s2*p11(2,)+d1,cl(4),'LineWidth',lw)
plot(p12(1,:),s2*s2*p12(2,)+d2,cl(4),'LineWidth',lw)
text(t2(2)-.5,tey,'2-fold','FontSize',12,'Color',cl(2))
text(t3(2)-.8,tey,'3-fold','FontSize',12,'Color',cl(3))
text(t4(3)-.8,tey,'4-fold','FontSize',12,'Color',cl(4))
axis([-1 14 -3 7.5])
title('Cubic B-splines With A Knot of Various Multiplicities')
axis off
hold off

```



For example, since the order of a cubic B-spline is 4, a double knot means just 2 smoothness conditions, i.e., just continuity across that knot of the function and its first derivative.

### Refinement and Knot Insertion

Any B-form can be *refined*, i.e., converted, by *knot insertion*, into the B-form for the same function, but for a finer knot sequence. The finer the knot sequence, the closer is the control polygon to the function being represented.


For example, this figure shows the original (in black) and refined (in red) control polygons for the cubic spline used earlier.

```

sp = savesp;
fnplt(sp,2.5);
hold on
c = fnbrk(sp,'c');
plot(aveknt(fnbrk(sp,'k'),4),c,':ok');
b = knt2brk(fnbrk(sp,'k'));
spref = fnrfn(sp,(b(2:end)+b(1:end-1))/2);
cr = fnbrk(spref,'c');
h2 = plot(aveknt(fnbrk(spref,'knots'),4),cr,':*r');
axis([-0.72 7 -0.5 3.5])
title('A Spline, its Control Polygon, and a Refined Control Polygon')
axis off
hold off


```

### A Spline, its Control Polygon, and a Refined Control Polygon



As a second example, we start with the vertices of the standard diamond as our control points, but run through the sequence twice.

```
ozmz = [1 0 -1 0];
c = [ozmz ozmz 1; 0 ozmz ozmz];
circle = spmak(-4:8,c);
fnplt(circle)
hold on
plot(c(1,:),c(2,:),':ok')
axis(1.1*[-1 1 -1 1])
axis equal, axis off
hold off
```




However, when we plot the resulting spline, we get a curve that begins and ends at the origin, due to the fact that we chose to make the knot sequence simple. Hence our spline vanishes at the endpoints of its basic interval,  $[-4 \dots 8]$ . We really only want the part of the spline that corresponds to the interval  $[0 \dots 4]$ , plotted more boldly in the figure below.

```
fnplt(circle)
hold on
fnplt(circle,[0 4],4)
plot(c(1,:),c(2,:),':ok')
axis(1.1*[-1 1 -1 1])
title('A Circle as Part of a Spline Curve with a Diamond as Control Polygon')
axis equal, axis off
hold off
```



### A Circle as Part of a Spline Curve with a Diamond as Control Polygon




To get just the circle, we restrict our spline to the interval  $[0 \dots 4]$ . We do this by converting to ppform, restricting to  $[0 \dots 4]$ , then converting to B-form.

```

circ = fn2fm(fnbrk(fn2fm(circle, 'pp'), [0 4]), 'B-');
fnplt(circ, 2.5)
hold on
cc = fnbrk(circ, 'c');
plot(cc(1,:), cc(2,:), ':ok')
axis(1.1*[-1 1 -1 1])
axis equal, axis off
hold off


```



Refinement of the resulting knot sequence leads to a control polygon much closer to the circle.

```
ccc = fnbrk(fnrfn(circ,.5:4),'c');  
hold on  
plot(ccc(1,:),ccc(2:4,:),'-r*')  
title('A Circle as a Spline Curve, its Control Polygon, and a Refinement')  
hold off
```

### A Circle as a Spline Curve, its Control Polygon, and a Refinement




### Multivariate Splines

A spline in Curve Fitting Toolbox can also be multivariate, namely, the tensor product of univariate splines. The B-form for such a function is only slightly more complicated, with the knots now a cell array containing the various univariate knot sequences, and the coefficient array suitably multidimensional.

For example, this random spline surface is cubic in the first variable (there are 11 knots and 7 coefficients in that variable), but only piecewise constant in the second variable ( $(2+5+2)-8 = 1$ ).

```
fnplt( spmak({augknt(0:4,4),augknt(0:4,3)}, rand(7,8)) )
```



## Construct and Work with the PPFORM

This example shows how to construct and work with the `ppform` of a spline in Curve Fitting Toolbox™.

### Introduction

A (univariate) piecewise polynomial, or *pp* for short, is characterized by its *break sequence*, `breaks` say, and its *coefficient array*, `coefs` say, of the local power form of its polynomial pieces. The break sequence is assumed to be strictly increasing,


$$\text{breaks}(1) < \text{breaks}(2) < \dots < \text{breaks}(l+1),$$

with  $l$  the number of polynomial pieces that make up the *pp*. In the figure below, `breaks` is `[0,1,4,6]`, hence  $l$  is 3.

While these polynomials may be of varying degrees, they are all recorded as polynomials of the same *order*  $k$ , i.e., the coefficient array `coefs` is of size  $[l, k]$ , with `coefs(j, :)` containing the  $k$  coefficients in the local power form for the  $j$ -th polynomial piece.

Here is an example of a *pp* made up of three quadratic polynomials, i.e.,  $l = k = 3$ . The breaks are marked in red.

```
sp = spmak([0 1 4 4 6],[2 -1]);
pp = fn2fm(sp, 'pp');
breaks = fnbrk(pp, 'b');
coefs = fnbrk(pp, 'c');
coefs(3,[1 2]) = [0 1];
pp = ppmak(breaks,coefs,1);
fnplt(pp,[breaks(1)-1 breaks(2)], 'g',1.8)
hold on
fnplt(pp, breaks([2 3]), 'b',1.8)
fnplt(pp,[breaks(3),breaks(4)+1], 'm',1.8)
lp1 = length(breaks);
xb = repmat(breaks,3,1);
yb = repmat([2;-2.2;NaN],1,lp1);
plot(xb(:),yb(:), 'r')
axis([-1 7 -2.5 2.3])
hold off
```



The precise description of the pp in terms of the break sequence `breaks` and the coefficient array `coefs` is

```
pp(t) = polyval(coefs(j,:), t-breaks(j))
        for breaks(j) <= t < breaks(j+1)
```

where, to recall,

```
polyval(a,x) = a(1)*x^(k-1) + a(2)*x^(k-2) + ... + a(k)*x^0.
```

For the pp in the figure above, `breaks(1)` is 0, and `coefs(1,:)` is `[-1/2 0 0]`, while `breaks(3)` is 4, and `coefs(3,:)` is `[0 1 -1]`. For `t` not in `[breaks(1) .. breaks(l+1)]`, `pp(t)` is defined by extending the first or last polynomial piece.

A pp is usually constructed through a process of interpolation or approximation. But it is also possible to make one up in `ppform` from scratch, using the command `ppmak`. For example, the pp above can be obtained as

```
breaks = [0 1 4 6];
coefs = [1/2 0 0 -1/2 1 1/2 0 1 -1];
fn = ppmak(breaks,coefs)
```

`fn =`

```
struct with fields:
```

```

form: 'pp'
breaks: [0 1 4 6]
coefs: [3x3 double]
pieces: 3
order: 3
dim: 1

```

This returns, in `fn`, a complete description of this pp function in the so-called pppform.

Various commands in Curve Fitting Toolbox can operate on this form. The remaining sections show some examples.

### Operating on Piecewise Polynomials

To evaluate a pp, use the `fnval` command.

```
fnval(fn, -1:7)
```

```
ans =
```

```
Columns 1 through 7
```

```
0.5000    0    0.5000    1.0000    0.5000   -1.0000    0
```

```
Columns 8 through 9
```


```
1.0000    2.0000
```

To differentiate a pp, use the `fnder` command.

```

dfn = fnder ( fn );
hold on
fnplt(dfn, 'jumps','y', 3)
hold off
h1 = findobj(gca,'Color','y');
legend(h1,{'First Derivative'},'location','SW')

```




Note that the derivative of the example pp is continuous at 1 but discontinuous at 4. Also note that, by default, `fnplt` plots a ppform on its *basic interval*, i.e., on the interval `[breaks(1) .. breaks(end)]`.

You can also use `fnder` to take the second derivative of a pp.

```
ddfn = fnder(fn, 2);
hold on
fnplt( ddfn, 'j', 'k', 1.6)
hold off
h2 = findobj(gca, 'Color', 'k');
legend([h1 h2], {'First Derivative' 'Second Derivative'}, 'location', 'SW')
```






The second derivative is piecewise constant.

Note that differentiation via `fnder` is done separately for each polynomial piece. For example, although the first derivative has a jump discontinuity across 4, the second derivative is not infinite there. This has consequences when we integrate the second derivative.

To integrate a pp, use the `fnint` command.

```
iddfn = fnint(ddfn);
hold on
fnplt(iddfn, 'b', .5)
hold off
h3 = findobj(gca, 'Color', 'b', 'LineWidth', .5);
legend([h1 h2 h3], {'First Derivative' 'Second Derivative' ...
                  'Integral of Second Derivative'}, 'location', 'SW')
```



Note that integration of the second derivative does recover the first derivative, except for the jump across 4, which cannot be recovered, since the integral of any pp function is continuous.

You can obtain parts with the aid of the command `fnbrk`. For example

```
breaks = fnbrk(fn, 'breaks')
```

```
breaks =
```


```
    0    1    4    6
```

recovers the break sequence of the pp in `fn`, while

```
piece2 = fnbrk(fn, 2);
```

recovers the second polynomial piece, as this plot confirms.

```
fnplt(pp,[breaks(1)-1 breaks(2)], 'g', 1.8)
hold on
fnplt(piece2, 'b', 2.5, breaks([2 3])+[-1 .5])
fnplt(pp,[breaks(3),breaks(4)+1], 'm', 1.8)
plot(xb(:),yb(:), 'r')
title('The Polynomial that Supplies the Second Polynomial Piece')
hold off
axis([-1 7 -2.5 2.3])
```




### Vector-Valued Piecewise Polynomials

A pp can also be vector-valued, to describe a curve, in 2-space or 3-space. In that case, each local polynomial coefficient is a vector rather than a number, but nothing else about the ppform changes. There is one additional part of the ppform to record this, the *dimension* of its target.

For example, here is a 2-vector-valued pp describing the unit square, as its plot shows. It is a 2D-curve, hence its dimension is 2.

```
square = ppmak(0:4, [1 0 0 1 -1 1 0 0 ; 0 0 1 0 0 1 -1 1]);
fnplt(square, 'r', 2)
axis([-0.5 1.5 -0.5 1.5])
axis equal
title('A Vector-Valued PP that Describes a Square')
```




### Multivariate Piecewise Polynomials

A pp in Curve Fitting Toolbox can also be multivariate, namely, a tensor product of univariate pp functions. The ppform of such a multivariate pp is only slightly more complicated, with `breaks` now a cell array containing the break sequence for each variable, and `coefs` now a multidimensional array. It is much harder to make up a non-random such function from scratch, so we won't try that here, particularly since the toolbox is meant to help with the construction of pp functions from some conditions about them. For example, the sphere in this figure is constructed with the aid of `csape`.

```
x = 0:4;
y = -2:2;
s2 = 1/sqrt(2);
v = zeros(3,7,5);
v(3,:,:)= [0 1 s2 0 -s2 -1 0].'*[1 1 1 1 1];
v(2,:,:)= [1 0 s2 1 s2 0 -1].'*[0 1 0 -1 0];
v(1,:,:)= [1 0 s2 1 s2 0 -1].'*[1 0 -1 0 1];
sph = csape({x,y},v,{'clamped','periodic'});
fnplt(sph)
axis equal
axis off
title('A Sphere Described by a Bicubic 3-Vector-Valued Spline')
```

### A Sphere Described by a Bicubic 3-Vector-Valued Spline



While the pform of a spline is efficient for *evaluation*, the *construction* of a spline from some data is usually handled more efficiently by first determining its *B-form*, i.e., its representation as a linear combination of B-splines. For more information, see “Construct and Work with the B-form” on page 12-40.


## How to Choose Knots

This example shows how to select and optimize knots using the `optknt` and `newknt` commands from Curve Fitting Toolbox™.

### Sample Data

Here are some sample data, much used for testing spline approximation with variable knots, the so-called Titanium Heat Data. They record some property of titanium measured as a function of temperature.

```
[xx,yy] = titanium;
plot(xx,yy,'x');
axis([500 1100 .55 2.25]);
title('The Titanium Heat Data');
hold on
```




Notice the rather sharp peak. We'll use these data to illustrate some methods for knot selection.

First, we pick a few data points from these somewhat rough data. We will interpolate using this subset, then compare results to the full dataset.

```
pick = [1 5 11 21 27 29 31 33 35 40 45 49];
tau = xx(pick);
y = yy(pick);
```

```
plot(tau,y,'ro');
legend({'Full Dataset' 'Subsampled Data'}, 'location','NW');
```



### General Considerations

A spline of order  $k$  with  $n+k$  knots has  $n$  degrees of freedom. Since we have 12 data sites,  $\tau(1) < \dots < \tau(12)$ , a fit with a cubic spline, i.e., a fourth order spline, requires a knot sequence  $t$  of length  $12+4$ .

Moreover, the knot sequence  $t$  must satisfy the *Schoenberg-Whitney conditions*, i.e., must be such that the  $i$ -th data site lies in the support of the  $i$ -th B-spline, i.e.,

$$t(i) < \tau(i) < t(i+k) \text{ for all } i,$$

with equality allowed only in case of a knot of multiplicity  $k$ .

One way to choose a knot sequence satisfying all these conditions is as the optimal knots, of Gaffney/Powell and Micchelli/Rivlin/Winograd.

### Optimal Knots

In *optimal* spline interpolation, to values at sites

$$\tau(1), \dots, \tau(n)$$

say, the knots are chosen so as to minimize the constant in a standard error formula. Specifically, the first and the last data site are chosen as  $k$ -fold knots. The remaining  $n-k$  knots are supplied by `optknt`.

Here is the beginning of the help from `optknt`:

OPTKNT Optimal knot distribution.

OPTKNT(TAU,K) returns an `optimal' knot sequence for interpolation at data sites TAU(1), ..., TAU(n) by splines of order K. TAU must be an increasing sequence, but this is not checked.

OPTKNT(TAU,K,MAXITER) specifies the number MAXITER of iterations to be tried, the default being 10.

The interior knots of this knot sequence are the  $n-K$  sign-changes in any absolutely constant function  $h \approx 0$  that satisfies

$$\int_{\text{TAU}(1)}^{\text{TAU}(n)} f(x)h(x) dx = 0$$

for all splines  $f$  of order  $K$  with knot sequence TAU.

### Trying OPTKNT


We try using `optknt` for interpolation on our example, interpolating by cubic splines to data

$(\text{tau}(i), y(i))$ , for  $i = 1, \dots, n$ .

```
k = 4;
osp = spapi( optknt(tau,k), tau,y);

fnplt(osp,'r');
hl = legend({'Full Dataset' 'Subsampled Data' ...
           'Cubic Spline Interpolant Using Optimal knots'}, ...
           'location','NW');
hl.Position = hl.Position-[.14,0,0,0];
```






This is a bit disconcerting!

Here, marked by stars, are also the interior optimal knots:

```
xi = fnbrk(osp, 'knots');
xi([1:k end+1-(1:k)]) = [];
plot(xi, repmat(1.4, size(xi)), '*');
hl = legend({'Full Dataset' 'Subsampled Data' ...
            'Cubic Spline Interpolant Using Optimal knots' ...
            'Optimal Knots'}, 'location', 'NW');
hl.Position = hl.Position - [.14, 0, 0, 0];
```



### What Happened?


The knot choice for optimal interpolation is designed to make the maximum over *all* functions  $f$  of the ratio

$$\frac{\text{norm}(f - I_f)}{\text{norm}(D^k f)}$$

as small as possible, where the numerator is the norm of the interpolation error,  $f - I_f$ , and the denominator is the norm of the  $k$ -th derivative of the interpolant,  $D^k f$ . Since our data imply that  $D^k f$  is rather large, the interpolation error near the flat part of the data is of acceptable size for such an 'optimal' scheme.

Actually, for these data, the ordinary cubic spline interpolant provided by `csapi` does quite well:

```
cs = csapi(tau,y);
fnplt(cs,'g',2);
hl = legend({'Full Dataset' 'Subsampled Data' ...
           'Cubic Spline Interpolant Using Optimal knots' ...
           'Optimal Knots' 'Cubic Spline Interpolant Using CSAPI'}, ...
           'location','NW');
hl.Position = hl.Position-[.14,0,0,0];
hold off
```



### Knot Choice for Least Squares Approximation


Knots must be selected when doing least-squares approximation by splines. One approach is to use equally-spaced knots to begin with, then use `newknt` with the approximation obtained for a better knot distribution.

The next sections illustrate these steps with the full titanium heat data set.

### Least Squares Approximation with Uniform Knot Sequence

We start with a uniform knot sequence.


```
unif = linspace(xx(1), xx(end), 2+fix(length(xx)/4));
sp = spap2(augknt(unif, k), k, xx, yy);
plot(xx,yy,'x');
hold on
fnplt(sp,'r');
axis([500 1100 .55 2.25]);
title('The Titanium Heat Data');
hl = legend({'Full Dataset' ...
           'Least Squares Cubic Spline Using Uniform Knots'}, ...
           'location','NW');
hl.Position = hl.Position- [.14,0,0,0];
```



This is not at all satisfactory. So we use `newknt` for a spline approximation of the same order and with the same number of polynomial pieces, but the breaks better distributed.

### Using NEWKNT to Improve the Knot Distribution

```
spgood = spap2(newknt(sp), k, xx,yy);
fnplt(spgood,'g',1.5);
hl = legend({'Full Dataset' ...
            'Least Squares Cubic Spline Using Uniform Knots' ...
            'Least Squares Cubic Spline Using NEWKNT'}, ...
            'location','NW');
hl.Position = hl.Position-[.14,0,0,0];
hold off
```



This is quite good. Incidentally, even one interior knot fewer would not have sufficed in this case.

## Cubic Spline Interpolation

This example shows how to use the `csapi` and `csape` commands from Curve Fitting Toolbox™ to construct cubic spline interpolants.

### The CSAPI Command


The command

```
values = csapi(x,y,xx)
```

returns the values at `xx` of the cubic spline interpolant to the given data  $(x, y)$ , using the not-a-knot end condition. This interpolant is a piecewise cubic function, with break sequence `x`, whose cubic pieces join together to form a function with two continuous derivatives. The "not-a-knot" end condition means that, at the first and last interior break, even the third derivative is continuous (up to round-off error).


Specifying only two data points results in a straight line interpolant.

```
x = [0 1];  
y = [2 0];  
xx = linspace(0,6,121);  
plot(xx,csapi(x,y,xx),'k-',x,y,'ro')  
title('Interpolant to Two Points')
```




Specifying three data points gives a parabola.

```
x = [2 3 5];  
y = [1 0 4];  
plot(xx,csapi(x,y,xx),'k-',x,y,'ro')  
title('Interpolant to Three Points')
```



More generally, four or more data points give a cubic spline.

```
x = [1 1.5 2 4.1 5];  
y = [1 -1 1 -1 1];  
plot(xx,csapi(x,y,xx),'k-',x,y,'ro')  
title('Cubic Spline Interpolant to Five Points')
```



### How to Check the Output of CSAPI

These look like nice interpolants, but how do we check that `csapi` performs as advertised?

We already saw that `csapi` interpolates, because we plotted the data points and the interpolant went right through those points. But to be sure that we get a cubic spline, it is best to start with data from a cubic spline of the expected sort and check whether `csapi` *reproduces* that cubic spline, i.e., gives back that cubic spline from which the data were taken.

### Example: The Truncated Power Function

One simple example of a cubic spline function to check against is the truncated third power, i.e., the function

$$f(x) = ((x - x_i)_+)^3,$$

where  $x_i$  is one of the breaks and the "+" subscript indicates the *truncation function*, provided by the command `subplus`:

`help subplus`

SUBPLUS Positive part.


$$y = \text{subplus}(x) := (x)_{\{+\}} = \begin{cases} x, & \text{if } x \geq 0 \\ 0, & \text{if } x < 0 \end{cases},$$



returns the positive part of  $X$ . Used for computing truncated powers.


The truncated 3rd power is plotted below for the particular choice  $\xi = 2$ . As expected, it is zero to the left of 2, and rises like  $(x-2)^3$  to the right of 2.

```
plot(xx, subplus(xx-2).^3, 'y', 'LineWidth', 3)
axis([0,6,-10,70])
```



Now we interpolate this particular cubic spline at the data sites 0:6, and plot the interpolant on top of the spline, in black.


```
x = 0:6;
y = subplus(x-2).^3;
values = csapi(x,y,xx);
hold on
plot(xx,values,'k',x,y,'ro')
hold off
title('Interpolant to ((x-2)_+)^3')
```



### The Interpolation Error

When comparing two functions, it is usually much more informative to plot their difference.

```
plot(xx, values - subplus(xx-2).^3)
title('Error in Cubic Spline Interpolation to  $((x-2)_+)^3$ ')
```



To put the size of their difference into context, you can also compute the maximum data value. This shows the error to be no worse than the inevitable round-off error.


```
max_y = max(abs(y))
```

```
max_y = 64
```

### A Truncated Power That Cannot be Reproduced

As a further test, we interpolate a truncated power whose `csapi`-produced interpolant at the sites `0:6` cannot coincide with it. For example, the first interior break of the interpolating spline is not really a knot since `csapi` uses the "not-a-knot" condition, hence the interpolant has three continuous derivatives at that site. This implies that we should not be able to reproduce the truncated 3rd power centered at that site since its third derivative is discontinuous across that site.

```
values = csapi(x, subplus(x-1).^3, xx);
plot(xx, values - subplus(xx-1).^3)
title('Error in Not-a-Knot Interpolant to ((x-1)_+)^3')
```



Since 1 is a first interior knot, it is not active for this interpolant.

The difference is as large as .18, but decays rapidly as we move away from 1. This illustrates that *cubic spline interpolation is essentially local*.

### Using the ppform Instead of Values

It is possible to retain the interpolating cubic spline in a form suitable for subsequent evaluation, or for calculating its derivatives, or for other manipulations. This is done by calling `csapi` in the form

```
pp = csapi(x,y)
```

which returns the ppform of the interpolant. You can evaluate this form at some new points `xx` by the command

```
values = fnval(pp,xx)
```

You can differentiate the interpolant by the command

```
dpp = fnder(pp)
```

or integrate it by the command

```
ipp = fnint(pp)
```

which return the ppform of the derivative or the integral, respectively.


**Example: Differentiating and Integrating the Interpolant**

To show differentiation of an interpolant, we plot the derivative of this truncated power

$$f_2'(x) = 3((x - 2)_+)^2,$$


(again in yellow) and then, on top of it, the derivative of our interpolant to the original truncated third power function (again in black).

```
plot(xx,3*subplus(xx-2).^2,'y','LineWidth',3)
pp = csapi(x,subplus(x-2).^3);
dpp = fnder(pp);
hold on
plot(xx,fval(dpp,xx),'k')
hold off
title('Derivative of Interpolant to ((x-2)_+)^3')
```



Again, the more informative comparison is to plot their difference, and as before this is no bigger than the round-off error.

```
plot(xx, fval(dpp,xx) - 3*subplus(xx-2).^2)
title('Error in Derivative of interpolant to ((x-2)_+)^3')
```




The second derivative of the truncated power is

$$f_2''(x) = 6(x - 2)_+$$

A plot of the difference between this function and the second derivative of the interpolant to the original function shows that there are now jumps, but they are still within the round-off error.

```
ddpp = fnder(dpp);
plot(xx, fnval(ddpp,xx) - 6*subplus(xx-2))
title('Error in Second Derivative of Interpolant to ((x-2)+)3')
```




The integral of the truncated power is

$$F_2(x) = ((x - 2)_+)^4/4.$$

A plot of the difference between this function and the integral of the interpolant to the original function again shows that the errors are within the round-off error.

```
ipp = fnint(pp);
plot(xx, fnval(ipp,xx) - subplus(xx-2).^4/4)
title('Error in Integral of Interpolant to ((x-2)_+)^3')
```



### The CSAPE Command

Like `csapi`, the `csape` command provides a cubic spline interpolant to given data. However, it permits various additional end conditions. Its simplest version,

```
pp = csape(x,y)
```

uses the Lagrange end condition, which is a common alternative to the not-a-knot condition used by `csapi`. `csape` does not directly return values of the interpolant, but only its `ppform`.


For example, consider again interpolation to the function

$$f_1(x) = ((x - 1)_+)^3,$$

which `csapi` fails to reproduce well. We plot the error of the not-a-knot interpolant returned by `csapi` (in black), along with the error of the interpolant obtained from `csape` (in red).

```
exact = subplus(xx-1).^3;
plot(xx, fnval(csapi(x,subplus(x-1).^3),xx) - exact,'k')
hold on
plot(xx, fnval(csape(x,subplus(x-1).^3),xx) - exact,'r')
title('Error in Not-a-Knot vs. Lagrange End Conditions')
legend({'Not-a-Knot' 'Lagrange'});
hold off
```





There is not much difference between the two interpolants in this case.

### Other End Conditions: The 'Natural' Spline Interpolant

The `csape` command also provides ways to specify several other types of end conditions for an interpolating cubic spline. For example, the command

```
pp = csape(x,y,'variational')
```


uses the so-called 'natural' end conditions. This means that the second derivative is zero at the two extreme breaks.

This step shows how to apply 'natural' cubic spline interpolation to the function

$$f_2(x) = ((x - 2)_+)^3,$$

and plot the error. The code below computes the 'natural' spline interpolant with an alternative argument syntax that is equivalent to the 'variational' argument: using 'second' specifies that `csape` should set the second derivative at the extreme data sites to the default value of 0.

```
pp = csape(x,subplus(x-2).^3,'second');
plot(xx, fval(pp,xx) - subplus(xx-2).^3)
title('Error in ''Natural'' Spline Interpolation to ((x-2)_+)^3')
```



Note the large error near the right end. This is due to the fact that the 'natural' end conditions implicitly insist on having a zero second derivative there.


### Other End Conditions: Prescribing Second Derivatives

We can also explicitly use the correct second derivatives to get a small error. First, we compute the correct second derivative values of the truncated power at the endpoints.

```
endcond = 6*subplus(x([1 end])-2);
```

Then we create the interpolant, specifying that second derivatives at the endpoints are to be matched to the second derivative values we just computed. We do this by providing `endcond(1)` for the left endpoint condition, and `endcond(2)` for the right, along with the data values.

```
pp = csape(x,[endcond(1) subplus(x-2).^3 endcond(2)], 'second');
plot(xx, fval(pp,xx) - subplus(xx-2).^3,'r')
title(['Error in Spline Interpolation to ((x-1)_+)^3'; ...
      ' When Matching the 2nd Derivative at Ends '])
```



### Other End Conditions: Prescribing Slopes

`csape` also permits specification of endpoint *slopes*. This is the *clamped* (or, *complete*) cubic spline interpolant. The statement

```
pp = csape(x, [sl, y, sr], 'clamped')
```

creates the cubic spline interpolant to the data  $(x, y)$  that also has slope  $sl$  at the leftmost data site and slope  $sr$  at the rightmost data site.

### Other End Conditions: Mixed End Conditions


It is even possible to mix these conditions. For example, our much-exercised truncated power function

$$f_1(x) = ((x - 1)_+)^3$$

has slope 0 at  $x=0$  and second derivative 30 at  $x=6$  (the last data site).

Therefore, by matching the slope at the left end and the curvature at the right, we expect no error in the resulting interpolant.


```
pp = csape(x, [0 subplus(x-1).^3 30], [1 2]);
plot(xx, fnval(pp,xx) - subplus(xx-1).^3)
title(['Error in Spline Interpolation to  $((x-1)_+)^3$ '; ...
      ' with Mixed End Conditions. '])
```



### Other End Conditions: Periodic Conditions

It is also possible to prescribe *periodic* end conditions. For example, the sine function is  $2\pi$ -periodic and has the values  $[0 \ -1 \ 0 \ 1 \ 0]$  at the sites  $(\pi/2)*(-2:2)$ . The difference, between the sine function and its periodic cubic spline interpolant at these sites, is only 2 percent. Not bad.

```
x = (pi/2)*(-2:2);
y = [0 -1 0 1 0];
pp = csape(x,y, 'periodic' );
xx = linspace(-pi,pi,201);
plot(xx, sin(xx) - fnval(pp,xx), 'x')
title('Error in Periodic Cubic Spline Interpolation to sin(x)')
```



### End Conditions Not Explicitly Covered by CSAPI or CSAPE

Any end condition not covered explicitly by `csapi` or `csape` can be handled by constructing the interpolant with the `csape` default side conditions, and then adding to it an appropriate scalar multiple of an interpolant to zero values and some side conditions. If there are two 'nonstandard' side conditions to be satisfied, you may have to solve a 2-by-2 linear system first.

For example, suppose that you want to compute the cubic spline interpolant  $s$  to the data

```
x = 0:.25:3;
q = @(x) x.*(-1 + x.*(-1+x.*x/5));
y = q(x);
```

and enforce the condition

$$\lambda(s) := a * (Ds)(e) + b * (D^2 s)(e) = c$$

on the first and second derivatives of  $s$  at the point  $e$ .

The data were generated from a quartic polynomial that happens to satisfy this side condition with specific parameters

```
e = x(1);
a = 2; b = -3; c = 4;
```

To construct the interpolant that satisfies this specific condition, we first construct the interpolant with the default end conditions

```
pp1 = csape(x,y);
```

and the first derivative of its first polynomial piece.

```
dp1 = fnder(fnbrk(pp1,1));
```

In addition, we construct the cubic spline interpolant to zero data values, specifying that it have a slope of 1 at  $e$ ,

```
pp0 = csape(x,[1,zeros(size(y)),0], [1,0]);
```

as well as constructing the first derivative of its first polynomial piece.

```
dp0 = fnder(fnbrk(pp0,1));
```

Then we compute  $\lambda$  for both  $pp1$  and  $pp0$ ,

```
lam1 = a*fnder(dp1,e) + b*fnder(dp1,e);
```

```
lam0 = a*fnder(dp0,e) + b*fnder(dp0,e);
```

and construct the correct linear combination of  $pp1$  and  $pp0$  to get a cubic spline


```
s := pp1 + ((c - lambda(pp1))/lambda(pp0)) * pp0
```

that does satisfy the desired condition, as well as the default end condition at the right endpoint. We form this linear combination with the help of `fncmb`.

```
s = fncmb(pp0,(c-lam1)/lam0,pp1);
```

A plot of the interpolation error shows that  $s$  fits the quartic polynomial slightly better near  $e$  than the interpolant  $pp1$  with the default conditions does.

```
xx = (-.3):.05:.7; yy = q(xx);  
plot(xx, fnval(pp1,xx) - yy, 'x')  
hold on  
plot(xx, fnval(s,xx) - yy, 'o')  
hold off  
legend({'Default conditions' 'Nonstandard conditions'}, 'location', 'SE')
```



If we want to enforce the condition

$$\mu(s) := (D^3 s)(3) = 14.6$$

on the third derivative of the interpolant (the quartic satisfies this condition), then we construct an additional cubic spline interpolating to zero values, and with zero first derivative at the left endpoint, hence certain to be independent from  $pp0$ .

```
pp2 = csape(x, [0, zeros(size(y)), 1], [0, 1]);
```

Then we find the coefficients  $d0$  and  $d2$  in the linear combination

$$s := pp1 + d0*pp0 + d2*pp2$$

that solves the linear system

$$\lambda(s) = c$$

$$\mu(s) = 14.6$$

Note that both  $pp0$  and  $pp2$  vanish at all interpolation sites, hence  $s$  will match the given data for any choice of  $d0$  and  $d2$ .

For amusement, we use the MATLAB® encoding facility to write a loop to compute  $\lambda(pp_j)$  and  $\mu(pp_j)$ , for  $j=0:2$ .

```
dd = zeros(2,3);
for j=0:2
```

```

J = num2str(j);
eval(['dpp',J,'=fnder(pp',J,');']);
eval(['ddpp',J,'=fnder(dpp',J,');']);
eval(['dd(1,1+',J,')=a*fnval(dpp',J,','e)+b*fnval(ddpp',J,','e);']);
eval(['dd(2,1+',J,')=fnval(fnder(ddpp',J,'),3);']);
end

```


Given the values of  $\lambda$  and  $\mu$  for  $pp_0$ ,  $pp_1$ , and  $pp_2$ , we then solve for the coefficients that define the correct linear combination.

```

d = dd(:, [1,3])\([c;14.6]-dd(:,2));
s = fncmb(fncmb(pp0,d(1),pp2,d(2)),pp1);

xxx = 0:.05:3;
yyy = q(xxx);
plot(xxx, yyy - fnval(s,xxx), 'x')
title('Error in Spline Interpolant to y = x*(-1 + x*(-1+x*x/5))')

```




For reassurance, we compare this error with the one obtained in complete cubic spline interpolation to this function:

```

hold on
plot(xxx, yyy - fnval(csape(x, [-1,y, -7+(4/5)*27], 'clamped'), xxx), 'o')
hold off
legend({'Nonstandard conditions' 'Endslope conditions'})

```





The errors differ (and not by much) only near the end points, testifying to the fact that both  $pp0$  and  $pp2$  are sizable only near their respective end points.

As a final check, we verify that  $s$  satisfies the desired third derivative condition at 3.

```
fnder(s,3),3)
```

```
ans = 14.6000
```

## Cubic Smoothing Splines

This example shows how to use the `csaps` and `spaps` commands from Curve Fitting Toolbox™ to construct cubic smoothing splines.

### The CSAPS Command

The command `csaps` provides the *smoothing* spline. This is a cubic spline that more or less follows the presumed underlying trend in noisy data. A smoothing parameter, to be chosen by you, determines just how closely the smoothing spline follows the given data. Here is the basic information, an abbreviated version of the documentation:

CSAPS Cubic smoothing spline.


```
VALUES = CSAPS(X, Y, P, XX)
```

Returns the values at `XX` of the cubic smoothing spline for the given data `(X,Y)` and depending on the smoothing parameter `P`, chosen from the interval `[0 .. 1]`. This smoothing spline `f` minimizes  $P * \sum_i W(i)(Y(i) - f(X(i)))^2 + (1-P) * \text{integral} (D^2 f)^2$

### Example: Noisy Data From a Cubic Polynomial


Here are some trial runs. We start with data from a simple cubic,  $q(x) := x^3$ , contaminate the values with some noise, and choose the value of the smoothing parameter to be `.5`. Then plot the resulting smoothed values, along with the underlying cubic, and the contaminated data.

```
xi = (0:.05:1);
q = @(x) x.^3;
yi = q(xi);
randomStream = RandStream.create( 'mcg16807', 'Seed', 23 );
ybad = yi+.3*(rand(randomStream, size(xi))-0.5);
p = .5;
xxi = (0:100)/100;
ys = csaps(xi,ybad,p,xxi);
plot(xi,yi, ':',xi,ybad, 'x',xxi,ys, 'r-')
title('Clean Data, Noisy Data, Smoothed Values')
legend( 'Exact', 'Noisy', 'Smoothed', 'Location', 'NorthWest' )
```



The smoothing is way overdone here. By choosing the smoothing parameter  $p$  closer to 1, we obtain a smoothing spline closer to the given data. We try  $p = .6, .7, .8, .9, 1$ , and plot the resulting smoothing splines.

```
yy = zeros(5,length(xxi));
p = [.6 .7 .8 .9 1];
for j=1:5
    yy(j,:) = csaps(xi,ybad,p(j),xxi);
end
hold on
plot(xxi,yy);
hold off
title('Smoothing Splines for Various Values of the Smoothing Parameter')
legend({'Exact','Noisy','p = 0.5','p = 0.6','p = 0.7','p = 0.8', ...
        'p = 0.9', 'p = 1.0'}, 'Location', 'NorthWest' )
```



We see that the smoothing spline can be very sensitive to the choice of the smoothing parameter. Even for  $p = 0.9$ , the smoothing spline is still far from the underlying trend, while for  $p = 1$ , we get the interpolant to the (noisy) data.

In fact, the formulation used by `csapi` (p.235ff of *A Practical Guide to Splines*) is very sensitive to scaling of the independent variable. A simple analysis of the equations used shows that the sensitive range for  $p$  is around  $1/(1+\epsilon)$ , with  $\epsilon := h^3/16$ , and  $h$  the average difference between neighboring sites. Specifically, you would expect a close following of the data when  $p = 1/(1+\epsilon/100)$  and some satisfactory smoothing when  $p = 1/(1+\epsilon*100)$ .

The plot below shows the smoothing spline for values of  $p$  near this magic number  $1/(1+\epsilon)$ . For this case, it is more informative to look at  $1-p$  since the magic number,  $1/(1+\epsilon)$ , is very close to 1.

```
epsilon = ((xi(end)-xi(1))/(numel(xi)-1))^3/16;
1 - 1/(1+epsilon)
```


```
ans = 7.8124e-06
```

```
plot(xi,yi,':',xi,ybad,'x')
hold on
labels = cell(1,5);
for j=1:5
    p = 1/(1+epsilon*10^(j-3));
    yy(j,:) = csaps(xi,ybad,p,xxi);
    labels{j} = ['1-p= ',num2str(1-p)];
end
```

```

plot(xxi,yy)
title('Smoothing Splines for Smoothing Parameter Near Its 'Magic' Value')
legend( [{'Exact'}, {'Noisy'}], labels, 'Location', 'NorthWest' )
hold off

```




In this example, the smoothing spline is very sensitive to variation of the smoothing parameter near the magic number. The one farthest from 1 seems the best choice from these, but you may prefer the one beyond that.

```

p = 1/(1+epsilon*10^3);
yy = csaps(xi,ybad,p,xxi);
hold on
plot( xxi, yy, 'y', 'LineWidth', 2 )
title( sprintf( 'The Smoothing Spline For 1-p = %s is Added, in Yellow', num2str(1-p) ) )
hold off

```



You can also supply `csaps` with error weights, to pay more attention to some data points than others. Also, if you do not supply the evaluation sites `xx`, then `csaps` returns the ppform of the smoothing spline.

Finally, `csaps` can also handle vector-valued data and even multivariate, gridded data.

### The SPAPS Command

The cubic smoothing spline provided by the command `spaps` differs from the one constructed in `csaps` only in the way it is selected. Here is an abbreviated version of the documentation for `spaps`:

SPAPS Smoothing spline.

`[SP,VALUES] = SPAPS(X,Y,TOL)` returns the B-form and, if asked, the values at `X`, of a cubic smoothing spline `f` for the given data  $(X(i), Y(:,i)), i=1,2, \dots, n$ .

The smoothing spline `f` minimizes the roughness measure

$$F(D^2 f) := \text{integral} ( D^2 f(t) )^2 dt \text{ on } X(1) < t < X(n)$$

over all functions `f` for which the error measure

$$E(f) := \text{sum}_j \{ W(j) * ( Y(:,j) - f(X(j)) )^2 : j=1, \dots, n \}$$

is no bigger than the given TOL. Here,  $D^M f$  denotes the  $M$ -th derivative of  $f$ . The weights  $W$  are chosen so that  $E(f)$  is the Composite Trapezoid Rule approximation for  $F(y-f)$ .

$f$  is constructed as the unique minimizer of  $\rho * E(f) + F(D^2 f)$ ,

with the smoothing parameter  $RHO$  so chosen so that  $E(f)$  equals TOL. Hence, `FN2FM(SP,'pp')` should be (up to roundoff) the same as the output from `CPAPS(X,Y,RHO/(1+RHO))`.


### Tolerance vs. Smoothing Parameter

It may be easier to supply a suitable tolerance for `spaps` than the smoothing parameter  $p$  required by `csaps`. In our earlier example, we added uniformly-distributed random noise from the interval  $0.3 * [-0.5 \dots 0.5]$ . Hence, we can estimate a reasonable value for `tol` as the value of the error measure  $e$  at such noise.

```
tol = sum((.3*(rand(randomStream, size(yi))- .5)).^2);
```

This plot shows the resulting smoothing spline constructed by `spaps`. Note that the error weights are specified to be uniform, which is their default value in `csaps`.

```
[sp,ys,rho] = spaps(xi,ybad,tol,ones(size(xi)));
plot(xi,yi,':',xi,ybad,'x',xi,ys,'r-')
title( sprintf( 'Clean Data, Noisy Data, Smoothed Values (1-p = %s )', num2str(1/(1+rho)) ) );
legend( {'Exact','Noisy','Smoothed'}, 'location', 'NorthWest' )
```




The figure title shows the value of  $p$  you would use in `csaps` to obtain exactly this smoothing spline for these data.

Here, in addition, is the smoothing spline provided by `csaps` when not given a smoothing parameter. In this case `csaps` chooses the parameter by a certain ad hoc procedure that attempts to locate the region where the smoothing spline is most sensitive to the smoothing parameter (similar to the earlier discussion).

```
hold on
plot(xxi, fnval(csaps(xi,ybad),xxi),'-')
title('Clean Data, Noisy Data, Smoothed Values')
legend({'Exact' 'Noisy' 'spaps, specified tolerance' ...
       'csaps, default smoothing parameter'}, 'Location', 'NorthWest' )
hold off
```





### CSAPS vs. SPAPS

The `csaps` and `spaps` commands differ in the way in which you specify a particular smoothing spline, via a smoothing parameter vs. a tolerance. Another difference is that `spaps` can provide a linear or a quintic smoothing spline, in addition to the cubic smoothing spline.

The quintic smoothing spline is better than the cubic smoothing spline in the situation when you would like the second derivative to move as little as possible.

## Fitting a Spline to Titanium Test Data

This example shows how to use commands from Curve Fitting Toolbox™ to fit a spline to titanium test data with manual and automatic selection of knots.


### Manual Knot Choice for Spline Interpolation

Here are some data that record a certain property of titanium, measured as a function of temperature. We'll use it to illustrate some issues with spline interpolation.

```
[xx,yy] = titanium;
```

A plot of the data shows a rather sharp peak.


```
plot(xx,yy,'bx');
frame = [-10 10 -.1 .3]+[min(xx),max(xx),min(yy),max(yy)];
axis(frame);
```



We pick a few data points from these somewhat rough data, since we want to interpolate. Here is a picture of the data, with the selected data points marked.


```
pick = [1 5 11 21 27 29 31 33 35 40 45 49];
tau = xx(pick);
y = yy(pick);
hold on
```

```
plot(tau,y,'ro');
hold off
```



Since a spline of order  $k$  with  $n+k$  knots has  $n$  degrees of freedom, and we have 12 data points, a fit with a fourth order spline requires  $12+4 = 16$  knots. Moreover, this knot sequence  $t$  must be such that the  $i$ -th data site lies in the support of the  $i$ -th B-spline. We achieve this by using the data sites as knots, but add two simple knots at either end.

```
dl = tau(2) - tau(1);
dr = tau(end) - tau(end-1);
t = [tau(1)-dl*[2 1] tau tau(end)+dr*[1 2]]; % construct the knot sequence
plot(tau,y,'ro');
hold on
axis(frame+[-2*dl 2*dr 0 0])
plot(t, repmat(frame(3)+.03,size(t)),'kx')
hold off
legend({'Data Values' 'Knots'}, 'location', 'NW')
```




We use this knot sequence to construct an interpolating cubic spline.

```
sp = spapi(t,tau,y);
```


Now, for the plot. Since we do not care about the part of the spline outside the data interval, we restrict the plot to that interval.

```
plot(tau,y,'ro')
axis(frame)
hold on
fnplt(sp,[tau(1) tau(end)], 'k')
hold off
```




A closer look at the left part of the spline fit shows some undulations.

```
xxx = linspace(tau(1),tau(5),41);  
plot(xxx, fnval(sp, xxx), 'k', tau, y, 'ro');  
axis([tau(1) tau(5) 0.6 1.2]);
```




The unreasonable bump in the first interval stems from the fact that our spline goes smoothly to zero at its first knot. To see that, here is a picture of the entire spline, along with its knot sequence and the data points.

```
fnplt(sp, 'k');  
hold on  
plot(tau, y, 'ro', t, repmat(.1, size(t)), 'kx');  
hold off  
legend({'Spline Interpolant' 'Data Values' 'Knots'}, 'location', 'NW')
```



Here is a simple way to enforce a more reasonable boundary behavior. We add two more data points outside the given data interval and choose as our data there the values of the straight line through the first two data points.


```
tt = [tau(1)-[4 3 2 1]*dl tau tau(end)+[1 2 3 4]*dr];
xx = [tau(1)-[2 1]*dl tau tau(end)+[1 2]*dr];
yy = [y(1)-[2 1]*(y(2)-y(1)) y y(end)+[1 2]*(y(end)-y(end-1))];
sp2 = spapi(tt,xx,yy);
plot(tau,y,'ro', xx([1 2 end-1 end]),yy([1 2 end-1 end]),'bo');
axis(frame+[-2*dl 2*dr 0 0]);
hold on
fnplt(sp2,'b',tau([1 end]))
hold off
legend({'Original Data' 'Data Added for End Conditions' ...
       'Fit with Added Data'},'location','NW')
```



Here is a comparison of the two spline fits, to show the reduction of the undulation in the first and last interval.


```
hold on
fnplt(sp,'k',tau([1 end]))
hold off
legend({'Original Data' 'Data Added for End Conditions' ...
       'Fit with Added Data' 'Original Fit'},'location','NW')
```





Finally, here is a closer look at the first four data intervals that shows more clearly the reduction of the undulation near the left end.


```
plot(tau,y,'ro',xxx,fval(sp2,xxx),'b',xxx,fval(sp,xxx),'k');
axis([tau(1) tau(5) .6 1.2]);
legend({'Original Data' 'Fit with Added Data' ...
       'Original Fit'},'location','NW')
```



### Automatic Knot Choice for Interpolation


If all this detail turns you off, let Curve Fitting Toolbox choose the knots for you. Specify the desired order of the interpolant as the first input argument to the spline interpolation command `spapi`, rather than a knot sequence.

```
autosp = spapi(4, tau, y);
knots = fnbrk(autosp, 'knots');
plot(tau, y, 'ro')
hold on
fnplt(autosp, 'g')
plot(knots, repmat(.5, size(knots)), 'gx')
hold off
legend({'Data Values' 'Fit With Knots Chosen by SPAPI' ...
       'Knots Chosen by SPAPI'}, 'location', 'NW')
```




Below is the result of a much better knot choice, obtained by shifting the knot at 842 slightly to the right and the knot at 985 slightly to the left.

```
knots([7 12]) = [851, 971];
adjsp = spapi(knots, tau, y);
hold on
fnplt(adjsp, 'r', 2)
plot(knots, repmat(.54, size(knots)), 'rx')
hold off
legend({'Data Values' 'Fit With Knots Chosen by SPAPI' ...
       'Knots Chosen by SPAPI' 'Fit With Knots Adjusted' ...
       'Adjusted Knots'}, 'location', 'NW')
```



Or else, simply try the standard cubic spline interpolant, supplied by `csapi`. This amounts to a slightly different choice of knots.

```
autocs = csapi(tau, y);  
plot(tau, y, 'ro')  
hold on  
fnplt(autocs, 'c')  
hold off
```




With such rapidly-varying data, it is hard to get agreement among all reasonable interpolants, even if each of them is a cubic spline. The plot below shows all five interpolants, for comparison.

```

plot(tau, y, 'ro')
hold on
fnplt(sp,'k',tau([1 end])) % black: original
fnplt(sp2,'b',tau([1 end])) % blue: with special end conditions
fnplt(autospl,'g') % green: automatic knot choice by SPAPI
fnplt(autocs,'c') % cyan: automatic knot choice by CSAPI
fnplt(adjsp,'r',2) % red: knot choice by SPAPI slightly changed
hold off
legend({'Data Values' 'Original Fit' 'Special End Conditions' ...
       'With Knots Chosen by SPAPI' 'With Knots Chosen by CSAPI' ...
       'With Adjusted Knots'},'location','NW')

```



## Splines in the Plane


This example shows how to use the `spmak`, `spcrv`, `cscvn` and `rscvn` commands from Curve Fitting Toolbox™ to construct spline curves in the plane. This includes plotting tangents and computing the area enclosed by a curve.

### A Simple Spline Curve

Curve Fitting Toolbox can handle *vector-valued* splines. A  $d$ -vector-valued univariate spline provides a curve in  $d$ -space. In this mode,  $d = 2$  is most common, as it gives plane curves.

Here is an example, in which a spline with 2-dimensional coefficients is constructed and plotted.

```
knots = [1,1:9,9];  
curve = spmak( knots, repmat([ 0 0; 1 0; 1 1; 0 1 ], 2,1).' );  
  
t = linspace(2,8,121);  
values = fnval(curve,t);  
plot(values(1,:),values(2,:), 'LineWidth',2);  
axis([-0.4 1.4 -0.2 1.2]), axis equal  
title('A Spline Curve');  
hold on
```




**A Word of Caution**

You may have noticed that this example did not use `fnplt` to plot the curve, but instead plotted some points on the curve obtained by `fnval`. Here is the code again:

```
t = linspace(2,8,121);
values = fnval(curve,t);
plot(values(1,:),values(2,:), 'LineWidth',2)
```

Using `fnplt` directly with this particular spline curve gives the red curve in the figure below.

```
fnplt(curve,'r',.5);
title('The Full Spline Curve, in Red')
```



The explanation?

The spline is of order 4, yet the end knots in the knot sequence  
knots

knots =

```
1 1 2 3 4 5 6 7 8 9 9
```


only have multiplicity 2. Therefore, all the B-splines of order 4 for this knot sequence are 0 at the endpoints of the basic interval. This makes the curve start and stop at (0,0).



## A Remedy

Since, in this case, we are really interested only in the curve segment corresponding to the parameter interval [3 .. 7], we can use `fnbrk` to extract that part, and then have no difficulty plotting it, in yellow, with `fnplt`.

```
mycv = fnbrk(curve,[3 7]);
fnplt(mycv,'y',2.5);
title('The Spline Curve of Interest, in Yellow')
```



## The Area Enclosed By This Curve

Since you now have a spline, namely `mycv`, that describes the curve (and nothing else), you can easily compute the area enclosed by this closed curve, as follows.

```
area = diff(fnval(fnint( ...
    fncmb(fncmb(mycv,[0 1]),'*',fnder(fncmb(mycv,[1 0]))) ...
    ),fnbrk(mycv,'interval')))
```

```
area =
    -0.8333
```

With a little effort, you can recognize this as the value of the integral

$$\int y(t) \, d(x(t)) = \int y(t) \, Dx(t) \, dt$$

over the basic interval of the spline `mycv`, with  $(x(t), y(t)) := \text{fnval}(\text{mycv}, t)$  the point on the curve corresponding to the parameter value  $t$ . Here, `fncmb(mycv, [1, 0])`, `fncmb(mycv, [0, 1])` describe the two components of the spline curve, i.e., the scalar-valued splines  $x$  and  $y$ .

Also, the curve is roughly a circle with radius  $1/2$ . Hence, you would expect an area of, roughly,

```
disp(pi/4)
```


```
0.7854
```

But why is the computed area *negative*? Because the area enclosed by the curve lies to the left as one travels on the curve with increasing  $t$ . To verify this, we draw some tangent vectors.

### Add Some Tangent Vectors

We redraw the curve and also draw the tangent vector to the curve at some points.


```
hold off
fnplt(mycv, 'y', 2.5); hold on
t = 3:.4:6.2;
cv = fnval(curve, t);
cdv = fnval(fnder(curve), t);
quiver(cv(1,:), cv(2,:), cdv(1,:), cdv(2,:));
title('A Spline Curve With Some Tangents')
axis([-0.4 1.4 -0.2 1.2]), axis equal
```



### The Intersection of the Curve With a Straight Line

If you wanted to determine the points of intersection of this spline curve with the straight line  $y = x$ , the following code would give them to you, and plot the segment of that straight line inside the curve:

```
cuts = fnval(mycv, ...
    mean(fnzeros(fncmb(fncmb(mycv,[0,1]),'-'),fncmb(mycv,[1,0])))
);
plot(cuts(1,:), cuts(2,:), 'y', 'LineWidth',2.5)
hold off
title('A Spline Curve With Some Tangents and a Cut Across')
```



### SPCRV: The Control Polygon and the Corresponding Spline Curve


Spline curves are used extensively in the generation of illustrations in which nothing more than a smooth curve of a certain roughly imagined shape is required. For this, Curve Fitting Toolbox contains a special command, `spcrv`, which can be used independently of the rest of the toolbox.

Given a sequence of points in the plane and, optionally, an order  $k$ , `spcrv` generates, by repeated midpoint knot insertion, the spline curve of order  $k$  whose control polygon is specified by the given sequence.

The figure below shows such a control polygon, and the corresponding spline curve of order 3.

```
points = [0 0; 1 0; 1 1; 0 2; -1 1; -1 0; 0 -1; 0 -2].';
values = spcrv(points,3);
plot(points(1,:),points(2,:), 'k');
```

```
axis([-2 2.25 -2.1 2.2]);
hold on
plot(values(1,:),values(2,:), 'r', 'LineWidth', 1.5);
legend({'Control Polygon' 'Quadratic Spline Curve'}, 'location', 'SE');
```




Notice that the curve touches each segment of the control polygon at its midpoint, and follows the shape outlined by the control polygon.

### Raising the Order

Raising the order  $k$  will pull the curve away from the control polygon and make it smoother, but also shorter. Here, we have added the corresponding spline curve of order 4.


```
value4 = spcrv(points,4);
plot(value4(1,:),value4(2,:), 'b', 'LineWidth', 2);
legend({'Control Polygon' 'Quadratic Spline Curve' ...
       'Cubic Spline Curve'}, 'location', 'SE');
```



### CSCVN

On the other hand, to obtain an interpolating curve, you could use the `cscvn` command, which provides a parametric 'natural' cubic spline curve.

```
fnplt(cscvn(points), 'g', 1.5);  
legend({'Control Polygon' 'Quadratic Spline Curve' ...  
       'Cubic Spline Curve' 'Interpolating Spline Curve'}, ...  
       'location', 'SE');
```




By adding the point  $(.95, -.05)$  near the second control point,  $(1,0)$ , we can create an interpolating spline curve that turns faster there.

```

np = size(points, 2);
fnplt( cscvn([ points(:,1) [.95; -.05] points(:,2:np) ]), 'm',1.5);
plot(.95,-.05,'*');
legend({'Control Polygon' 'Quadratic Spline Curve' ...
        'Cubic Spline Curve' 'Interpolating Spline Curve' ...
        'Faster Turning Near (1,0)'}, ...
        'location','SE');
hold off

```



### RSCVN


You can also obtain a tangent-continuous curve composed of circular arcs that passes through a given sequence of points in the plane and, optionally, is orthogonal to given normal directions at the points. The command `rscvn` provides such a curve.

For example, the following generates a circle

```
c = rscvn([-1 1 -1;0 0 0],[1 1;0 0]);
```

as its plot shows.

```
fnplt(c);
axis([-1.05 1.05 -1.05 1.05]), axis equal, axis off
```



`c` is a quadratic rational spline consisting of just two pieces, as the following commands make clear.

```
[form, order, breaks] = fnbrk(c, 'f', 'o', 'b')
```

```
form =
```

```
    'rBform'
```

```
order =
```

```
    3
```

```
breaks =
```

```
    0    2    4
```

It is easy to generate striking patterns with this tool using just a few data points. For example, here is a version of the design on the Bronze Triskele Medallion in the Ulster Museum in Belfast, supposedly done by pieces of circular arcs a long time ago.

```
pp = [zeros(1,7); 5.4, 3, 6.9, 2.75, 2.5, .5, 5];  
alpha = 2*pi/3; ca = cos(alpha); sa = sin(alpha); c = [ca sa; -sa ca];  
d = [0 0 .05 -.05; 1 -1 .98 .98]; d = [d c*d];  
yin = rscvn([pp(:, [7,1:3]), c*pp(:,3:4), pp(:,3)], d(:, [1 2 1 4 7 5 1])));
```



```
fnplt(yin), hold on, fnplt(fncmb(yin,c)), fnplt(fncmb(yin,c'))  
yang = rscvn([pp(:,6),-pp(:,6),pp(:,5),c*pp(:,4)],[d(:, [2 1 1]),c(:,2)]);  
fnplt(yang), fnplt(fncmb(yang,c)), fnplt(fncmb(yang,c'))  
axis([-7.2 7.2 -7.2 7.2]), axis equal, axis off, hold off
```




## Constructing Spline Curves in 2D and 3D

This example shows how to use the `cscvn` command from Curve Fitting Toolbox™ to construct cubic spline curves in two and three dimensions.

### Selecting the Points

This example will show how to draw a smooth curve through a list of points, in the order in which they occur. First, we select some random points in the plane, and store them in a matrix, one point per *column*.


```
npts = 10;
xy = [randn(1,npts); randn(1,npts)];
plot(xy(1,:),xy(2,:), 'ro', 'LineWidth',2);
text(xy(1,:), xy(2,:),[repmat(' ',npts,1), num2str((1:npts)')])
ax = gca;
ax.XTick = [];
ax.YTick = [];
```



### Connecting the Points

Next, construct the curve using the `cscvn` command and plot it using `fnplt`.

```
hold on
fnplt(cscvn(xy), 'r',2)
hold off
```




You could also use the `getcurve` command if you wanted to input the list of points interactively.

### 3-D Spline Curves

It's just as easy to create spline curves in three dimensions. This time, we'll do something less random. First, we generate the points.


```
npts = 13;
t = linspace(0,8*pi,npts);
z = linspace(-1,1,npts);
omz = sqrt(1-z.^2);
xyz = [cos(t).*omz; sin(t).*omz; z];
plot3(xyz(1,:),xyz(2,:),xyz(3,:), 'ro', 'LineWidth',2);
text(xyz(1,:),xyz(2,:),xyz(3,:),[repmat(' ',npts,1), num2str((1:npts)')])
ax = gca;
ax.XTick = [];
ax.YTick = [];
ax.ZTick = [];
box on
```



### Connecting the Points

Here is the 3D spline curve through these points provided by `cscvn`. By appending the first point to the end of the list, we get a smooth *closed* curve.

```
hold on
fnplt(cscvn(xyz(:, [1:end 1])), 'r', 2)
hold off
```




## Smoothing a Histogram

This example shows how to use spline commands from Curve Fitting Toolbox™ to smooth a histogram.

Here is a histogram of some random values that might represent data that were collected on some measurement.

```
y = randn(1,5001);
hist(y);
```



We would like to derive from this histogram a smoother approximation to the underlying distribution. We do this by constructing a spline function  $f$  whose average value over each bar interval equals the height of that bar.

If  $h$  is the height of one of these bars, and its left and right edges are at  $L$  and  $R$ , then we want the spline  $f$  to satisfy

$$\text{integral} \{f(x) : L < x < R\} / (R - L) = h,$$

or, with  $F$  the indefinite integral of  $f$ , i.e.,  $DF = f$ ,


$$F(R) - F(L) = h \cdot (R - L).$$

```
[heights,centers] = hist(y);
hold on
```

```

ax = gca;
ax.XTickLabel = [];
n = length(centers);
w = centers(2)-centers(1);
t = linspace(centers(1)-w/2,centers(end)+w/2,n+1);
p = fix(n/2);
fill(t([p p p+1 p+1]),[0 heights([p p]),0], 'w')
plot(centers([p p]),[0 heights(p)], 'r:')
h = text(centers(p)-.2,heights(p)/2, ' h');
dep = -70;
tL = text(t(p),dep, 'L');
tR = text(t(p+1),dep, 'R');
hold off

```



So, with  $n$  the number of bars,  $t(i)$  the left edge of the  $i$ -th bar,  $dt(i)$  its width, and  $h(i)$  its height, we want

$$F(t(i+1)) - F(t(i)) = h(i) * dt(i), \text{ for } i = 1:n,$$

or, setting arbitrarily  $F(t(1)) = 0$ ,

$$F(t(i)) = \sum \{h(j)*dt(j) : j=1:i-1\}, \text{ for } i = 1:n+1.$$

```

dt = diff(t);
Fvals = cumsum([0,heights.*dt]);

```


Add to this the two end conditions  $DF(t(1)) = 0 = DF(t(n+1))$ , and we have all the data we need to get  $F$  as a complete cubic spline interpolant.

```
F = spline(t, [0, Fvals, 0]);
```

The two extra zero values in the second argument indicate the zero endslope conditions.

Finally, the derivative,  $f = DF$ , of the spline  $F$  is the smoothed version of the histogram.

```
DF = fnder(F); % computes its first derivative
h.String = 'h(i)';
tL.String = 't(i)';
tR.String = 't(i+1)';
hold on
fnplt(DF, 'r', 2)
hold off
ylims = ylim;
ylim([0,ylims(2)]);
```





## Bivariate Tensor Product Splines

This example shows how to use the spline commands in Curve Fitting Toolbox™ to fit tensor product splines to bivariate gridded data.

### Introduction

Since Curve Fitting Toolbox can handle splines with *vector* coefficients, it is easy to implement interpolation or approximation to gridded data by tensor product splines. Most spline construction commands in the toolbox take advantage of this.

However, you might be interested in seeing a detailed description of how approximation to gridded data by tensor products is actually done for bivariate data. This will also come in handy when you need some tensor product construction not provided by the commands in the toolbox.

### Example: Least-Squares Approximation to Gridded Data


Consider, for example, least-squares approximation to given data

$$z(i,j) = f(x(i),y(j)) \text{ for } i = 1:I, j = 1:J.$$

Here are some gridded data, taken from Franke's sample function. Note that the grid is somewhat denser near the boundary, to help pin down the approximation there.

```
x = sort([(0:10)/10,.03 .07, .93 .97]);
y = sort([(0:6)/6,.03 .07, .93 .97]);
[xx,yy] = ndgrid(x,y); % note: ndgrid rather than meshgrid
z = franke(xx,yy);

mesh(x,y,z,');
xlabel('x'); ylabel('y');
view(150,50);
title('Data from the Franke Function');
```



### A note about NDGRID vs. MESHGRID

Note that the statements

```
[xx,yy] = ndgrid(x,y);
```

```
z = franke(xx,yy);
```

used above make certain that  $z(i, j)$  is the value of the function being approximated at the grid point  $(x(i), y(j))$ .

However, the MATLAB® command `mesh(x,y,z)` expects  $z(j, i)$  (note the reversed order of  $i$  and  $j$ ) as the value at the grid point  $(x(i), y(j))$ . For that reason, the above plot was generated by the statement

```
mesh(x,y,z.');
```

i.e., using the transpose of the matrix  $z$ .

Such transposing would not have been necessary had we used `meshgrid` instead of `ndgrid`. But the resulting  $z$  would not have followed approximation theory standards.

### Choice of Spline Space in the Y-Direction

Next, we choose a spline order  $k_y$  and a knot sequence  $\text{knots}_y$  for the  $y$ -direction

```
ky = 3;
knotsy = augknt([0, .25, .5, .75, 1], ky);
```

and then obtain

```
sp = spap2(knotsy, ky, y, z);
```

a spline curve whose  $i$ -th component is an approximation to the curve  $(y, z(i, :))$  for  $i=1:I$ .


### Evaluation

In particular,

```
yy = -.1:.05:1.1;
vals = fnval(sp, yy);
```

creates the matrix `vals` whose  $(i, j)$ -th element can be taken as an approximation to the value  $f(x(i), yy(j))$  of the underlying function  $f$  at the grid point  $(x(i), yy(j))$ . This is evident when we plot `vals`.

```
mesh(x, yy, vals. ');
xlabel('x'); ylabel('y');
view(150, 50);
title('Simultaneous Approximation to All Curves in the Y-Direction');
```



Note that, for each  $x(i)$ , both the first two and the last two values are zero since both the first two and the last two sites in `yy` are outside the basic interval for the spline `sp`.

Also note the "ridges" that run along the y-direction, most noticeable near the peaks of the surface. They confirm that we are plotting smooth curves in one direction only.

### From Curves to a Surface; Choosing a Spline Space in the X-Direction

To get an actual surface, we now have to go one step further. Consider the coefficients `coefsy` of the spline `sp`, as obtained by

```
coefsy = fnbrk(sp, 'c');
```

Abstractly, you can think of the spline `sp` as the vector-valued function

$$y \mapsto \sum_r \text{coefsy}(:, r) B_{\{r, ky\}}(y)$$

$r$

with the  $i$ -th element, `coefsy(i, r)`, of the vector coefficient `coefsy(:, r)` corresponding to  $x(i)$  for  $i=1:I$ . This suggests approximating each curve  $(x, \text{coefsy}(:, r))$  by a spline, using the same order `kx` and the same appropriate knot sequence `knotsx` for every  $r$ .

```
kx = 4;
knotsx = augknt(0:.2:1, kx);
sp2 = spap2(knotsx, kx, x, coefsy.');
```

The use of the `spap2` command here needs, perhaps, an explanation.

Recall that `spap2(knots, k, x, fx)` treats `fx(:, j)` as the value at  $x(j)$ , i.e., takes each *column* of `fx` as a data value. Since we wanted to fit the value `coefsy(i, :)` at  $x(i)$ , for all  $i$ , we have to provide `spap2` with the *transpose* of `coefsy`.

Now consider the *transpose* of the coefficient matrix of the resulting spline "curve" `sp2`, obtained as

```
coefs = fnbrk(sp2, 'c').';
```

`coefs` provides the *bivariate* spline approximation

$$(x, y) \mapsto \sum_q \sum_r \text{coefs}(q, r) B_{\{q, kx\}}(x) B_{\{r, ky\}}(y)$$


$q \quad r$

to the original data

$$(x(i), y(j)) \mapsto f(x(i), y(j)) = z(i, j).$$

We use `spcol` to provide the values  $B_{\{q, kx\}}(xv(i))$  and  $B_{\{r, ky\}}(yv(j))$  needed to evaluate this spline surface at some grid points  $(xv(i), yv(j))$  and then plot the values.

```
xv = 0:.025:1; yv = 0:.025:1;
values = spcol(knotsx, kx, xv) * coefs * spcol(knotsy, ky, yv).';
mesh(xv, yv, values. ');
xlabel('x'); ylabel('y');
view(150, 50);
title('The Spline Approximant');
```



### Why Does This Evaluation Work?

The statement

```
values = spcol(knotsx,kx,xv) * coefs * spcol(knotsy,ky,yv).'
```

used above makes good sense since, for example, `spcol(knotsx,kx,xv)` is the matrix whose  $(i, q)$ -th entry equals the value  $B_{\{q,kx\}}(xv(i))$  at  $xv(i)$  of the  $q$ -th B-spline of order  $kx$  for the knot sequence `knotsx`, while we want to evaluate the expression

$$\sum_q \sum_r \text{coefs}(q,r) B_{\{q,kx\}}(x) B_{\{r,ky\}}(y)$$

at  $(x,y) = (xv(i),yv(j))$ .

### More Efficient Alternatives

Since the matrices `spcol(knotsx,kx,xv)` and `spcol(knotsy,ky,yv)` are banded, it may be more efficient for "large" `xv` and `yv` (though perhaps more memory-consuming) to make use of `fnval`.

```
value2 = fnval(spmak(knotsx,fnval(spmak(knotsy,coefs),yv).'
```

In fact, `fnval` and `spmak` can deal directly with multivariate splines, hence the above statement can be replaced by

```
value3 = fnval( spmak({knotsx,knotsy},coefs), {xv,yv} );
```

Better yet, the construction of the approximation can be done by *one* call to `spap2`, therefore we can obtain these values directly from the given data by the statement

```
value4 = fnval( spap2({knotsx,knotsy},[kx ky],[x,y],z), {xv,yv} );
```

### Check it Out

Here is a check, specifically, the *relative* difference between the values computed in these four different ways.

```
diffs = abs(values-value2) + abs(values-value3) + abs(values-value4);  
max(max(diffs)) / max(max(abs(values)))
```

```
ans = 1.1206e-15
```

The four methods return the same values, up to round-off error.

### Error of the Approximation

Here is a plot of the error, i.e., the difference between the given data value and the value of the spline approximation at those data sites.

```
errors = z - spcol(knotsx,kx,x)*coefs*spcol(knotsy,ky,y).';  
mesh(x,y,errors. ');  
xlabel('x'); ylabel('y');  
view(150,50);  
title('Error at the Given Data Sites');
```



The *relative* error is

```
max(max(abs(errors))) / max(max(abs(z)))
```

```
ans = 0.0539
```

This is perhaps not too impressive. On the other hand, the ratio

```
(degrees of freedom used) / (number of data points)
```

is only

```
numel(coefs)/numel(z)
```

```
ans = 0.2909
```

### Apparent Bias of This Approach

The approach followed here seems **biased**: We first think of the given data values  $z$  as describing a vector-valued function of  $y$ , and then we treat the matrix formed by the vector coefficients of the approximating curve as describing a vector-valued function of  $x$ .

What happens when we take things in the opposite order, i.e., think of  $z$  as describing a vector-valued function of  $x$ , and then treat the matrix made up from the vector coefficients of the approximating curve as describing a vector-valued function of  $y$ ?

Perhaps surprisingly, the final approximation is the same, up to roundoff. The next section contains the numerical experiment confirming that.

### Doing It the Other Way Around: Start With a Spline Space in X

First, we fit a spline curve to the data, but this time with  $x$  as the independent variable, hence it is the rows of  $z$  which now become the data values. Correspondingly, we must supply  $z.'$  (rather than  $z$ ) to `spap2`, and obtain


```
spb = spap2(knotsx,kx,x,z.');
```

a spline approximation to all the curves  $(x, z(:, j))$  for  $j=1:J$ . In particular,

```
valsb = fnval(spb,xv).';
```

creates a matrix whose  $(i, j)$ -th element can be taken as an approximation to the value  $f(xv(i), y(j))$  of the underlying function  $f$  at the grid point  $(xv(i), y(j))$ . This is evident when we plot `valsb`.

```
mesh(xv,y,valsb. ');
xlabel('x'); ylabel('y');
view(150,50);
title('Simultaneous Approximation to All Curves in the X-Direction');
```



Again note the ridges, this time running along the  $x$ -direction. They confirm that, once again, we are plotting smooth curves in one direction only.

### From Curves to a Surface: Using a Spline Space in the Y-Direction

Now comes the second step, to get the actual surface.



Let `coefsx` be the coefficients for `spb`, i.e.,

```
coefsx = fnbrk(spb, 'c');
```

Abstractly, you can think of the spline `spb` as the vector-valued function

$$x \mapsto \sum_r \text{coefsx}(r, :) B_{\{r, kx\}}(x)$$

with the  $j$ -th entry `coefsx(r, j)` of the vector coefficient `coefsx(r, :)` corresponding to  $y(j)$ , for all  $j$ . Thus, we now fit each curve  $(y, \text{coefsx}(r, :))$  by a spline, using the same order `ky` and the same appropriate knot sequence `knotsy` for each  $r$ .

```
spb2 = spap2(knotsy, ky, y, coefsx.');
```

In the construction of `spb2`, we again need to transpose the coefficient matrix from `spb`, since `spap2` takes the columns of its last input argument as the data values.

For this reason, there is now no need to transpose the coefficient matrix `coefsb` of the resulting "curve".

```
coefsb = fnbrk(spb2, 'c');
```

Claim: `coefsb` equals the earlier coefficient array `coefs`, up to round-off. For a proof of this, see the discussion of the tensor product construct in Curve Fitting Toolbox documentation. Here, we simply make the following check.

```
max(max(abs(coefs - coefsb)))
ans = 7.7716e-16
```

Thus, the *bivariate* spline approximation

$$(x, y) \mapsto \sum_q \sum_r \text{coefsb}(q, r) B_{\{q, kx\}}(x) B_{\{r, ky\}}(y)$$

to the original data

$$(x(i), y(j)) \mapsto f(x(i), y(j)) = z(i, j)$$

obtained coincides with the earlier one, which generated `coefs` rather than `coefsb`.

As observed earlier, you can carry out the entire construction we just went through (in two ways), using just two statements, one for the construction of the least-squares approximant, the other for its evaluation at a rectangular mesh.

```
tsp = spap2({knotsx, knotsy}, [kx, ky], {x, y}, z);
valuet = fnval(tsp, {xv, yv});
```

Here, as another check, is the relative difference between the values computed earlier and those computed now:

```
max(max(abs(values - valuet))) / max(max(abs(values)))
ans = 3.7353e-16
```

**Another Example: Interpolation**

Since the data come from a smooth function, we should be interpolating it, i.e., using `spapi` instead of `spap2`, or, equivalently, use `spap2` with the appropriate knot sequences. For illustration, here is the same process done with `spapi`.

To recall, the (univariate) data sites were

x

`x = 1×15`

0 0.0300 0.0700 0.1000 0.2000 0.3000 0.4000 0.5000 0.6000 0.7000

y

`y = 1×11`

0 0.0300 0.0700 0.1667 0.3333 0.5000 0.6667 0.8333 0.9300 0.9900

We use again quadratic splines in y, hence use knots midway between data sites.

```
knotsy = augknt( [0 1 (y(2:(end-2))+y(3:(end-1)))/2 ], ky);
spi = spapi(knotsy,y,z);
coefsy = fnbrk(spi,'c');
```

**Interpolation of Resulting Coefficients**

We use again cubic splines in x, and use the not-a-knot condition. We therefore use all but the second and the second-to-last data points as knots.

```
knotsx = augknt(x([1,3:(end-2),end]), kx);
spi2 = spapi(knotsx,x,coefsy.);
icoefs = fnbrk(spi2,'c').;
```


**Evaluation**

We are now ready to evaluate the interpolant

```
ivalues = spcol(knotsx,kx,xv)*icoefs*spcol(knotsy,ky,yv).;
```

and plot the interpolant at a fine mesh.

```
mesh(xv,yv,ivalues.);
xlabel('x'); ylabel('y');
view(150,50);
title('The Spline Interpolant');
```



Again, the steps above can be carried out using just two statements, one for the construction of the interpolant, the other for its evaluation at a rectangular mesh.

```
tsp = spapi({knotsx,knotsy},{x,y},z);
valuet = fnval(tsp,{xv,yv});
```


For a check, we also compute the relative difference between the values computed earlier and those computed now.

```
max(max(abs(ivalues-valuet))) / max(max(abs(ivalues)))
ans = 3.6712e-16
```

### Error of the Approximation

Next, we compute the error of the interpolant as an approximation to the Franke function.

```
fvalues = franke(repmat(xv.',1,length(yv)),repmat(yv,length(xv),1));
error = fvalues - ivalues;
mesh(xv,yv,error. ');
xlabel('x'); ylabel('y');
view(150,50);
title('Interpolation error');
```



The *relative* approximation error is

```
max(max(abs(error))) / max(max(abs(fvalues)))
```

```
ans = 0.0409
```

## Solving a Nonlinear ODE with a Boundary Layer by Collocation

This example shows how to use spline commands from Curve Fitting Toolbox™ solve a nonlinear ordinary differential equation (ODE).

### The Problem

We consider the nonlinear singularly perturbed problem

$$\epsilon D^2g(x) + (g(x))^2 = 1 \text{ on } [0..1]$$

$$Dg(0) = g(1) = 0.$$

This problem is already quite difficult for  $\epsilon = .001$ , so we choose a modest

$$\epsilon = .1;$$

### The Approximation Space

We seek an approximate solution by collocation from  $C^1$  piecewise cubics with a specified break sequence `breaks`, hence want the order `k` to be 4.

$$\text{breaks} = (0:4)/4;$$

$$k = 4;$$

We obtain the corresponding knot sequence as

$$\text{knots} = \text{augknt}(\text{breaks}, k, 2)$$

$$\text{knots} = 1 \times 14$$

0            0            0            0    0.2500    0.2500    0.5000    0.5000    0.7500    0.7500

Whatever the choice of order and knots, the corresponding spline space has dimension

$$n = \text{length}(\text{knots}) - k$$

$$n = 10$$

### Discretization

The number of degrees of freedom, 10, fits nicely with the fact that we expect to collocate at two sites per polynomial piece, for a total of 8 conditions, bringing us to 10 conditions altogether once we add the two side conditions.

We choose two Gauss sites for each interval. For the 'standard' interval  $[-1/2 .. 1/2]$  of unit length, these are the two sites

$$\text{gauss} = .5773502692 * [-1/2; 1/2];$$

From this, we obtain the whole collection of collocation sites by

$$\text{ninterv} = \text{length}(\text{breaks}) - 1;$$

$$\text{temp} = (\text{breaks}(2:\text{ninterv}+1) + \text{breaks}(1:\text{ninterv})) / 2;$$

$$\text{temp} = \text{temp}([1 \ 1], :) + \text{gauss} * \text{diff}(\text{breaks});$$

$$\text{colsites} = \text{temp}(:).';$$

**The Numerical Problem**

The numerical problem we want to solve is to find a piecewise polynomial (or *pp*)  $y$  of the given order, and with the given knots, that satisfies the nonlinear system

$$Dy(0) = 0$$

$$(y(x))^2 + \text{epsilon } D^2y(x) = 1 \text{ for } x \text{ in } \text{colsites}$$

$$y(1) = 0$$

**Linearization**

If  $y$  is our current approximation to the solution, then the linear problem for the better (?) solution  $z$  by Newton's method reads

$$Dz(0) = 0$$

$$w_0(x)z(x) + \text{epsilon } D^2z(x) = b(x) \text{ for } x \text{ in } \text{colsites}$$

$$z(1) = 0$$

$$\text{with } w_0(x) := 2y(x) \text{ and } b(x) := (y(x))^2 + 1.$$

In fact, by choosing  $w_0(1) := 1$ ,  $w_1(0) := 1$ , and

$$w_2(x) := \text{epsilon}, \quad w_1(x) := 0 \text{ for } x \text{ in } \text{colsites}$$

and choosing all other values of  $w_0$ ,  $w_1$ ,  $w_2$ , and  $b$  not yet specified to be zero, we can give our system the uniform shape

$$w_0(x)z(x) + w_1(x)Dz(x) + w_2(x)D^2z(x) = b(x) \text{ for } x \text{ in } \text{sites}$$

where

$$\text{sites} = [0, \text{colsites}, 1];$$

**Linear System to be Solved**

This system converts into one for the B-spline coefficients of its solution  $z$ . For this, we need the zeroth, first, and second derivative at every  $x$  in  $\text{sites}$  and for every relevant B-spline. These values are supplied by the `spcol` command.

Here is the essential part of the documentation for `spcol`:

SPCOL B-spline collocation matrix.

COLLOC = SPCOL(KNOTS,K,TAU) is the matrix

$$[ D^m(i)B_j(\text{TAU}(i)) : i=1:\text{length}(\text{TAU}), j=1:\text{length}(\text{KNOTS})-K ],$$

with  $D^m(i)B_j$  the  $m(i)$ -fold derivative of  $B_j$ ,

$B_j$  the  $j$ -th B-spline of order  $K$  for the knot sequence  $\text{KNOTS}$ ,

$\text{TAU}$  a sequence of sites,

both `KNOTS` and `TAU` are assumed to be nondecreasing, and `m(i)` is the integer  $\#\{ j < i : \text{TAU}(j) = \text{TAU}(i) \}$ , i.e., the 'cumulative' multiplicity of `TAU(i)` in `TAU`.

We use `spcol` to supply the matrix

```
colmat = spcol(knots,k, brk2knt(sites,3));
```

with `brk2knt` used here to triple each entry of `sites`, and thus we get in `colmat`, for each `x` in `sites`, the value and the first and second derivatives at `x` of all the relevant B-splines.

From this, we get the collocation matrix by combining the row triple associated with `x` using the weights  $w_0(x)$ ,  $w_1(x)$ ,  $w_2(x)$  to get the row corresponding to `x` of the matrix of our linear system.

### Need Initial Guess for Y

We also need a current approximation `y` from our spline space. Initially, we get it by interpolating some reasonable initial guess from our `pp` space at `sites`. For that guess, we use the parabola


$$x^2 - 1$$

which does satisfy the end conditions and lies in our spline space. We obtain its B-form by interpolation at `sites`. We select the relevant interpolation matrix from the full matrix `colmat`. Here it is, in several cautious steps:

```
intmat = colmat([2 1+(1:(n-2))*3,1+(n-1)*3],:);
coefs = intmat\[0 colsites.*colsites-1 0].';
y = spmak(knots,coefs.');
```

We plot the result, to be sure -- it should be exactly  $x^2 - 1$ .

```
fnplt(y,'g');
legend('Initial Guess (x^2-1)', 'location', 'NW');
axis([-0.01 1.01 -1.01 0.01]);
hold on
```



### Iteration

We can now complete the construction and solution of the linear system for the improved approximate solution  $z$  from our current guess  $y$ . In fact, with the initial guess  $y$  available, we now set up an iteration, to be terminated when the change  $z - y$  is less than a specified tolerance.

```
tolerance = 6.e-9;
```

The max-norms of the change  $z - y$  at each iteration are shown as output below, and the figure shows each of the iterates.

```
while 1
    vtau = fnval(y,colsites);
    weights = [0 1 0;
               [2*vtau.' zeros(n-2,1) repmat(epsilon,n-2,1)];
               1 0 0];
    colloc = zeros(n,n);
    for j = 1:n
        colloc(j,:) = weights(j,:)*colmat(3*(j-1)+(1:3),:);
    end
    coefs = colloc\[0 vtau.*vtau+1 0].';
    z = spmak(knots,coefs. ');
    fnplt(z,'k');
    maxdif = max(max(abs(z.coefs-y.coefs)));
    fprintf('maxdif = %g\n',maxdif)
    if (maxdif<tolerance), break, end
```




```

    % now reiterate
    y = z;
end

maxdif = 0.206695
maxdif = 0.01207
maxdif = 3.95151e-05
maxdif = 4.43216e-10

legend({'Initial Guess (x^2-1)' 'Iterates'}, 'location', 'NW');

```



That looks like quadratic convergence, as expected from a Newton iteration.

### Getting Ready for a Smaller Epsilon

If we now decrease `epsilon`, we create more of a boundary layer near the right endpoint, and this calls for a nonuniform mesh. We use `newknt` to construct an appropriate (finer) mesh from the current approximation.

```

knots = newknt(z, ninterv+1);
breaks = knt2brk(knots);
knots = augknt(breaks,4,2);
n = length(knots)-k;

```

### Collocation Sites for New Breaks

Next, we get the collocation sites corresponding to the new breaks

```

ninterv = length(breaks)-1;
temp = ((breaks(2:ninterv+1)+breaks(1:ninterv))/2);
temp = temp([1 1], :) + gauss*diff(breaks);
colsites = temp(:).';
sites = [0,colsites,1];

```

and then the new collocation matrix.

```
colmat = spcol(knots,k, brk2knt(sites,3));
```


### Initial Guess

We obtain the initial guess  $y$  as the interpolant from the current spline space to the computed solution  $z$ . We plot the resulting interpolant to be sure -- it should be close to our current solution.

```

intmat = colmat([2 1+(1:(n-2))*3,1+(n-1)*3],:);
y = spmak(knots,[0 fnval(z,colsites) 0]/intmat. ');
fnplt(y,'c');
ax = gca;
h = ax.Children;
legend(h([6 5 1]),{'Initial Guess (x^2-1)' 'Iterates'...
                  'New Initial Guess for New Value of epsilon'}, ...
      'location','NW');

```



### Iteration with Smaller Epsilon

Now we divide epsilon by 3 and repeat the above iteration. Convergence is again quadratic.

```


epsilon = epsilon/3;
while 1
    vtau = fnval(y,colsites);
    weights = [0 1 0;
               [2*vtau.' zeros(n-2,1) repmat(epsilon,n-2,1)];
               1 0 0];
    colloc = zeros(n,n);
    for j = 1:n
        colloc(j,:) = weights(j,:)*colmat(3*(j-1)+(1:3),:);
    end
    coefs = colloc\[0 vtau.*vtau+1 0].';
    z = spmak(knots,coefs. ');
    fnplt(z,'b');
    maxdif = max(max(abs(z.coefs-y.coefs)));
    fprintf('maxdif = %g\n',maxdif)
    if (maxdif<tolerance), break, end

    % now reiterate
    y = z;
end

maxdif = 0.237937
maxdif = 0.0184488
maxdif = 0.000120467
maxdif = 4.78116e-09

ax = gca;
h = ax.Children;
legend(h([10 9 5 4]), ...
       {'Initial Guess (x^2-1) for epsilon = .1' 'Iterates' ...
        sprintf('Initial Guess for epsilon = %.3f',epsilon) ...
        'Iterates'}, 'location','NW');

```



### Very Small Epsilon

For a much smaller epsilon, we merely repeat these calculations, dividing epsilon by 3 each time.

```
for ee = 1:4
    knots = newknt(z, ninterv+1);
    breaks = knt2brk(knots);
    knots = augknt(breaks,4,2);
    n = length(knots)-k;

    ninterv = length(breaks)-1;
    temp = ((breaks(2:ninterv+1)+breaks(1:ninterv))/2);
    temp = temp([1 1], :) + gauss*diff(breaks);
    colsites = temp(:).';
    sites = [0,colsites,1];

    colmat = spcol(knots,k, brk2knt(sites,3));

    intmat = colmat([2 1+(1:(n-2))*3,1+(n-1)*3],:);
    y = spmak(knots,[0 fnval(z,colsites) 0]/intmat. ');
    fnplt(y,'c')


    epsilon = epsilon/3;
    while 1
        vtau = fnval(y,colsites);
        weights = [0 1 0;
                  [2*vtau.' zeros(n-2,1) repmat(epsilon,n-2,1)];
                  1 0 0];
```

```

colloc = zeros(n,n);
for j = 1:n
    colloc(j,:) = weights(j,:)*colmat(3*(j-1)+(1:3),:);
end
coefs = colloc\[0 vtau.*vttau+1 0].';
z = spmak(knots,coefs. ');
fnplt(z,'b');
maxdif = max(max(abs(z.coefs-y.coefs)));
if (maxdif<tolerance), break, end

% now reiterate
y = z;
end
end
ax = gca;
h = ax.Children;
legend(h([30 29 25 24]), ...
    {'Initial Guess (x^2-1) for epsilon = .1' 'Iterates' ...
    'Initial Guesses for epsilon = .1/3^j, j=1:5' ...
    'Iterates'}, 'location', 'NW');

```



### Plot the Breaks Used for Smallest Epsilon

Here is the final distribution of breaks, showing newknt to have worked well in this case.

```


breaks = fnbrk(fn2fm(z,'pp'),'b');
bb = repmat(breaks,3,1);
cc = repmat([0;-1;NaN],1,length(breaks));

```

```

plot(bb(:),cc(:),'r');
hold off
ax = gca;
h = ax.Children;
legend(h([31 30 26 25 1]), ...
      {'Initial Guess (x^2-1) for epsilon = .1' 'Iterates' ...
       'Initial Guesses for epsilon = .1/3^j, j=1:5' ...
       'Iterates' 'Breaks for epsilon = .1/3^5'}, 'location','NW');

```



### Plot Residual for Smallest Epsilon

Recall that we are solving the ODE


$$\epsilon D^2g(x) + (g(x))^2 = 1 \text{ on } [0..1]$$

As a check, we compute and plot the residual for the computed solution for the smallest epsilon. This, too, looks satisfactory.

```

xx = linspace(0,1,201);
plot(xx, 1 - epsilon*fnder(z,2),xx) - (fnder(z,xx)).^2);
title('Residual for the Computed Solution for Smallest epsilon');

```



## Construct Chebyshev Spline

This example shows how to use commands from Curve Fitting Toolbox™ to construct a Chebyshev spline.

### Chebyshev (a.k.a. Equioscillating) Spline Defined

By definition, for given knot sequence  $t$  of length  $n+k$ ,  $C = C_{\{t, k\}}$  is the unique element of  $S_{\{t, k\}}$  of max-norm 1 that maximally oscillates on the interval  $[t_k \dots t_{n+1}]$  and is positive near  $t_{n+1}$ . This means that there is a unique strictly increasing  $\tau$  of length  $n$  so that the function  $C$  in  $S_{\{k, t\}}$  given by

$$C(\tau(i)) = (-1)^{n-i},$$

for all  $i$ , has max-norm 1 on  $[t_k \dots t_{n+1}]$ . This implies that

$$\tau(1) = t_k,$$

$$\tau(n) = t_{n+1},$$

and that

$$t_i < \tau(i) < t_{k+i},$$


for all  $i$ . In fact,

$$t_{i+1} \leq \tau(i) \leq t_{i+k-1},$$

for all  $i$ . This brings up the point that the knot sequence  $t$  is assumed to make such an inequality possible, which turns out to be equivalent to having all the elements of  $S_{\{k, t\}}$  continuous.


```
t = augknt([0 1 1.1 3 5 5.5 7 7.1 7.2 8], 4 );
[tau,C] = chbpnt(t,4);
xx = sort([linspace(0,8,201),tau]);
plot(xx,fval(C,xx),'LineWidth',2);
hold on
breaks = knt2brk(t);
bbb = repmat(breaks,3,1);
sss = repmat([1;-1;NaN],1,length(breaks));
plot(bbb(:), sss(:),'r');
hold off
ylim([-2 2]);
title('The Chebyshev Spline for a Particular Knot Sequence');
legend({'Chebyshev Spline' 'Knots'});
```





In short, the Chebyshev spline  $C$  looks just like the Chebyshev polynomial. It performs similar functions. For example, its extrema  $\tau$  are particularly good sites to interpolate at from  $S_{\{k, \tau\}}$  since the norm of the resulting projector is about as small as can be.

```
hold on
plot(tau,zeros(size(tau)),'k+');
hold off
legend({'Chebyshev Spline' 'Knots' 'Extrema'});
```



### Choice of Spline Space

In this example, we try to construct  $C$  for a given spline space.

We deal with cubic splines with simple interior knots, specified by

```
k = 4;
breaks = [0 1 1.1 3 5 5.5 7 7.1 7.2 8];
t = augknt(breaks, k)
```

```
t = 1×16
```

```
0 0 0 0 1.0000 1.1000 3.0000 5.0000 5.5000 7.0000
```

thus getting a spline space of dimension

```
n = length(t) - k
```

```
n = 12
```

**Initial Guess**

As our initial guess for the  $\tau$ , we use the knot averages

$$\tau(i) = (t_{\{i+1\}} + \dots + t_{\{i+k-1\}})/(k-1)$$


recommended as good interpolation site choices, and plot the resulting first approximation to  $C$ .

```
tau = aveknt(t,k)
```

```
tau = 1×12
```

```
    0    0.3333    0.7000    1.7000    3.0333    4.5000    5.8333    6.5333    7.1000    7.4
```

```
b = (-ones(1,n)).^(n-1:-1:0);
c = spapi(t,tau,b);
plot(breaks([1 end]),[1 1], 'k', breaks([1 end]),[-1 -1], 'k');
hold on
fnplt(c, 'r', 1);
hold off
ylim([-2 2]);
title('First Approximation to an Equioscillating Spline');
```



### Iteration

For the complete leveling, use the Remez algorithm. This means that we construct a new `tau` as the extrema of our current approximation, `c`, to `C` and try again.

To find the extrema, first calculate the derivative `Dc` of the current approximation `c`.

```
Dc = fnder(c);
```

Take the zeros of `Dc` using the `fnzeros` function. The zeros represent the extrema of the current approximation `c`. The result is the new guess for `tau`.

```
tau(2:n-1) = mean(fnzeros(Dc))
```

```
tau = 1x12
```


```
0 0.2765 0.9057 1.7438 3.0779 4.5531 5.5830 6.5841 7.0809 7.3
```

```
plot(breaks([1 end]),[1 1], 'k', breaks([1 end]),[-1 -1], 'k');
hold on
```

```

fnplt(c,'r',1);
plot(tau(2:n-1),zeros(1,n-2),'x');
hold off
title('First Approximation to an Equioscillating Spline');
ax = gca;
h = ax.Children;
legend(h([2 1]),{'Approximation','Extrema'});
axis([0 8 -2 2]);

```



### End of First Iteration Step

We compute the resulting new approximation to the Chebyshev spline using the new guess for  $\tau$ .

```
cnew = spapi(t,tau,b);
```

The new approximation is more nearly an equioscillating spline.

```


plot(breaks([1 end]),[1 1],'k', breaks([1 end]),[-1 -1],'k');
hold on
fnplt(c,'r',1);
fnplt(cnew,'k',1);

```

```

hold off
ax = gca;
h = ax.Children;
legend(h([2 1]),{'First Approximation' 'Updated Approximation'});
axis([0 8 -2 2]);

```



If this is not close enough, simply try again, starting from this new  $\tau$ . For this particular example, the next iteration already provides the Chebyshev spline to graphic accuracy.

### Use of Chebyshev-Demko Points

The Chebyshev spline for a given spline space  $S_{\{k, \tau\}}$ , along with its extrema, are available as optional outputs from the `chbpnt` command in the toolbox. These extrema were proposed as good interpolation sites by Steven Demko, hence are now called the Chebyshev-Demko sites. This section shows an example of their use.

If you have decided to approximate the square-root function on the interval  $[0 \dots 1]$  by cubic splines with knot sequence


```
k = 4;  
n = 10;  
t = augknt(((0:n)/n).^8,k);
```

then a good approximation to the square-root function from that specific spline space is given by

```
tau = chbpnt(t,k);  
sp = spapi(t,tau,sqrt(tau));
```

as is evidenced by the near equioscillation of the error.

```
xx = linspace(0,1,301);  
plot(xx, fval(sp,xx)-sqrt(xx));  
title({'Error in Interpolant to Square Root', 'at Chebyshev-Demko Sites.'});
```



## Export Fit from Curve Fitter App to Simulink Lookup Table

This example shows how to create a surface fit using the Curve Fitter app, and then export the fit to a Simulink® 2-D Lookup Table (Simulink). You can follow the same workflow to export a curve fit to a 1-D Lookup Table (Simulink).

### Create Surface Fit in Curve Fitter App

Load the BatteryDataFitter data set.

```
load BatteryDataFitter
```


The table batteryMeasurementData in the data set contains three battery measurement variables: Temperature, SOC (State of Charge), and Resistance.

Open the Curve Fitter app.

```
curveFitter
```


Alternatively, on the **Apps** tab click the **Show more** arrow to display the apps gallery. In the **Math, Statistics and Optimization** group, click **Curve Fitter**.

In the Curve Fitter app, select the data variables for the fit. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. In the Select Fitting Data dialog box, select the table name batteryMeasurementData for each data variable. Then, select Temperature as the **X data** value, SOC as the **Y data** value, and Resistance as the **Z data** value.




The Curve Fitter app plots the data points as you select variables. By default, the app creates an interpolant surface fit that passes through the data points. To obtain a smoother fit, in the **Fit Options** pane, select **Cubic spline** for **Interpolation method**. For more information about interpolation methods, see “About Interpolation Methods” on page 6-3.






The app creates an interpolant fit with cubic spline interpolation and no extrapolation. The data has two outliers at the maximum and minimum values of Resistance. To remove the outliers, click **Exclude outliers** on the axes toolbar, and then click each outlier in the fit plot.




The interpolant surface fit plot now excludes the two outliers.




By default, the app does not extrapolate outside of the fitting data's convex hull for the cubic spline interpolation method. To estimate Resistance outside of the convex hull using nearest neighbor extrapolation, select Nearest neighbor for **Extrapolation method** in the **Fit Options** pane. For more information about extrapolation methods, see "Extrapolation for Interpolant Fit Types" on page 6-8.

The extrapolated Resistance values appear as steps that surround the fitting data domain.




### Export Fit to Simulink Lookup Table

In the Curve Fitter app, in the **Export** section, click **Export** and select **Create Simulink Lookup Table**.




Use the Create Simulink Lookup Table dialog box to specify the **Breakpoints 1** and **Breakpoints 2** values for the Temperature and SOC variables, respectively. You can specify the breakpoints as a set of explicit or even-spaced values.

The `Explicit values` option allows you to specify the breakpoints by using any expression that returns a vector. For example, you can use the colon operator (as shown in the following figure), a comma-separated list (for example, 240, 255.6, 271.2, 286.8, 302.4), or a function (for example, `exp(1:10)`). The **Lookup table preview** section shows a preview of the Simulink lookup table with a heat map corresponding to the table values.



The `Even spacing` option allows you to specify a set of evenly spaced breakpoints. For each breakpoint set, specify the first point, spacing, and number of points.




In this case, accept the default options and click **Export Table to Simulink** to export the fit and extrapolated values to a Simulink lookup table.


### Simulink Model with Lookup Table

The app opens a new Simulink model containing a 2-D lookup table block. The name of the block is `surfaceblock` (or `curveblock` if you create it from a curve fit). The model also has two constant inputs (or one input for a curve fit) and a display output.


Lookup table block created using Curve Fitter. Use Model Explorer to view the block parameters (stored in model workspace).



Note that the extrapolation method for the block is different from the extrapolation method used during surface fitting. By default, Extrapolation method is set to **Clip**. You can edit Extrapolation method and other methods by double-clicking the lookup table block and displaying the **Algorithm** tab in the **Block Parameters** dialog box.




To view and edit the breakpoints, click **Edit table and breakpoints** on the **Table and Breakpoints** tab of the **Block Parameters** dialog box. For an example of how to edit the breakpoints, see “Enter Breakpoints and Table Data” (Simulink).



### Use Lookup Table in Another Simulink Model

You can use the lookup table created by the Curve Fitter app in another Simulink model. Copy the `surfaceblock` block and paste it into a new or existing model. You must also copy and paste `surfaceBlockParameters` from the model workspace of the current model to the other model's workspace. `surfaceBlockParameters` is a `Simulink.LookupTable` (Simulink) object. To find the `surfaceBlockParameters` object, on the **Modeling** tab, in the **Design** section, click the arrow to display the gallery and select **Model Workspace** under **Repositories**. In the model workspace, you can also configure the code generation settings.



## See Also

### Apps

Curve Fitter

### Blocks

2-D Lookup Table | 1-D Lookup Table

### Objects

Simulink.LookupTable

## Related Examples

- “Interactive Curve and Surface Fitting” on page 2-2
- “Interpolation with Curve Fitting Toolbox” on page 6-3
- “Anatomy of a Lookup Table” (Simulink)
- “Edit Lookup Table Data with Lookup Table Spreadsheet” (Simulink)
- “Characteristics of Lookup Table Data” (Simulink)



## Fit Polynomial Model to Data

This example shows how to fit a polynomial model to data using the linear least-squares method.

Load the `patients` data set.

```
load patients
```

The variables `Diastolic` and `Systolic` contain data for diastolic and systolic blood pressure measurements, respectively. Fit a third-degree polynomial to the data with `Diastolic` as the predictor variable and `Systolic` as the response.

```
polymodel = fit(Diastolic,Systolic,"poly3")
```

```
polymodel =  
Linear model Poly3:  
polymodel(x) = p1*x^3 + p2*x^2 + p3*x + p4  
Coefficients (with 95% confidence bounds):  
p1 =   -0.001061  (-0.003673, 0.001551)  
p2 =    0.2844   (-0.3701, 0.9389)  
p3 =   -24.72   (-79.2, 29.76)  
p4 =    821.1   (-685.5, 2328)
```


`polymodel` contains the results of the fit. Display the least-squares method used to estimate the coefficients by using the function `fitoptions`.

```
opts = fitoptions(polymodel);  
opts.Method
```

```
ans =  
'LinearLeastSquares'
```

The output shows that `polymodel` is fit to the data with the linear least-squares method. Evaluate `polymodel` at the values in `Diastolic`, and display the result together with a scatter plot of the blood pressure data.

```
plot(polymodel,Diastolic,Systolic)
```



The plot shows that `polymodel` follows the bulk of the data.

## See Also

**Functions**  
`fit` | `plot`

## More About

- “Introduction to Least-Squares Fitting” on page 4-87

## Improve Model Fit with Weights

This example shows how to fit a polynomial model to data using both the linear least-squares method and the weighted least-squares method for comparison.

Generate sample data from different normal distributions by using the `randn` function.

```
rng("default") % For reproducibility

rnorm = [];
idx = [];

for k=1:20
    r = k*randn([20,1]) + (1/20)*(k^3);
    rnorm = [rnorm;r];
    idx = [idx;ones(20,1).*k];
end
```

The dependent variable `rnorm` contains sample data from 20 normal distributions. The independent variable `idx` contains integers indicating whether two elements in `rnorm` are sampled from the same normal distribution.

Fit a third-degree polynomial model to `idx` and `rnorm`. Return information about the coefficient estimates and the algorithm used to fit the model.

```
[p3fit,~,fitinfo] = fit(idx,rnorm,"poly3")


p3fit =
    Linear model Poly3:
    p3fit(x) = p1*x^3 + p2*x^2 + p3*x + p4
    Coefficients (with 95% confidence bounds):
    p1 =    0.05156    (0.0438, 0.05932)
    p2 =   -0.03993   (-0.2875, 0.2076)
    p3 =    0.1418   (-2.124, 2.408)
    p4 =    0.0462   (-5.585, 5.678)

fitinfo = struct with fields:
    numobs: 400
    numparam: 4
    residuals: [400x1 double]
    Jacobian: [400x4 double]
    exitflag: 1
    algorithm: 'QR factorization and solve'
    iterations: 1
```

`p3fit` contains the estimates for the model coefficients with 95% confidence intervals. The default fitting method for fitting a polynomial model is linear least squares. `fitinfo` contains information about the fitting algorithm used to fit the coefficients to the data. The error in the data can be estimated by the residuals stored in `fitinfo`.

Plot the residuals using a stem plot.

```
stem(idx,fitinfo.residuals)
xlabel("idx")
ylabel("residuals")
```



The plot of the residuals shows that their variance increases as the values in `idx` increase. The nonconstant variances across the different values of `idx` indicate that the weighted least-squares fitting method is more appropriate for calculating the model coefficients.

Create a vector of zeros for later storage of the weights.

```
W = zeros(length(rnorm),1);
```

The weights you supply transform the residual variances so that they are constant for different values of `idx`. Define the weight for each element in `rnorm` as the reciprocal of the residual variance for the corresponding value in `idx`. Then fit the model with the weights.

```
for k=1:20
    rnorm_idx = rnorm(idx==k);
    recipvar = 1/var(rnorm_idx);
    w = (idx==k).*recipvar;
    W = W+w;
end
[wp3fit,~,wfitinfo] = fit(idx,rnorm,"poly3","Weights",W)
```


```
wp3fit =
Linear model Poly3:
wp3fit(x) = p1*x^3 + p2*x^2 + p3*x + p4
Coefficients (with 95% confidence bounds):
p1 =    0.04894    (0.04419, 0.0537)
p2 =    0.03601   (-0.08744, 0.1595)
p3 =   -0.4262   (-1.253, 0.4009)
p4 =    0.9836   (-0.1959, 2.163)
```

```
wfitinfo = struct with fields:
    numobs: 400
    numparam: 4
    residuals: [400x1 double]
    Jacobian: [400x4 double]
    exitflag: 1
    algorithm: 'QR factorization and solve'
    iterations: 1
```

`wp3fit` and `wfitinfo` contain the results of the weighted least-squares fitting.

Display `p3fit`, `wp3fit`, and `rnorm` in the same plot.


```
plot(p3fit,idx,rnorm)
hold on
plot(wp3fit,"g")
xlabel("idx")
ylabel("rnorm")
legend(["rnorm","linear least-squares fit","weighted least-squares fit"])
hold off
```



The plot shows `wp3fit` closely tracking `p3fit`.

You can determine whether `wp3fit` is a better fit than `p3fit` by plotting the residuals.

```
stem(idx,wfitinfo.residuals)
xlabel("idx")
ylabel("residuals")
```



The output shows that the `wp3fit` residuals are smaller than the `p3fit` residuals. The variances of the `wp3fit` residuals are also more similar for different values of `idx` than the variances of the `p3fit` residuals.

## See Also

### Functions

`fit` | `stem`

## More About

- “Introduction to Least-Squares Fitting” on page 4-87

## Compare Robust Fitting Methods

This example shows how to fit a polynomial model to data using the bisquare weights, least absolute residuals (LAR), and linear least-squares methods.

Create a vector of noisy data by using the function `randn`.

```
rng("default") % Set the seed for reproducibility
noise = randn([200,1]);
```

Create a vector of evenly spaced points between 0 and  $2\pi$  by using the `linspace` function. Create a vector of sample data by adding the noisy data to one sine wave cycle.


```
theta = linspace(0,2*pi,200)';
data = sin(theta) + noise;
```

Add outliers to the data by replacing every tenth value of data with a random value from the normal distribution. Specify a mean of 5 and standard deviation of 1 for the random values.

```
for i=10:10:200
    data(i) = randn+5;
end
```


Display a box plot of the sample data.

```
boxchart(data)
```



Place your cursor on the box plot to display the box plot statistics.






The figure indicates that the outliers are data points with values greater than 4.288.

Fit four third-degree polynomial models to the data by using the function `fit` with different fitting methods. Use the two robust least-squares fitting methods: bisquare weights method to calculate the coefficients of the first model, and the LAR method to calculate the coefficients of the third model. Use the linear least-squares method to calculate the coefficients of the second and fourth models. To remove the outliers from the data in the fitting of the fourth model, exclude data points greater than 4.288.

```
bisquarepolyfit = fit(theta,data,"poly3",'Robust',"Bisquare");
linearpolyfit = fit(theta,data,"poly3");
larpolyfit = fit(theta,data,"poly3",Robust="LAR");
excludeoutlierspolyfit = fit(theta,data,"poly3",...
    Exclude=data>4.288);
```

Compare the bisquare weights and linear least-squares fits by plotting them in the same plot with the data.


```
plot(bisquarepolyfit,theta,data)
hold on
plot(linearpolyfit,"g")
legend("data","bisquare weights fit","linear least-squares fit")
xlabel("theta")
ylabel("data")
hold off
```



As shown in the plot, the curve of the linear-least squares fit is higher and closer to the outliers than the curve of the bisquare weights fit. The curve of the bisquare weights fit is more central to the bulk of the data. The relative positions of the curves indicate that the outliers have a larger effect on the linear least-squares fit.

Compare the bisquare weights and LAR fits.


```
plot(bisquarepolyfit,theta,data)
hold on
plot(larpolyfit,"g")
legend("data","bisquare weights fit","LAR fit")
xlabel("theta")
ylabel("data")
hold off
```



The curve of the LAR fit follows the curve of the bisquare weights fit closely, and is not as influenced by the outliers compared to the linear least-squares fit. You can zoom in to the plot to see that the curve of the LAR fit is slightly higher than the curve of the bisquare weights fit for most values of theta.

Compare the bisquare weights fit to the linear-least squares fit without outliers.

```
plot(bisquarepolyfit,theta,data)
hold on
plot(excludeoutlierspolyfit,"g")
legend("data","bisquare weights fit","linear least-squares fit (without outliers)")
xlabel("theta")
ylabel("data")
hold off
```



The linear-least squares fit does not appear to be greatly influenced by the outliers. However, the fit is not as central to the bulk of the data compared to the bisquare weights fit. Together, the plots indicate that, out of the four models, the model fit with the bisquare weights method is the most central to the bulk of the data.

## See Also

### Functions

`fit` | `boxchart`

## More About

- “Introduction to Least-Squares Fitting” on page 4-87

## Fit Exponential Model to Data

This example shows how to fit an exponential model to data using the trust-region and Levenberg-Marquardt nonlinear least-squares algorithms.


Load the census data set.

```
load census
```

The variables `pop` and `cdate` contain data for the population size and the year the census was taken, respectively.

Display a scatter plot of the data.

```
scatter(cdate,pop)  
xlabel("Year")  
ylabel("Population")
```



The plot shows that the population increases from year to year in a shape that resembles an exponential function.


Fit a two-term exponential model to the population data using the default trust-region fitting algorithm. Return the results of the fit and the goodness-of-fit statistics.

```
[exp_tr,gof_tr] = fit(cdate,pop,"exp2")  
  
exp_tr =  
  General model Exp2:  
  exp_tr(x) = a*exp(b*x) + c*exp(d*x)  
  Coefficients (with 95% confidence bounds):  
    a = 7.169e-17  
    b = 0.02155  
    c = 0  
    d = 0.02155  
  
gof_tr = struct with fields:  
    sse: 1.2412e+04  
    rsquare: 0.8995  
    dfe: 17  
    adjrsquare: 0.8818  
    rmse: 27.0209
```

`exp_tr` contains the results of the fit, including coefficients calculated with the trust-region fitting algorithm. The goodness-of-fit statistics stored in `gof_tr` include the root mean squared error (RMSE) of 27.0209.

Plot the model in `exp_tr` together with a scatter plot of the data.

```
plot(exp_tr,cdate,pop)  
legend(["data","predicted value"])  
xlabel("Year")  
ylabel("Population")
```



The plot shows that the model in `exp_tr` does not closely follow the census data.

Improve the fit by using the Levenberg-Marquardt fitting algorithm to calculate the coefficients.

```
[exp_lm, gof_lm] = fit(cdate, pop, "exp2", Algorithm="Levenberg-Marquardt")
```


```
exp_lm =
  General model Exp2:
  exp_lm(x) = a*exp(b*x) + c*exp(d*x)
  Coefficients (with 95% confidence bounds):
    a =  4.282e-17  (-1.125e-11, 1.126e-11)
    b =   0.02477  (-5.67, 5.719)
    c = -3.933e-17  (-1.126e-11, 1.126e-11)
    d =   0.02481  (-5.696, 5.745)
```

```
gof_lm = struct with fields:
  sse: 475.9498
  rsquare: 0.9961
  dfe: 17
  adjrsquare: 0.9955
  rmse: 5.2912
```

`exp_lm` contains the results of the fit, including coefficients calculated with the Levenberg-Marquardt fitting algorithm. The goodness-of-fit statistics stored in `gof_lm` include the RMSE of 5.2912, which is smaller than the RMSE for `exp_tr`. The relative sizes of the RMSEs indicate that the model stored in `exp_lm` fits the data more accurately than the model stored in `exp_tr`.

Plot the model in `exp_lm` together with a scatter plot of the data.

```
plot(exp_lm, cdate, pop)
legend(["data", "predicted value"])
xlabel("Year")
ylabel("Population")
```



The plot shows that the model in `exp_lm` follows the census data more closely than the model in `exp_tr`.

## See Also

**Functions**  
fit | plot



## **More About**

- “Introduction to Least-Squares Fitting” on page 4-87



# Functions

---

# Curve Fitter

Fit curves and surfaces to data

## Description

The Curve Fitter app provides a flexible interface where you can interactively fit curves and surfaces to data and view plots.

With the Curve Fitter app, you can:

- Create, plot, and compare multiple fits.
- Use linear or nonlinear regression, interpolation, smoothing, and custom equations.
- View goodness-of-fit statistics, display confidence intervals and residuals, remove outliers, and assess fits with validation data.
- Automatically generate code to fit and plot curves and surfaces, or export fits to the workspace for further analysis.
- Export a curve or surface fit to a Simulink lookup table. For an example, see “Export Fit from Curve Fitter App to Simulink Lookup Table” on page 12-164.

The screenshot displays the Curve Fitter app interface. The top toolbar includes options for File (New, Open, Save, Duplicate), Data (Select Data), Fit Type (Polynomial, Exponential), Fit (Update Fit: Auto, Manual), Visualization (Fit Plot, Residuals Plot, Contour Plot, Prediction Bounds), and Export. The main workspace shows a 'Fit Plot' with 'pop' vs 'cdate' data points and a blue 'poly2' fit curve. Below it is a 'Residuals Plot' showing 'poly2 - residuals'. The right-hand 'Fit Options' panel is set to 'Exponential' with the equation  $a \cdot \exp(b \cdot x) + c \cdot \exp(d \cdot x)$  and 2 terms. The 'Results' panel shows the fit name 'poly2' and the equation  $f(x) = a \cdot \exp(b \cdot x) + c \cdot \exp(d \cdot x)$ . Below the results is a 'Table of Fits' table.

| Fit State | Fit name | Data      | Fit type | R-square | SSE   | DFE | Adj R-sq | RMS   |
|-----------|----------|-----------|----------|----------|-------|-----|----------|-------|
| ✓         | poly2    | pop vs... | exp2     | 0.89955  | 12412 | 17  | 0.88182  | 27.02 |

## Open the Curve Fitter App

- MATLAB Toolstrip: On the **Apps** tab, under **Math, Statistics and Optimization**, click the app icon.
- MATLAB command prompt: Enter `curveFitter`.

## Examples

- “Interactive Curve and Surface Fitting” on page 2-2
- “Data Selection” on page 2-11
- “Compare Fits in Curve Fitter App” on page 2-19
- “Generate Code and Export Fits to the Workspace” on page 7-13
- “Export Fit from Curve Fitter App to Simulink Lookup Table” on page 12-164

## Programmatic Use

`curveFitter` opens the Curve Fitter app or brings focus to the app if it is already open.

`curveFitter(x,y)` opens the Curve Fitter app and creates a curve fit to the data in  $x$  and  $y$ . The  $x$  and  $y$  arguments must be numeric, have two or more elements, and have the same number of elements.

`curveFitter(x,y,z)` opens the Curve Fitter app and creates a surface fit to the data in  $x$ ,  $y$ , and  $z$ . The  $x$ ,  $y$ , and  $z$  arguments must be numeric, have two or more elements, and have compatible sizes. The sizes are compatible if either of the following statements is true.

- $x$ ,  $y$ , and  $z$  are arrays with the same number of elements.
- $x$  and  $y$  are vectors of length  $n$  and  $m$ , respectively, and  $z$  is an  $m$ -by- $n$  matrix.

`curveFitter(x,y,[],w)` opens the Curve Fitter app and creates a curve fit with weights  $w$ . The weights  $w$  must be a numeric array and have the same number of elements as  $x$  and  $y$ .

`curveFitter(x,y,z,w)` opens the Curve Fitter app and creates a surface fit with weights  $w$ . The weights  $w$  must be a numeric array and have the same number of elements as  $z$ .

`curveFitter(filename)` loads the Curve Fitter session in `filename` into the Curve Fitter app. `filename` must have the extension `.sfit`.

## Tips

- When selecting data for fitting curves or surfaces in Curve Fitter, you can specify to use table variables. On the **Curve Fitter** tab, in the **Data** section, click **Select Data**. The app opens a dialog box. For each data variable (**X data**, **Y data**, **Z data**, or **Weights**), first select the table name and then select the name of the column variable that you want to use.

You can also specify validation data using table variables. Click **Validation Data** in the **Data** section of the **Curve Fitter** tab to open the Select Validation Data dialog box.

To programmatically open the Curve Fitter app and create a curve fit to  $x$  and  $y$ , where  $x$  and  $y$  are variables in table `tbl`, enter `curveFitter(tbl.x, tbl.y)` at the MATLAB command line. Similarly, enter `curveFitter(tbl.x, tbl.y, tbl.z)` to create a surface fit in the Curve Fitter app for the table variables  $x$ ,  $y$ , and  $z$ .

## Version History

Introduced before R2006a

### **R2022a: The Curve Fitter app replaces the Curve Fitting app and provides similar functionality with an improved layout**

*Behavior changed in R2022a*

The Curve Fitting app has been renamed to Curve Fitter. The Curve Fitter app supports the same workflows as the previous Curve Fitting app, with some minor changes and an improved layout. For example, Curve Fitter allows you to generate MATLAB code for a selected fit, while the previous Curve Fitting app allowed you to generate MATLAB code for multiple fits at a time.

The layout of the Curve Fitter app differs from the previous Curve Fitting app. Curve Fitter has a toolstrip at the top that shows the curve and surface fitting workflow, and the app includes these panes that display fit information:

- **Fits** pane that displays plots
- **Fit Options** pane that displays editable options for the current fit
- **Results** pane that describes the current fit
- **Table Of Fits** pane that displays all the fits

If you enter `cftool` at the MATLAB command line, the software opens the Curve Fitter app. You can still open saved Curve Fitting app sessions (pre-R2022a) in Curve Fitter. For the recommended way to open the Curve Fitter app, see “Open the Curve Fitter App” on page 13-0 .

## See Also

### Functions

`fit`

### Topics

“Interactive Curve and Surface Fitting” on page 2-2

“Data Selection” on page 2-11

“Compare Fits in Curve Fitter App” on page 2-19

“Generate Code and Export Fits to the Workspace” on page 7-13

“Export Fit from Curve Fitter App to Simulink Lookup Table” on page 12-164

## aptknt

Acceptable knot sequence

### Syntax

```
knots = aptknt(tau,k)
[knots,k] = aptknt(tau,k)
```

### Description

`knots = aptknt(tau,k)` returns a knot sequence suitable for interpolation at the data sites `tau` by splines of order `k` with that knot sequence, provided `tau` has at least `k` entries, is nondecreasing, and satisfies  $\tau(i) < \tau(i+k-1)$  for all `i`. In that case, there is exactly one spline of order `k` with knot sequence `knots` that matches given values at those sites. This is so because the sequence `knots` returned satisfies the Schoenberg-Whitney conditions

$$\text{knots}(i) < \tau(i) < \text{knots}(i+k), \quad i=1:\text{length}(\tau)$$

with equality only at the extreme knots, each of which occurs with exact multiplicity `k`.

If `tau` has fewer than `k` entries, then `k` is reduced to the value `length(tau)`. An error results if `tau` fails to be nondecreasing and/or  $\tau(i) = \tau(i+k-1)$  for some `i`.

`[knots,k] = aptknt(tau,k)` also returns the actual `k` used (which equals the smaller of the input `k` and `length(tau)`).

### Examples

If `tau` is equally spaced, e.g., equal to `linspace(a,b,n)` for some  $n \geq 4$ , and `y` is a sequence of the same size as `tau`, then `sp = spapi(aptknt(tau,4),tau,y)` gives the cubic spline interpolant with the not-a-knot end condition. This is the same cubic spline as produced by the command `spline(tau,y)`, but in B-form rather than ppform.

### Cautionary Note

If `tau` is very nonuniform, then use of the resulting knot sequence for interpolation to data at the sites `tau` may lead to unsatisfactory results.

### Algorithms

The  $(k-1)$ -point averages  $\text{sum}(\tau(i+1:i+k-1))/(k-1)$  of the sequence `tau`, as supplied by `aveknt(tau,k)`, are augmented by a  $k$ -fold `tau(1)` and a  $k$ -fold `tau(end)`. In other words, the command gives the same result as `augknt([tau(1),aveknt(tau,k),tau(end)],k)`, provided `tau` has at least `k` entries and `k` is greater than 1.

### See Also

`augknt` | `aveknt` | `newknt` | `optknt`

## argnames

Input argument names of `cf`, `sfit`, or `fittype` object

### Syntax

```
args = argnames(fun)
```

### Description

`args = argnames(fun)` returns the input argument (variable and coefficient) names of the `cf`, `sfit`, or `fittype` object `fun` as an `n`-by-1 cell array of character vectors `args`, where `n = numargs(fun)`.

### Examples

```
f = fittype('a*x^2+b*exp(n*x)');
nargs = numargs(f)
nargs =
     4
args = argnames(f)
args =
    'a'
    'b'
    'n'
    'x'
```

## Version History

Introduced in R2006b

### See Also

`fittype` | `formula` | `numargs`



# augknt

Augment knot sequence

## Syntax

```
augknt(knots,k)
augknt(knots,k,mults)
[augknt,addl] = augknt(...)
```

## Description

`augknt(knots,k)` returns a nondecreasing and augmented knot sequence that has the first and last knot with exact multiplicity  $k$ . (This may actually shorten the knot sequence.)

`augknt(knots,k,mults)` makes sure that the augmented knot sequence returned will, in addition, contain each interior knot `mults` times. If `mults` has exactly as many entries as there are interior knots, then the  $j$ th one will appear `mults(j)` times. Otherwise, the uniform multiplicity `mults(1)` is used. If `knots` is strictly increasing, this ensures that the splines of order  $k$  with knot sequence `augknt` satisfy  $k$ -`mults(j)` smoothness conditions across `knots(j+1)`,  $j=1:\text{length}(\text{knots})-2$ .

`[augknt,addl] = augknt(...)` also returns the number `addl` of knots added on the left. (This number may be negative.)

## Examples

If you want to construct a cubic spline on the interval  $[a..b]$ , with two continuous derivatives, and with the interior break sequence `xi`, then `augknt([a,b,xi],4)` is the knot sequence you should use.

If you want to use Hermite cubics instead, i.e., a cubic spline with only one continuous derivative, then the appropriate knot sequence is `augknt([a,xi,b],4,2)`.

`augknt([1 2 3 3 3],2)` returns the vector `[1 1 2 3 3]`, as does `augknt([3 2 3 1 3],2)`. In either case, `addl` would be 1.

## aveknt

Provide knot averages

### Syntax

```
tstar = aveknt(t,k)
```

### Description

`tstar = aveknt(t,k)` returns the averages of successive  $k-1$  knots, i.e., the sites

$$t_i^* := (t_{i+1} + \dots + t_{i+k-1}) / (k-1), \quad i = 1:n$$

which are recommended as good interpolation site choices when interpolating from splines of order  $k$  with knot sequence  $t = (t_i)_{i=1}^{n+k}$ .

### Examples

`aveknt([1 2 3 3 3],3)` returns the vector `[2.5000 3.0000]`, while `aveknt([1 2 3],3)` returns the empty vector.

With  $k$  and the strictly increasing sequence `breaks` given, the statements

```
t = augknt(breaks,k); x = aveknt(t);  
sp = spapi(t,x,sin(x));
```

provide a spline interpolant to the sine function on the interval `[breaks(1) . . breaks(end)]`.

For `sp` the B-form of a scalar-valued univariate spline function, and with `tstar` and `a` computed as

```
tstar = aveknt(fnbrk(sp,'knots'),fnbrk(sp,'order'));  
a = fnbrk(sp,'coefs');
```

the points  $(tstar(i), a(i))$  constitute the *control points* of the spline, i.e., the vertices of the spline's *control polygon*.

### See Also

`aptknt` | `chbpnt` | `optknt`

# bkbrk

Part(s) of almost block-diagonal matrix

## Syntax

```
[nb,rows,ncols,last,blocks] = bkbrk(blokmat)
bkbrk(blokmat)
```

## Description

`[nb,rows,ncols,last,blocks] = bkbrk(blokmat)` returns the details of the almost block-diagonal matrix contained in `blokmat`, with `rows` and `last` `nb`-vectors, and `blocks` a matrix of size `[sum(rows),ncols]`.

This utility program is not likely to be of interest to the casual user. It is used in `slvblk` to decode the information, provided by `scol`, about a spline collocation matrix in an almost block diagonal form especially suited for splines. But `bkbrk` can also decode the almost block-diagonal form used in [1].

`bkbrk(blokmat)` returns nothing, but the details are printed out. This is of use when trying to understand what went wrong with such a matrix.

## References

[1] C. de Boor and R. Weiss. "SOLVEBLOK: A package for solving almost block diagonal linear systems." *ACM Trans. Mathem. Software* 6 (1980), 80-87.

## See Also

`slvblk` | `scol`

## brk2knt

Convert breaks with multiplicities into knots

### Syntax

```
knots = brk2knt(breaks,mults)
```

### Description

`knots = brk2knt(breaks,mults)` returns the sequence `knots` that is the sequence `breaks` but with `breaks(i)` occurring `mults(i)` times, all `i`. In particular, `breaks(i)` will not appear unless `mults(i)>0`. If, as one would expect, `breaks` is a strictly increasing sequence, then `knots` contains each `breaks(i)` exactly `mults(i)` times.

If `mults` does not have exactly as many entries as does `breaks`, then all `mults(i)` are set equal to `mults(1)`.

### Examples

The statements

```
t = [1 1 2 2 2 3 4 5 5];  
[xi,m] = knt2brk(t);  
tt = brk2knt(xi,m)
```

give `[1 2 3 4 5]` for `xi`, `[2 3 1 1 2]` for `m`, and, finally, `t` for `tt`.

### See Also

`augknt`

# bspligui

Experiment with B-spline as function of its knots

## Syntax

bspligui

## Description

bspligui starts a graphical user interface for exploring how a B-spline depends on its knots. As you add, move, or delete knots, you see the B-spline and its first three derivatives change accordingly.

You observe the following basic facts about the B-spline with knot sequence  $t_0 \leq \dots \leq t_k$ :

- The B-spline is positive on the open interval  $(t_0..t_k)$ . It is zero at the end knots,  $t_0$  and  $t_k$ , unless they are knots of multiplicity  $k$ . The B-spline is also zero outside the closed interval  $[t_0..t_k]$ , but that part of the B-spline is not shown in the user interface.
- Even at its maximum, the B-spline is never bigger than 1. It reaches the value 1 inside the interval  $(t_0..t_k)$  only at a knot of multiplicity at least  $k-1$ . On the other hand, that maximum cannot be arbitrarily small; it seems smallest when there are no interior knots.
- The B-spline is piecewise polynomial of order  $k$ , i.e., its polynomial pieces all are of degree  $<k$ . For  $k = 1:4$ , you can even observe that all its nonzero polynomial pieces are of exact degree  $k - 1$ , by looking at the first three derivatives of the B-spline. This means that the degree goes up/down by 1 every time you add/delete a knot.
- Each knot  $t_j$  is a break for the B-spline, but it is permissible for several knots to coincide. Therefore, the number of nontrivial polynomial pieces is maximally  $k$  (when all the knots are different) and minimally 1 (when there are no “interior” knots), and any number between 1 and  $k$  is possible.
- The smoothness of the B-spline across a break depends on the multiplicity of the corresponding knot. If the break occurs in the knot sequence  $m$  times, then the  $(k-m)$ th derivative of the B-spline has a jump across that break, while all derivatives of order lower than  $(k-m)$  are continuous across that break. Thus, by varying the multiplicity of a knot, you can control the smoothness of the B-spline across that knot.
- As one knot approaches another, the highest derivative that is continuous across both develops a jump and the higher derivatives become unbounded. But nothing dramatic happens in any of the lower-order derivatives.
- The B-spline is *bell-shaped* in the following sense: if the first derivative is not identically zero, then it has exactly one sign change in the interval  $(t_0..t_k)$ , hence the B-spline itself is *unimodal*, meaning that it has exactly one maximum. Further, if the second derivative is not identically zero, then it has exactly two sign changes in that interval. Finally, if the third derivative is not identically zero, then it has exactly three sign changes in that interval. This illustrates the fact that, for  $j = 0:k - 1$ , if the  $j$ th derivative is not identically zero, then it has exactly  $j$  sign changes in the interval  $(t_0..t_k)$ ; it is this property that is meant by the term “bell-shaped”. For this claim to be strictly true, one has to be careful with the meaning of “sign change” in case there are knots with multiplicities. For example, the  $(k-1)$ st derivative is piecewise constant, hence it cannot have  $k-1$  sign changes in the straightforward sense unless there are  $k$  polynomial pieces, i.e., unless all the knots are simple.

**See Also**

`bspline` | `chbpnt` | `spcol`

# bspline

Plot B-spline and its polynomial pieces

## Syntax

```
bspline(t)
bspline(t,window)
pp = bspline(t)
```

## Description

`bspline(t)` plots the B-spline with knot sequence `t`, as well as the polynomial pieces of which it is composed. For more information about spline fitting, see [About Splines in Curve Fitting Toolbox](#) on page 1-8.

`bspline(t,window)` plots the B-spline with knot sequence `t`, as well as the polynomial pieces of which it is composed, in the subplot window specified by `window`.

`pp = bspline(t)` plots nothing and returns the ppform of the B-spline.


## Examples

### Plot a B-spline of Order 4

This example shows how to create a B-spline of order 4 using the `bspline` function.

### Create a Knot Sequence and Plot the B-spline

This figure shows a B-spline of order 4 and the four cubic polynomials that composes it.



To replicate this figure in MATLAB®, first create a knot sequence. A knot sequence must be non-decreasing.


```
t = [0 1.5 2.3 4 5];
```

As you have defined five knots, the B-spline will be of order 4.

Then plot the B-spline with knot sequence `t`, as well as its polynomial pieces, by using the `bspline` function.

```
bspline(t)
```





This B-spline consists of 4 polynomial pieces: the red, green, purple, and black curves in the plot, each of degree 3.

The vertical lines mark the knots  $t$  that you have previously defined.

The B-spline with knots  $t(i) \leq \dots \leq t(i+k)$  is positive on the interval  $(t(i)..t(i+k))$  and is zero outside that interval. It is piecewise-polynomial of order  $k$  with breaks at the sites  $t(i), \dots, t(i+k)$ . These knots may coincide, and the precise *multiplicity* governs the smoothness with which the two polynomial pieces join there.


### Plot Another B-spline in a New Subplot

Create a second knot sequence.

```
t2=[2 3 4 5];
```

Plot the B-spline with knot sequence  $t_2$  in the same figure but in a different subplot.

```
bspline(t,1)
bspline(t2 ,2)
```



Copyright 2019 The MathWorks, Inc.

## Input Arguments

### **t** — Knot sequence of spline

vector (default)

Non-decreasing sequence of the knots of the B-spline, specified as a vector.

Data Types: `single` | `double`

### **window** — Subplot window

scalar (default)

Index of the subplot of a 2x2 window, specified as a scalar. This value must be less than 5.

Data Types: `single` | `double`

## Output Arguments

### **pp** — Spline in ppform

spline structure

Spline in ppform, returned as a structure with these fields. For more information on ppform, see The ppform on page 10-8

**Form — Form of spline**

pp

Form of the spline, returned as pp. pp indicates that the spline is given in piecewise polynomial form.

**Breaks — Knot locations of spline**

vector | cell array

Knot positions of the spline, returned as a vector or as a cell array of vectors for multivariate data. Vectors contain strictly increasing elements that represent the start and end of each of the intervals over which the polynomial pieces are defined.

**Coefs — Coefficients of polynomials**

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

**Pieces — Number of polynomial pieces**

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

**Order — Order of polynomials**

scalar | vector

Order of the polynomial function describing each polynomial piece of the spline, returned as a scalar or as a vector containing the order in each variable for multivariate data.

**Dim — Dimensionality**

scalar

Dimensionality of the target function, returned as a scalar.

## Version History

**Introduced in R2006b****See Also**

bspligui

**Topics**

“Introducing Spline Fitting” on page 8-2

“Types of Splines: ppform and B-form” on page 10-2

## category

Category of fit of `cf`, `sfit`, or `fittype` object

### Syntax

```
cname = category(fun)
```

### Description

`cname = category(fun)` returns the fit category `cname` of the `cf`, `sfit`, or `fittype` object `fun`, where `cname` is one of 'custom', 'interpolant', 'library', or 'spline'.

### Examples

```
f1 = fittype('a*x^2+b*exp(n*x)');  
category(f1)  
ans =  
custom
```

```
f2 = fittype('pchipinterp');  
category(f2)  
ans =  
interpolant
```

```
f3 = fittype('fourier4');  
category(f3)  
ans =  
library
```

```
f4 = fittype('smoothingspline');  
category(f4)  
ans =  
spline
```

## Version History

Introduced in R2006b

### See Also

`fittype` | `type`

### Topics

“List of Library Models for Curve and Surface Fitting” on page 4-10

# cfit

Constructor for `cfit` object

## Syntax

```
cfun = cfit(ffun, coeff1,...,coeffn)
```

## Description

`cfun = cfit(ffun, coeff1,...,coeffn)` constructs the `cfit` object `cfun` using the model type specified by the `fittype` object `ffun` and the coefficient values `coeff1`, `coeff2`, etc.

---

**Note** `cfit` is called by the `fit` function when fitting `fittype` objects to data. To create a `cfit` object that is the result of a regression, use `fit`.

You should only call `cfit` directly if you want to assign values to coefficients and problem parameters of a `fittype` object *without* performing a fit.

---

## Examples

### Construct a `cfit` object from a `fittype` object

Create a `fittype` object and call the `cfit` function.

```
f = fittype('a*x^2+b*exp(n*x)')
c = cfit(f,1,10.3,-1e2)

f =
  General model:
    f(a,b,n,x) = a*x^2+b*exp(n*x)
c =
  General model:
    c(x) = a*x^2+b*exp(n*x)
  Coefficients:
    a =          1
    b =         10.3
    n =        -100
```

## Input Arguments

### **ffun** — Model type

`fittype` (default)

Model type the `cfit` function uses to construct the `cfit` object, specified as a `fittype` constructed with the `fittype` function.

Example: `fittype('poly2')`

**coeff1, ..., coeffn — Coefficient values**

scalar (default)

Coefficient values of the `cfi`t object, specified as scalars.

Data Types: `single` | `double`

**Output Arguments****`cfun` — `cfi`t object**

`cfi`t

Function output, returned as a `cfi`t object.

**Version History**

Introduced before R2006a

**See Also**

`fit` | `fitttype` | `feval`

**Topics**

“Evaluate Curve Fit” on page 7-16

“Fit Postprocessing”

# chbpnt

Chebyshev-Demko points

## Syntax

```
tau = chbpnt(t,k)
chbpnt(t,k,tol)
[tau,sp] = chbpnt(...)
```

## Description

`tau = chbpnt(t,k)` are the extreme sites of the Chebyshev spline of order `k` with knot sequence `t`. These are particularly good sites at which to interpolate data by splines of order `k` with knot sequence `t` because the resulting interpolant is often quite close to the best uniform approximation from that spline space to the function whose values at `tau` are being interpolated.

`chbpnt(t,k,tol)` also specifies the tolerance `tol` to be used in the iterative process that constructs the Chebyshev spline. This process is terminated when the relative difference between the absolutely largest and the absolutely smallest local extremum of the spline is smaller than `tol`. The default value for `tol` is `.001`.

`[tau,sp] = chbpnt(...)` also returns, in `sp`, the Chebyshev spline.

## Examples

### Approximate Square Root Function

Create a knot sequence of ten zeros and ten ones using the `augknt` function.

```
k = 10;
t = augknt([0,1],k);
```

Create a vector of interpolation sites by calculating the Chebyshev-Demko points for the Chebyshev spline of order 10 with knot sequence `t`.

```
sites = chbpnt(t,k);
```

Create a vector of interpolation points by evaluating the function `sqrt` at the Chebyshev-Demko points. Use the function `spapi` to interpolate through the evaluated points with a tenth-order spline from the knot sequence `t`. The knots in `t` indicate that the spline fit consists of a single polynomial with boundaries at 0 and 1.

```
interpolationPoints = sqrt(sites);
sp = spapi(t,sites,interpolationPoints)
```


```
sp = struct with fields:
    form: 'B-'
    knots: [0 0 0 0 0 0 0 0 0 0 1 1 1 1 1 1 1 1 1]
    coefs: [-1.7088e-16 0.8842 -0.7101 2.4484 -1.1869 1.9678 0.3331 0.9940 0.9349 1]
    number: 10
```

```
order: 10
dim: 1
```

The structure `sp` contains the properties of the spline. The `coefs` field of `sp` is a vector of coefficients for the polynomial that approximates the square root function in the interval  $[0, 1]$ .

Compare `sp` and the square root function by displaying them in the same plot.

```
x = linspace(0,1,1000);
plot(x,sqrt(x))
hold on
fnplt(sp,'-',0.75)
legend(["square root function" "spline"],Location="best")
```



The plot shows that the spline closely follows the square root function.

## Algorithms

The Chebyshev spline for the given knot sequence and order is constructed iteratively, using the Remez algorithm, using as initial guess the spline that takes alternately the values 1 and  $-1$  at the sequence `aveknt(t, k)`. The example “Construct Chebyshev Spline” on page 12-156 gives a detailed discussion of one version of the process as applied to a particular example.



**See Also**  
aveknt

## coeffnames

Coefficient names of `cfits`, `sfits`, or `fittype` object

### Syntax

```
coeffs = coeffnames(fun)
```

### Description

`coeffs = coeffnames(fun)` returns the coefficient (parameter) names of the `cfits`, `sfits`, or `fittype` object `fun` as an `n`-by-1 cell array of character vectors `coeffs`, where `n = numcoeffs(fun)`.

### Examples

```
f = fittype('a*x^2+b*exp(n*x)');
ncoeffs = numcoeffs(f)
ncoeffs =
     3
coeffs = coeffnames(f)
coeffs =
    'a'
    'b'
    'n'
```

## Version History

Introduced in R2006b

### See Also

`fittype` | `formula` | `numcoeffs` | `probnames` | `coeffvalues`

# coeffvalues

Coefficient values of `cf` or `sfit` object

## Syntax

```
coeffvals= coeffvalues(fun)
```

## Description

`coeffvals= coeffvalues(fun)` returns the values of the coefficients, or parameters, of the `cf` or `sfit` object `fun` as a 1-by-`n` vector `coeffvals`, where `n = numcoeffs(fun)`.

## Examples

### Obtain the Coefficient Values of a Quadratic Polynomial Curve

Load the data in the `census.mat` file and construct a `fittype` for a quadratic polynomial curve.

```
load census
f = fittype('poly2');
```

Obtain the coefficient names and the formula for the `fittype` object `f`.

```
coefficientNames = coeffnames(f)

coefficientNames = 3x1 cell
    {'p1'}
    {'p2'}
    {'p3'}
```

```
formula(f)
```

```
ans =
'p1*x^2 + p2*x + p3'
```

Fit the curve to the data and retrieve the coefficient values.

```
c = fit(cdate,pop,f);
coefficientValues = coeffvalues(c)
```

```
coefficientValues = 1x3
10^4 x
    0.0000    -0.0024    2.1130
```

## Input Arguments

**fun** — `cf` or `sfit` object

`cf` | `sfit`

Object of which you want to calculate the coefficients, specified as a `cfi`t or `sfi`t object.

## Output Arguments

### **coeffvals** — Coefficients values

scalar | vector

Values of the coefficients of the `cfi`t or `sfi`t object `fun`, returned as a scalar or vector.

## Version History

Introduced before R2006a

## See Also

`coeffnames` | `confint` | `predint` | `probvalues` | `cfi`t | `sfi`t

## Topics

“Introducing Spline Fitting” on page 8-2

## confint

Confidence intervals for fit coefficients of `cf` or `sfit` object

### Syntax

```
ci = confint(fitresult)
ci = confint(fitresult,level)
```

### Description

`ci = confint(fitresult)` returns 95% confidence bounds `ci` on the coefficients associated with the `cf` or `sfit` object `fitresult`. `fitresult` must be an output from the `fit` function to contain the necessary information for `ci`. `ci` is a 2-by-`n` array where `n = numcoeffs(fitresult)`. The top row of `ci` contains the lower bound for each coefficient; the bottom row contains the upper bound.

`ci = confint(fitresult,level)` returns confidence bounds at the confidence level specified by `level`. `level` must be between 0 and 1. The default value of `level` is 0.95.

### Examples

#### Obtain the Confidence Intervals for Fit Coefficients Using the `confint` Function

Load the data and call the `fit` function to obtain the `fitresult` information.

```
load census

fitresult = fit(cdate,pop,'poly2')

fitresult =

    Linear model Poly2:
    fitresult(x) = p1*x^2 + p2*x + p3
    Coefficients (with 95% confidence bounds):
    p1 =    0.006541  (0.006124, 0.006958)
    p2 =   -23.51  (-25.09, -21.93)
    p3 =  2.113e+04  (1.964e+04, 2.262e+04)
```

To obtain the confidence intervals, call the `confint` function on `fitresult`.

```
ci = confint(fitresult,0.95)

ci =

    0.0061242    -25.086    19641
    0.0069581    -21.934    22618
```

`fit` and `confint` display the confidence bounds in slightly different formats.

## Input Arguments

### **fitresult** — Fit information for confidence bounds calculation

`cfits` | `sfits`

Fit information for confidence bounds calculation, specified as a `cfits` or `sfits` object. `fitresult` must be an output from the `fit` function.

### **level** — Confidence level

0.95 (default) | scalar value in the range (0,1)

Confidence level, specified as a scalar. This argument must be between 0 and 1

Data Types: `single` | `double`

## Output Arguments

### **ci** — Confidence intervals

matrix

Confidence bounds on the coefficients associated with the `cfits` or `sfits` object `fitresult`, returned as a matrix.

## Tips

To calculate confidence bounds, `confint` uses  $R^{-1}$  (the inverse  $R$  factor from  $QR$  decomposition of the Jacobian), the degrees of freedom for error, and the root mean squared error. This information is automatically returned by the `fit` function and contained within `fitresult`.

If coefficients are bounded and one or more of the estimates are at their bounds, those estimates are regarded as fixed and do not have confidence bounds.

Note that you cannot calculate confidence bounds if `category(fitresult)` is `'spline'` or `'interpolant'`.

## Version History

Introduced before R2006a

## See Also

`fit` | `predint`

## Topics

“Introducing Spline Fitting” on page 8-2

## csape

Cubic spline interpolation with end conditions

### Syntax

```
pp = csape(x,y)
pp = csape(x,y,conds)
pp = csape(x,[e1,y,e2],conds)
pp = csape({x1,...,xn}, ___)
```

### Description

`pp = csape(x,y)` returns the cubic spline interpolation to the given data  $(x,y)$  in ppform form. The function applies Lagrange end conditions to each end of the data, and matches the spline endslopes to the slope of the cubic polynomial that fits the last four data points at each end. Data values at the same site are averaged.

`pp = csape(x,y,conds)` uses the end conditions specified by `conds`.

`pp = csape(x,[e1,y,e2],conds)` uses the end conditions specified by `conds` and the values `e1` and `e2` for the left and right end condition values, respectively.

`pp = csape({x1,...,xn}, ___)` returns the cubic spline interpolation for gridded data using the univariate mesh inputs  $x_1, \dots, x_n$ . In this case, `y` is an  $n+r$ -dimensional array, where  $r$  is the dimensionality of each data value. `conds` is a cell array with  $n$  entries, which provides end conditions for each of the  $n$  variables. In some cases, you must supply end conditions for end conditions. You can use this syntax with any of the arguments in the previous syntaxes.

### Examples

#### Use Customized End Conditions with csape

You can implement custom end conditions using the `csape` function. Suppose you want to enforce the following condition at the leftmost endpoint,  $e = x(1)$

$$\lambda(s) \equiv aDs(e) + bD^2s(e) = c$$

for the given scalars  $a, b$ , and  $c$ . You can compute the cubic spline interpolation  $s$  as the sum of  $s_1$  (the cubic spline interpolation of the given data using the default end conditions) and  $s_0$  (the cubic spline interpolation of zero data using some nontrivial end conditions):

$$s = s_1 + \frac{c - \lambda(s_1)}{\lambda(s_0)} s_0$$

The end conditions you specify in  $s_0$  do not have to be the final desired end conditions  $\lambda(s)$ .

This example uses the titanium test data, a standard data set used in data fitting. Load the data using the `titanium` function.

```
[x,y] = titanium;
```

Define the coefficients for  $\lambda(s)$ .

```
a = -2;  
b = -1;  
c = 0;
```

The end condition applies to the leftmost end of the data set.

```
e = x(1);
```

Now, calculate the cubic spline interpolation of the data set without imposing the end conditions.

```
s1 = csape(x,y);
```

To calculate  $s_0$ , use zero data of the same length as  $y$  with an additional set of nontrivial end conditions.

```
yZero = zeros(1,length(y));
```

The 1-by-2 matrix `conds` sets the end conditions by specifying the spline derivatives to fix. This example uses end conditions only on the left end of the data, so use `conds` to fix the first derivative at the left end. At the right end, fix the value of the function itself.

```
conds = [1 0];
```

To specify the values to fix the function or its derivatives to, add them as additional values to the data set for fitting - in this case, `yZero`. The first element specifies the value at the left end, while the last element specifies the value at for the right end.

At the left end, fix the first derivative of the spline to have a value of 1. At the right end, fix the function itself to be 0 (the original value of the final element of `yZero`). Concatenate these end condition values at the respective ends of `yZero` and use `csape` to find the spline that fits the data with these end condition values.

```
s0 = csape(x,[1 yZero 0],conds);
```

Calculate the fully fitted spline from that data by using the aforementioned expression for  $s$ . To do this, calculate the values for  $\lambda_0 = \lambda(s_0)$  and  $\lambda_1 = \lambda(s_1)$  using the first and second derivatives of the splines  $s_0$  and  $s_1$ .

```
d1s1 = fnder(fnbrk(s1,1));  
d2s1 = fnder(d1s1);  
d1s0 = fnder(fnbrk(s0,1));  
d2s0 = fnder(d1s0);
```

Calculate the derivatives of the first polynomial piece of the spline, as the end conditions apply to the left end of the data only.

```
lam1 = a*fnder(d1s1, e) + b*fnder(d2s1,e);  
lam0 = a*fnder(d1s0, e) + b*fnder(d2s0,e);
```

Now use  $\lambda_1$  and  $\lambda_0$  to calculate the final, fully fitted spline.

```
pp = fncmb(s0,(c-lam1)/lam0,s1);
```


Plot the spline to compare the results of the default fit and the end conditions.



```

fnplt(pp,[594, 632])
hold on
fnplt(s1,'b--',[594, 632])
plot(x,y,'ro','MarkerFaceColor','r')
hold off
axis([594, 632, 0.62, 0.655])
legend 'Desired end conditions' ...
'Default end-conditions' 'Data' ...
Location SouthEast

```



The stationary point near the first data point shows that the end conditions are implemented in the fit.

### Fit Multivariate Data

Use `csape` to fit multivariate, vector-valued data. This example fits vector-valued data using different end conditions for each independent variable.

First, define the data. For this example, define the 3-dimensional vectors  $v$  over a 2-dimensional field, with clamped conditions or prescribed slopes in the  $x$  direction and periodic end conditions in the  $y$  direction.

```

x = 0:4;
y = -2:2;

```

```

s2 = 1/sqrt(2);

v = zeros( 3, 7, 5 );
v(1, :, :) = [1 0 s2 1 s2 0 -1].'*[1 0 -1 0 1];
v(2, :, :) = [1 0 s2 1 s2 0 -1].'*[0 1 0 -1 0];
v(3, :, :) = [0 1 s2 0 -s2 -1 0].'*[1 1 1 1 1];

```

$v$  is a 3-dimensional array with  $v(:, i+1, j)$  as the vector value at coordinate  $x(i), y(j)$ . Two additional entries in the  $x$  dimension specify the slope values: the data points  $v(:, 1, j)$  and  $v(:, 7, j)$  provide the value of the first derivative along the lines  $x = 0$  and  $x = 4$  for the clamped end conditions. In the  $y$  dimension, the periodic end conditions do not require any additional specification.

Now, calculate the multivariate cubic spline interpolation using `csape`.

```
sph = csape({x,y},v,{'clamped','periodic'});
```

To plot the result, first evaluate the spline over a suitable interval.


```

values = fnval(sph,{0:.1:4,-2:.1:2});

surf(squeeze(values(1, :, :)), ...
     squeeze(values(2, :, :)), squeeze(values(3, :, :)));

axis equal
axis off

```



You can also evaluate and plot the spline surface using the simple command `fnplt(sph)`. Note that `v` is a 3-dimensional array, and `v(:,i+1,j)` is the 3-vector to match at  $(x(i), y(j))$ ,  $i=1:5$ ,  $j=1:5$ . Additionally, in accordance with `conds{1}` being 'clamped', `size(v,2)` is 7 (and not 5), and the first and last entry of `v(r, :, j)` specify the end slope values.

### Supply End Conditions for End Conditions

In some cases, you must supply end conditions of end conditions. In this bivariate example, you reproduce the bicubic polynomial  $g(x,y) = x^3y^3$  by complete bicubic interpolation. You then derive the needed data, including end condition values, directly from  $g$  to make it easier to see how the end condition values must be placed. Finally, you check the result.

```
sites = {[0 1],[0 2]}; coefs = zeros(4, 4); coefs(1,1) = 1;
g = ppmak(sites,coefs);
Dxg = fnval(fnder(g,[1 0]),sites);
Dyg = fnval(fnder(g,[0 1]),sites);
Dxyg = fnval(fnder(g,[1 1]),sites);

f = csape(sites,[Dxyg(1,1), Dxg(1,:), Dxyg(1,2); ...
               Dyg(:,1), fnval(g,sites), Dyg(:,2); ...
               Dxyg(2,1), Dxg(2,:), Dxyg(2,2)], ...
         {'complete','complete'});

if any(squeeze(fnbrk(f,'c'))-coefs)
    disp('this is wrong')
end
```

## Input Arguments

### **x** — Data sites

vector | cell array

Data sites of data values  $y$  to fit, specified as a vector or as a cell array for multivariate data. The function creates spline  $s$  knots at each data site  $x$  such that  $s(x(j)) = y(:,j)$  for all  $j$ .

For multivariate, gridded data, specify  $x$  as a cell array that provides the data site in each variable dimension, such that  $s(x1(i), x2(j), \dots, xn(k)) = y(:,i,j,\dots,k)$ .

Data Types: single | double

### **y** — Data values to fit

vector | matrix | array

Data values to fit during creation of the spline, specified as a vector, matrix, or array. You can specify the data values  $y(:,j)$  as scalars, matrices, or  $n$ -dimensional arrays. Data values given at the same data site  $x$  are averaged.

Data Types: single | double

### **conds** — End conditions

'clamped' | 'complete' | 'not-a-knot' | 'periodic' | 'second' | 'variational' | 1-by-2 matrix

End conditions for the spline, specified as 'complete' or 'clamped', 'not-a-knot', 'periodic', 'second', 'variational', or as a 1-by-2 matrix. The predefined options for `conds`

impose identical end conditions at each end of the data. You can specify different end conditions at each end by supplying `conds` as a 1-by-2 matrix.

The available predefined end conditions are as follows.

|                            |                                                                                                                                                                                                                                                                                    |
|----------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 'complete' or<br>'clamped' | Match the endslopes to the given values <code>e1</code> and <code>e2</code> . If you do not provide values for <code>e1</code> and <code>e2</code> , this option matches the default Lagrangian end conditions.                                                                    |
| 'not-a-knot'               | Make the second and second-last sites inactive knots. This option ignores any values you provide for <code>e1</code> and <code>e2</code> .                                                                                                                                         |
| 'periodic'                 | Match the first and second derivatives at the left end with those at the right end.                                                                                                                                                                                                |
| 'second'                   | Match the end second derivatives to the given values <code>e1</code> and <code>e2</code> . If you do not provide values <code>e1</code> and <code>e2</code> , this option uses the default value of 0 for both. With the default values, this option is the same as 'variational'. |
| 'variational'              | Set the end second derivatives equal to zero. This option ignores any values you provide for <code>e1</code> and <code>e2</code> .                                                                                                                                                 |

To specify different end conditions at each end, supply `conds` as a 1-by-2 matrix. The elements of this matrix elements specify the order of the spline derivative fixed by the end conditions. Setting `conds(j) = i` fixes the  $i$ th derivative  $D^i s$  to an end condition value.

The default end condition value is the derivative of the cubic interpolant at the left four sites when `conds(1) = 1` and is 0 otherwise. Set end condition values for the left and right sides of the data by specifying `e1` and `e2`, respectively.

You can specify the value of `conds(j)` as 0, 1, or 2. If you specify a different value or do not specify `conds(j)`, then `conds(j)` is 1 and the corresponding end condition value is the default value.

The following pre-defined end conditions are available.

|                    |                                |                                              |
|--------------------|--------------------------------|----------------------------------------------|
| <b>clamped</b>     | $Ds(e) = e_j$                  | if <code>conds(j) == 1</code>                |
| <b>curved</b>      | $D^2s(e) = e_j$                | if <code>conds(j) == 2</code>                |
| <b>periodic</b>    | $D^r s(a) = D^r s(b), r = 1,2$ | if <code>conds == [0 0]</code>               |
| <b>variational</b> | $D^2s(e) = 0$                  | if <code>conds(j) == 2 &amp; e_j == 0</code> |

$e$ ,  $a$ , and  $b$  refer to the left or right data locations;  $e_j$  is `e1` for the left end of the data and `e2` for the right end of the data.

You can supply the optional end condition values `e1` and `e2` whether you use predefined or user-defined options for `conds`. However, note that some predefined options for `conds` ignore any end condition values you provide.

Example: 'clamped', [1 0]

### **e1 – Left end condition value**

scalar

Left end condition value for the spline, specified as a scalar value. `e1` specifies the value for the  $i$ th derivative at the left end of the data, where `conds` provides  $i$ . Even if you use different end conditions

at the two ends, if you supply an end condition value at one end you must also supply one for the other end.

Note that some predefined options for `conds` ignore any end condition values you provide.

The default value for `e1` is the derivative of the cubic interpolant at the left four sites when `conds(1) = 1` and is 0 otherwise.

Data Types: `single` | `double`

### **e2 — Right end condition value**

scalar

Right end condition value for the spline, specified as a scalar value. `e2` specifies the value for the  $i$ th derivative at the right end of the data, where `conds` provides  $i$ . Even if you use different end conditions at the two ends, if you supply an end condition value at one end you must also supply one for the other end.

Note that some predefined options for `conds` ignore any end condition values you provide.

The default value for `e2` is the derivative of the cubic interpolant at the right four sites when `conds(2) = 1` and is 0 otherwise.

Data Types: `single` | `double`

## **Output Arguments**

### **pp — Spline in `ppform`**

spline structure

Spline in `ppform`, returned as a structure with these fields.

### **Form — Form of spline**

`pp`

Form of the spline, returned as `pp`. `pp` indicates that the spline is given in piecewise polynomial form.

### **Breaks — Knot locations of spline**

vector | cell array

Knot positions of the spline, returned as a vector or as a cell array of vectors for multivariate data. Vectors contain strictly increasing elements that represent the start and end of each of the intervals over which the polynomial pieces are defined.

### **Coefs — Coefficients of polynomials**

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

### **Pieces — Number of polynomial pieces**

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

**Order — Order of polynomials**

scalar | vector

Order of the polynomial function describing each polynomial piece of the spline, returned as a scalar or as a vector containing the order in each variable for multivariate data.

**Dim — Dimensionality**

scalar

Dimensionality of the target function, returned as a scalar.

**Algorithms**

The relevant tridiagonal linear system is constructed and solved using the sparse matrix capabilities of MATLAB.

The `csape` command calls on a much expanded version of the Fortran routine CUBSPL in *PGS*.

**Version History****Introduced before R2006a****See Also**

csapi | spapi | spline

# csapi

Cubic spline interpolation

## Syntax

```
pp = csapi(x,y)
values = csapi(x,y,xx)
```

## Description

---

**Note** For a simpler but less flexible method to interpolate cubic splines, try the Curve Fitter app or the `fit` function and see “About Smoothing Splines” on page 6-14.

---

`pp = csapi(x,y)` returns the ppform of a cubic spline  $s$  with knot sequence  $x$  that takes the values  $y(:,j)$  at  $x(j)$  for  $j=1:\text{length}(x)$ . The values  $y(:,j)$  can be scalars, vectors, matrices, and ND-arrays. The function averages the data points with the same data site and then sorts them by their sites. With  $x$  the resulting sorted data sites, the spline  $s$  satisfies the not-a-knot end conditions, such as

$$\text{jump}_{x(2)}D_s^3 = 0 = \text{jump}_{x(\text{end}-1)}D_s^3(s)$$

where  $D^3s$  is the third derivative of  $s$ .

If  $x$  is a cell array of sequences  $x_1, \dots, x_m$  of lengths  $n_1, \dots, n_m$ , then  $y$  is an array of size  $[n_1, \dots, n_m]$  (or of size  $[d, n_1, \dots, n_m]$  if the interpolant is  $d$ -valued). In that case, `pp` is the ppform of an  $m$ -cubic spline interpolant  $s$  to such data. In particular,

$$s(x(i_1), \dots, x(i_m)) = y(:, i_1, \dots, i_m)$$

with  $i_1 = 1:n_1$  and  $i_m = 1:n_m$ .

To perform operations on this interpolating cubic spline, such as evaluation, differentiation, plotting, use the `pp` structure. For more information, see the `fnval`, `fnder`, `fnplt` functions.

`values = csapi(x,y,xx)` returns the values of the smoothing spline evaluated at the points `xx`. This syntax is the same as `fnval(csapi(x,y),xx)`.

This command is essentially the MATLAB function `spline`, which, in turn, is a stripped-down version of the Fortran routine `CUBSPL` in `PGS`, except that `csapi` (and now also `spline`) accepts vector-valued data and can handle gridded data.

## Examples

### Interpolant to Two, Three, and Five Points

This example shows how to use the `csapi` command from Curve Fitting Toolbox™ to construct cubic spline interpolants.

### Interpolant to Two Points


The command

```
values = csapi(x,y,xx)
```

returns the values at  $xx$  of the cubic spline interpolant to the given data  $(x, y)$ , using the not-a-knot end condition. This interpolant is a piecewise cubic function with break sequence  $x$ , whose cubic pieces join together to form a function with two continuous derivatives. The "not-a-knot" end condition means that, at the first and last interior break, even the third derivative is continuous (up to round-off error).

Specifying only two data points results in a straight line interpolant.

```
x = [0 1];  
y = [2 0];  
xx = linspace(0,6,121);  
plot(xx,csapi(x,y,xx),'k-',x,y,'ro')  
title('Interpolant to Two Points')
```




### Interpolant to Three Points

If you specify three data points, the function outputs a parabola.

```
x = [2 3 5];  
y = [1 0 4];  
plot(xx,csapi(x,y,xx),'k-',x,y,'ro')  
title('Interpolant to Three Points')
```






### Interpolant to Five Points

More generally, if you specify four or five data points, the function outputs a cubic spline.

```
x = [1 1.5 2 4.1 5];  
y = [1 -1 1 -1 1];  
plot(xx,csapi(x,y,xx),'k-',x,y,'ro')  
title('Cubic Spline Interpolant to Five Points')
```




### Plot Bicubic Spline Interpolant to Ricker Wavelet

Up to rounding errors, and assuming that  $x$  is a vector with at least four entries, the statement `pp = csapi(x,y)` puts the same spline into `pp` as the following statement, except that the description of the spline obtained this second way does not use breaks at  $x(2)$  and  $x(n-1)$ :

```
pp = fn2fm(spapi(augknt(x([1 3:(end-2) end]),4),x,y), "pp");
```

As a simple bivariate example, plot a bicubic spline interpolant to a Ricker wavelet.


```
x = .0001 + (-4:.2:4);
y = -3:.2:3;
[yy,xx] = meshgrid(y,x);
r = pi*sqrt(xx.^2+yy.^2);
z = sin(r)./r;
bcs = csapi({x,y},z);
fnplt(bcs)
axis([-5 5 -5 5 -.5 1])
```



Since MATLAB® considers the entry  $z(i, j)$  as the value at  $(x(j), y(i))$ , the code reverses  $x$  and  $y$  in the call to `meshgrid`. The Curve Fitting Toolbox® instead follows the Approximation Theory standard whereas  $z(i, j)$  is the value at  $(x(i), y(j))$ .

For this reason, you have to be cautious when you are plotting values of such a bivariate spline with the aid of the MATLAB `mesh` function, as shown here:

```
xf = linspace(x(1),x(end),41);  
yf = linspace(y(1),y(end),41);  
mesh(xf,yf,fnval(bcs,{xf,yf})).'
```



Note the use of the transpose of the matrix of values obtained from `fncval`.

## Input Arguments

### **x — Data sites**

vector | cell array

Data sites of data values  $y$  to be fit, specified as a vector or as a cell array for multivariate data. Spline  $f$  is created with knots at each data site  $x$  such that  $f(x(j)) = y(:, j)$  for all values of  $j$ .

For multivariate, gridded data, you can specify  $x$  as a cell array that specifies the data site in each variable dimension:  $f(x1(i), x2(j), \dots, xn(k)) = y(:, i, j, \dots, k)$ .

Data Types: `single` | `double`

### **y — Data values to fit**

vector | matrix | array

Data values to fit during creation of the spline, specified as a vector, matrix, or array. Data values  $y(:, j)$  can be scalars, matrices, or  $n$ -dimensional arrays. Data values given at the same data site  $x$  are averaged.

Data Types: `single` | `double`

### **xx — Evaluation points**

vector | cell array

Evaluation points over which the spline is evaluated, specified as a vector or as a cell array of vectors for multivariate data. Spline evaluation is performed using `fnval`.

Data Types: `single` | `double`

## Output Arguments

### **pp** — Spline in `ppform`

spline structure

Spline in `ppform`, returned as a structure with these fields. For more information on `ppform`, see `The ppform` on page 10-8.

### **Form** — Form of spline

`pp`

Form of the spline, returned as `pp`. `pp` indicates that the spline is given in piecewise polynomial form.

### **Breaks** — Knot locations of spline

vector | cell array

Knot positions of the spline, returned as a vector or as a cell array of vectors for multivariate data. Vectors contain strictly increasing elements that represent the start and end of each of the intervals over which the polynomial pieces are defined.

### **Coefs** — Coefficients of polynomials

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

### **Pieces** — Number of polynomial pieces

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

### **Order** — Order of polynomials

scalar | vector

Order of the polynomial function describing each polynomial piece of the spline, returned as a scalar or as a vector containing the order in each variable for multivariate data.

### **Dim** — Dimensionality

scalar

Dimensionality of the target function, returned as a scalar.

### **values** — Evaluated spline

vector | matrix | array

Evaluated spline, returned as a vector or as a matrix or array for multivariate data. The spline is evaluated at the given evaluation points `xx`.

## Algorithms

`csapi` is an implementation of the Fortran routine `CUBSPL` from *PGS*.

The algorithm constructs and solves the relevant tridiagonal linear system using the MATLAB sparse matrix capability.

The algorithm also uses the not-a-knot end condition, forcing the first and second polynomial piece of the interpolant to coincide, as well as the second-to-last and the last polynomial piece.

## Version History

**Introduced in R2006b**

### See Also

`csape` | `spapi` | `spline`

### Topics

“Introducing Spline Fitting” on page 8-2

## csaps

Cubic smoothing spline

### Syntax

```
pp = csaps(x,y)
pp = csaps(x,y,p)
pp = csaps(x,y,p,[],w)
values = csaps(x,y,p,xx)
values = csaps(x,y,p,xx,w)
[ ___ ] = csaps({x1,...,xm},y, ___ )
[ ___ ,P] = csaps( ___ )
```

### Description

---

**Note** For a simpler but less flexible method to generate smoothing splines, try the Curve Fitter app or the `fit` function.

---

`pp = csaps(x,y)` returns the cubic smoothing spline interpolation to the given data  $(x,y)$  in `pp` form. The value of spline  $f$  at data site  $x(j)$  approximates the data value  $y(:,j)$  for  $j = 1:\text{length}(x)$ .

The smoothing spline  $f$  minimizes

$$p \sum_{j=1}^n w_j \left| y_j - f(x_j) \right|^2 \quad + \quad (1-p) \int \lambda(t) \left| D^2 f(t) \right|^2 dt$$

error measure
roughness measure

Here,  $n$  is the number of entries of  $x$  and the integral is over the smallest interval containing all the entries of  $x$ .  $y_j$  and  $x_j$  refer to the  $j$ th entries of  $y$  and  $x$ , respectively.  $D^2 f$  denotes the second derivative of the function  $f$ .

The default values for the error measure weights  $w_j$  are 1. The default value for the piecewise constant weight function  $\lambda$  in the roughness measure is the constant function 1. By default, `csaps` chooses a value for the smoothing parameter  $p$  based on the given data sites  $x$ .

To evaluate a smoothing spline outside its basic interval, you must first extrapolate it. Use the command `pp = fnxtr(pp)` to ensure that the second derivative is zero outside the interval spanned by the data sites.

`pp = csaps(x,y,p)` specifies the smoothing parameter  $p$ . You can also supply the roughness measure weights  $\lambda$  by providing  $p$  as a vector whose first entry is  $p$  and  $i$ th entry is the value of  $\lambda$  on the interval  $(x(i-1),x(i))$ .

`pp = csaps(x,y,p,[],w)` also specifies the weights  $w$  in the error measure.

`values = csaps(x,y,p,xx)` uses the smoothing parameter  $p$  and returns the values of the smoothing spline evaluated at the points  $xx$ . This syntax is the same as `fnval(csaps(x,y,p),xx)`.

`values = csaps(x,y,p,xx,w)` uses the smoothing parameter `p` and the error measure weights `w`, and returns the values of the smoothing spline evaluated at the points `xx`. This syntax is the same as `fnval(csaps(x,y,p,[],w),xx)`

`[ ___ ] = csaps({x1,...,xm},y, ___)` provides the ppform of an  $m$ -variate tensor-product smoothing spline to data on the rectangular grid described by  $\{x_1, \dots, x_m\}$ . You can use this syntax with any of the arguments in the previous syntaxes.

`[ ___,P] = csaps( ___)` also returns the value of the smoothing parameter used in the final spline result whether or not you specify `p`. This syntax is useful for experimentation in which you can start with `[pp,P] = csaps(x,y)` and obtain a reasonable first guess for `p`.

## Examples

### Fit Splines with Different Smoothing Parameters

Fit smoothing splines using the `csaps` function with different values for the smoothing parameter `p`. Use values of `p` between the extremes of 0 and 1 to see how they affect the shape and closeness of the fitted spline.

Load the titanium data set.

```
[x, y] = titanium();
```

When `p = 0`, `s0` is the least-squares straight line fit to the data. When `p = 1`, `s1` is the variational, or natural, cubic spline interpolant.


For  $0 < p < 1$ , `sp` is a smoothing spline that is a trade-off between the two extremes: smoother than the interpolant `s1` and closer to the data than the straight line `s0`.

```
p = 0.00009;
```

```
s0 = csaps(x,y,0);
sp = csaps(x,y,p);
s1 = csaps(x,y,1);
```

```
figure
fnplt(s0);
hold on
fnplt(sp);
fnplt(s1);
plot(x,y,'ko');
hold off
title('Smoothing splines with different values for p');
legend('p = 0', ['p = ' num2str( p )], 'p = 1', 'Location', 'northwest')
```





### Adjust Smoothing Parameters and Weights

Adjust the smoothing parameter, error measure weights, and roughness measure weights.

Create a sine curve with noise.

```
x = linspace(0,2*pi,21); y = sin(x)+(rand(1,21)-.5)*.3;
```

Fit a smoothing spline to the data. Specify the smoothing parameter  $p = 0.4$  and error measure weights  $w$  that vary across the data.

```
pp = csaps(x,y,0.4,[],[ones(1,10), repmat(5,1,10), 0]);
```

The function returns a smooth fit to the noisy data that is much closer to the data in the right half because of the much larger error measure weight there. Note that the error weighting of zero for the last data point excludes this point from the fit.


Now fit a smoothing spline using the same data, smoothing parameter and error measure weights, but with adjusted roughness measure weights.

```
pp1 = csaps(x,y, [.4,ones(1,10), repmat(.2,1,10)], [], ...
             [ones(1,10), repmat(5,1,10), 0]);
```

The roughness measure weight is only 0.2 in the right half of the interval. Correspondingly, the fit is rougher but closer on the right side of the data (except for the last data point, which is ignored).

Plot both fits for comparison.

```
figure
hold on
fnplt(pp, 'b');
fnplt(pp1, 'r--')
plot(x,y,'ok')
hold off
ylim([-1.5 1.5])
title(['Cubic smoothing spline, with right half treated ',...
      'differently'])
legend('Larger error weight', 'Larger error and smaller roughness weight')
```



### Smooth Bivariate Data


Fit a smoothing spline to bivariate data generated by the peaks function with added uniform noise. Use `csaps` to obtain the new, smoothed data points and the smoothing parameters `csaps` determines for the fit.

Create the grid. For this example, the grid is a 51-by-61 uniform grid.

```
x = {linspace(-2,3,51),linspace(-3,3,61)};
[xx,yy] = ndgrid(x{1},x{2});
```

Generate the noisy data using the `peaks` function and random numbers in the interval  $\left[-\frac{1}{2}, \frac{1}{2}\right]$ .

```
y = peaks(xx, yy);  
noisy = y + (rand(size(y)) - 0.5);  
figure  
surf(xx,yy,noisy)  
axis off
```




Fit the data. Use `csaps` to obtain the smoothed data values evaluated over the grid `x` and the default smoothing parameter used in the fit.

```
[sval,p] = csaps(x,noisy,[],x);
```

The plot of the fit shows that some roughness remains. Note that you must transpose the array `sval`.


```
figure  
surf(x{1},x{2},sval.')
```

```
axis off
```



For a somewhat smoother approximation, specify a value for  $p$  that is slightly smaller than the `csaps` default value.

```
ssval = csaps(x, noisy, .996, x);  
figure  
surf(x{1}, x{2}, ssval. ')  
axis off
```



## Input Arguments

### **x — Data sites**

vector | cell array

Data sites of data values  $y$  to be fit, specified as a vector or as a cell array for multivariate data. Spline  $f$  is created with knots at each data site  $x$  such that  $f(x(j)) = y(:, j)$  for all values of  $j$ .

For multivariate, gridded data, you can specify  $x$  as a cell array that specifies the data site in each variable dimension:  $f(x1(i), x2(j), \dots, xn(k)) = y(:, i, j, \dots, k)$ .

Data Types: single | double

### **y — Data values to fit**

vector | matrix | array

Data values to fit during creation of the spline, specified as a vector, matrix, or array. Data values  $y(:, j)$  can be scalars, matrices, or  $n$ -dimensional arrays. Data values given at the same data site  $x$  are averaged.

Data Types: single | double

### **p — Smoothing parameter**

scalar in the range  $[0, 1]$  | vector | cell array | empty array

Smoothing parameter, specified as a scalar value between 0 and 1 or as a cell array of values for multivariate data. You can also specify values for the roughness measure weights  $\lambda$  by providing  $p$  as a vector. To provide roughness measure weights for multivariate data, use a cell array of vectors. If you provide an empty array, the function chooses a default value for  $p$  based on the data sites  $x$  and the default value of 1 for the roughness measure weight  $\lambda$ .

The smoothing parameter determines the relative weight to place on the contradictory demands of having  $f$  be smooth or having  $f$  be close to the data. For  $p = 0$ ,  $f$  is the least-squares straight-line fit to the data. For  $p = 1$ ,  $f$  is the variational, or natural, cubic spline interpolant. As  $p$  moves from 0 to 1, the smoothing spline changes from one extreme to the other.

The favorable range for  $p$  is often near  $1/(1 + h^3/6)$ , where  $h$  is the average spacing of the data sites. The function chooses a default value for  $p$  within this range. For uniformly spaced data, you can expect a close fit with  $p = 1/(1 + h^3/60)$  and some satisfactory smoothing with  $p = 1/(1 + h^3/0.6)$ . You can input  $p > 1$ , but this choice leads to a smoothing spline even rougher than the variational cubic spline interpolant.

If the input  $p$  is negative or empty, then the function uses the default value for  $p$ .

You can specify the roughness measure weights  $\lambda$  alongside the smoothing parameter by providing  $p$  as a vector. This vector must be the same size as  $x$ , with the  $i$ th entry the value of  $\lambda$  on the interval  $(x(i-1) \dots x(i))$ , for  $i = 2:\text{length}(x)$ . The first entry of the input vector  $p$  is the desired value of the smoothness parameter  $p$ . By providing roughness measure weights, you can make the resulting smoothing spline smoother (with larger weight values) or closer to the data (with smaller weight values) in different parts of the interval. Roughness measure weights must be nonnegative.

If you have difficulty choosing  $p$  but have some feeling for the size of the noise in  $y$ , consider using `spaps(x, y, tol)` instead. This function chooses  $p$  such that the roughness measure is as small as possible, subject to the condition that the error measure does not exceed `tol`. In this case, the error measure usually equals the specified value for `tol`.

Data Types: `single` | `double`

#### **w — Error measure weights**

vector | cell array

Error measure weights  $w$  in the error measure, specified as a vector of nonnegative entries of the same size as  $x$ .

The default value for the weight vector  $w$  in the error measure is `ones(size(x))`.

#### **xx — Evaluation points**

vector | cell array

Evaluation points over which the spline is evaluated, specified as a vector or as a cell array of vectors for multivariate data. Spline evaluation is performed using `fncval`.

Data Types: `single` | `double`

## **Output Arguments**

#### **pp — Spline in `ppform`**

spline structure

Spline in `ppform`, returned as a structure with these fields.

**Form — Form of spline**

pp

Form of the spline, returned as pp. pp indicates that the spline is given in piecewise polynomial form.

**Breaks — Knot locations of spline**

vector | cell array

Knot positions of the spline, returned as a vector or as a cell array of vectors for multivariate data. Vectors contain strictly increasing elements that represent the start and end of each of the intervals over which the polynomial pieces are defined.

**Coefs — Coefficients of polynomials**

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

**Pieces — Number of polynomial pieces**

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

**Order — Order of polynomials**

scalar | vector

Order of the polynomial function describing each polynomial piece of the spline, returned as a scalar or as a vector containing the order in each variable for multivariate data.

**Dim — Dimensionality**

scalar

Dimensionality of the target function, returned as a scalar.

**values — Evaluated spline**

vector | matrix | array

Evaluated spline, returned as a vector or as a matrix or array for multivariate data. The spline is evaluated at the given evaluation points xx.

**P — Smoothing parameter**

scalar | cell array

Smoothing parameter used to calculate the spline, returned as a scalar or as a cell array of scalar values for multivariate data. P is between 0 and 1.

**Algorithms**

csaps is an implementation of the Fortran routine `SMOOTH` from *PGS*.

The calculation of the smoothing spline requires solving a linear system whose coefficient matrix has the form  $p*A + (1-p)*B$ , with the matrices A and B depending on the data sites x. The default value of p makes  $p*\text{trace}(A)$  equal  $(1-p)*\text{trace}(B)$ .

## **Version History**

**Introduced before R2006a**

### **See Also**

spap2 | spaps | tpaps



## cscvn

“Natural” or periodic interpolating cubic spline curve

### Syntax

```
curve = cscvn(points)
```

### Description

`curve = cscvn(points)` returns a parametric variational, or *natural*, cubic spline curve (in ppform) passing through the given sequence points  $(:j)$ ,  $j = 1:\text{end}$ . The parameter value  $t(j)$  for the  $j$ -th point follows the Eugene Lee's [1] centripetal scheme, as accumulated square root of chord length:

$$\sum_{i < j} \sqrt{\| \text{points}(:, i + 1) - \text{points}(:, i) \|_2}$$

If the first and last point coincide and there are no other repeated points) then the function constructs a periodic cubic spline curve. However, double points result in corners.


### Examples

#### Plot Interpolating Cubic Spline Curves

This example shows how to construct and plot several different interpolating cubic spline curves using the `cscvn` function.


This code generates a sequence of points and then plots the cubic spline generated from the `cscvn` function. The chosen points are marked as circles:

```
points=[0 1 1 0 -1 -1 0 0; 0 0 1 2 1 0 -1 -2];
fnplt(cscvn(points)); hold on,
plot(points(1,:),points(2:,:),'o'), hold off
```




This code plots a circular curve through the four vertices of the standard diamond (because of the periodic boundary conditions enforced):

```
fnplt(cscvn( [1 0 -1 0 1; 0 1 0 -1 0] ))
```




This code shows a corner at the double point as well as at the curve endpoint:

```
fnplt(cscvn( [1 0 -1 -1 0 1;0 1 0 0 -1 0] ))
```



Finally, this code generates a closed curve with one double point, which results in a corner. Dedicate this to your loved ones.

```
c=fnplt(cscvn([0 .82 .92 0 0 -.92 -.82 0; .66 .9 0 ...  
-.83 -.83 0 .9 .66])); fill(c(1,:),c(2,:), 'r'), axis equal
```



## Input Arguments

### **points** — Sequence of points

scalar | vector | matrix

Sequence of points at which the parametric "natural" cubic spline interpolates to, specified as a scalar, vector, or matrix.

## Output Arguments

### **curve** — Spline in ppform

spline structure

Spline in ppform, returned as a structure with these fields.

### **Form** — Form of spline

pp

Form of the spline, returned as pp. pp indicates that the spline is given in piecewise polynomial form.

### **Breaks** — Knot locations of spline

vector | cell array

Knot positions of the spline, returned as a vector or as a cell array of vectors for multivariate data. Vectors contain strictly increasing elements that represent the start and end of each of the intervals over which the polynomial pieces are defined.

### Coefs — Coefficients of polynomials

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

### Pieces — Number of polynomial pieces

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

### Order — Order of polynomials

scalar | vector

Order of the polynomial function describing each polynomial piece of the spline, returned as a scalar or as a vector containing the order in each variable for multivariate data.

### Dim — Dimensionality

scalar

Dimensionality of the target function, returned as a scalar.

## Algorithms

`cscvn` determines the break sequence `t` as

$$t_k = \begin{cases} 0, & k = 1 \\ \sum_{i=1}^{k-1} \left( \sum_{j=1}^d (p_{i+1,j} - p_{i,j})^2 \right)^{\frac{1}{4}}, & k > 1 \end{cases}$$

where  $t_k$  is the element at position  $k$  in `t`,  $1 \leq k \leq n-1$ , and  $p$  is the transpose of the  $d$ -by- $n$  matrix points. If `points` contains repeated points, `cscvn` uses `csape` with either periodic or variational end conditions to construct the smooth pieces. `cscvn` returns the break sequence `t` in the `breaks` field of the curve output argument.

## Version History

Introduced in R2006b

## References

- [1] E. T. Y. Lee. "Choosing nodes in parametric curve interpolation." *Computer-Aided Design* 21 (1989), 363-370.

## See Also

`csape` | `fnplt` | `getcurve`

**Topics**

“Introducing Spline Fitting” on page 8-2

“The ppform” on page 10-8

## datastats

Data statistics

### Syntax

```
xds = datastats(x)
[xds,yds] = datastats(x,y)
```

### Description

`xds = datastats(x)` returns statistics for the column vector `x` to the structure `xds`. Fields in `xds` are listed in the table below.

| Field  | Description                        |
|--------|------------------------------------|
| num    | The number of data values          |
| max    | The maximum data value             |
| min    | The minimum data value             |
| mean   | The mean value of the data         |
| median | The median value of the data       |
| range  | The range of the data              |
| std    | The standard deviation of the data |

`[xds,yds] = datastats(x,y)` returns statistics for the column vectors `x` and `y` to the structures `xds` and `yds`, respectively. `xds` and `yds` contain the fields listed in the table above. `x` and `y` must be of the same size.

### Examples

Compute statistics for the census data in `census.mat`:

```
load census
[xds,yds] = datastats(cdate,pop)
xds =
    num: 21
    max: 1990
    min: 1790
    mean: 1890
    median: 1890
    range: 200
    std: 62.048
yds =
    num: 21
    max: 248.7
    min: 3.9
    mean: 85.729
    median: 62.9
    range: 244.8
    std: 78.601
```



## Tips

If  $x$  or  $y$  contains complex values, only the real parts are used in computing the statistics. Data containing `Inf` or `NaN` are processed using the usual MATLAB rules.

## Version History

Introduced before R2006a

## See Also

`excludedata` | `smooth`

## dependnames

Dependent variable of `cf`, `sfit`, or `fitttype` object

### Syntax

```
dep = dependnames(fun)
```

### Description

`dep = dependnames(fun)` returns the (single) dependent variable name of the `cf`, `sfit`, or `fitttype` object `fun` as a 1-by-1 cell array of character vectors `dep`.

### Examples

```
f1 = fitttype('a*x^2+b*exp(n*x)');  
dep1 = dependnames(f1)  
dep1 =  
    'y'
```

```
f2 = fitttype('a*x^2+b*exp(n*x)', 'dependent', 'power');  
dep2 = dependnames(f2)  
dep2 =  
    'power'
```

## Version History

Introduced in R2006b

### See Also

`indepnames` | `fitttype` | `formula`

# differentiate

Differentiate `cfit` or `sfit` object

## Syntax

```
fx = differentiate(F0, X)
[fx, fxx] = differentiate(F0, X)
[fx, fy] = differentiate(F0, X, Y)
[fx, fy] = differentiate(F0, [X, Y])
[fx, fy, fxx, fxy, fyy] = differentiate(F0, ...)
```

## Description

---

**Note** Use these syntaxes for `cfit` objects.

---

`fx = differentiate(F0, X)` differentiates the `cfit` object `F0` at the points specified by the vector `X` and returns the result in `fx`.

`[fx, fxx] = differentiate(F0, X)` differentiates the `cfit` object `F0` at the points specified by the vector `X` and returns the result in `fx` and the second derivative in `fxx`.

---

**Note** Use these syntaxes for `sfit` objects.

---

`[fx, fy] = differentiate(F0, X, Y)` differentiates the surface `F0` at the points specified by `X` and `Y` and returns the result in `fx` and `fy`.

`F0` is a surface fit (`sfit`) object generated by the `fit` function.

`X` and `Y` must be double-precision arrays and the same size and shape as each other.

All return arguments are the same size and shape as `X` and `Y`.

If `F0` represents the surface  $z = f(x, y)$ , then `FX` contains the derivatives with respect to  $x$ , that is,  $\frac{df}{dx}$ , and `FY` contains the derivatives with respect to  $y$ , that is,  $\frac{df}{dy}$ .

`[fx, fy] = differentiate(F0, [X, Y])`, where `X` and `Y` are column vectors, allows you to specify the evaluation points as a single argument.

`[fx, fy, fxx, fxy, fyy] = differentiate(F0, ...)` computes the first and second derivatives of the surface fit object `F0`.

`fxx` contains the second derivatives with respect to  $x$ , that is,  $\frac{\partial^2 f}{\partial x^2}$ .

`fxy` contains the mixed second derivatives, that is,  $\frac{\partial^2 f}{\partial x \partial y}$ .

fyy contains the second derivatives with respect to y, that is,  $\frac{\partial^2 f}{\partial y^2}$ .

## Examples

### Find the Derivatives of a Curve Using the differentiate Function

Create a baseline sinusoidal signal.

```
xdata = (0:.1:2*pi)';  
y0 = sin(xdata);
```

Add response-dependent Gaussian noise to the signal.

```
noise = 2*y0.*randn(size(y0));  
ydata = y0 + noise;
```

Fit the noisy data with a custom sinusoidal model.


```
f = fitype('a*sin(b*x)');  
fit1 = fit(xdata,ydata,f,'StartPoint',[1 1]);
```

Find the derivatives of the fit at the predictors.

```
[d1,d2] = differentiate(fit1,xdata);
```


Plot the data, the fit, and the derivatives.

```
subplot(3,1,1)  
plot(fit1,xdata,ydata) % cfit plot method  
subplot(3,1,2)  
plot(xdata,d1,'m') % double plot method  
grid on  
legend('1st derivative')  
subplot(3,1,3)  
plot(xdata,d2,'c') % double plot method  
grid on  
legend('2nd derivative')
```



You can also compute and plot derivatives directly with the `cfitsystem` plot method, as follows:

```
figure
plot(fit1,xdata,ydata,{'fit','deriv1','deriv2'})
```



The plot method, however, does not return data on the derivatives, unlike the `differentiate` method.

### Find the Derivatives of a Surface Using the `differentiate` Function

You can use the `differentiate` method to compute the gradients of a fit and then use the `quiver` function to plot these gradients as arrows. This example plots the gradients over the top of a contour plot.

Create the derivation points and fit the data.

```
x = [0.64;0.95;0.21;0.71;0.24;0.12;0.61;0.45;0.46;...
0.66;0.77;0.35;0.66];
y = [0.42;0.84;0.83;0.26;0.61;0.58;0.54;0.87;0.26;...
0.32;0.12;0.94;0.65];
z = [0.49;0.051;0.27;0.59;0.35;0.41;0.3;0.084;0.6;...
0.58;0.37;0.19;0.19];
fo = fit( [x, y], z, 'poly32', 'normalize', 'on' );
[xx, yy] = meshgrid( 0:0.04:1, 0:0.05:1 );
```

Compute the gradients of the fit using the `differentiate` function.


```
[fx, fy] = differentiate( fo, xx, yy );
```

Use the `quiver` function to plot the gradients.

```

plot( fo, 'Style', 'Contour' );
hold on
h = quiver( xx, yy, fx, fy, 'r', 'LineWidth', 2 );
hold off
colormap( copper )

```



If you want to use derivatives in an optimization, you can, for example, implement an objective function for `fmincon` as follows.

```

function [z, g, H] = objectiveWithHessian( xy )
% The input xy represents a single evaluation point
z = f( xy );
if nargin > 1
[fx, fy, fxx, fxy, fyy] = differentiate( f, xy );
g = [fx, fy];
H = [fxx, fxy; fxy, fyy];
end
end

```

## Input Arguments

### **F0 — cfit function**

`cfit` | `sfit`

Function to differentiate, specified as a `cfit` object for curves or as a `sfit` object for surfaces.

### **X — Differentiation points**

array

Points at which to differentiate the function, specified as a vector. For surfaces, this argument must have the same size and shape of **Y**.

### **Y — Differentiation points**

array

Points at which to differentiate the function, specified as a vector. For surfaces, this argument must have the same size and shape of **X**.

## Output Arguments

### **fx — First derivative with respect to x**

vector

First derivative of the function, returned as a vector of the same size and shape of **X** and **Y**.

If **F0** is a surface,  $z = f(x, y)$ , then **fx** contains the derivatives with respect to  $x$ .

### **fxx — Second derivative with respect to x**

vector

Second derivative of the function, returned as a vector of the same size and shape of **X** and **Y**.

If **F0** is a surface,  $z = f(x, y)$ , then **fxx** contains the second derivatives with respect to  $x$ .

### **fy — First derivative with respect to y**

vector

First derivative of the function, returned as a vector of the same size and shape of **X** and **Y**.

If **F0** is a surface,  $z = f(x, y)$ , then **fy** contains the derivatives with respect to  $y$ .

### **fyy — Second derivative with respect to y**

vector

Second derivative of the function, returned as a vector of the same size and shape of **X** and **Y**.

If **F0** is a surface,  $z = f(x, y)$ , then **fyy** contains the second derivatives with respect to  $y$ .

### **fxxy — Mixed second derivative**

vector

Mixed second derivative of the function, returned as a vector of the same size and shape of **X** and **Y**.



## Tips

For library models with closed forms, the toolbox calculates derivatives analytically. For all other models, the toolbox calculates the first derivative using the centered difference quotient

$$\frac{df}{dx} = \frac{f(x + \Delta x) - f(x - \Delta x)}{2\Delta x}$$

where  $x$  is the value at which the toolbox calculates the derivative,  $\Delta x$  is a small number (on the order of the cube root of `eps`),  $f(x + \Delta x)$  is `fun` evaluated at  $x + \Delta x$ , and  $f(x - \Delta x)$  is `fun` evaluated at  $x - \Delta x$ .

The toolbox calculates the second derivative using the expression

$$\frac{d^2f}{dx^2} = \frac{f(x + \Delta x) + f(x - \Delta x) - 2f(x)}{(\Delta x)^2}$$

The toolbox calculates the mixed derivative for surfaces using the expression

$$\frac{\partial^2 f}{\partial x \partial y}(x, y) = \frac{f(x + \Delta x, y + \Delta y) - f(x - \Delta x, y + \Delta y) - f(x + \Delta x, y - \Delta y) + f(x - \Delta x, y - \Delta y)}{4\Delta x \Delta y}$$

## Version History

Introduced before R2006a

### See Also

`fit` | `plot` | `integrate`

### Topics

"Introducing Spline Fitting" on page 8-2

## excludedata

Exclude data from fit

### Syntax

```
tf = excludedata(x,y,'box',box)
tf = excludedata(x,y,'domain',domain)
tf = excludedata(x,y,'range',range)
tf = excludedata(x,y,'indices',indices)
```

### Description

`tf = excludedata(x,y,'box',box)` returns a logical array that indicates which elements are outside the box in the xy-plane specified by `box`. The elements of `tf` equal 1 for data points outside the box and 0 for data points inside the box. To exclude data when fitting a curve using `fit`, specify `tf` as the 'Exclude' value.

`tf = excludedata(x,y,'domain',domain)` identifies data points that have x-values outside the interval domain.

`tf = excludedata(x,y,'range',range)` identifies the data points with y-values outside the interval range.

`tf = excludedata(x,y,'indices',indices)` identifies the data points with indices equal to `indices`.

### Examples

#### Visualize Exclusion Rules

Visualize exclusion rules using random data.

Generate random x and y data.


```
xdata = -3 + 6*rand(1,1e4);
ydata = -3 + 6*rand(1,1e4);
```

As an example, exclude data that is either inside the box `[-1 1 -1 1]` or outside the domain `[-2 2]`.

```
outliers1 = ~excludedata(xdata,ydata,'box',[-1 1 -1 1]);
outliers2 = excludedata(xdata,ydata,'domain',[-2 2]);
outliers = outliers1|outliers2;
```

Plot the data that is not excluded. The white area corresponds to regions that are excluded.

```
plot(xdata(~outliers),ydata(~outliers),'.')
axis([-3 3 -3 3])
axis square
```




### Exclude Data from Curve Fit

Load the vote counts and county names for the state of Florida from the 2000 U.S. presidential election.

```
load flvote2k
```

Use the vote counts for the two major party candidates, Bush and Gore, as predictors for the vote counts for the third-party candidate Buchanan, and plot the scatters:

```
plot(bush,buchanan,'rs')
hold on
plot(gore,buchanan,'bo')
legend('Bush data','Gore data')
```



Assume a model where a fixed proportion of Bush or Gore voters choose to vote for Buchanan.

```
f = fitype({'x'})
```

```
f =
  Linear model:
  f(a,x) = a*x
```

Exclude the data from absentee voters, who did not use the controversial “butterfly” ballot.


```
nobutterfly = strcmp(counties, 'Absentee Ballots');
```

Perform a bisquare weights robust fit of the model to the two data sets, excluding absentee voters.

```
bushfit = fit(bush,buchanan,f,'Exclude',nobutterfly,'Robust','on');
gorefit = fit(gore,buchanan,f,'Exclude',nobutterfly,'Robust','on');
```

Robust fits give outliers a low weight, so large residuals from a robust fit can be used to identify the outliers.

```
figure
plot(bushfit,bush,buchanan,'rs','residuals')
hold on
plot(gorefit,gore,buchanan,'bo','residuals')
```



Calculate the residuals.

```
bushres = buchanan - feval(bushfit,bush);
goreres = buchanan - feval(gorefit,gore);
```

Identify large residuals as those outside the range [-500 500].

```
bushoutliers = excludedata(bush,bushres, 'range', [-500 500]);
goreoutliers = excludedata(gore,goreres, 'range', [-500 500]);
```

Display the counties corresponding to the outliers. Miami-Dade and Broward counties correspond to the largest predictor values. Palm Beach county, the only county in the state to use the “butterfly” ballot, corresponds to the largest residual values.

```
counties(bushoutliers)
```

```
ans = 2x1 cell
    {'Miami-Dade'}
    {'Palm Beach'}
```

```
counties(goreoutliers)
```

```
ans = 3x1 cell
    {'Broward'   }
    {'Miami-Dade'}
    {'Palm Beach'}
```

## Input Arguments

### **x — Data sites**

numeric vector

Data sites of data values, specified as a numeric vector.

### **y — Data values**

numeric vector

Data values, specified as a numeric vector.

### **box — Box to find data outside of**

numeric vector with four elements

Box to find data outside of, specified as a numeric vector [xmin xmax ymin ymax] with four elements.

Example: [-1 1 0 2]

### **domain — Domain to find data outside of**

numeric vector with two elements

Domain to find data outside of, specified as a numeric vector [xmin xmax] with two elements.

Example: [-1 1]

### **range — Range to find data outside of**

numeric vector with two elements

Range to find data outside of, specified as a numeric vector [ymin ymax] with two elements.

Example: [3 4]

### **indices — Indices of data points to find**

numeric vector

Indices of data points to find, specified as a numeric vector.

Example: [3 7 9]

## Version History

Introduced before R2006a

## See Also

fit | fitoptions

## feval

Evaluate `cfit`, `sfit`, or `fittype` object

### Syntax

```
y = feval(cfun,x)
z = feval(sfun,[x,y])
z = feval(sfun,x,y)
y = feval(ffun,coeff1,coeff2,...,x)
z = feval(ffun,coeff1,coeff2,...,x,y)
```

### Description

---

**Note** You can use `feval` to evaluate fits, but you can treat fit objects as functions and call `feval` indirectly using this syntax instead:

```
y = cfun(x)           % cfit objects;
z = sfun(x,y)         % sfit objects
z = sfun([x, y])     % sfit objects
y = ffun(coef1,coef2,...,x) % curve fittype objects;
z = ffun(coef1,coef2,...,x,y) % surface fittype objects;
```

Alternatively, you can use the `feval` method to evaluate the estimated function, either at your original data points, or at new locations. The latter is referred to as interpolation or prediction, depending on the type of model. You can also use `feval` to extrapolate the estimated function's value at new locations that are not within the range of the original data.

---

`y = feval(cfun,x)` evaluates the `cfit` object `cfun` at the predictor values in the column vector `x` and returns the response values in the column vector `y`.

`z = feval(sfun,[x,y])` evaluates the `sfit` object `sfun` at the predictor values in the two column matrix `[x,y]` and returns the response values in the column vector `z`.

`z = feval(sfun,x,y)` evaluates the `sfit` object `sfun` at the predictor values in the matrices `x` and `y` that must be the same size. It returns the response values in the matrix `z` that will be the same size as `x` and `y`.

`y = feval(ffun,coeff1,coeff2,...,x)` assigns the coefficients `coeff1`, `coeff2`, etc. to the `fittype` object `ffun`, evaluates it at the predictor values in the column vector `x`, and returns the response values in the column vector `y`. `ffun` cannot be a `cfit` object in this syntax. To evaluate `cfit` objects, use the first syntax.

`z = feval(ffun,coeff1,coeff2,...,x,y)` achieves a similar result for a `fittype` object for a surface.

### Examples

### Evaluate `fittype` and `cfits` objects using the `confint` function

Create the `fittype` and `cfits` objects, and a random matrix of predictor values.

```
f = fittype('a*x^2+b*exp(n*x)');  
c = cfits(f,1,10.3,-1e2);  
X = rand(2)
```

```
X =  
    0.0579    0.8132  
    0.3529    0.0099
```

To evaluate the `fittype` object, `f`, call the `feval` function.

```
y1 = feval(f,1,10.3,-1e2,X)
```

```
y1 =  
    0.0349    0.6612  
    0.1245    3.8422
```

Alternatively, you can treat fit objects as functions and call `feval` indirectly using this syntax.

```
y1 = f(1,10.3,-1e2,X)
```

```
y1 =  
    0.0349    0.6612  
    0.1245    3.8422
```

Now evaluate the `cfits` object, `c`.

```
y2 = feval(c,X)
```

```
y2 =  
    0.0349  
    0.1245  
    0.6612  
    3.8422
```

Alternatively, call `feval` indirectly.

```
y2 = c(X)
```

```
y2 =  
    0.0349  
    0.1245  
    0.6612  
    3.8422
```

## Input Arguments

### **cfun** — `cfits` function

`cfits`

Function to evaluate, specified as a `cfits` object.

### **sfun** — `sfits` function

`sfits`

Function to evaluate, specified as an `sfits` object.



**ffun – fittype function**

fittype

Function to evaluate, specified as a fittype object.

**x – Evaluation points**

vector | matrix

Points at which to evaluate the function, specified as a vector or matrix.

**y – Evaluation points**

vector | matrix

Points at which to evaluate the function, specified as a vector or matrix.

**coeff1, coeff2, ... – Coefficients**

scalar

One or more coefficients assigned to the fittype object ffun, specified as scalars.

**Output Arguments****y – Response values**

column vector

Response values of the function evaluated at the predictors values in the column vector x, returned as a column vector.

**z – Response values**

matrix

Response values of the function evaluated at the predictors values in the two column matrix [x,y], returned as a matrix.

**Version History****Introduced before R2006a****See Also**

fit | fittype | cfit

**Topics**

“Introducing Spline Fitting” on page 8-2

## fit

Fit curve or surface to data

### Syntax

```
fitobject = fit(x,y,fitType)
fitobject = fit([x,y],z,fitType)
fitobject = fit(x,y,fitType,fitOptions)
fitobject = fit(x,y,fitType,Name=Value)
[fitobject,gof] = fit(x,y,fitType)
[fitobject,gof,output] = fit(x,y,fitType)
```

### Description

`fitobject = fit(x,y,fitType)` creates the fit to the data in `x` and `y` with the model specified by `fitType`.

`fitobject = fit([x,y],z,fitType)` creates a surface fit to the data in vectors `x`, `y`, and `z`.

`fitobject = fit(x,y,fitType,fitOptions)` creates a fit to the data using the algorithm options specified by the `fitOptions` object.

`fitobject = fit(x,y,fitType,Name=Value)` creates a fit to the data using the library model `fitType` with additional options specified by one or more `Name=Value` pair arguments. Use `fitoptions` to display available property names and default values for the specific library model.

`[fitobject,gof] = fit(x,y,fitType)` returns goodness-of-fit statistics in the structure `gof`.

`[fitobject,gof,output] = fit(x,y,fitType)` returns fitting algorithm information in the structure `output`.

### Examples

#### Fit a Quadratic Curve

Load the census sample data set.

```
load census;
```

The vectors `pop` and `cdate` contain data for the population size and the year the census was taken, respectively.

Fit a quadratic curve to the population data.

```
f=fit(cdate,pop,'poly2')
```


```
f =
  Linear model Poly2:
  f(x) = p1*x^2 + p2*x + p3
  Coefficients (with 95% confidence bounds):
```

```
p1 = 0.006541 (0.006124, 0.006958)
p2 = -23.51 (-25.09, -21.93)
p3 = 2.113e+04 (1.964e+04, 2.262e+04)
```

`f` contains the results of the fit, including coefficient estimates with 95% confidence bounds.

Plot the fit in `f` together with a scatter plot of the data.

```
plot(f,cdate,pop)
```



The plot shows that the fitted curve closely follows the population data.

### Fit a Polynomial Surface

Load the `franke` sample data set.

```
load franke
```

The vectors `x`, `y`, and `z` contain data generated from Franke's bivariate test function, with added noise and scaling.

Fit a polynomial surface to the data. Specify a degree of two for the `x` terms and degree of three for the `y` terms.

```
sf = fit([x, y],z,'poly23')
```

```


Linear model Poly23:
sf(x,y) = p00 + p10*x + p01*y + p20*x^2 + p11*x*y + p02*y^2 + p21*x^2*y
          + p12*x*y^2 + p03*y^3
Coefficients (with 95% confidence bounds):
p00 =      1.118   (0.9149, 1.321)
p10 =  -0.0002941 (-0.000502, -8.623e-05)
p01 =      1.533   (0.7032, 2.364)
p20 =  -1.966e-08 (-7.084e-08, 3.152e-08)
p11 =   0.0003427 (-0.0001009, 0.0007863)
p02 =     -6.951  (-8.421, -5.481)
p21 =   9.563e-08 (6.276e-09, 1.85e-07)
p12 =  -0.0004401 (-0.0007082, -0.0001721)
p03 =      4.999   (4.082, 5.917)

```

`sf` contains the results of the fit, including coefficient estimates with 95% confidence bounds.

Plot the fit in `sf` together with a scatterplot of the data.

```
plot(sf,[x,y],z)
```




### Fit a Surface Using Variables in a MATLAB Table

Load the `franke` data and convert it to a MATLAB® table.

```
load franke
T = table(x,y,z);
```

Specify the variables in the table as inputs to the fit function, and plot the fit.

```
f = fit([T.x, T.y],T.z,'linearinterp');  
plot( f, [T.x, T.y], T.z )
```



### Create Fit Options and Fit Type Before Fitting

Load and plot the data, create fit options and fit type using the `fittype` and `fioptions` functions, then create and plot the fit.

Load and plot the data in `census.mat`.

```
load census  
plot(cdate,pop,'o')
```



Create a fit options object and a fit type for the custom nonlinear model  $y = a(x - b)^n$ , where  $a$  and  $b$  are coefficients and  $n$  is a problem-dependent parameter.

```
fo = fitoptions('Method','NonlinearLeastSquares',...
               'Lower',[0,0],...
               'Upper',[Inf,max(cdate)],...
               'StartPoint',[1 1]);
ft = fittype('a*(x-b)^n','problem','n','options',fo);
```

Fit the data using the fit options and a value of  $n = 2$ .

```
[curve2,gof2] = fit(cdate,pop,ft,'problem',2)
```

```
curve2 =
  General model:
  curve2(x) = a*(x-b)^n
  Coefficients (with 95% confidence bounds):
    a =    0.006092 (0.005743, 0.006441)
    b =    1789 (1784, 1793)
  Problem parameters:
    n =          2
```

```
gof2 = struct with fields:
  sse: 246.1543
  rsquare: 0.9980
  dfe: 19
  adjrsquare: 0.9979
```

```
rmse: 3.5994
```

Fit the data using the fit options and a value of  $n = 3$ .


```
[curve3,gof3] = fit(cdate,pop,ft,'problem',3)
```

```
curve3 =  
  General model:  
  curve3(x) = a*(x-b)^n  
  Coefficients (with 95% confidence bounds):  
    a = 1.359e-05 (1.245e-05, 1.474e-05)  
    b = 1725 (1718, 1731)  
  Problem parameters:  
    n = 3
```

```
gof3 = struct with fields:  
    sse: 232.0058  
    rsquare: 0.9981  
    dfe: 19  
    adjrsquare: 0.9980  
    rmse: 3.4944
```

Plot the fit results with the data.

```
hold on  
plot(curve2,'m')  
plot(curve3,'c')  
legend('Data','n=2','n=3')  
hold off
```



### Fit Multiple Polynomials

Load the carbon12alpha nuclear reaction sample data set.


```
load carbon12alpha
```

`angle` is a vector of emission angles in radians. `counts` is a vector of raw alpha particle counts that correspond to the angles in `angle`.

Display a scatter plot of the counts plotted against the angles.

```
scatter(angle,counts)
```





The scatter plot shows that the counts oscillate as the angle increases between 0 and 4.5. To fit a polynomial model to the data, specify the `fitType` input argument as "poly#" where # is an integer from one to nine. You can fit models of up to nine degrees. See "List of Library Models for Curve and Surface Fitting" on page 4-10 for more information.


Fit a fifth-degree, seventh-degree, and ninth-degree polynomial to the nuclear reaction data. Return the goodness-of-fit statistics for each fit.

```
[f5,gof5] = fit(angle,counts,"poly5");
[f7,gof7] = fit(angle,counts,"poly7");
[f9,gof9] = fit(angle,counts,"poly9");
```

Generate a vector of query points between 0 and 4.5 by using the `linspace` function. Evaluate the polynomial fits at the query points, and then plot them together with the nuclear reaction data.

```
xq = linspace(0,4.5,1000);
```

```
figure
hold on
scatter(angle,counts,"k")
plot(xq,f5(xq))
plot(xq,f7(xq))
plot(xq,f9(xq))
ylim([-100,550])
legend("original data","fifth-degree polynomial","seventh-degree polynomial","ninth-degree polynomial")
```



The plot indicates that the ninth-degree polynomial follows the data most closely.

Display the goodness-of-fit statistics for each fit by using the `struct2table` function.

```
gof = struct2table([gof5 gof7 gof9],RowNames=["f5" "f7" "f9"])
```

```
gof=3x5 table
```

|    | sse        | rsquare | dfe | adjrsquare | rmse   |
|----|------------|---------|-----|------------|--------|
| f5 | 1.0901e+05 | 0.54614 | 18  | 0.42007    | 77.82  |
| f7 | 32695      | 0.86387 | 16  | 0.80431    | 45.204 |
| f9 | 3660.2     | 0.98476 | 14  | 0.97496    | 16.169 |

The sum-of-squares error (SSE) for the ninth-degree polynomial fit is smaller than the SSEs for the fifth-degree and seventh-degree fits. This result confirms that the ninth-degree polynomial follows the data most closely.

### Specify Normalize and Robust Options

Load the census sample data set. Fit a cubic polynomial and specify the `Normalize` (center and scale) and `Robust` fitting options.

```


load census;
f = fit(cdate,pop,'poly3','Normalize','on','Robust','Bisquare')

f =
Linear model Poly3:
f(x) = p1*x^3 + p2*x^2 + p3*x + p4
where x is normalized by mean 1890 and std 62.05
Coefficients (with 95% confidence bounds):
p1 =    -0.4619   (-1.895, 0.9707)
p2 =     25.01   (23.79, 26.22)
p3 =     77.03   (74.37, 79.7)
p4 =     62.81   (61.26, 64.37)

```

Plot the fit.

```
plot(f,cdate,pop)
```



### Fit a Curve Defined by a File

Define a function in a file and use it to create a fit type and fit a curve.

Define a function in a MATLAB file.

```

function y = piecewiseLine(x,a,b,c,d,k)
% PIECEWISELINE A line made of two pieces

```

```

% that is not continuous.

y = zeros(size(x));

% This example includes a for-loop and if statement
% purely for example purposes.
for i = 1:length(x)
    if x(i) < k,
        y(i) = a + b.* x(i);
    else
        y(i) = c + d.* x(i);
    end
end
end

```

Save the file.

Define some data, create a fit type specifying the function `piecewiseLine`, create a fit using the fit type `ft`, and plot the results.

```

x = [0.81;0.91;0.13;0.91;0.63;0.098;0.28;0.55;...
0.96;0.96;0.16;0.97;0.96];
y = [0.17;0.12;0.16;0.0035;0.37;0.082;0.34;0.56;...
0.15;-0.046;0.17;-0.091;-0.071];
ft = fittype( 'piecewiseLine( x, a, b, c, d, k )' )
f = fit( x, y, ft, 'StartPoint', [1, 0, 1, 0, 0.5] )
plot( f, x, y )

```

### Exclude Points from Fit

Load some data and fit a custom equation specifying points to exclude. Plot the results.

Load data and define a custom equation and some start points.

```

[x, y] = titanium;

gaussEqn = 'a*exp(-((x-b)/c)^2)+d'

gaussEqn =
'a*exp(-((x-b)/c)^2)+d'

startPoints = [1.5 900 10 0.6]

startPoints = 1x4

    1.5000    900.0000    10.0000    0.6000

```

Create two fits using the custom equation and start points, and define two different sets of excluded points, using an index vector and an expression. Use `Exclude` to remove outliers from your fit.

```

f1 = fit(x',y',gaussEqn,'Start', startPoints, 'Exclude', [1 10 25])

f1 =
General model:
f1(x) = a*exp(-((x-b)/c)^2)+d
Coefficients (with 95% confidence bounds):

```

```

a =      1.493 (1.432, 1.554)
b =     897.4 (896.5, 898.3)
c =      27.9 (26.55, 29.25)
d =     0.6519 (0.6367, 0.6672)

```

```
f2 = fit(x',y',gaussEqn,'Start', startPoints, 'Exclude', x < 800)
```

```

f2 =
General model:
f2(x) = a*exp(-((x-b)/c)^2)+d
Coefficients (with 95% confidence bounds):
a =      1.494 (1.41, 1.578)
b =     897.4 (896.2, 898.7)
c =      28.15 (26.22, 30.09)
d =     0.6466 (0.6169, 0.6764)


```

Plot both fits.

```

plot(f1,x,y)
title('Fit with data points 1, 10, and 25 excluded')


```



```

figure
plot(f2,x,y)
title('Fit with data points excluded such that x < 800')

```



### Exclude Points and Plot Fit Showing Excluded Data

You can define the excluded points as variables before supplying them as inputs to the fit function. The following steps recreate the fits in the previous example and allow you to plot the excluded points as well as the data and the fit.

Load data and define a custom equation and some start points.

```
[x, y] = titanium;
gaussEqn = 'a*exp(-((x-b)/c)^2)+d'
gaussEqn =
'a*exp(-((x-b)/c)^2)+d'
startPoints = [1.5 900 10 0.6]
startPoints = 1x4
    1.5000    900.0000    10.0000    0.6000
```

Define two sets of points to exclude, using an index vector and an expression.


```
exclude1 = [1 10 25];
exclude2 = x < 800;
```

Create two fits using the custom equation, startpoints, and the two different excluded points.


```
f1 = fit(x',y',gaussEqn,'Start', startPoints, 'Exclude', exclude1);
f2 = fit(x',y',gaussEqn,'Start', startPoints, 'Exclude', exclude2);
```

Plot both fits and highlight the excluded data.

```
plot(f1,x,y,exclude1)
title('Fit with data points 1, 10, and 25 excluded')
```



```
figure;
plot(f2,x,y,exclude2)
title('Fit with data points excluded such that x < 800')
```




For a surface fitting example with excluded points, load some surface data and create and plot fits specifying excluded data.


```
load franke
f1 = fit([x y],z,'poly23', 'Exclude', [1 10 25]);
f2 = fit([x y],z,'poly23', 'Exclude', z > 1);

figure
plot(f1, [x y], z, 'Exclude', [1 10 25]);
title('Fit with data points 1, 10, and 25 excluded')
```





```
figure
plot(f2, [x y], z, 'Exclude', z > 1);
title('Fit with data points excluded such that z > 1')
```



### Compare Extrapolation Methods


Generate some noisy data using the `membrane` and `randn` functions.

```
n = 41;  
M = membrane(1,20)+0.02*randn(n);  
[X,Y] = meshgrid(1:n);
```

The matrix `M` contains data for the L-shaped membrane with added noise. The matrices `X` and `Y` contain the row and column index values, respectively, for the corresponding elements in `M`.

Display a surface plot of the data.

```
figure(1)  
surf(X,Y,M)
```



The plot shows a wrinkled L-shaped membrane. The wrinkles in the membrane are caused by the noise in the data.

Fit two surfaces through the wrinkled membrane using linear interpolation. For the first surface, specify the linear extrapolation method. For the second surface, specify the extrapolation method as nearest neighbor.


```
flinextrap = fit([X(:),Y(:)],M(:),"linearinterp",ExtrapolationMethod="linear");
fnearextrap = fit([X(:),Y(:)],M(:),"linearinterp",ExtrapolationMethod="nearest");
```

Investigate the differences between the extrapolation methods by using the `meshgrid` function to evaluate the fits at query points extending outside the convex hull of the X and Y data.


```
[Xq,Yq] = meshgrid(-10:50);
Zlin = flinextrap(Xq,Yq);
Znear = fnearextrap(Xq,Yq);
```

Plot the evaluated fits.

```
figure(2)
surf(Xq,Yq,Zlin)
title("Linear Extrapolation")
xlabel("X")
ylabel("Y")
zlabel("M")
```



```
figure(3)
surf(Xq,Yq,Znear)
title("Nearest Neighbor Extrapolation")
xlabel("X")
ylabel("Y")
zlabel("M")
```



The linear extrapolation method generates spikes outside of the convex hull. The plane segments that form the spikes follow the gradient at points on the convex hull's border. The nearest neighbor extrapolation method uses the data on the border to extend the surface in each direction. This method of extrapolation generates waves that mimic the border.

### Return Goodness-of-Fit Statistics and Fitting Algorithm Information

Fit a smoothing spline curve, and return goodness-of-fit statistics and information about the fitting algorithm.

Load the `enso` sample data set. The `enso` sample data set contains data for the monthly averaged atmospheric pressure differences between Easter Island and Darwin, Australia.


```
load enso;
```

Fit a smoothing spline curve to the data in `month` and `pressure`, and return goodness-of-fit statistics and the output structure.

```
[curve,gof,output] = fit(month,pressure,"smoothingspline");
```


Plot the fitted curve with the data used to fit the curve.

```
plot(curve,month,pressure);
xlabel("Month");
ylabel("Pressure");
```




Plot the residuals against the x-data (month).

```
plot(curve,month,pressure,"residuals")  
xlabel("Month")  
ylabel("Residuals")
```



Use the residuals data in the output structure to plot the residuals against the y-data (pressure). To access the residuals field of output, use dot notation.

```
residuals = output.residuals;  
plot( pressure,residuals, ".")  
xlabel("Pressure")  
ylabel("Residuals")
```




### Fit a Single-Term Exponential

Generate data with an exponential trend, and then fit the data using the first equation in the curve fitting library of exponential models (a single-term exponential). Plot the results.

```
x = (0:0.2:5)';  
y = 2*exp(-0.2*x) + 0.5*randn(size(x));  
f = fit(x,y, 'expl');  
plot(f,x,y)
```





### Fit a Custom Model Using an Anonymous Function

You can use anonymous functions to make it easier to pass other data into the `fit` function.

Load data and set `Emax` to 1 before defining your anonymous function:

```
data = importdata( 'OpioidHypnoticSynergy.txt' );
Propofol      = data.data(:,1);
Remifentanil  = data.data(:,2);
Algoetry      = data.data(:,3);
Emax = 1;
```

Define the model equation as an anonymous function:

```
Effect = @(IC50A, IC50B, alpha, n, x, y) ...
    Emax*( x/IC50A + y/IC50B + alpha*( x/IC50A )...
    .* ( y/IC50B ) ).^n ./(( x/IC50A + y/IC50B + ...
    alpha*( x/IC50A ) .* ( y/IC50B ) ).^n + 1);
```

Use the anonymous function `Effect` as an input to the `fit` function, and plot the results:

```
AlgoetryEffect = fit( [Propofol, Remifentanil], Algoetry, Effect, ...
    'StartPoint', [2, 10, 1, 0.8], ...
    'Lower', [-Inf, -Inf, -5, -Inf], ...
```

```
'Robust', 'LAR' )
plot( AlgometryEffect, [Propofol, Remifentanil], Algometry )
```

For more examples using anonymous functions and other custom models for fitting, see the `fittype` function.

### Find Coefficient Order to Set Start Points and Bounds

For the properties `Upper`, `Lower`, and `StartPoint`, you need to find the order of the entries for coefficients.

Create a fit type.

```
ft = fittype('b*x^2+c*x+a');
```

Get the coefficient names and order using the `coeffnames` function.

```
coeffnames(ft)
```

```
ans = 3x1 cell
      {'a'}
      {'b'}
      {'c'}
```

Note that this is different from the order of the coefficients in the expression used to create `ft` with `fittype`.

Load data, create a fit and set the start points.

```
load enso
fit(month,pressure,ft,'StartPoint',[1,3,5])
```

```
ans =
  General model:
  ans(x) = b*x^2+c*x+a
  Coefficients (with 95% confidence bounds):
  a =      10.94   (9.362, 12.52)
  b =   0.0001677 (-7.985e-05, 0.0004153)
  c =    -0.0224 (-0.06559, 0.02079)
```

This assigns initial values to the coefficients as follows:  $a = 1$ ,  $b = 3$ ,  $c = 5$ .

Alternatively, you can get the fit options and set start points and lower bounds, then refit using the new options.

```
options = fitoptions(ft)
```

```
options =
  nlsqoptions with properties:

      StartPoint: []
           Lower: []
           Upper: []
      Algorithm: 'Trust-Region'
  DiffMinChange: 1.0000e-08
```

```

DiffMaxChange: 0.1000
  Display: 'Notify'
  MaxFunEvals: 600
  MaxIter: 400
  TolFun: 1.0000e-06
  TolX: 1.0000e-06
  Robust: 'Off'
  Normalize: 'off'
  Exclude: []
  Weights: []
  Method: 'NonlinearLeastSquares'

```

```

options.StartPoint = [10 1 3];
options.Lower = [0 -Inf 0];
fit(month,pressure,ft,options)

```

```

ans =
  General model:
  ans(x) = b*x^2+c*x+a
  Coefficients (with 95% confidence bounds):
  a =      10.23   (9.448, 11.01)
  b =   4.335e-05  (-1.82e-05, 0.0001049)
  c =   5.523e-12  (fixed at bound)

```

## Input Arguments

### **x** — Data to fit

matrix

Data to fit, specified as a matrix with either one (curve fitting) or two (surface fitting) columns. You can specify variables in a MATLAB table using `tablename.varname`. Cannot contain `Inf` or `NaN`. Only the real parts of complex data are used in the fit.

Example: `x`

Example: `[x,y]`

Data Types: `double`

### **y** — Data to fit

vector

Data to fit, specified as a column vector with the same number of rows as `x`. You can specify a variable in a MATLAB table using `tablename.varname`. Cannot contain `Inf` or `NaN`. Only the real parts of complex data are used in the fit.

Use `prepareCurveData` or `prepareSurfaceData` if your data is not in column vector form.

Data Types: `double`

### **z** — Data to fit

vector

Data to fit, specified as a column vector with the same number of rows as `x`. You can specify a variable in a MATLAB table using `tablename.varname`. Cannot contain `Inf` or `NaN`. Only the real parts of complex data are used in the fit.

Use `prepareSurfaceData` if your data is not in column vector form. For example, if you have 3 matrices, or if your data is in grid vector form, where `length(X) = n`, `length(Y) = m` and `size(Z) = [m,n]`.

Data Types: `double`

### **fitType — Model type to fit**

character vector | string scalar | string array | cell array of character vectors | anonymous function | `fittype`

Model type to fit, specified as a character vector or string scalar representing a library model name or MATLAB expression, a string array of linear model terms or a cell array of character vectors of such terms, an anonymous function, or a `fittype` created with the `fittype` function. You can use any of the valid first inputs to `fittype` as an input to `fit`.

For a list of library model names, see “Model Names and Equations” on page 4-11.

To fit a custom model, use a MATLAB expression, a cell array of linear model terms, or an anonymous function. You can also create a `fittype` using the `fittype` function, and then use it as the value of the `fitType` input argument. For an example, see “Fit a Custom Model Using an Anonymous Function” on page 13-103. For examples that use linear model terms, see the `fittype` function.

Example: `"poly2"`

### **fitOptions — Algorithm options**

`fitoptions`

Algorithm options constructed using the `fitoptions` function. This is an alternative to specifying name-value pair arguments for fit options.

### **Name-Value Pair Arguments**

Specify optional pairs of arguments as `Name1=Value1, ..., NameN=ValueN`, where `Name` is the argument name and `Value` is the corresponding value. Name-value arguments must appear after other arguments, but the order of the pairs does not matter.

*Before R2021a, use commas to separate each name and value, and enclose Name in quotes.*

Example: `Lower=[0,0], Upper=[Inf,max(x)], StartPoint=[1 1]` specifies fitting method, bounds, and start points.

### **Options for All Fitting Methods**

#### **Normalize — Option to center and scale data**

`'off'` (default) | `'on'`

Option to center and scale the data, specified as the comma-separated pair consisting of `'Normalize'` and `'on'` or `'off'`.

Data Types: `char`

#### **Exclude — Points to exclude from fit**

expression | index vector | logical vector | empty

Points to exclude from the fit, specified as the comma-separated pair consisting of `'Exclude'` and one of:

- An expression describing a logical vector, e.g.,  $x > 10$ .
- A vector of integers indexing the points you want to exclude, e.g., [1 10 25].
- A logical vector for all data points where true represents an outlier, created by `excludedata`.

For an example, see “Exclude Points from Fit” on page 13-90.

Data Types: `logical` | `double`

### **Weights — Weights for fit**

[ ] (default) | vector

Weights for the fit, specified as the comma-separated pair consisting of 'Weights' and a vector the same size as the response data  $y$  (curves) or  $z$  (surfaces).

Data Types: `double`

### **problem — Values to assign to problem-dependent constants**

cell array | `double`

Values to assign to the problem-dependent constants, specified as the comma-separated pair consisting of 'problem' and a cell array with one element per problem dependent constant. For details, see `fittype`.

Data Types: `cell` | `double`

### **Smoothing Options**

#### **SmoothingParam — Smoothing parameter**

scalar value in the range (0,1)

Smoothing parameter, specified as the comma-separated pair consisting of 'SmoothingParam' and a scalar value between 0 and 1. The default value depends on the data set. Only available if the fit type is `smoothingspline`.

Data Types: `double`

#### **Span — Proportion of data points to use in local regressions**

0.25 (default) | scalar value in the range (0,1)

Proportion of data points to use in local regressions, specified as the comma-separated pair consisting of 'Span' and a scalar value between 0 and 1. Only available if the fit type is `lowess` or `loess`.

Data Types: `double`

### **Interpolation Options**

#### **ExtrapolationMethod — Extrapolation method**

"auto" (default) | "none" | "linear" | "nearest" | "thinplate" | "biharmonic" | "pchip" | "cubic"

Extrapolation method for an interpolant fit, specified as one of the following values.

| Value       | Description                                                                                                                                                                                                                                                                                                                                         | Supported Fits                                                                                                                                                                           |
|-------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| "auto"      | Default value for all interpolant fit types. Set <code>ExtrapolationMethod</code> to "auto" to automatically assign an extrapolation method during fitting.                                                                                                                                                                                         | All interpolant fit types and cubicspline curve fits                                                                                                                                     |
| "none"      | No extrapolation. Query points outside of the convex hull of the fitting data evaluate to NaN.<br><br><code>fit</code> sets the extrapolation method to "none" when you set <code>ExtrapolationMethod</code> to "auto" for <code>cubicinterp</code> and <code>linearinterp</code> surface fits.                                                     | Curve fits — <code>cubicspline</code> and <code>pchipinterp</code><br><br>Curve and surface fits — <code>cubicinterp</code> , <code>linearinterp</code> , and <code>nearestinterp</code> |
| "linear"    | Linear extrapolation based on boundary gradients.<br><br><code>fit</code> sets the extrapolation method to "linear" when you set <code>ExtrapolationMethod</code> to "auto" for "linearinterp" curve fits.                                                                                                                                          | Surface fits — <code>cubicinterp</code> and <code>nearestinterp</code><br><br>Curve and surface fits — <code>linearinterp</code>                                                         |
| "nearest"   | Nearest neighbor extrapolation. This method evaluates to the value of the nearest point on the boundary of the fitting data's convex hull.<br><br><code>fit</code> sets the extrapolation method to "nearest" when you set <code>ExtrapolationMethod</code> to "auto" for "nearestinterp" curve and surface fits.                                   | Curve fits — <code>cubicspline</code> and <code>pchipinterp</code><br><br>Curve and surface fits — <code>cubicinterp</code> , <code>linearinterp</code> , and <code>nearestinterp</code> |
| "thinplate" | Thin-plate spline extrapolation. This method extends the thin-plate interpolating spline outside of the fitting data's convex hull. For more information, see <code>tpaps</code> .<br><br><code>fit</code> sets the extrapolation method to "thinplate" when you set <code>ExtrapolationMethod</code> to "auto" for "thinplateinterp" surface fits. | Surface fits — <code>thinplateinterp</code>                                                                                                                                              |

| Value        | Description                                                                                                                                                                                                                                                                                                                                                  | Supported Fits                           |
|--------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------|
| "biharmonic" | <p>Biharmonic spline extrapolation. This method extends the biharmonic interpolating spline outside of the fitting data's convex hull.</p> <p><code>fit</code> sets the extrapolation method to "biharmonic" when you set <code>ExtrapolationMethod</code> to "auto" for "biharmonicinterp" surface fits.</p>                                                | Surface fits — biharmonicinterp          |
| "pchip"      | <p>Piecewise cubic hermite interpolating polynomial (PCHIP) extrapolation. This method extends a shape-preserving PCHIP outside of the fitting data's convex hull. For more information, see pchip.</p> <p><code>fit</code> sets the extrapolation method to "pchip" when you set <code>ExtrapolationMethod</code> to "auto" for pchipinterp curve fits.</p> | Curve fits — pchipinterp                 |
| "cubic"      | <p>Cubic spline extrapolation. This method extends a cubic interpolating spline outside of the fitting data's convex hull.</p> <p><code>fit</code> sets the extrapolation method to "cubic" when you set <code>ExtrapolationMethod</code> to "auto" for cubicinterp and cubicspline curve fits. For more information, see spline.</p>                        | Curve fits — cubicinterp and cubicspline |

Data Types: char | string

### Linear and Nonlinear Least-Squares Options

#### Robust — Robust linear least-squares fitting method

'off' (default) | LAR | Bisquare

Robust linear least-squares fitting method, specified as the comma-separated pair consisting of 'Robust' and one of these values:

- 'LAR' specifies the least absolute residual method.
- 'Bisquare' specifies the bisquare weights method.

Available when the fit type Method is LinearLeastSquares or NonlinearLeastSquares.

Data Types: `char`

### **Lower — Lower bounds on coefficients to be fitted**

[ ] (default) | vector

Lower bounds on the coefficients to be fitted, specified as the comma-separated pair consisting of 'Lower' and a vector. The default value is an empty vector, indicating that the fit is unconstrained by lower bounds. If bounds are specified, the vector length must equal the number of coefficients. Find the order of the entries for coefficients in the vector value by using the `coeffnames` function. For an example, see “Find Coefficient Order to Set Start Points and Bounds” on page 13-104. Individual unconstrained lower bounds can be specified by `-Inf`.

Available when the Method is `LinearLeastSquares` or `NonlinearLeastSquares`.

Data Types: `double`

### **Upper — Upper bounds on coefficients to be fitted**

[ ] (default) | vector

Upper bounds on the coefficients to be fitted, specified as the comma-separated pair consisting of 'Upper' and a vector. The default value is an empty vector, indicating that the fit is unconstrained by upper bounds. If bounds are specified, the vector length must equal the number of coefficients. Find the order of the entries for coefficients in the vector value by using the `coeffnames` function. For an example, see “Find Coefficient Order to Set Start Points and Bounds” on page 13-104. Individual unconstrained upper bounds can be specified by `+Inf`.

Available when the Method is `LinearLeastSquares` or `NonlinearLeastSquares`.

Data Types: `logical`

## **Nonlinear Least-Squares Options**

### **StartPoint — Initial values for the coefficients**

[ ] (default) | vector

Initial values for the coefficients, specified as the comma-separated pair consisting of 'StartPoint' and a vector. Find the order of the entries for coefficients in the vector value by using the `coeffnames` function. For an example, see “Find Coefficient Order to Set Start Points and Bounds” on page 13-104.

If no start points (the default value of an empty vector) are passed to the `fit` function, starting points for some library models are determined heuristically. For rational and Weibull models, and all custom nonlinear models, the toolbox selects default initial values for coefficients uniformly at random from the interval (0,1). As a result, multiple fits using the same data and model might lead to different fitted coefficients. To avoid this, specify initial values for coefficients with a `fitoptions` object or a vector value for the `StartPoint` value.

Available when the Method is `NonlinearLeastSquares`.

Data Types: `double`

### **Algorithm — Algorithm to use for fitting procedure**

'Trust-Region' (default) | 'Levenberg-Marquardt'

Algorithm to use for the fitting procedure, specified as the comma-separated pair consisting of 'Algorithm' and either 'Levenberg-Marquardt' or 'Trust-Region'.



Available when the Method is NonlinearLeastSquares.

Data Types: char

### **DiffMaxChange — Maximum change in coefficients for finite difference gradients**

0.1 (default)

Maximum change in coefficients for finite difference gradients, specified as the comma-separated pair consisting of 'DiffMaxChange' and a scalar.

Available when the Method is NonlinearLeastSquares.

Data Types: double

### **DiffMinChange — Minimum change in coefficients for finite difference gradients**

10<sup>-8</sup> (default)

Minimum change in coefficients for finite difference gradients, specified as the comma-separated pair consisting of 'DiffMinChange' and a scalar.

Available when the Method is NonlinearLeastSquares.

Data Types: double

### **Display — Display option in Command Window**

'notify' (default) | 'final' | 'iter' | 'off'

Display option in the command window, specified as the comma-separated pair consisting of 'Display' and one of these options:

- 'notify' displays output only if the fit does not converge.
- 'final' displays only the final output.
- 'iter' displays output at each iteration.
- 'off' displays no output.

Available when the Method is NonlinearLeastSquares.

Data Types: char

### **MaxFunEvals — Maximum number of evaluations of model allowed**

600 (default)

Maximum number of evaluations of the model allowed, specified as the comma-separated pair consisting of 'MaxFunEvals' and a scalar.

Available when the Method is NonlinearLeastSquares.

Data Types: double

### **MaxIter — Maximum number of iterations allowed for fit**

400 (default)

Maximum number of iterations allowed for the fit, specified as the comma-separated pair consisting of 'MaxIter' and a scalar.

Available when the Method is NonlinearLeastSquares.

Data Types: `double`

### **TolFun — Termination tolerance on model value**

$10^{-6}$  (default)

Termination tolerance on the model value, specified as the comma-separated pair consisting of 'TolFun' and a scalar.

Available when the Method is `NonlinearLeastSquares`.

Data Types: `double`

### **TolX — Termination tolerance on coefficient values**

$10^{-6}$  (default)

Termination tolerance on the coefficient values, specified as the comma-separated pair consisting of 'TolX' and a scalar.

Available when the Method is `NonlinearLeastSquares`.

Data Types: `double`

## **Output Arguments**

### **fitobject — Fit result**

`cf` | `sf`

Fit result, returned as a `cf` (for curves) or `sf` (for surfaces) object. See “Fit Postprocessing” for functions for plotting, evaluating, calculating confidence intervals, integrating, differentiating, or modifying your fit object.

### **gof — Goodness-of-fit statistics**

`gof` structure

Goodness-of-fit statistics, returned as the `gof` structure including the fields in this table.

| Field                   | Value                                                   |
|-------------------------|---------------------------------------------------------|
| <code>sse</code>        | Sum of squares due to error                             |
| <code>rsquare</code>    | R-squared (coefficient of determination)                |
| <code>dfe</code>        | Degrees of freedom in the error                         |
| <code>adjrsquare</code> | Degree-of-freedom adjusted coefficient of determination |
| <code>rmse</code>       | Root mean squared error (standard error)                |

Example: `gof.rmse`

### **output — Fitting algorithm information**

`output` structure

Fitting algorithm information, returned as the `output` structure containing information associated with the fitting algorithm.

Fields depend on the algorithm. For example, the `output` structure for nonlinear least-squares algorithms includes the fields shown in this table.

| Field         | Value                                                                                                                                                                                                                                                                             |
|---------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| numobs        | Number of observations (response values)                                                                                                                                                                                                                                          |
| numparam      | Number of unknown parameters (coefficients) to fit                                                                                                                                                                                                                                |
| residuals     | Vector of raw residuals (observed values minus the fitted values)                                                                                                                                                                                                                 |
| Jacobian      | Jacobian matrix                                                                                                                                                                                                                                                                   |
| exitflag      | Describes the exit condition of the algorithm. Positive flags indicate convergence, within tolerances. Zero flags indicate that the maximum number of function evaluations or iterations was exceeded. Negative flags indicate that the algorithm did not converge to a solution. |
| iterations    | Number of iterations                                                                                                                                                                                                                                                              |
| funcCount     | Number of function evaluations                                                                                                                                                                                                                                                    |
| firstorderopt | Measure of first-order optimality (absolute maximum of gradient components)                                                                                                                                                                                                       |
| algorithm     | Fitting algorithm employed                                                                                                                                                                                                                                                        |

Example: `output.Jacobian`

## Version History

### Introduced before R2006a

#### R2023b: Specify extrapolation method for curve interpolant fits

Starting in 2023b, you can specify additional extrapolation methods for interpolant curve fits by using the `ExtrapolationMethod` name-value argument. For more information, see “Extrapolation for Interpolant Fit Types” on page 6-8.

#### R2023b: Specify sigmoidal and logarithmic fit types

Starting in R2023b, you can specify sigmoidal and logarithmic fit types for curve fits. For more information, see “List of Library Models for Curve and Surface Fitting” on page 4-10.

#### R2023a: Specify extrapolation method for surface interpolant fits

Starting in 2023a, you can specify the extrapolation method for interpolant fits by using the `ExtrapolationMethod` name-value argument. For curve fits, Curve Fitting Toolbox supports only the default extrapolation methods available in previous releases.

## See Also

### Apps

Curve Fitter

### Functions

`fittype` | `fitoptions` | `prepareCurveData` | `prepareSurfaceData` | `feval` | `plot` | `confint`

**Topics**

“Fit Postprocessing”

“List of Library Models for Curve and Surface Fitting” on page 4-10

“Custom Models” on page 5-2

“Parametric Fitting” on page 4-2

# fitoptions

Create or modify fit options object

## Syntax

```
fitOptions = fitoptions
fitOptions = fitoptions(libraryModelName)
fitOptions = fitoptions(libraryModelName,Name,Value)
fitOptions = fitoptions(fitType)
fitOptions = fitoptions(Name,Value)
newOptions = fitoptions(fitOptions,Name,Value)
newOptions = fitoptions(options1,options2)
```

## Description

`fitOptions = fitoptions` creates the default fit options object `fitOptions`.

`fitOptions = fitoptions(libraryModelName)` creates the default fit options object for the library model.

`fitOptions = fitoptions(libraryModelName,Name,Value)` creates fit options for the specified library model with additional options specified by one or more `Name,Value` pair arguments.

`fitOptions = fitoptions(fitType)` gets the fit options object for the specified `fitType`. Use this syntax to work with fit options for custom models.

`fitOptions = fitoptions(Name,Value)` creates fit options with additional options specified by one or more `Name,Value` pair arguments.

`newOptions = fitoptions(fitOptions,Name,Value)` modifies the existing fit options object `fitOptions` and returns updated fit options in `newOptions` with new options specified by one or more `Name,Value` pair arguments.

`newOptions = fitoptions(options1,options2)` combines the existing fit options objects `options1` and `options2` in `newOptions`.

- If `Method` agrees, the nonempty values for the properties in `options2` override the corresponding values in `options1` in `newOptions`.
- If `Method` differs, `newOptions` contains the `options1` value for `Method` and values from `options2` for `Normalize`, `Exclude`, and `Weights`.

## Examples

### Modify Default Fit Options to Normalize Data

Create the default fit options object and set the option to center and scale the data before fitting.

```
options = fitoptions;
options.Normal = 'on'

options =
  basefitoptions with properties:

    Normalize: 'on'
    Exclude: []
    Weights: []
    Method: 'None'
```

### Create Default Fit Options for Gaussian Fit

```
options = fitoptions('gauss2')

options =
  nlsqoptions with properties:

    StartPoint: []
    Lower: [-Inf -Inf 0 -Inf -Inf 0]
    Upper: []
    Algorithm: 'Trust-Region'
    DiffMinChange: 1.0000e-08
    DiffMaxChange: 0.1000
    Display: 'Notify'
    MaxFunEvals: 600
    MaxIter: 400
    TolFun: 1.0000e-06
    TolX: 1.0000e-06
    Robust: 'Off'
    Normalize: 'off'
    Exclude: []
    Weights: []
    Method: 'NonlinearLeastSquares'
```

### Set Polynomial Fit Options

Create fit options for a cubic polynomial and set center and scale and robust fitting options.

```
options = fitoptions('poly3', 'Normalize', 'on', 'Robust', 'Bisquare')

options =
  llsoptions with properties:

    Lower: []
    Upper: []
    Robust: 'Bisquare'
    Normalize: 'on'
    Exclude: []
    Weights: []
    Method: 'LinearLeastSquares'
```

### Create Fit Options for Linear Least Squares

```
options = fitoptions('Method', 'LinearLeastSquares')
```

```
options =
  llsqoptions with properties:

    Lower: []
    Upper: []
    Robust: 'Off'
    Normalize: 'off'
    Exclude: []
    Weights: []
    Method: 'LinearLeastSquares'
```

### Specify Extrapolation Method for Interpolant Fits

Create a `fitoptions` object for a linear interpolant fit with nearest neighbor extrapolation.

```
linearoptions = fitoptions("linearinterp",ExtrapolationMethod="nearest")
```

```
linearoptions =
  linearinteroptions with properties:

    ExtrapolationMethod: 'nearest'
    Normalize: 'off'
    Exclude: []
    Weights: []
    Method: 'LinearInterpolant'
```

Create a second `fitoptions` object for a cubic interpolant fit with nearest neighbor extrapolation.

```
cubicoptions = fitoptions("cubicinterp",ExtrapolationMethod="nearest")
```

```
cubicoptions =
  cubicsplineinteroptions with properties:

    ExtrapolationMethod: 'nearest'
    Normalize: 'off'
    Exclude: []
    Weights: []
    Method: 'CubicSplineInterpolant'
```

You can use the fit options in `linearoptions` to create a `linearinterp` fit object using the `fit` function. Use `cubicoptions` to create a `cubicinterp` fit.

### Use Identical Fit Options in Multiple Fits

Modifying the default fit options object is useful when you want to set the `Normalize`, `Exclude`, or `Weights` properties, and then fit your data using the same options with different fitting methods. For example, the following uses the same fit options to fit different library model types.

```
load census
options = fitoptions;
options.Normalize = 'on';
f1 = fit(cdate,pop,'poly3',options);
f2 = fit(cdate,pop,'expl',options);
f3 = fit(cdate,pop,'cubicspline',options)

f3 =
    Cubic interpolating spline:
        f3(x) = piecewise polynomial computed from p
            with cubic extrapolation
            where x is normalized by mean 1890 and std 62.05
    Coefficients:
        p = coefficient structure
```

### Find and Change the Smoothing Fit Option

Find the smoothing parameter. Data-dependent fit options such as the `smooth` parameter are returned in the third output argument of the `fit` function.

```
load census
[f,gof,out] = fit(cdate,pop,'SmoothingSpline');
smoothparam = out.p
```

```
smoothparam = 0.0089
```

Modify the default smoothing parameter for a new fit.

```
options = fitoptions('Method','SmoothingSpline',...
    'SmoothingParam',0.0098);
[f,gof,out] = fit(cdate,pop,'SmoothingSpline',options);
```


### Apply Coefficient Bounds to Improve Gaussian Fit

Create a Gaussian fit, inspect the confidence intervals, and specify lower bound fit options to help the algorithm.

Create a noisy sum of two Gaussian peaks, one with a small width, and one with a large width.

```
a1 = 1; b1 = -1; c1 = 0.05;
a2 = 1; b2 = 1; c2 = 50;
x = (-10:0.02:10)';
gdata = a1*exp(-((x-b1)/c1).^2) + ...
        a2*exp(-((x-b2)/c2).^2) + ...
        0.1*(rand(size(x))-0.5);
plot(x,gdata)
```





Fit the data using the two-term Gaussian library model.

```
gfit = fit(x,gdata,'gauss2')
```

```
gfit =
```

```
General model Gauss2:
```

```
gfit(x) = a1*exp(-((x-b1)/c1)^2) + a2*exp(-((x-b2)/c2)^2)
```

```
Coefficients (with 95% confidence bounds):
```

```
a1 = -0.145 (-1.486, 1.195)
```

```
b1 = 9.725 (-14.71, 34.15)
```


```
c1 = 7.117 (-15.84, 30.07)
```

```
a2 = 14.06 (-1.958e+04, 1.961e+04)
```

```
b2 = 607.1 (-3.194e+05, 3.207e+05)
```

```
c2 = 376 (-9.739e+04, 9.814e+04)
```

```
plot(gfit,x,gdata)
```



The algorithm is having difficulty, as indicated by the wide confidence intervals for several coefficients.

To help the algorithm, specify lower bounds for the nonnegative amplitudes  $a_1$  and  $a_2$  and widths  $c_1$ ,  $c_2$ .

```
options = fitoptions('gauss2', 'Lower', [0 -Inf 0 0 -Inf 0]);
```

Alternatively, you can set properties of the fit options using the form `options.Property = NewPropertyValue`.


```
options = fitoptions('gauss2');
options.Lower = [0 -Inf 0 0 -Inf 0];
```

Recompute the fit using the bound constraints on the coefficients.

```
gfit = fit(x,gdata,'gauss2',options)
```

```
gfit =
General model Gauss2:
gfit(x) = a1*exp(-((x-b1)/c1)^2) + a2*exp(-((x-b2)/c2)^2)
Coefficients (with 95% confidence bounds):
a1 =      1.005   (0.966, 1.044)
b1 =      -1     (-1.002, -0.9988)
c1 =     0.0491  (0.0469, 0.0513)
a2 =     0.9985  (0.9958, 1.001)
b2 =     0.8059  (0.3879, 1.224)
c2 =     50.6   (46.68, 54.52)
```

```
plot(gfit,x,gdata)
```



This is a much better fit. You can further improve the fit by assigning reasonable values to other properties in the fit options object.

### Copy and Combine Fit Options

Create fit options and set lower bounds.

```
options = fitoptions('gauss2', 'Lower', [0 -Inf 0 0 -Inf 0])
```

```
options =
  nlsqoptions with properties:
    StartPoint: []
      Lower: [0 -Inf 0 0 -Inf 0]
      Upper: []
    Algorithm: 'Trust-Region'
    DiffMinChange: 1.0000e-08
    DiffMaxChange: 0.1000
    Display: 'Notify'
    MaxFunEvals: 600
    MaxIter: 400
    TolFun: 1.0000e-06
    TolX: 1.0000e-06
```

```
    Robust: 'Off'  
    Normalize: 'off'  
    Exclude: []  
    Weights: []  
    Method: 'NonlinearLeastSquares'
```

Make a new copy of the fit options and modify the robust parameter.

```
newoptions = fitoptions(options, 'Robust', 'Bisquare')
```

```
newoptions =  
    nlsqoptions with properties:  
  
    StartPoint: []  
        Lower: [0 -Inf 0 0 -Inf 0]  
        Upper: []  
    Algorithm: 'Trust-Region'  
    DiffMinChange: 1.0000e-08  
    DiffMaxChange: 0.1000  
    Display: 'Notify'  
    MaxFunEvals: 600  
    MaxIter: 400  
    TolFun: 1.0000e-06  
    TolX: 1.0000e-06  
    Robust: 'Bisquare'  
    Normalize: 'off'  
    Exclude: []  
    Weights: []  
    Method: 'NonlinearLeastSquares'
```

Combine fit options.

```
options2 = fitoptions(options, newoptions)
```

```
options2 =  
    nlsqoptions with properties:  
  
    StartPoint: []  
        Lower: [0 -Inf 0 0 -Inf 0]  
        Upper: []  
    Algorithm: 'Trust-Region'  
    DiffMinChange: 1.0000e-08  
    DiffMaxChange: 0.1000  
    Display: 'Notify'  
    MaxFunEvals: 600  
    MaxIter: 400  
    TolFun: 1.0000e-06  
    TolX: 1.0000e-06  
    Robust: 'Bisquare'  
    Normalize: 'off'  
    Exclude: []  
    Weights: []  
    Method: 'NonlinearLeastSquares'
```

## Change Custom Model Fit Options

Create a linear model fit type.

```
lft = fitttype({'x','sin(x)','1'})
lft =
    Linear model:
    lft(a,b,c,x) = a*x + b*sin(x) + c
```

Get the fit options for the fit type lft.

```
fo = fitoptions(lft)
fo =
    llsqoptions with properties:
        Lower: []
        Upper: []
        Robust: 'Off'
        Normalize: 'off'
        Exclude: []
        Weights: []
        Method: 'LinearLeastSquares'
```

Set the normalize fit option.

```
fo.Normalize = 'on'
fo =
    llsqoptions with properties:
        Lower: []
        Upper: []
        Robust: 'Off'
        Normalize: 'on'
        Exclude: []
        Weights: []
        Method: 'LinearLeastSquares'
```

## Input Arguments

### LibraryModelName — Library model to fit

character vector | string scalar

Library model to fit, specified as a character vector or string scalar. This table shows some common examples.

| Library Model Name | Description                |
|--------------------|----------------------------|
| 'poly1'            | Linear polynomial curve    |
| 'poly11'           | Linear polynomial surface  |
| 'poly2'            | Quadratic polynomial curve |

| Library Model Name | Description                       |
|--------------------|-----------------------------------|
| 'linearinterp'     | Piecewise linear interpolation    |
| 'cubicinterp'      | Piecewise cubic interpolation     |
| 'smoothingspline'  | Smoothing spline (curve)          |
| 'lowess'           | Local linear regression (surface) |
| 'log10'            | Base-10 logarithmic curve         |
| 'logistic4'        | Four-parameter logistic curve     |

For a list of library model names, see “Model Names and Equations” on page 4-11.

Example: 'poly2'

Data Types: char | string

### **fitType — Model type to fit**

fittype

Model type to fit, specified as a `fittype` constructed with the `fittype` function. Use this to work with fit options for custom models.

### **fitOptions — Algorithm options**

fitoptions

Algorithm options, specified as a `fitoptions` object created using the `fitoptions` function.

### **options1 — Algorithm options to combine**

fitoptions

Algorithm options to combine, constructed using the `fitoptions` function.

### **options2 — Algorithm options to combine**

fitoptions

Algorithm options to combine, constructed using the `fitoptions` function.

### **Name-Value Pair Arguments**

Specify optional pairs of arguments as `Name1=Value1, ..., NameN=ValueN`, where `Name` is the argument name and `Value` is the corresponding value. Name-value arguments must appear after other arguments, but the order of the pairs does not matter.

*Before R2021a, use commas to separate each name and value, and enclose Name in quotes.*

Example: 'Method', 'NonlinearLeastSquares', 'Lower', [0,0], 'Upper', [Inf,max(x)], 'Startpoint', [1 1] specifies fitting method, bounds, and start points.

### **Options for All Fitting Methods**

#### **Normalize — Option to center and scale data**

'off' (default) | 'on'

Option to center and scale the data, specified as the comma-separated pair consisting of 'Normalize' and 'on' or 'off'.

Data Types: char

**Exclude — Points to exclude from fit**

expression | index vector | logical vector | empty

Points to exclude from the fit, specified as the comma-separated pair consisting of 'Exclude' and one of:

- An expression describing a logical vector, e.g.,  $x > 10$ .
- A vector of integers indexing the points you want to exclude, e.g., [1 10 25].
- A logical vector for all data points where true represents an outlier, created by `excludedata`.

For examples, see `fit`.

**Weights — Weights for fit**

[] (default) | vector

Weights for the fit, specified as the comma-separated pair consisting of 'Weights' and a vector the same size as number of data points.

Data Types: double

**Method — Fitting method**

'None' (default) | 'NearestInterpolant' | 'LinearInterpolant' | 'PchipInterpolant' | 'CubicSplineInterpolant' | ...

Fitting method, specified as the comma-separated pair consisting of 'Method' and one of the fitting methods in this table.

| Fitting Method           | Description                                         |
|--------------------------|-----------------------------------------------------|
| 'NearestInterpolant'     | Nearest neighbor interpolation                      |
| 'LinearInterpolant'      | Linear interpolation                                |
| 'PchipInterpolant'       | Piecewise cubic Hermite interpolation (curves only) |
| 'CubicSplineInterpolant' | Cubic spline interpolation                          |
| 'BiharmonicInterpolant'  | Biharmonic surface interpolation                    |
| 'SmoothingSpline'        | Smoothing spline                                    |
| 'LowessFit'              | Lowess smoothing (surfaces only)                    |
| 'LinearLeastSquares'     | Linear least squares                                |
| 'NonlinearLeastSquares'  | Nonlinear least squares                             |

Data Types: char | string

**Interpolation Options****ExtrapolationMethod — Extrapolation method**

"auto" (default) | "none" | "linear" | "nearest" | "thinplate" | "biharmonic" | "pchip" | "cubic"

Extrapolation method for an interpolant fit, specified as one of the following values:

| Value        | Description                                                                                                                                                                                                    | Supported Fits                                                                                                                                                                           |
|--------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| "auto"       | Default value for all interpolant fit types. Set <code>ExtrapolationMethod</code> to "auto" to automatically assign an extrapolation method when you use the <code>fit</code> function.                        | All interpolant fit types and <code>cubicspline</code> curve fits                                                                                                                        |
| "none"       | No extrapolation. When you use <code>fitOptions</code> with the <code>fit</code> function to evaluate query points outside of the convex hull, <code>fit</code> returns <code>NaN</code> .                     | Curve fits — <code>cubicspline</code> and <code>pchipinterp</code><br><br>Curve and surface fits — <code>cubicinterp</code> , <code>linearinterp</code> , and <code>nearestinterp</code> |
| "linear"     | Linear extrapolation based on boundary gradients                                                                                                                                                               | Surface fits — <code>cubicinterp</code> and <code>nearestinterp</code><br><br>Curve and surface fits — <code>linearinterp</code>                                                         |
| "nearest"    | Nearest neighbor extrapolation. This method evaluates to the value of the nearest point on the boundary of the fitting data's convex hull.                                                                     | Curve fits — <code>cubicspline</code> and <code>pchipinterp</code><br><br>Curve and surface fits — <code>cubicinterp</code> , <code>linearinterp</code> , and <code>nearestinterp</code> |
| "thinplate"  | Thin-plate spline extrapolation. This method extends the thin-plate interpolating spline outside of the fitting data's convex hull. For more information, see <code>tpaps</code> .                             | Surface fits — <code>thinplateinterp</code>                                                                                                                                              |
| "biharmonic" | Biharmonic spline extrapolation. This method extends the biharmonic interpolating spline outside of the fitting data's convex hull.                                                                            | Surface fits — <code>biharmonicinterp</code>                                                                                                                                             |
| "pchip"      | Piecewise cubic hermite interpolating polynomial (PCHIP) extrapolation. This method extends a shape-preserving PCHIP outside of the fitting data's convex hull. For more information, see <code>pchip</code> . | Curve fits — <code>pchipinterp</code>                                                                                                                                                    |
| "cubic"      | Cubic spline extrapolation. This method extends a cubic interpolating spline outside of the fitting data's convex hull.                                                                                        | Curve fits — <code>cubicinterp</code> and <code>cubicspline</code>                                                                                                                       |

Data Types: `char` | `string`



## Smoothing Options

### SmoothingParam — Smoothing parameter

scalar value in the range (0,1)

Smoothing parameter, specified as the comma-separated pair consisting of 'SmoothingParam' and a scalar value between 0 and 1. The default value depends on the data set. Only available if the Method is SmoothingSpline. For more information, see “About Smoothing Splines” on page 6-14.

Data Types: double

### Span — Proportion of data points to use in local regressions

0.25 (default) | scalar value in the range (0,1)

Proportion of data points to use in local regressions, specified as the comma-separated pair consisting of 'Span' and a scalar value between 0 and 1. Only available if the Method is LowessFit.

Data Types: double

## Linear and Nonlinear Least-Squares Options

### Robust — Robust linear least-squares fitting method

'off' (default) | 'LAR' | 'Bisquare'

Robust linear least-squares fitting method, specified as the comma-separated pair consisting of 'Robust' and one of these values:

- 'LAR' specifies the least absolute residual method.
- 'Bisquare' specifies the bisquare weights method.

Available when the Method is LinearLeastSquares or NonlinearLeastSquares.

Data Types: char

### Lower — Lower bounds on coefficients to be fitted

[ ] (default) | vector

Lower bounds on the coefficients to be fitted, specified as the comma-separated pair consisting of 'Lower' and a vector. The default value is an empty vector, indicating that the fit is unconstrained by lower bounds. If bounds are specified, the vector length must equal the number of coefficients. Find the order of the entries for coefficients in the vector value by using the `coeffnames` function. For an example, see `fit`. Individual unconstrained lower bounds can be specified by `-Inf`.

Available when the Method is LinearLeastSquares or NonlinearLeastSquares.

Data Types: double

### Upper — Upper bounds on coefficients to be fitted

[ ] (default) | vector

Upper bounds on the coefficients to be fitted, specified as the comma-separated pair consisting of 'Upper' and a vector. The default value is an empty vector, indicating that the fit is unconstrained by upper bounds. If bounds are specified, the vector length must equal the number of coefficients. Find the order of the entries for coefficients in the vector value by using the `coeffnames` function. For an example, see `fit`. Individual unconstrained upper bounds can be specified by `+Inf`.

Available when the Method is LinearLeastSquares or NonlinearLeastSquares.

Data Types: logical

### **Nonlinear Least-Squares Options**

#### **StartPoint — Initial values for coefficients**

[ ] (default) | vector

Initial values for the coefficients, specified as the comma-separated pair consisting of 'StartPoint' and a vector. Find the order of the entries for coefficients in the vector value by using the `coeffnames` function. For an example, see `fit`.

If no start points (the default value of an empty vector) are passed to the `fit` function, starting points for some library models are determined heuristically. For rational and Weibull models, and all custom nonlinear models, the toolbox selects default initial values for coefficients uniformly at random from the interval (0,1). As a result, multiple fits using the same data and model might lead to different fitted coefficients. To avoid this, specify initial values for coefficients with a vector value for the `StartPoint` property.

Available when the Method is `NonlinearLeastSquares`.

Data Types: double

#### **Algorithm — Algorithm to use for fitting procedure**

'Levenberg-Marquardt' (default) | 'Trust-Region'

Algorithm to use for the fitting procedure, specified as the comma-separated pair consisting of 'Algorithm' and either 'Levenberg-Marquardt' or 'Trust-Region'.

Available when the Method is `NonlinearLeastSquares`.

Data Types: char

#### **DiffMaxChange — Maximum change in coefficients for finite difference gradients**

0.1 (default)

Maximum change in coefficients for finite difference gradients, specified as the comma-separated pair consisting of 'DiffMaxChange' and a scalar.

Available when the Method is `NonlinearLeastSquares`.

Data Types: double

#### **DiffMinChange — Minimum change in coefficients for finite difference gradients**

$10^{-8}$  (default)

Minimum change in coefficients for finite difference gradients, specified as the comma-separated pair consisting of 'DiffMinChange' and a scalar.

Available when the Method is `NonlinearLeastSquares`.

Data Types: double

#### **Display — Display option in the Command Window**

'notify' (default) | 'final' | 'iter' | 'off'

Display option in the command window, specified as the comma-separated pair consisting of 'Display' and one of these options:

- 'notify' displays output only if the fit does not converge.
- 'final' displays only the final output.
- 'iter' displays output at each iteration.
- 'off' displays no output.

Available when the Method is NonlinearLeastSquares.

Data Types: char

### **MaxFunEvals — Maximum number of evaluations of model allowed**

600 (default)

Maximum number of evaluations of the model allowed, specified as the comma-separated pair consisting of 'MaxFunEvals' and a scalar.

Available when the Method is NonlinearLeastSquares.

Data Types: double

### **MaxIter — Maximum number of iterations allowed for fit**

400 (default)

Maximum number of iterations allowed for the fit, specified as the comma-separated pair consisting of 'MaxIter' and a scalar.

Available when the Method is NonlinearLeastSquares.

Data Types: double

### **TolFun — Termination tolerance on model value**

$10^{-6}$  (default)

Termination tolerance on the model value, specified as the comma-separated pair consisting of 'TolFun' and a scalar.

Available when the Method is NonlinearLeastSquares.

Data Types: double

### **TolX — Termination tolerance on coefficient values**

$10^{-6}$  (default)

Termination tolerance on the coefficient values, specified as the comma-separated pair consisting of 'TolX' and a scalar.

Available when the Method is NonlinearLeastSquares.

Data Types: double

## **Output Arguments**

### **fitOptions — Algorithm options**

options object

Algorithm options, returned as an options object.

**newOptions — New algorithm options**

options object

New algorithm options, returned as an options object.

## Version History

**Introduced before R2006a****R2023b: Specify extrapolation method for curve interpolant fits**

Starting in 2023b, you can specify additional extrapolation methods for interpolant curve fits by using the `ExtrapolationMethod` name-value argument. For more information, see “Extrapolation for Interpolant Fit Types” on page 6-8.

**R2023b: Specify sigmoidal and logarithmic fit types**

Starting in R2023b, you can specify sigmoidal and logarithmic fit types for curve fits. For more information, see “List of Library Models for Curve and Surface Fitting” on page 4-10.

**R2023a: fitoptions returns value objects***Behavior change in future release*

Starting in R2023a, `fitoptions` returns value objects instead of handle objects. For more information, see Comparison of Handle and Value Classes.

**R2023a: Specify extrapolation method for surface interpolant fits**

Starting in 2023a, you can specify the extrapolation method for interpolant fits by using the `ExtrapolationMethod` name-value argument. For curve fits, Curve Fitting Toolbox supports only the default extrapolation methods available in previous releases.

## See Also

**Apps**

Curve Fitter

**Functions**`fit` | `fitttype` | `get` | `set` | `setoptions`**Topics**

“Specify Fit Options and Optimized Starting Points” on page 4-5

“Fit Postprocessing”

“List of Library Models for Curve and Surface Fitting” on page 4-10

# fitype

Fit type for curve and surface fitting

## Syntax

```
aFitype = fitype(libraryModelName)

aFitype = fitype(expression)
aFitype = fitype(expression,Name,Value)

aFitype = fitype(linearModelTerms)
aFitype = fitype(linearModelTerms,Name,Value)

aFitype = fitype(anonymousFunction)
aFitype = fitype(anonymousFunction,Name,Value)
```

## Description

`aFitype = fitype(libraryModelName)` creates the `fitype` object `aFitype` for the model specified by `libraryModelName`.

`aFitype = fitype(expression)` creates a fit type for the model specified by the MATLAB expression.

`aFitype = fitype(expression,Name,Value)` constructs the fit type with additional options specified by one or more `Name,Value` pair arguments.

`aFitype = fitype(linearModelTerms)` creates a fit type for a custom linear model with terms specified by the expressions in `linearModelTerms`.

`aFitype = fitype(linearModelTerms,Name,Value)` constructs the fit type with additional options specified by one or more `Name,Value` pair arguments.

`aFitype = fitype(anonymousFunction)` creates a fit type for the model specified by `anonymousFunction`.

`aFitype = fitype(anonymousFunction,Name,Value)` constructs the fit type with additional options specified by one or more `Name,Value` pair arguments.

## Examples

### Create Fit Types for Library Models

Construct fit types by specifying library model names.

Construct a `fitype` object for the cubic polynomial library model.

```
f = fitype('poly3')
```

```
f =
  Linear model Poly3:
  f(p1,p2,p3,p4,x) = p1*x^3 + p2*x^2 + p3*x + p4
```

Construct a fit type for the library model `rat33` (a rational model of the third degree for both the numerator and denominator).

```
f = fittype('rat33')

f =
  General model Rat33:
  f(p1,p2,p3,p4,q1,q2,q3,x) = (p1*x^3 + p2*x^2 + p3*x + p4) /
    (x^3 + q1*x^2 + q2*x + q3)
```

For a list of library model names, see `libraryModelName`.

### Create Custom Nonlinear Model

Create a fit type for a custom nonlinear model, designating `n` as the problem-dependent parameter and `u` as the independent variable.

```
g = fittype("n*u^a",...
          problem="n",...
          independent="u")

g =
  General model:
  g(a,n,u) = n*u^a
```

Create a fit type for a logarithmic fit to some data, use the fit type to create a fit, and then plot the fit.

```
x = linspace(1,100);
y = 7*log(x+5);
myfittype = fittype("a*log(x+b)",...
                  dependent="y",independent="x",...
                  coefficients=["a" "b"])
```


```
myfittype =
  General model:
  myfittype(a,b,x) = a*log(x+b)
```

```
myfit = fit(x',y',myfittype)
```

Warning: Start point not provided, choosing random start point.

```
myfit =
  General model:
  myfit(x) = a*log(x+b)
  Coefficients (with 95% confidence bounds):
  a =          7 (7, 7)
  b =          5 (5, 5)
```

```
plot(myfit,x,y)
```



The plot shows that the fit follows the data.

### Create Custom Linear Model

To use a linear fitting algorithm, specify a cell array of terms.

Identify the linear model terms you need to input to `fitype`:  $a*x + b*\sin(x) + c$ . The model is linear in  $a$ ,  $b$  and  $c$ . It has three terms  $x$ ,  $\sin(x)$  and  $1$  (because  $c=c*1$ ). To specify this model you use this cell array of terms: `LinearModelTerms = {'x', 'sin(x)', '1'}`.

Use the cell array of linear model terms as the input to `fitype`.

```
ft = fitype({'x', 'sin(x)', '1'})
```

```
ft =
  Linear model:
  ft(a,b,c,x) = a*x + b*sin(x) + c
```

Create a linear model fit type for  $a*\cos(x) + b$ .

```
ft2 = fitype({'cos(x)', '1'})
```

```
ft2 =
  Linear model:
  ft2(a,b,x) = a*cos(x) + b
```

Create the fit type again and specify coefficient names.

```
ft3 = fittype({'cos(x)', '1'}, 'coefficients', {'a1', 'a2'})

ft3 =
  Linear model:
  ft3(a1,a2,x) = a1*cos(x) + a2
```

### Fit a Curve Defined by a File

Define a function in a file and use it to create a fit type and fit a curve.

Define a function in a MATLAB file.

```
function y = piecewiseLine(x,a,b,c,d,k)
% PIECEWISELINE  A line made of two pieces
% that is not continuous.

y = zeros(size(x));

% This example includes a for-loop and if statement
% purely for example purposes.
for i = 1:length(x)
    if x(i) < k,
        y(i) = a + b.* x(i);
    else
        y(i) = c + d.* x(i);
    end
end
end
```

Save the file.

Define some data, create a fit type specifying the function `piecewiseLine`, create a fit using the fit type `ft`, and plot the results.

```
x = [0.81;0.91;0.13;0.91;0.63;0.098;0.28;0.55;...
     0.96;0.96;0.16;0.97;0.96];
y = [0.17;0.12;0.16;0.0035;0.37;0.082;0.34;0.56;...
     0.15;-0.046;0.17;-0.091;-0.071];
ft = fittype( 'piecewiseLine( x, a, b, c, d, k )' )
f = fit( x, y, ft, 'StartPoint', [1, 0, 1, 0, 0.5] )
plot( f, x, y )
```

### Create Fit Types Using Anonymous Functions

Create a fit type using an anonymous function.

```
g = fittype( @(a, b, c, x) a*x.^2+b*x+c )
```

Create a fit type using an anonymous function and specify independent and dependent parameters.



```
g = fitype( @(a, b, c, d, x, y) a*x.^2+b*x+c*exp(...
    -(y-d).^2 ), 'independent', {'x', 'y'},...
    'dependent', 'z' );
```

Create a fit type for a surface using an anonymous function and specify independent and dependent parameters, and problem parameters that you will specify later when you call fit.

```
g = fitype( @(a,b,c,d,x,y) a*x.^2+b*x+c*exp( -(y-d).^2 ), ...
    'problem', {'c','d'}, 'independent', {'x', 'y'}, ...
    'dependent', 'z' );
```

### Use an Anonymous Function to Pass in Workspace Data to the Fit

Use an anonymous function to pass workspace data into the `fitype` and `fit` functions.

Create and plot an S-shaped curve. In later steps, you stretch and move this curve to fit to some data.

```
% Breakpoints.
xs = (0:0.1:1).';
% Height of curve at breakpoints.
ys = [0; 0; 0.04; 0.1; 0.2; 0.5; 0.8; 0.9; 0.96; 1; 1];
% Plot S-shaped curve.
xi = linspace( 0, 1, 241 );
plot( xi, interp1( xs, ys, xi, 'pchip' ), 'LineWidth', 2 )
hold on
plot( xs, ys, 'o', 'MarkerFaceColor', 'r' )
hold off
title S-curve
```

Create a fit type using an anonymous function, taking the values from the workspace for the curve breakpoints (`xs`) and the height of the curve at the breakpoints (`ys`). Coefficients are `b` (base) and `h` (height).

```
ft = fitype( @(b, h, x) interp1( xs, b+h*ys, x, 'pchip' ) )
```

Plot the `fitype` specifying example coefficients of base `b=1.1` and height `h=-0.8`.

```
plot( xi, ft( 1.1, -0.8, xi ), 'LineWidth', 2 )
title 'Fitype with b=1.1 and h=-0.8'
```

Load and fit some data, using the fit type `ft` created using workspace values.

```
% Load some data
xdata = [0.012;0.054;0.13;0.16;0.31;0.34;0.47;0.53;0.53;...
    0.57;0.78;0.79;0.93];
ydata = [0.78;0.87;1;1.1;0.96;0.88;0.56;0.5;0.5;0.5;0.63;...
    0.62;0.39];
% Fit the curve to the data
f = fit( xdata, ydata, ft, 'Start', [0, 1] )
% Plot fit
plot( f, xdata, ydata )
title 'Fitted S-curve'
```

### Use Anonymous Functions to Work with Problem Parameters and Workspace Variables

This example shows the differences between using anonymous functions with problem parameters and workspace variable values.

Load data, create a fit type for a curve using an anonymous function with problem parameters, and call `fit` specifying the problem parameters.

```
% Load some data.
xdata = [0.098;0.13;0.16;0.28;0.55;0.63;0.81;0.91;0.91;...
         0.96;0.96;0.96;0.97];
ydata = [0.52;0.53;0.53;0.48;0.33;0.36;0.39;0.28;0.28;...
         0.21;0.21;0.21;0.2];

% Create a fittype that has a problem parameter.
g = fittype( @(a,b,c,x) a*x.^2+b*x+c, 'problem', 'c' )

% Examine coefficients. Observe c is not a coefficient.
coeffnames( g )

% Examine arguments. Observe that c is an argument.
argnames( g )

% Call fit and specify the value of c.
f1 = fit( xdata, ydata, g, 'problem', 0, 'StartPoint', [1, 2] )

% Note: Specify start points in the calls to fit to
% avoid warning messages about random start points
% and to ensure repeatability of results.

% Call fit again and specify a different value of c,
% to get a new fit.
f2 = fit( xdata, ydata, g, 'problem', 1, 'start', [1, 2] )

% Plot results. Observe the specified c constants
% do not make a good fit.
plot( f1, xdata, ydata )
hold on
plot( f2, 'b' )
hold off
```

Modify the previous example to create the same fits using workspace values for variables, instead of using problem parameters. Using the same data, create a fit type for a curve using an anonymous function with a workspace value for variable `c`:

```
% Remove c from the argument list.
try
    g = fittype( @(a,b,x) a*x.^2+b*x+c )
catch e
    disp( e.message )
end

% Observe error because now c is undefined.
% Define c and create fittype:
c = 0;
g1 = fittype( @(a,b,x) a*x.^2+b*x+c )

% Call fit (now no need to specify problem parameter).
f1 = fit( xdata, ydata, g1, 'StartPoint', [1, 2] )
```

```

% Note that this f1 is the same as the f1 above.
% To change the value of c, recreate the fitype.
c = 1;
g2 = fitype( @(a,b,x) a*x.^2+b*x+c ) % uses c = 1
f2 = fit( xdata, ydata, g2, 'StartPoint', [1, 2] )
% Note that this f2 is the same as the f2 above.
% Plot results
plot( f1, xdata, ydata )
hold on
plot( f2, 'b' )
hold off

```

## Input Arguments

### LibraryModelName — Library model to fit

character vector | string scalar

Library model to fit, specified as a character vector or string scalar. This table shows some common examples.

| Library Model Name | Description                       |
|--------------------|-----------------------------------|
| 'poly1'            | Linear polynomial curve           |
| 'poly11'           | Linear polynomial surface         |
| 'poly2'            | Quadratic polynomial curve        |
| 'linearinterp'     | Piecewise linear interpolation    |
| 'cubicinterp'      | Piecewise cubic interpolation     |
| 'smoothing spline' | Smoothing spline (curve)          |
| 'lowess'           | Local linear regression (surface) |
| 'log10'            | Base-10 logarithmic curve         |
| 'logistic4'        | Four-parameter logistic curve     |

For a list of library model names, see “Model Names and Equations” on page 4-11.

Example: 'poly2'

Data Types: char | string

### expression — Model to fit

character vector | string scalar

Model to fit, specified as a character vector or string scalar. You can specify any MATLAB command and therefore any .m file. See “Fit a Curve Defined by a File” on page 13-134.

Data Types: char | string

### LinearModelTerms — Model to fit

cell array of character vectors | string array

Model to fit, specified as a cell array of character vectors or a string array. Specify the model terms by the expressions in the character vectors or string scalars. Do not include coefficients in the expressions for the terms. See “Linear Model Terms” on page 13-140.

Data Types: cell

**anonymousFunction — Model to fit**

anonymous function

Model to fit, specified as an anonymous function. For details, see “Input Order for Anonymous Functions” on page 13-139.

Data Types: char

**Name-Value Pair Arguments**

Specify optional pairs of arguments as `Name1=Value1, ..., NameN=ValueN`, where `Name` is the argument name and `Value` is the corresponding value. Name-value arguments must appear after other arguments, but the order of the pairs does not matter.

*Before R2021a, use commas to separate each name and value, and enclose Name in quotes.*

Example: `'coefficients',{'a1','a2'}`

**coefficients — Coefficient names**

character vector | string scalar | cell array of character vectors | string array

Coefficient names, specified as the comma-separated pair consisting of `'coefficients'` and a character vector, string scalar, cell array of character vectors, or string array. You can use multicharacter symbol names. You cannot use these names: `i`, `j`, `pi`, `inf`, `nan`, `eps`.

Data Types: char | string | cell

**dependent — Dependent (response) variable name**

y (default) | character vector | string scalar

Dependent (response) variable name, specified as the comma-separated pair consisting of `'dependent'` and a character vector or string scalar. If you do not specify the dependent variable, the function assumes `y` is the dependent variable.

Data Types: char | string

**independent — Independent (response) variable names**

x (default) | character vector | string scalar | cell array of character vectors | string array

Independent (response) variable names, specified as the comma-separated pair consisting of `'independent'` and a character vector, string scalar, cell array of character vectors, or string array. If you do not specify the independent variable, the function assumes `x` is the independent variable.

Data Types: char | string | cell

**options — Fit options**

fitoptions

Fit options, specified as the comma-separated pair consisting of `'options'` and the name of a `fitoptions` object.

**problem — Problem-dependent (fixed) parameter names**

character vector | string scalar | cell array or character vectors | string array

Problem-dependent (fixed) parameter names, specified as the comma-separated pair consisting of `'problem'` and a character vector, string scalar, cell array of character vectors, or string array with one element per problem dependent constant.

Data Types: `char` | `string` | `cell`

## Output Arguments

### **aFitype** — Model to fit

fitype object

Model to fit, returned as a `fitype`. A `fitype` encapsulates information describing a model. To create a fit, you need data, a `fitype`, and (optionally) `fitoptions` and an exclusion rule. You can use a `fitype` as an input to the `fit` function.

## More About

### Dependent and Independent Variables

How do I decide which variables are dependent and independent?

To determine dependent and independent variables and coefficients, consider this equation:

$$y = f(x) = a + (b * x) + (c * x^2).$$

- $y$  is the dependent variable.
- $x$  is the independent variable.
- $a$ ,  $b$ , and  $c$  are the coefficients.

The 'independent' variable is what you control. The 'dependent' variable is what you measure, i.e., it depends on the independent variable. The 'coefficients' are the parameters that the fitting algorithm estimates.

For example, if you have census data, then the year is the independent variable because it does not depend on anything. Population is the dependent variable, because its value depends on the year in which the census is taken. If a parameter like growth rate is part of the model, so the fitting algorithm estimates it, then the parameter is one of the 'coefficients'.

The `fitype` function determines input arguments by searching the fit type expression input for variable names. `fitype` assumes  $x$  is the independent variable,  $y$  is the dependent variable, and all other variables are coefficients of the model.  $x$  is used if no variable exists.

### Input Order for Anonymous Functions

If the fit type expression input is an anonymous function, then the order of inputs must be correct. The input order enables the `fitype` function to determine which inputs are coefficients to estimate, problem-dependent parameters, and independent variables.

The order of the input arguments to the anonymous function must be:

```
fcn = @(coefficients,problemparameters,x,y) expression
```

You need at least one coefficient. The problem parameters and  $y$  are optional. The last arguments,  $x$  and  $y$ , represent the independent variables: just  $x$  for curves, but  $x$  and  $y$  for surfaces. If you don't want to use  $x$  and/or  $y$  to name the independent variables, then specify different names using the 'independent' argument name-value pair. However, whatever name or names you choose, these arguments must be the last arguments to the anonymous function.

Anonymous functions make it easier to pass other data into the `fitype` and `fit` functions.

- 1 Create a fit type using an anonymous function and a variable value (`c`) from the workspace.

```
c = 1;
g = fitype( @(a, b, x) a*x.^2+b*x+c )
```

- 2 The `fitype` function can use the variable values in your workspace when you create the fit type. To pass in new data from the workspace, recreate the fit type, e.g.,

```
c = 5 % Change value of c.
g = fitype( @(a, b, x) a*x.^2+b*x+c )
```

- 3 Here, the value of `c` is fixed when you create the fit type. To specify the value of `c` at the time you call `fit`, you can use problem parameters. For example, make a fit with `c = 2` and then a new fit with `c = 3`.

```
g = fitype( @(a,b,x,c) a*x.^2+b*x+c, 'problem', 'c' )
f1 = fit( xdata, ydata, g, 'problem', 2 )
f2 = fit( xdata, ydata, g, 'problem', 3 )
```

## Linear Model Terms

How do I define linear model terms?

To use a linear fitting algorithm, specify `linearModelTerms` as a cell array or string array of terms. For example:

```
afitype = fitype({expr1,...,exprn})
```

Specify the model terms by the expressions in the character vectors `expr2, ..., exprn`. Do not include coefficients in the expressions for the terms. If there is a constant term, use `'1'` as the corresponding expression in the cell array.

To specify a linear model of the following form:

$$\text{coeff1} * \text{term1} + \text{coeff2} * \text{term2} + \text{coeff3} * \text{term3} + \dots$$

where no coefficient appears within any of `term1`, `term2`, etc., use a cell array or string array where each term, without coefficients, is specified in a cell or element of `expr`, as follows:

```
LinearModelTerms = {'term1', 'term2', 'term3', ... }
```

For example, the model

$$a*x + b*\sin(x) + c$$

is linear in `a`, `b`, and `c`. It has three terms `x`, `sin(x)` and `1` (because `c=c*1`) and therefore `expr` is:

```
LinearModelTerms = {'x', 'sin(x)', '1'}
```

In the Curve Fitter app, select a **Linear Fitting** fit in the **Custom** group in the **Fit Type** section.

## Algorithms

If the fit type expression input is a character vector, string scalar, or anonymous function, then the toolbox uses a nonlinear fitting algorithm to fit the model to data.

If the fit type expression input is a cell array or string array of terms, then the toolbox uses a linear fitting algorithm to fit the model to data.

## Version History

Introduced before R2006a

### **R2023b: Specify sigmoidal and logarithmic fit types**

Starting in R2023b, you can specify sigmoidal and logarithmic fit types for curve fits. For more information, see “List of Library Models for Curve and Surface Fitting” on page 4-10.

## See Also

### **Functions**

fit | fitoptions

### **Apps**

Curve Fitter

### **Topics**

“Custom Linear Fitting” on page 5-7

“Parametric Fitting” on page 4-2

## fn2fm

Convert to specified form

### Syntax

```
g = fn2fm(f, form)
sp = fn2fm(f, 'B-', sconds)
fn2fm(f)
```

### Description

`g = fn2fm(f, form)` describes the same function as is described by `f`, but in the form specified by the character vector or string scalar `form`. Choices for `form` are 'B-', 'pp', 'BB', 'rB', 'rp', for the B-form, the ppform, the BBform, and the two rational spline forms, respectively.

The B-form describes a function as a weighted sum of the B-splines of a given order `k` for a given knot sequence, and the BBform (or, Bernstein-Bézier form) is the special case when each knot in that sequence appears with maximal multiplicity, `k`. The ppform describes a function in terms of its local polynomial coefficients. The B-form is good for constructing and/or shaping a function, while the ppform is cheaper to evaluate.

Conversion from a polynomial form to the corresponding rational form is possible only if the function in the polynomial form is vector-valued, in which case its last component is designated as the denominator. Converting from a rational form to the corresponding polynomial form simply reverses this process by reinterpreting the denominator of the function in the rational form as an additional component of the piecewise polynomial function.

Conversion to or from the stform is not possible at present.

If `form` is 'B-' (and `f` is in ppform), then the actual smoothness of the function in `f` across each of its interior breaks has to be guessed. This is done by looking, for each interior break, for the first derivative whose jump across that break is not *small* compared to the size of that derivative nearby. The default tolerance used in this is `1.e-12`.

`sp = fn2fm(f, 'B-', sconds)` permits you to supply, as the input argument `sconds`, a tolerance (strictly between 0 and 1) to be used in the conversion from ppform to B-form.

Alternatively, you can input `sconds` as a vector with integer entries, with at least as many entries as the ppform in `f` has *interior* breaks. In that case, `sconds(i)` specifies the number of smoothness conditions to be used across the *i*th *interior* break. If the function in `f` is a tensor product, then `sconds`, if given, must be a cell array.

`fn2fm(f)` converts a possibly old version of a form into its present version.

### Examples

`sp = fn2fm(spline(x,y), 'B-')` gives the interpolating cubic spline provided by the MATLAB command `spline`, but in B-form rather than in ppform.



```
p0 = ppmak([0 1],[3 0 0]);
p1 = fn2fm(fn2fm(fnrfn(p0,[.4 .6]),'B-'),'pp');
```

gives `p1` identical to `p0` (up to round-off in the coefficients) since the spline has no discontinuity in any derivative across the additional breaks introduced by `fnrfn`, hence conversion to B-form ignores these additional breaks, and conversion to `ppform` does not retain any knot multiplicities (like the knot multiplicities introduced, by conversion to B-form, at the endpoints of the spline's basic interval).

## Cautionary Note

When going from B-form to `ppform`, any jump discontinuity at the first and last knot,  $t(1)$  or  $t(\text{end})$ , will be lost since the `ppform` considers  $f$  to be defined outside its basic interval by extension of the first, respectively, the last polynomial piece. For example, while `sp=spmak([0 1],1)` gives the characteristic function of the interval  $[0..1]$ , `pp=fn2fm(spmak([0 1],1),'pp')` is the constant polynomial,  $x \mapsto 1$ .

## Algorithms

For a multivariate (tensor-product) function, univariate algorithms are applied in each variable.

For the conversion from B-form (or BBform) to `ppform`, the utility command `sprpp` is used to convert the B-form of all polynomial pieces to their local power form, using repeated knot insertion at the left endpoint.

The conversion from B-form to BBform is accomplished by inserting each knot enough times to increase its multiplicity to the order of the spline.

The conversion from `ppform` to B-form makes use of the dual functionals discussed in “Types of Splines: `ppform` and B-form” on page 10-2. Without further information, such a conversion has to ascertain the actual smoothness across each interior break of the function in  $f$ .

## See Also

`ppmak` | `spmak` | `rsmak` | `stmak`

## fnbrk

Name and part(s) of form

### Syntax

```
[out1,...,outn] = fnbrk(f,part1,...,partm)
fnbrk(f,interval)
fnbrk(pp,j)
fnbrk(f)
```

### Description

`[out1,...,outn] = fnbrk(f,part1,...,partm)` returns the part(s) of the form in `f` specified by `part1,...,partn` (assuming that  $n \leq m$ ). These are the parts used when the form was put together, in `spmak` or `ppmak` or `rpmak` or `rsmak` or `stmak`, but also other parts derived from these.

You only need to specify the beginning character(s) of the relevant option.

Regardless of what particular form `f` is in, `parti` can be one of the following, specified as a character vector or string scalar.

|                |                                          |
|----------------|------------------------------------------|
| 'form'         | The particular form used                 |
| 'variables'    | The dimension of the function's domain   |
| 'dimension'    | The dimension of the function's target   |
| 'coefficients' | The coefficients in that particular form |
| 'interval'     | The basic interval of that form          |

Depending on the form in `f`, additional parts may be asked for.

If `f` is in B-form (or BBform or rBform), then additional choices for `parti` are

|                |                                    |
|----------------|------------------------------------|
| 'knots'        | The knot sequence                  |
| 'coefficients' | The B-spline coefficients          |
| 'number'       | The number of coefficients         |
| 'order'        | The polynomial order of the spline |

If `f` is in ppform (or rpform), then additional choices for `parti` are

|                |                                                                             |
|----------------|-----------------------------------------------------------------------------|
| 'breaks'       | The break sequence                                                          |
| 'coefficients' | The local polynomial coefficients                                           |
| 'pieces'       | The number of polynomial pieces                                             |
| 'order'        | The polynomial order of the spline                                          |
| 'guide'        | The local polynomial coefficients, but in the form needed for PPVALU in PGS |

If the function in `f` is multivariate, then the corresponding multivariate parts are returned. This means, e.g., that knots, breaks, and the basic interval, are cell arrays, the coefficient array is, in general, higher than two-dimensional, and order, number and pieces are vectors.

If `f` is in `stform`, then additional choices for `parti` are

|                |                                 |
|----------------|---------------------------------|
| 'centers'      | The centers                     |
| 'coefficients' | The coefficients                |
| 'number'       | Number of coefficients or terms |
| 'type'         | The particular type             |

`fnbrk(f,interval)` with `interval` a 1-by-2 matrix `[a b]` with `a<b` does not return a particular part. Rather, it returns a description of the univariate function described by `f` and in the same form but with the basic interval changed, to the interval given. If, instead, `interval` is `[]`, `f` is returned unchanged. This is of particular help when the function in `f` is  $m$ -variate, in which case `interval` must be a cell array with  $m$  entries, with the  $i$ th entry specifying the desired interval in the  $i$ th dimension. If that  $i$ th entry is `[]`, the basic interval in the  $i$ th dimension is unchanged.

`fnbrk(pp,j)`, with `pp` the `ppform` of a univariate function and `j` a positive integer, does not return a particular part, but returns the `ppform` of the  $j$ th polynomial piece of the function in `pp`. If `pp` is the `ppform` of an  $m$ -variate function, then `j` must be a cell array of length  $m$ . In that case, each entry of `j` must be a positive integer or else an interval, to single out a particular polynomial piece or else to specify the basic interval in that dimension.

`fnbrk(f)` returns nothing, but a description of the various parts of the form is printed at the command line instead.

## Examples

If `p1` and `p2` contain the B-form of two splines of the same order, with the same knot sequence, and the same target dimension, then

```
p1plusp2 = spmak(fnbrk(p1,'k'),fnbrk(p1,'c')+fnbrk(p2,'c'));
```

provides the (pointwise) sum of those two functions.

If `pp` contains the `ppform` of a bivariate spline with at least four polynomial pieces in the first variable, then `ppp=fnbrk(pp,{4,[-1 1]})` gives the spline that agrees with the spline in `pp` on the rectangle `[b4 .. b5] x [-1 .. 1]`, where `b4`, `b5` are the fourth and fifth entry in the break sequence for the first variable.

## See Also

`ppmak` | `rpmak` | `rsmak` | `spmak` | `stmak`

## fnchg

Change part(s) of form

### Syntax

```
f = fnchg(f,part,value)
```

### Description

`f = fnchg(f,part,value)` returns the given function description `f` but with the specified `part` changed to the specified `value`.

The character vector or string scalar `part` can be (the beginning character(s) of) :

|             |                                        |
|-------------|----------------------------------------|
| 'dimension' | The dimension of the function's target |
| 'interval'  | The basic interval of that form        |

The specified `value` for `part` is not checked for consistency with the rest of the description in `f` in case the character vector or string scalar `part` terminates with the letter `z`.

### Examples

`fndir(f,directions)` returns a vector-valued function even when the function described by `f` is ND-valued. You can correct this by using `fnchg` as follows:

```
fdir = fnchg( fndir(f,directions),...  
            'dim',[fnbrk(f,'dim'),size(directions,2)] );
```

### See Also

fnbrk

## fncmb

Arithmetic with function(s)

### Syntax

```
fn = fncmb(function,operation)
f = fncmb(function,function)
fncmb(function,matrix,function)
fncmb(function,matrix,function,matrix)
f = fncmb(function,op,function)
```

### Description

The intent is to make it easy to carry out the standard linear operations of scaling and adding within a spline space without having to deal explicitly with the relevant parts of the function(s) involved.

`fn = fncmb(function,operation)` returns (a description of) the function obtained by applying to the values of the function in `function` the operation specified by `operation`. The nature of the operation depends on whether `operation` is a *scalar*, a *vector*, a *matrix*, or a *character vector or string scalar*, as follows.

|                                   |                                                                                                        |
|-----------------------------------|--------------------------------------------------------------------------------------------------------|
| Scalar                            | Multiply the function by that scalar.                                                                  |
| Vector                            | Add that vector to the function's values; this requires the function to be vector-valued.              |
| Matrix                            | Apply that matrix to the function's coefficients.                                                      |
| Character vector or string scalar | Apply the function specified by that character vector or string scalar to the function's coefficients. |

The remaining options only work for *univariate* functions. See [Limitations](#) for more information.

`f = fncmb(function,function)` returns (a description of) the pointwise sum of the two functions. The two functions must be of the same form. This particular case of just two input arguments is not included in the above table since it only works for univariate functions.

`fncmb(function,matrix,function)` is the same as `fncmb(fncmb(function,matrix),function)`.

`fncmb(function,matrix,function,matrix)` is the same as `fncmb((fncmb(function,matrix),fncmb(function,matrix)))`.

`f = fncmb(function,op,function)` returns the ppform of the spline obtained by the pointwise combining of the two functions, as specified by the character vector or string scalar `op`. The argument `op` can be one of '+', '-', or '\*'. If the second function is to be a constant, it is sufficient simply to supply here that constant.

### Examples

`fncmb(fn,3.5)` multiplies (the coefficients of) the function in `fn` by 3.5.

`fncmb(f,3,g,-4)` returns the linear combination, with weights 3 and -4, of the function in `f` and the function in `g`.

`fncmb(f,3,g)` adds 3 times the function in `f` to the function in `g`.

If the function  $f$  in `f` happens to be scalar-valued, then `f3=fncmb(f,[1;2;3])` contains the description of the function whose value at  $x$  is the 3-vector  $(f(x), 2f(x), 3f(x))$ . Note that, by the convention throughout this toolbox, the subsequent statement `fval(f3,x)` returns a 1-column-matrix.

If `f` describes a surface in  $R^3$ , i.e., the function in `f` is 3-vector-valued bivariate, then `f2 = fncmb(f,[1 0 0;0 0 1])` describes the projection of that surface to the  $(x, z)$ -plane.

The following commands produce the picture of a ... spirochete?

```
c = rsmak('circle');
fnplt(fncmb(c,diag([1.5,1]))); axis equal, hold on
sc = fncmb(c,.4);
fnplt(fncmb(sc,-[.2;-.5]))
fnplt(fncmb(sc,-[.2,-.5]))
hold off, axis off
```

If `t` is a knot sequence of length  $n+k$  and `a` is a matrix with  $n$  columns, then `fncmb(spmak(t,eye(n)),a)` is the same as `spmak(t,a)`.

`fncmb(spmak([0:4],1),'+',ppmak([-1 5],[1 -1]))` is the piecewise-polynomial with breaks `-1:5` that, on the interval  $[0 .. 4]$ , agrees with the function  $x \mapsto B(x|0,1,2,3,4) + x$  (but has no active break at 0 or 1, hence differs from this function outside the interval  $[0 .. 4]$ ).

`fncmb(spmak([0:4],1),'-',0)` has the same effect as `fn2fm(spmak([0:4],1),'pp')`.

Assuming that `sp` describes the B-form of a spline of order  $<k$ , the output of

```
fn2fm(fncmb(sp,'+',ppmak(fnbrk(sp,'interv'),zeros(1,k))),'B-')
```

describes the B-form of the same spline, but with its order raised to  $k$ .

## Limitations

`fncmb` only works for *univariate* functions, except for the case `fncmb(function,operation)`, i.e., when there is just one function in the input.

Further, if two functions are involved, then they must be of the same type. This means that they must either both be in B-form or both be in ppform, and, moreover, have the same knots or breaks, the same order, and the same target. The only exception to this is the command of the form `fncmb(function,op,function)`.

## Algorithms

The coefficients are extracted (via `fnbrk`) and operated on by the specified matrix or operation (and, possibly, added), then recombined with the rest of the function description (via `ppmak`, `spmak`, `rpmak`, `rsmak`, `stmak`). To be sure, when the function is rational, the matrix is only applied to the coefficients of the numerator. Again, if we are to translate the function values by a given vector and the function is in ppform, then only the coefficients corresponding to constant terms are so translated.

If there are two functions input, then they must be of the same type (see Limitations, below) *except* for the following.

`fncmb(f1, op, f2)` returns the ppform of the function

$$x \mapsto f1(x) \text{ op } f2(x)$$

with `op` one of '+', '-', '\*', and `f1`, `f2` of arbitrary polynomial form. If, in addition, `f2` is a scalar or vector, it is taken to be the function that is constantly equal to that scalar or vector.

## fnder

Differentiate function

### Syntax

```
fprime = fnder(f,dorder)
fnder(f)
```

### Description

`fprime = fnder(f,dorder)` returns the `dorder`-th derivative of the function in `f`. The default value of `dorder` is 1. For negative `dorder`, the particular `|dorder|`-th indefinite integral is returned that vanishes `|dorder|`-fold at the left endpoint of the basic interval.

The output is of the same form as the input, they are either both ppforms, or both B-forms, or both stforms.

If the function in `f` is  $m$ -variate, then `dorder` must be given, and must be of length  $m$ .

Also:

- If `f` is in ppform, or in B-form with its last knot of sufficiently high multiplicity, then, up to rounding errors, `f` and `fnder(fnint(f))` are the same.
- If `f` is in ppform and `fa` is the value of the function in `f` at the left end of its basic interval, then, up to rounding errors, `f` and `fnint(fnder(f),fa)` are the same, unless the function described by `f` has jump discontinuities.
- If `f` contains the B-form of  $f$ , and  $t_1$  is its leftmost knot, then, up to rounding errors, `fnint(fnder(f))` contains the B-form of  $f - f(t_1)$ . However, its leftmost knot will have lost one multiplicity (if it had multiplicity  $> 1$  to begin with). Also, its rightmost knot will have full multiplicity even if the rightmost knot for the B-form of  $f$  in `f` doesn't. To verify this, create a spline, `sp = spmak([0 0 1], 1)`. This spline is, on its basic interval `[0..1]`, the straight line that is 1 at 0 and 0 at 1. Now integrate its derivative: `spdi = fnint(fnder(sp))`. The spline in `spdi` has the same basic interval, but, on that interval, it agrees with the straight line that is 0 at 0 and -1 at 1.

`fnder(f)` is the same as `fnder(f,1)`.

## Examples

### B-splines with Simple Knots and Their Derivatives

This example shows how to calculate the first and second order derivative functions of three B-splines of order 2, 3, and 4. Then it plots the splines, and their derivatives, and compares the results.

```
% Create the knots sequences
t1 = [0 .8 2];
t2 = [3 4.4 5 6];
t3 = [7 7.9 9.2 10 11];
```



```

tt = [t1 t2 t3];

% Accessory variables and commands for plotting purposes
cl = ['g','r','b','k','k'];
v = 5.4; d1 = 2.5; d2 = 0; s1 = 1; s2 = .5;
ext = tt([1 end])+[-.5 .5];
plot(ext([1 2]),[v v],cl(5))
hold on
plot(ext([1 2]),[d1 d1],cl(5))
plot(ext([1 2]),[d2 d2],cl(5))
ts = [tt;tt;NaN(size(tt))];
ty = repmat(.2*[-1;0;NaN],size(tt));
plot(ts(:),ty(:)+v,cl(5))
plot(ts(:),ty(:)+d1,cl(5))
plot(ts(:),ty(:)+d2,cl(5))

% Spline 1 (linear)
b1 = spmak(t1,1);
p1 = [t1;0 1 0];
% Calculate the first and second derivative of spline 1
db1 = fnder(b1);
p11 = fnplt(db1,'j');
p12 = fnplt(fnder(db1));
lw = 2;
plot(p1(1,:),p1(2,:)+v,cl(2),'LineWidth',lw)
plot(p11(1,:),s1*p11(2,:)+d1,cl(2),'LineWidth',lw)
plot(p12(1,:),s2*p12(2,:)+d2,cl(2),'LineWidth',lw)


% Spline 2 (quadratic)
b1 = spmak(t2,1);
p1 = fnplt(b1);
% Calculate the first and second derivative of spline 2
db1 = fnder(b1);
p11 = [t2;fnval(db1,t2)];
p12 = fnplt(fnder(db1),'j');
plot(p1(1,:),p1(2,:)+v,cl(3),'LineWidth',lw)
plot(p11(1,:),s1*p11(2,:)+d1,cl(3),'LineWidth',lw)
plot(p12(1,:),s2*p12(2,:)+d2,cl(3),'LineWidth',lw)

% Spline 3 (cubic)
b1 = spmak(t3,1);
p1 = fnplt(b1);
% Calculate the first and second derivative of spline 3
db1 = fnder(b1);
p11 = fnplt(db1);
p12=[t3;fnval(fnder(db1),t3)];
plot(p1(1,:),p1(2,:)+v,cl(4),'LineWidth',lw)
plot(p11(1,:),s1*p11(2,:)+d1,cl(4),'LineWidth',lw)
plot(p12(1,:),s2*p12(2,:)+d2,cl(4),'LineWidth',lw)

% Formatting the plot
tey = v+1.5;
text(t1(2)-.5,tey,'linear','FontSize',12,'Color',cl(2))
text(t2(2)-.8,tey,'quadratic','FontSize',12,'Color',cl(3))
text(t3(3)-.5,tey,'cubic','FontSize',12,'Color',cl(4))
text(-2,v,'B','FontSize',12)
text(-2,d1,'DB','FontSize',12)
text(-2,d2,'D^2B')

```

```
axis([-1 12 -2 7.5])
title({'B-splines with Simple Knots and Their Derivatives'})
axis off
hold off
```



## Input Arguments

### f — Spline function

spline structure

Spline in either ppform, B-form or stform, specified as a structure with these fields:

### Form — Form of spline

pp | B- | tp00

Form of the spline, returned as pp, B-, or tp00. pp indicates that the spline is given in piecewise polynomial form, B- indicates that the spline is given in B-form, and tp00 indicates that the spline is given in stform.

### Knots — Knot locations of spline

vector | cell array

Knot positions of the spline, returned as a vector or as a cell array of vectors for multivariate data. Vectors contain strictly increasing elements that represent the start and end of each of the intervals over which the polynomial pieces are defined.

**Coefs — Coefficients of polynomials**

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

**Number — Number of polynomial pieces**

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

**Order — Order of polynomials**

scalar | vector

Order of the polynomial function describing each polynomial piece of the spline, returned as a scalar or as a vector containing the order in each variable for multivariate data.

**Dim — Dimensionality**

scalar

Dimensionality of the target function, returned as a scalar.

**dorder — Derivative order**

scalar | vector

Order of the derivative of the function  $f$ , specified as a scalar or vector for multivariate functions.

Data Types: `single` | `double`

**Output Arguments****fprime — Derivative function**

spline structure

Derivative function of the  $f$  spline in either `ppform`, `B-form`, or `stform`, returned as a structure with these fields:

**Form — Form of spline**`pp` | `B-` | `tp00`

Form of the spline, returned as `pp`, `B-`, or `tp00`. The form of the derivative function is the same as the form of the  $f$  function. `pp` indicates that the spline is given in piecewise polynomial form, `B-` indicates that the spline is given in `B-form`, and `tp00` indicates that the spline is given in `stform`.

**Knots — Knot locations of spline**

vector | cell array

Knot positions of the spline, returned as a vector or as a cell array of vectors for multivariate data. Vectors contain strictly increasing elements that represent the start and end of each of the intervals over which the polynomial pieces are defined.

**Coefs — Coefficients of polynomials**

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

**Number — Number of polynomial pieces**

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

**Order — Order of polynomials**

scalar | vector

Order of the polynomial function describing each polynomial piece of the spline, returned as a scalar or as a vector containing the order in each variable for multivariate data.

**Dim — Dimensionality**

scalar

Dimensionality of the target function, returned as a scalar.

**Limitations**

- The `fnder` function does not work with rational splines. To work with rational splines, use the `fntlr` function instead.
- The `fnder` function works for `stforms` only in a limited way: if the type is `tp00`, then `dorder` can be `[1,0]` or `[0,1]`.

**Algorithms**

For differentiation of either polynomial form, the `fnder` function finds the derivatives in the piecewise-polynomial sense. The function differentiates each polynomial piece separately, and ignores jump discontinuities between polynomial pieces during differentiation.

For the B-form, the function uses the [PGS; (X.10)] formulas for differentiation.

For the `stform`, differentiation relies on knowing a formula for the relevant derivative of the basis function of the particular type.

**Version History****Introduced before R2006a****See Also**`fndir` | `fnint` | `fnplt` | `fnval`**Topics**

“Introducing Spline Fitting” on page 8-2

## fndir

Directional derivative of function

### Syntax

```
df = fndir(f,y)
```

### Description

`df = fndir(f,y)` is the ppform of the directional derivative, of the function  $f$  in  $f$ , in the direction of the (column-)vector  $y$ . This means that `df` describes the function

$$D_y f(x) := \lim_{t \rightarrow 0} (f(x + ty) - f(x))/t.$$

If  $y$  is a matrix, with  $n$  columns, and  $f$  is  $d$ -valued, then the function in `df` is  $\text{prod}(d)*n$ -valued. Its value at  $x$ , reshaped to be of size  $[d, n]$ , has in its  $j$ th “column” the directional derivative of  $f$  at  $x$  in the direction of the  $j$ th column of  $y$ . If you prefer `df` to reflect explicitly the actual size of  $f$ , use instead

```
df = fnchg( fndir(f,y), 'dim',[fnbrk(f,'dim'),size(y,2)] );
```

Since `fndir` relies on the ppform of the function in  $f$ , it does not work for rational functions nor for functions in `stform`.

### Examples

For example, if  $f$  describes an  $m$ -variate  $d$ -vector-valued function and  $x$  is some point in its domain, then, e.g., with this particular ppform  $f$  that describes a scalar-valued bilinear polynomial,


```
f = ppmak({0:1,0:1},[1 0;0 1]); x = [0;0];
[d,m] = fnbrk(f,'dim','var');
jacobian = reshape(fnval(fndir(f,eye(m)),x),d,m)
```

is the Jacobian of that function at that point (which, for this particular *scalar*-valued function, is its gradient, and it is zero at the origin).

As a related example, the next statements plot the gradients of (a good approximation to) the Franke function at a regular mesh:

```
xx = linspace(-.1,1.1,13); yy = linspace(0,1,11);
[x,y] = ndgrid(xx,yy); z = franke(x,y);
pp2dir = fndir(csapi({xx,yy},z),eye(2));
grads = reshape(fnval(pp2dir,[x(:) y(:)].'),...
    [2,length(xx),length(yy)]);
quiver(x,y,squeeze(grads(1,:,:),squeeze(grads(2,:,:),:)))
```

Here is the resulting plot.



## Algorithms

The function in `f` is converted to `ppform`, and the directional derivative of its polynomial pieces is computed formally and in one vector operation, and put together again to form the `ppform` of the directional derivative of the function in `f`.

## See Also

`fnchg` | `fnder` | `fnint` | `franke`

# fnint

Integrate function

## Syntax

```
intgrf = fnint(f,value)
fnint(f)
```

## Description

`intgrf = fnint(f,value)` is the description of an indefinite integral of the *univariate* function whose description is contained in `f`. The integral is normalized to have the specified `value` at the left endpoint of the function's basic interval, with the default value being zero.

The output is of the same type as the input, i.e., they are both ppforms or both B-forms. `fnint` does not work for rational splines nor for functions in `stform`.

`fnint(f)` is the same as `fnint(f,0)`.

Indefinite integration of a *multivariate* function, in coordinate directions only, is available via `fnder(f,dorder)` with `dorder` having nonpositive entries.

## Examples

The statement `diff(fnval(fnint(f),[a b]))` provides the definite integral over the interval `[a .. b]` of the function described by `f`.

If `f` is in ppform, or in B-form with its last knot of sufficiently high multiplicity, then, up to rounding errors, `f` and `fnder(fnint(f))` are the same.

If `f` is in ppform and `fa` is the value of the function in `f` at the left end of its basic interval, then, up to rounding errors, `f` and `fnint(fnder(f),fa)` are the same, unless the function described by `f` has jump discontinuities.

If `f` contains the B-form of  $f$ , and  $t_1$  is its leftmost knot, then, up to rounding errors, `fnint(fnder(f))` contains the B-form of  $f - f(t_1)$ . However, its leftmost knot will have lost one multiplicity (if it had multiplicity  $> 1$  to begin with). Also, its rightmost knot will have full multiplicity even if the rightmost knot for the B-form of  $f$  in `f` doesn't.

Here is an illustration of this last fact. The spline in `sp = spmak([0 0 1], 1)` is, on its basic interval `[0..1]`, the straight line that is 1 at 0 and 0 at 1. Now integrate its derivative: `spdi = fnint(fnder(sp))`. As you can check, the spline in `spdi` has the same basic interval, but, on that interval, it agrees with the straight line that is 0 at 0 and -1 at 1.

See the examples "Intro to B-form" and "Intro to ppform" for examples.

## Algorithms

For the B-form, the formula [PGS; (X.22)] for integration is used.

**See Also**

`fnder` | `fnplt` | `fnval`



## fnjmp

Jumps, i.e.,  $f(x+) - f(x-)$

### Syntax

```
jumps = fnjmp(f,x)
```

### Description

`jumps = fnjmp(f,x)` is like `fnval(f,x)` except that it returns the jump  $f(x+) - f(x-)$  across  $x$  (rather than the value at  $x$ ) of the function  $f$  described by  $f$  and that it only works for univariate functions.

This is a function for spline specialists.

### Examples

`fnjmp(ppmak(1:4,1:3),1:4)` returns the vector `[0,1,1,0]` since the `pp` function here is 1 on `[1 .. 2]`, 2 on `[2 .. 3]`, and 3 on `[3 .. 4]`, hence has zero jump at 1 and 4 and a jump of 1 across both 2 and 3.

If  $x$  is `cos([4:-1:0]*pi/4)`, then `fnjmp(fnder(spmak(x,1),3),x)` returns the vector `[12 -24 24 -24 12]` (up to round-off). This is consistent with the fact that the spline in question is a so called perfect cubic B-spline, i.e., has an absolutely constant third derivative (on its basic interval). The modified command

```
fnjmp(fnder(fn2fm(spmak(x,1),'pp'),3),x)
```

returns instead the vector `[0 -24 24 -24 0]`, consistent with the fact that, in contrast to the B-form, a spline in `ppform` does not have a discontinuity in any of its derivatives at the endpoints of its basic interval. Note that `fnjmp(fnder(spmak(x,1),3),-x)` returns the vector `[12,0,0,0,12]` since `-x`, though theoretically equal to  $x$ , differs from  $x$  by round-off, hence the third derivative of the B-spline provided by `spmak(x,1)` does not have a jump across `-x(2)`, `-x(3)`, and `-x(4)`.

## fnmin

Minimum of function in given interval

### Syntax

```
fnmin(f)
fnmin(f,interv)
[minval,minsit] = fnmin(f,...)
```

### Description

`fnmin(f)` returns the minimum value of the *scalar-valued univariate* spline in `f` on its basic interval.

`fnmin(f,interv)` returns the minimum value of the *scalar-valued univariate* spline in `f` on the interval `[a..b]` specified by `interv`.

`[minval,minsit] = fnmin(f,...)` also returns a location, `minsit`, at which the function in `f` takes that minimum value, `minval`.

### Examples

#### Compute the Maximum and Minimum Values of a Spline

This example shows how to calculate the maximum and minimum values of a spline in `f` using the `fnmin` function.


#### Calculate the Maximum Value

Construct and plot a spline `f` with 21 knots and 15 random coefficients.

```
f = spmak(1:21,rand(1,15) - .5);
fnplt(f)
```

Compute the maximum value of `f` as the negative of the minimum of `-f`, then plot it as a horizontal line at the height of the computed maximum.


```
maxval = -fnmin(fncmb(f,-1));
hold on, plot(fnbrk(f,'interv'),maxval([1 1])), hold off
```



### Calculate the Minimum Value

Construct and plot a spline using the `spmak` function.

```
f2 = spmak(1:5, -1);  
fnplt(f2)
```



Compute the minimum value of `f2` and the site at which the spline takes on this minimum value.

```
[y,x] = fmin(spmak(1:5,-1))
```

```
y = -0.6667
```

```
x = 3
```

## Input Arguments

### **f** — Spline structure

structure

Structure of a spline with the fields:

### **form** — Polynomial spline representation

char

Form of the spline, returned as char.

### **knots** — Knot sequence

vector

Non-decreasing sequence of the knots of the spline, returned as a vector.

### **coefs** — Coefficients of spline

scalar | vector | matrix

Coefficients of the spline, returned as a scalar, vector, matrix.

**number — Spline number**

scalar

Number of pieces of the spline, returned as a scalar.

**order — Spline order**

scalar

Order of the spline, returned as a scalar.

**dim — Dimension of coefficients**

scalar

Dimension of the coefficients of the spline, returned as a scalar.

**interv — Searching interval**

vector (default)

Range of values where the function computes the minimum value of  $f$ , specified as a vector.

Data Types: `single` | `double`

## Output Arguments

**minval — Minimum value of spline**

scalar

Minimum value of the scalar-valued univariate spline in  $f$ , returned as a scalar.

**minsite — Site of minimum value**

scalar

Site at which the spline in  $f$  takes on the minimum value, `minval`, returned as a scalar.

## Algorithms

The `fnmin` algorithm first changes the basic interval of the function to the given interval, if any. On the interval, `fnmin` then finds all local extrema of the function as left and right limits at a jump and as zeros of the function's first derivative. It then evaluates the function at these extrema and at the endpoints of the interval, and determines the minimum over all these values.

## Version History

Introduced in R2006b

## See Also

`fnval` on page 13-172 | `fnzeros` on page 13-182

## Topics

“Introducing Spline Fitting” on page 8-2

## fnplt

Plot function

### Syntax

```
fnplt(f)
fnplt(f,symbol,interv,linewidth,jumps)
points = fnplt(f,...)
[points, t] = fnplt(f,...)
```

### Description

`fnplt(f)` plots the function in `f` on its basic interval.

If  $f$  is univariate, then:

- If  $f$  is scalar-valued, `fnplt` plots the graph of  $f$ .
- If  $f$  is 2-vector-valued, `fnplt` plots the planar curve.
- If  $f$  is  $d$ -vector-valued with  $d > 2$ , `fnplt` plots the space curve given by the first three components of  $f$ .

If  $f$  is bivariate, then:

- If  $f$  is scalar-valued, `fnplt` plots the graph of  $f$ , using `surf`.
- If  $f$  is 2-vector-valued, `fnplt` plots the image in the plane of a regular grid in its domain.
- If  $f$  is  $d$ -vector-valued with  $d > 2$ , `fnplt` plots the parametric surface given by the first three components of its values, using `surf`.

If  $f$  is a function of more than two variables, then `fnplt` plots the bivariate function, obtained by choosing the midpoint of the basic interval in each of the variables other than the first two.

---

**Note** The basic interval for  $f$  in B-form is the interval containing *all* the knots. This means that  $f$  is sure to vanish at the endpoints of the basic interval unless the first and the last knot are both of full multiplicity  $k$ , with  $k$  the order of the spline  $f$ . Failure to have such full multiplicity is particularly annoying when  $f$  is a spline curve, since the plot of that curve as produced by `fnplt` is then bound to start and finish at the origin, regardless of what the curve might otherwise do.

Further, since B-splines are zero outside their support, any function in B-form is zero outside the basic interval of its form. This is very much in contrast to a function in `ppform` whose values outside the basic interval of the form are given by the extension of its leftmost, respectively rightmost, polynomial piece.

---

`fnplt(f,symbol,interv,linewidth,jumps)` permits you to modify the plotting by the specification of additional input arguments. You can place these arguments in whatever order you like, from the following list:

- A *character vector or string scalar* that specifies a plotting symbol, such as `'-.'` or `'*'`; the default is `'-'`.

- A *scalar* to specify the linewidth; the default value is 1.
- A *character vector or string scalar* that starts with the letter 'j' to indicate that any jump in the *univariate* function being plotted appears as a jump. The default is to fill in any jump by a (near-)vertical line.
- A *vector* of the form [a,b], to indicate the interval over which to plot the *univariate* function in f. If the function in f is *m*-variate, then this optional argument must be a cell array whose *ith* entry specifies the interval over which the *ith* argument is to vary. In effect, for this *arg*, the command `fnplt(f,arg,...)` has the same effect as the command `fnplt(fnbrk(f,arg),...)`. The default is the basic interval of f.
- An empty matrix, character vector, or string scalar, to indicate use of default(s). This option is useful when your particular choice depends on some other variables.

`points = fnplt(f,...)` plots nothing and returns the two-dimensional points or three-dimensional points it would have plotted instead.

`[points, t] = fnplt(f,...)` also returns, for a vector-valued f, the corresponding vector t of parameter values.

## Examples

### Plot a Spline Using the fnplt Function

This simple example shows how to plot a spline using the `fnplt` function.

Create a vector of data sites.

```
x=linspace(0,2*pi,21);
```

Generate a spline with the data sites x previously created.


```
f = spapi(4,x,sin(x))
```

```
f = struct with fields:
```

```
  form: 'B-'
  knots: [0 0 0 0 0.6283 0.9425 1.2566 1.5708 1.8850 2.1991 2.5133 2.8274 3.1416 3.4558 3.7699]
  coefs: [1.3771e-17 0.2098 0.5226 0.8224 0.9668 1.0166 0.9668 0.8224 0.5975 0.3141 8.9245e-17]
  number: 21
  order: 4
  dim: 1
```

Finally plot the spline using the `fnplt` function.

```
fnplt(f,'r',3,[1 3])
```



## Input Arguments

### **f** — Function to plot

scalar | vector | ND-array | spline structure

Function you want to plot, specified as a scalar, vector, ND-array, or a spline in either ppform, B-form or stform.

### **symbol** — Plotting symbol

character vector | string scalar

Symbol used to plot the function, specified as a character vector or string scalar.

Data Types: char | string

### **interv** — Plotting interval

vector | cell array

Interval over which to plot the univariate function in **f**, specified as a vector. If the function in **f** is *m*-variate, then this parameter must be a cell array whose *i*-th entry specifies the interval over which the *i*-th argument is to vary.

Data Types: single | double

### **linewidth** — Plotting line width

scalar



Width of the plotting line, specified as a scalar.

Data Types: `single` | `double`

### **jumps — Jump plotting specification**

character vector | string scalar

Specify how to plot a jump in the *univariate* function, specified as a character vector or string scalar. The default is to fill in any jump by a (near-)vertical line.

Data Types: `char` | `string`

## **Output Arguments**

### **points — Plotting function points**

vector | matrix

Two dimensional or three dimensional points of the function that would have been plotted, returned as a vector or matrix.

### **t — Parameter values**

vector | matrix

Corresponding parameter values of function *f*, returned as a vector or matrix.

## **Algorithms**

The `fnplt` functions generates a vector *x* of evaluation points by the union of:

- 1 101 equally spaced sites filling out the plotting interval
- 2 Any breakpoints in the plotting interval.

Then `fnplt` evaluates the univariate function *f* described by *f* at these *x* evaluation points. If *f* is real-valued, it plots the points (*x*,*f*(*x*)). If *f* is vector-valued, it plots the first two or three components of *f*(*x*).

The bivariate function *f* described by *f* is evaluated on a 51-by-51 uniform grid if *f* is scalar-valued or *d*-vector-valued with *d* > 2 and the result plotted by `surf`. In the contrary case, *f* is evaluated along the meshlines of a 11-by-11 grid, and the resulting planar curves are plotted.

## **Version History**

Introduced before R2006a

### **See Also**

`fnder` | `fnint` | `fnval`

### **Topics**

“Introducing Spline Fitting” on page 8-2

## fnrfn

Refine partition of form

### Syntax

```
g = fnrfn(f,addpts)
```

### Description

`g = fnrfn(f,addpts)` describes the same function as does `f`, but uses more terms to do it. This is of use when the sum of two or more functions of different forms is wanted or when the number of degrees of freedom in the form is to be increased to make fine local changes possible. The precise action depends on the form in `f`.

If the form in `f` is a B-form or BBform, then the entries of `addpts` are inserted into the existing knot sequence, subject to the following restriction: The multiplicity of no knot exceed the order of the spline. The equivalent B-form with this refined knot sequence for the function given by `f` is returned.

If the form in `f` is a ppform, then the entries of `addpts` are inserted into the existing break sequence, subject to the following restriction: The break sequence be strictly increasing. The equivalent ppform with this refined break sequence for the function in `f` is returned.

`fnrfn` does not work for functions in `stform`.

If the function in `f` is m-variate, then `addpts` must be a cell array, `{addpts1,..., addptsm}`, and the refinement is carried out in each of the variables. If the *i*th entry in this cell array is empty, then the knot or break sequence in the *i*th variable is unchanged.

### Examples

Construct a spline in B-form, plot it, then apply two midpoint refinements, and also plot the control polygon of the resulting refined spline, expecting it to be quite close to the spline itself:

```
k = 4; sp = spapi( k, [1,1:10,10], [cos(1),sin(1:10),cos(10)] );
    fnplt(sp), hold on
    sp3 = fnrfn(fnrfn(sp));
    plot( aveknt( fnbrk(sp3,'knots'),k), fnbrk(sp3,'coefs'), 'r')
    hold off
```

A third refinement would have made the two curves indistinguishable.

Use `fnrfn` to add two B-splines of the same order:

```
B1 = spmak([0:4],1); B2 = spmak([2:6],1);
    B1r = fnrfn(B1,fnbrk(B2,'knots'));
    B2r = fnrfn(B2,fnbrk(B1,'knots'));
    B1pB2 = spmak(fnbrk(B1r,'knots'),fnbrk(B1r,'c')+fnbrk(B2r,'c'));
    fnplt(B1,'r'),hold on, fnplt(B2,'b'), fnplt(B1pB2,'y',2)
    hold off
```

## Algorithms

The standard *knot insertion* algorithm is used for the calculation of the B-form coefficients for the refined knot sequence, while Horner's method is used for the calculation of the local polynomial coefficients at the additional breaks in the refined break sequence.

## See Also

fncmb | ppmak | spmak

## fntlr

Taylor coefficients

### Syntax

```
taylor = fntlr(f,dorder,x)
```

### Description

`taylor = fntlr(f,dorder,x)` returns the nonnormalized Taylor coefficients, up to the given order `dorder` and at the given `x`, of the function described in `f`.

For a univariate function and a scalar `x`, this is the vector

$$T(f, dorder, x) = [f(x); Df(x); \dots; D^{dorder-1}f(x)]$$

If, more generally, the function in `f` is `d`-valued with `d>1` or even `prod(d)>1` and/or is `m`-variate for some `m>1`, then `dorder` is expected to be an `m`-vector of positive integers, `x` is expected to be a matrix with `m` rows, and, in that case, the output is of size `[prod(d)*prod(dorder), size(x,2)]`, with its `j`-th column containing

$$T(f, dorder, x(:,j))(i1, \dots, im) = D_1^{i1-1} \dots D_m^{im-1} f(x(:,j))$$

for `i1=1:dorder(1), \dots, im=1:dorder(m)`. Here,  $D_j f$  is the partial derivative of  $f$  with respect to its  $i$ th argument.

### Examples

If `f` contains a univariate function and `x` is a scalar or a 1-row matrix, then `fntlr(f,3,x)` produces the same output as the statements

```
df = fnder(f); [fnval(f,x); fnval(df,x); fnval(fnder(df),x)];
```

As a more complicated example, look at the Taylor vectors of order 3 at 21 equally spaced points for the rational spline whose graph is the unit circle:

```
ci = rsmak('circle'); in = fnbrk(ci,'interv');
t = linspace(in(1),in(2),21); t(end)=[];
v = fntlr(ci,3,t);
```

We plot `ci` along with the points `v(1:2,:)`, to verify that these are, indeed, points on the unit circle.


```
fnplt(ci), hold on, plot(v(1,:),v(2:,:), 'o')
```

Next, to verify that `v(3:4,j)` is a vector tangent to the circle at the point `v(1:2,j)`, we use the MATLAB `quiver` command to add the corresponding arrows to our plot:

```
quiver(v(1,:),v(2,:),v(3,:),v(4,:))
```

Finally, what about `v(5:6,:)`? These are second derivatives, and we add the corresponding arrows by the following `quiver` command, thus finishing “First and Second Derivative of a Rational Spline Giving a Circle” on page 13-171.

```
quiver(v(1,:),v(2,:),v(5,:),v(6:)), axis equal, hold off
```



### First and Second Derivative of a Rational Spline Giving a Circle

Now, our curve being a circle, you might have expected the 2nd derivative arrows to point straight to the center of that circle, and that would have been indeed the case if the function in `ci` had been using arclength as its independent variable. Since the parameter used is not arclength, we use the formula, given in “Example: B-form Spline Approximation to a Circle” on page 10-18, to compute the curvature of the curve given by `ci` at these selected points. For ease of comparison, we switch over to the variables used there and then simply use the commands from there.

```
dspt = v(3:4,:); ddspt = v(5:6,:);
kappa = abs(dspt(1,:).*ddspt(2,:)-dspt(2,:).*ddspt(1,:))./...
    (sum(dspt.^2)).^(3/2);
max(abs(kappa-1))
ans = 2.2204e-016
```

The numerical answer is reassuring: at all the points tested, the curvature is 1 to within roundoff.

### See Also

`fnder` | `fndir`

## fnval

Evaluate spline function

### Syntax

```
v = fnval(f,x)
fnval(x,f)
fnval(...,'l')
```

### Description

$v = \text{fnval}(f, x)$  provides the value  $f(x)$  at the points in  $x$  of the spline function  $f$  whose description is contained in  $f$ .

If  $f$  is scalar-valued and univariate, the output  $v$  is obtained by replacing each entry of  $x$  by the value of  $f$  at that entry. This is the intent in all other cases, except that, for a  $d$ -valued  $m$ -variate function,  $d$ -vectors replaces  $m$ -vectors.

For a univariate  $f$ :

- If  $f$  is scalar-valued, then  $v$  is of the same size as  $x$ .
- If  $f$  is  $[d_1, \dots, d_r]$ -valued, and  $x$  has size  $[n_1, \dots, n_s]$ , then  $v$  has size  $[d_1, \dots, d_r, n_1, \dots, n_s]$ , with  $v(:, \dots, :, j_1, \dots, j_s)$  the value of  $f$  at  $x(j_1, \dots, j_s)$ , - except that:
  - $n_1$  is ignored if it is 1 and  $s$  is 2, i.e., if  $x$  is a row vector;
  - MATLAB ignores any trailing singleton dimensions of  $x$ .

For an  $m$ -variate  $f$  with  $m > 1$ , with  $f [d_1, \dots, d_r]$ -valued,  $x$  might be either an array, or else a cell array  $\{x_1, \dots, x_m\}$ .

- If  $x$  is an array, of size  $[n_1, \dots, n_s]$ , then  $n_1$  must equal  $m$ , and  $v$  has size  $[d_1, \dots, d_r, n_2, \dots, n_s]$ , with  $v(:, \dots, :, j_2, \dots, j_s)$  the value of  $f$  at  $x(:, j_2, \dots, j_s)$ , - except that:
  - $d_1, \dots, d_r$  is ignored in case  $f$  is scalar-valued, i.e., both  $r$  and  $n_1$  are 1;
  - MATLAB ignores any trailing singleton dimensions of  $x$ .
- If  $x$  is a cell array, then it must be of the form  $\{x_1, \dots, x_m\}$ , with  $x_j$  a vector, of length  $n_j$ , and, in that case,  $v$  has size  $[d_1, \dots, d_r, n_1, \dots, n_m]$ , with  $v(:, \dots, :, j_1, \dots, j_m)$  the value of  $f$  at  $(x_1(j_1), \dots, x_m(j_m))$ , - except that  $d_1, \dots, d_r$  is ignored in case  $f$  is scalar-valued, i.e., both  $r$  and  $n_1$  are 1.

If  $f$  has a jump discontinuity at  $x$ , then the value  $f(x +)$ , i.e., the limit from the right, is returned, except when  $x$  equals the right end of the basic interval of the form; for such  $x$ , the value  $f(x -)$ , i.e., the limit from the left, is returned.

$\text{fnval}(x, f)$  is the same as  $\text{fnval}(f, x)$ .

$\text{fnval}(\dots, 'l')$  treats  $f$  as continuous from the left. This means that if  $f$  has a jump discontinuity at  $x$ , then the value  $f(x -)$ , i.e., the limit from the left, is returned, except when  $x$  equals the left end of the basic interval; for such  $x$ , the value  $f(x +)$  is returned.

If the function is *multivariate*, then the above statements concerning continuity from the left and right apply coordinate wise.

## Examples

### Evaluate Functions at Specified Points

This example shows how to interpolate some data and plot and evaluate the resulting functions.

Define some data.

```
x = [0.074 0.31 0.38 0.53 0.57 0.58 0.59 0.61 0.61 0.65 0.71 0.81 0.97];  
y = [0.91 0.96 0.77 0.5 0.5 0.51 0.51 0.53 0.53 0.57 0.62 0.61 0.31];
```

Interpolate the data and plot the resulting function, f.

```
f = csapi( x, y )
```

```
f = struct with fields:
```

```
    form: 'pp'
```

```
    breaks: [0.0740 0.3100 0.3800 0.5300 0.5700 0.5800 0.5900 0.6100 0.6500 0.7100 0.8100 0.9700]
```


```
    coefs: [11x4 double]
```

```
    pieces: 11
```

```
    order: 4
```

```
    dim: 1
```

```
fnplt( f )
```



Find the value of the function  $f$  at  $x = 0.5$ .

```
fnval( f, 0.5 )
```

```
ans = 0.5294
```

Find the value of the function  $f$  at  $0, 0.1, \dots, 1$ .

```
fnval( f, 0:0.1:1 )
```

```
ans = 1×11
```

```
0.3652    1.0220    1.1579    0.9859    0.7192    0.5294    0.5171    0.6134    0.6172    0.4
```


Create a function  $f2$  that represents a surface.

```
x = 0.0001+(-4:0.2:4);
y = -3:0.2:3;
[yy, xx] = meshgrid( y, x );
r = pi*sqrt( xx.^2+yy.^2 );
z = sin( r )./r;
f2 = csapi( {x,y}, z );
```

Plot the function  $f2$ .

```
fnplt( f2 )
axis( [-5, 5, -5, 5, -0.5, 1] );
```





Find the value of the function `f2` at  $x = -2$  and  $y = 3$ .

```
fnval( f2, [-2; 3] )
```

```
ans = -0.0835
```

## Input Arguments

### **f** – Spline function

object

Spline function that you want to evaluate, specified as an object.

### **x** – Evaluation points

vector | matrix | cell

Points at which you want to evaluate the spline function `f`, specified as a vector, matrix or cell array.

## Output Arguments

### **v** – Values at specified points

scalar | vector | matrix | cell

Value  $f(x)$  at the points in `x` of the spline function `f`, returned as a scalar, vector, matrix or cell array.

## Algorithms

For each entry of  $x$ , the function determines the relevant break-interval or knot-interval and assembles the relevant information. Depending on whether  $f$  is in `ppform` or in `B-form`, nested multiplication or the B-spline recurrence (see, e.g., [PGS; X.(3)]) are then used vector-fashion for the simultaneous evaluation at all entries of  $x$ . Evaluation of a multivariate polynomial spline function takes full advantage of the tensor product structure.

Evaluation of a rational spline follows up evaluation of the corresponding vector-valued spline by division of all but its last component by its last component.

Evaluation of a function in `stform` makes essential use of `stcol`, and tries to keep the matrices involved to reasonable size.

## Version History

**Introduced in R2006b**

### See Also

`fnbrk` | `ppmak` | `rsmak` | `spmak` | `stmak`

### Topics

“Introducing Spline Fitting” on page 8-2

“The `ppform`” on page 10-8

“The `B-form`” on page 10-13

# fnxtr

Extrapolate spline

## Syntax

```
pp = fnxtr(f,order)
pp = fnxtr(f)
```

## Description

`pp = fnxtr(f,order)` returns a spline of order `order` that extrapolates the spline `f`. `pp` equals `f` on its basic interval, but `pp` is a polynomial of the given order outside that interval. `pp` satisfies at least `order` smoothness conditions at the ends of the basic interval of `f`, that is, at the new breaks. It is most useful to use a positive value of `order` that is smaller than the order of `f`.

`pp = fnxtr(f)` uses an extrapolation order equal to 2. It is equivalent to `fnxtr(f,2)`.

## Examples

### Extrapolate Cubic Smoothing Spline

Create a cubic smoothing spline on the unit interval.


```
x = rand(1,21);
spline = csaps(x,x.^3);
```

Create an extrapolating spline of order 2.

```
order = 2;
extrSpline = fnxtr(spline,order);
```

Plot the original spline together with the extrapolating spline.


```
fnplt(spline,[-.5 1.4])
hold on
fnplt(extrSpline,[-.5 1.4])
legend('Cubic smoothing spline','Extrapolating spline')
hold off
```



### Extrapolate Bivariate B-Spline


Create and plot a bivariate B-spline.

```
spline = spmak({0:3,0:4},1);  
fnplt(spline)
```



Create an extrapolating spline. To extrapolate in the first variable only, specify a negative integer as the extrapolation order in the second variable.

```
order = [3,-1];  
extrSpline = fnxtr(spline,order);  
fnplt(extrSpline)
```



## Input Arguments

### **f** — Spline to extrapolate

structure

Spline to extrapolate, specified as a structure. **f** must be a spline in B-form, BBform, or ppform.

Data Types: `struct`

### **order** — Order of extrapolating spline

integer | vector of integers

Order of extrapolating spline, specified as an integer or a vector of integers.

If **order** is zero, then the extrapolating spline describes the same spline as `fn2fm(f, 'B-')`, but is in ppform and has a larger basic interval.

If **order** is at least as large as the order of **f**, then the extrapolating spline is the same spline as `gn2fm(f, 'pp')`, but uses two more pieces and has a larger basic interval.

If **f** is *m*-variate, then **order** can be a vector with *m* elements, where `order(i)` is the order used to extrapolate in the *i*-th variable. To exclude the *i*-th variable from being used in the extrapolation, specify `order(i)` as a negative integer.

Example: 1

## Output Arguments

### **pp — Spline in ppform**

spline structure

Spline in ppform, returned as a structure with these fields.

### **Form — Form of spline**

pp

Form of the spline, returned as pp. pp indicates that the spline is given in piecewise polynomial form.

### **Breaks — Knot locations of spline**

vector | cell array

Knot positions of the spline, returned as a vector or as a cell array of vectors for multivariate data. Vectors contain strictly increasing elements that represent the start and end of each of the intervals over which the polynomial pieces are defined.

### **Coefs — Coefficients of polynomials**

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

### **Pieces — Number of polynomial pieces**

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

### **Order — Order of polynomials**

scalar | vector

Order of the polynomial function describing each polynomial piece of the spline, returned as a scalar or as a vector containing the order in each variable for multivariate data.

### **Dim — Dimensionality**

scalar

Dimensionality of the target function, returned as a scalar.

## Version History

**Introduced in R2006a**

### **See Also**

ppmak | spmak | fn2fm

## fnzeros

Roots of spline

### Syntax

```
x = fnzeros(spline)
x = fnzeros(spline,I)
```

### Description

`x = fnzeros(spline)` finds the zeros of a scalar-valued univariate spline in its basic interval. A spline zero is either a point or a closed interval over which the spline is zero.

`x = fnzeros(spline,I)` finds the zeros in the interval I.


### Examples

#### Find Roots of Spline

Create and plot a piecewise linear spline.

```
spline = spmak(augknt(1:7,2),[1,0,1,-1,0,0,1]);
figure
fnplt(spline)
```





Find the roots of the spline. The spline has each of the three kinds of zeros: touch zero, cross zero, and zero over an interval.


```
x = fnzeros(spline)
```

```
x = 2×3
```

```
    2.0000    3.5000    5.0000
    2.0000    3.5000    6.0000
```

Plot the roots of the spline using right-pointing triangles at the left endpoints and left-pointing triangles at the right endpoints.

```
nz = size(x,2);
hold on
plot(x(1,:),zeros(1,nz),'r>',x(2,:),zeros(1,nz),'r<','MarkerSize',10)
hold off
```




### Find Local Extrema of Spline

Create a spline with many local extrema. Locate the local extrema of the spline by finding the roots of its first derivative.

```
spline = spmak(1:31,rand(1,25)-0.5);  
x = fnzeros(fnder(spline));
```

Plot the spline and its local extrema.


```
figure  
fnplt(spline)  
hold on  
x = unique(x(:));  
y = fnval(spline,x);  
plot(x,y,'ro')  
xlim([-Inf Inf])  
hold off
```



### Find Roots of Discontinuous Spline

Create and plot a discontinuous piecewise linear spline.

```
spline = spmak([0 0 1 1 2 2],[-1 1 -1 1]);  
figure  
fnplt(spline);
```



Find the roots of the spline. The roots include the jump through zero at  $x = 1$ .

```
x = fnzeros(spline)
```

```
x = 2×3
```

```
    0.5000    1.0000    1.5000  
    0.5000    1.0000    1.5000
```

## Input Arguments

### **spline** – Spline

structure

Spline, specified as a structure. `spline` must represent a scalar-valued univariate spline.

Data Types: `struct`

### **I** – Interval to find zeros in

numeric vector with two elements

Interval to find zeros in, specified as a numeric vector with two elements.

## Output Arguments

### **x** — Location of roots

matrix with two rows

Locations of roots of spline, returned as a matrix with two rows. The elements of the first row are the left endpoints of the intervals and the elements of the second row are the right endpoints. Each column contains the left and right endpoint of a single interval. The roots are in increasing order.

There are three different types of intervals:

- If the endpoints are different, then the spline is zero on the entire interval. In this case, the largest possible interval is given, regardless of knots that may be in the interior of the interval.
- If the endpoints are the same and coincident with a knot, then the spline has a zero at that point. The spline could cross zero, touch zero, or be discontinuous at this point.
- If the endpoints are the same and not coincident with a knot, then the spline has a zero crossing at this point.

## Algorithms

To find the roots of a spline, `fnzeros` first converts the spline to B-form. The function then performs some preprocessing to handle discontinuities and then uses the algorithm of [1].

## Version History

Introduced before R2006a

## References

- [1] Mørken, Knut, and Martin Reimers. "An unconditionally convergent method for computing zeros of splines and polynomials." *Mathematics of Computation* 76, no. 258 (2007): 845-865.

## See Also

`fnmin` | `fnval`

## formula

Formula of `cf`fit, `s`fit, or `f`ittype object

### Syntax

```
formula(fun)
```

### Description

`formula(fun)` returns the formula of the `cf`fit, `s`fit, or `f`ittype object `fun` as a character array.

### Examples

```
f = fittype('weibull');
formula(f)
ans =
a*b*x^(b-1)*exp(-a*x^b)

g = fittype('cubicspline');
formula(g)
ans =
piecewise polynomial
```

## Version History

Introduced in R2006b

### See Also

`fittype` | `coeffnames` | `numcoeffs` | `probnames` | `coeffvalues`

# franke

Franke's bivariate test function

## Syntax

```
z = franke(x,y)
```

## Description

`z = franke(x,y)` returns the value  $z(i)$  of Franke's function at the site  $(x(i),y(i))$ ,  $i=1:\text{numel}(x)$ , with  $z$  of the same size as  $x$  and  $y$  (which must be of the same size).


Franke's function is the following weighted sum of four exponentials:

$$\begin{aligned} & \frac{3}{4}e^{-\left((9x-2)^2 + (9y-2)^2\right)/4} + \frac{3}{4}e^{-\left((9x+1)^2/49 + (9y+1)/10\right)} \\ & + \frac{1}{2}e^{-\left((9x-7)^2 + (9y-3)^2\right)/4} - \frac{1}{5}e^{-\left((9x-4)^2 + (9y-7)^2\right)} \end{aligned}$$

## Examples

The following commands provide a plot of Franke's function:

```
pts = (0:50)/50; [x,y] = ndgrid(pts,pts); z = franke(x,y);  
surf(x,y,z), view(145,-2), set(gca,'FontSize',16)
```



## References

- [1] Richard Franke. "A critical comparison of some methods for interpolation of scattered data." *Naval Postgraduate School Tech.Rep.* NPS-53-79-003, March 1979.

## get

Get fit options structure property names and values

### Syntax

```
get(options)
s = get(options)
value = get(options,field)
```

### Description

`get(options)` displays all property names and values of the fit options structure `options`.

`s = get(options)` returns a copy of the fit options structure `options` as the structure `s`.

`value = get(options,field)` returns the value of the property *field* of the fit options structure `options`. *field* can be a cell array of character vectors, in which case `value` is also a cell array.

### Examples

#### Obtain Property Values of a fit options Structure Using get

Create a fitoptions structure and call the `get` function to obtain its property values.

```
options = fitoptions('fourier1');
methodOptions = get(options,'Method')
maxIterOptions = get(options,'MaxIter')
set(options,'Maxiter',1e3);
maxIterOptions = get(options,'MaxIter')
```

```
methodOptions =
    'NonlinearLeastSquares'
```

```
maxIterOptions =
```

```
    400
```

```
maxIterOptions =
```

```
    1000
```

Property values can also be referenced and assigned using the dot notation. For example:

```
options.MaxIter
```

```
ans =
    1000
```

```
options.MaxIter = 500;
options.MaxIter
```



```
ans =  
    500
```

## Input Arguments

### **options** — fitoptions object

fitoptions (default)

fitoptions object of which you want to get the property names and values, specified as a fitoptions object.

### **field** — Property value

string scalar | character vector | cell array of character vectors

Property value of the fitoptions object options that you want to get, specified as a string scalar, character vector, or a cell array of character vectors.

Data Types: char | string | cell

## Output Arguments

### **s** — fitoptions object

fitoptions

Copy of the fitoptions object, returned as a fitoptions object.

### **value** — Property value

scalar | vector | matrix | cell

Property value of the fitoptions object s, returned as a scalar, a vector, a matrix, or a cell.

## Version History

Introduced before R2006a

## See Also

fitoptions | set

## getcurve

Interactive creation of cubic spline curve

### Syntax

```
[xy,spcv] = getcurve
```

### Description

`[xy,spcv] = getcurve` displays a gridded window and asks you for input. As you click on points in the gridded window, the broken line connecting these points is displayed. To indicate that you are done, click outside the gridded window. Then a cubic spline curve, `spcv`, through the point sequence, `xy`, is computed (via `cscvn`) and drawn. The point sequence and, optionally, the spline curve are output.

If you want a closed curve, place the last point *close* to the initial point.

If you would like the curve to have a corner at some point, click on that point twice (or more times) in succession.

You can't use `getcurve` over an existing figure, but you can use these functions to do the same thing: MATLAB function `ginput`, and `cscvn` in Curve Fitting Toolbox.

### Examples

#### Draw a Spline Over an Image

You can't use `getcurve` over an existing figure, but you can use these functions to do the same thing. The following example code allows you to click an existing image to draw a spline through the points.

Draw the default image.

```
image
```

The function `ginput` collects mouse click points until you press **Enter**.

```
[x, y] = ginput
```

Click on the axis to select points. Press **Enter** when you have finished selecting points.

Fit and plot a spline through the points using the `cscvn` function.

```
spcv = cscvn( [x, y].' )  
hold on  
fnplt( spcv )  
hold off
```

### See Also

`cscvn`

# indepnames

Independent variable of `cfits`, `sfits`, or `fitttype` object

## Syntax

```
indep = indepnames(fun)
```

## Description

`indep = indepnames(fun)` returns the independent variable name or names (`indep`) of the `cfits`, `sfits`, or `fitttype` object `fun`. For curves `indep` is a 1-by-1 cell array of character vectors, and for surfaces `indep` is a 2-by-1 cell array of character vectors.

## Examples

```
f1 = fitttype('a*x^2+b*exp(n*x)');  
indep1 = indepnames(f1)  
indep1 =  
    'x'
```

```
f2 = fitttype('a*x^2+b*exp(n*x)', 'independent', 'n');  
indep2 = indepnames(f2)  
indep2 =  
    'n'
```

## Version History

Introduced in R2006b

## See Also

`dependnames` | `fitttype` | `formula`

## integrate

Integrate cfit object

### Syntax

```
int = integrate(fun,x,x0)
```

### Description

`int = integrate(fun,x,x0)` integrates the cfit object `fun` at the points specified by the vector `x`, starting from `x0`, and returns the result in `int`.

### Examples

#### Find the Integral of a Fit Using the integrate Function

Create a baseline sinusoidal signal.

```
xdata = (0:.1:2*pi)';  
y0 = sin(xdata);
```

Add response-dependent Gaussian noise to the signal.

```
noise = 2*y0.*randn(size(y0));  
ydata = y0 + noise;
```

Fit the noisy data with a custom sinusoidal model.


```
f = fitttype('a*sin(b*x)');  
fit1 = fit(xdata,ydata,f,'StartPoint',[1 1]);
```

Find the integral of the fit at the predictors.

```
int = integrate(fit1,xdata,0);
```


Plot the data, the fit, and the integral.

```
subplot(2,1,1)  
plot(fit1,xdata,ydata) % cfit plot method  
subplot(2,1,2)  
plot(xdata,int,'m') % double plot method  
grid on  
legend('integral')
```



You can also compute integrals and plot them directly with the `cfits` plot method:

```
figure  
plot(fit1,xdata,ydata,{'fit','integral'})
```



The plot method, however, does not return data on the integral.

## Input Arguments

### **fun** — cfit function

cfit

Function to integrate, specified as a cfit object.

### **x** — Integration points

numeric vector

Points at which to integrate the function, specified as a numeric vector.

### **x0** — Lower bound for integration

numeric scalar

Lower bound for integration, specified as a numeric scalar.

## Output Arguments

### **int** — Integration results

numeric vector

Result of the integration, returned as a numeric vector of the same size as **x**.

## **Version History**

Introduced before R2006a

### **See Also**

`fit` | `plot` | `differentiate`

### **Topics**

"Introducing Spline Fitting" on page 8-2

## islinear

Determine if `cfit`, `sfit`, or `fittype` object is linear

### Syntax

```
flag = islinear(fun)
```

### Description

`flag = islinear(fun)` returns a flag of 1 if the `cfit`, `sfit`, or `fittype` object `fun` represents a linear model, and a flag of 0 if it does not.

---

**Note** `islinear` assumes that all custom models specified by the `fittype` function using the syntax `ftype = fittype('expr')` are nonlinear models. To create a linear model with `fittype` that will be recognized as linear by `islinear` (and, importantly, by the algorithms of `fit`), use the syntax `ftype = fittype({'expr1', 'expr2', ..., 'exprn'})`.

---

### Examples

```
f = fittype('a*x+b')
f =
    General model:
    f(a,b,x) = a*x+b

g = fittype({'x', '1'})
g =
    Linear model:
    g(a,b,x) = a*x + b

h = fittype('poly1')
h =
    Linear model Poly1:
    h(p1,p2,x) = p1*x + p2

islinear(f)
ans =
    0
islinear(g)
ans =
    1
islinear(h)
ans =
    1
```

### Version History

Introduced in R2006b



**See Also**

fittype

## knt2brk, knt2mlt

Convert knots to breaks and their multiplicities

### Syntax

```
knt2brk(knots)
[breaks,mults] = knt2brk(knots)
m = knt2mlt(t)
[m,sortedt] = knt2mlt(t)
```

### Description

The commands extract the distinct elements from a sequence, as well as their multiplicities in that sequence, with *multiplicity* taken in two slightly different senses.

`knt2brk(knots)` returns the distinct elements in `knots`, and in increasing order, hence is the same as `unique(knots)`.

`[breaks,mults] = knt2brk(knots)` additionally provides, in `mults`, the multiplicity with which each distinct element occurs in `knots`. Explicitly, `breaks` and `mults` are of the same length, and `knt2brk` is complementary to `brk2knt` in that, for any knot sequence `knots`, the two commands `[xi,mults] = knt2brk(knots); knots1 = brk2knt(xi,mults);` give `knots1` equal to `knots`.

`m = knt2mlt(t)` returns a vector of the same length as `t`, with `m(i)` counting, in the vector `sort(t)`, the number of entries before its *i*th entry that are equal to that entry. This kind of multiplicity vector is needed in `spapi` or `spcol` where such multiplicity is taken to specify which particular derivatives are to be matched at the sites in `t`. Precisely, if `t` is nondecreasing and `z` is a vector of the same length, then `sp = spapi(knots, t, z)` attempts to construct a spline *s* (with knot sequence `knots`) for which  $D^{m(i)}s(t(i))$  equals  $z(i)$ , all *i*.

`[m,sortedt] = knt2mlt(t)` also returns the output from `sort(t)`.

Neither `knt2brk` nor `knt2mlt` is likely to be used by the casual user of this toolbox.

### Examples

```
[xi,mults]=knt2brk([1 2 3 3 1 3]) returns [1 2 3] for xi and [2 1 3] for mults.
```

```
[m,t]=knt2mlt([1 2 3 3 1 3]) returns [0 1 0 0 1 2] for m and [1 1 2 3 3 3] for t.
```

### See Also

`brk2knt` | `spapi` | `spcol`

# newknt

New break distribution

## Syntax

```
newknts = newknt(f,newl)
newknt(f)
[... ,distfn] = newknt(...)
```

## Description

`newknts = newknt(f,newl)` returns the knot sequence whose interior knots cut the basic interval of  $f$  into `newl` pieces, in such a way that a certain piecewise linear monotone function related to the high derivative of  $f$  is equidistributed.

The intent is to choose a knot sequence suitable to the fine approximation of a function  $g$  whose rough approximation in  $f$  is assumed to contain enough information about  $g$  to make this feasible.

`newknt(f)` uses for `newl` its default value, namely the number of polynomial pieces in  $f$ .

`[... ,distfn] = newknt(...)` also returns, in `distfn`, the ppform of that piecewise linear monotone function being equidistributed.

## Examples

If the error in the least-squares approximation  $sp$  to some data  $x, y$  by a spline of order  $k$  seems uneven, you might try for a more equitable distribution of knots by using

```
spap2(newknt(sp),k,x,y);
```

For another example, see "Solving a Nonlinear ODE with a Boundary Layer by Collocation" on page 12-145.

## Algorithms

This is the Fortran routine `NEWNOT` in *PGS*. With  $k$  the order of the piecewise-polynomial function  $f$  in `pp`, the function  $|D^k f|$  is approximated by a piecewise constant function obtained by local, discrete, differentiation of the variation of  $D^{k-1}f$ . The new break sequence is chosen to subdivide the basic interval of the piecewise-polynomial  $f$  in such a way that

$$\int_{\text{newknts}(i)}^{\text{newknts}(i+1)} |D^k f|^{1/k} = \text{const}, \quad i = k:k + \text{newl} - 1$$

## numargs

Number of input arguments of `cfits`, `sfits`, or `fittype` object

### Syntax

```
nargs = numargs(fun)
```

### Description

`nargs = numargs(fun)` returns the number of input arguments `nargs` of the `cfits`, `sfits`, or `fittype` object `fun`.

### Examples

```
f = fittype('a*x^2+b*exp(n*x)');
nargs = numargs(f)
nargs =
     4
args = argnames(f)
args =
     'a'
     'b'
     'n'
     'x'
```

## Version History

**Introduced in R2006b**

### See Also

`fittype` | `formula` | `argnames`

## numcoeffs

Number of coefficients of `cf`, `sfit`, or `fittype` object

### Syntax

```
ncoeffs = numcoeffs(fun)
```

### Description

`ncoeffs = numcoeffs(fun)` returns the number of coefficients `ncoeffs` of the `cf`, `sfit`, or `fittype` object `fun`.

### Examples

```
f = fittype('a*x^2+b*exp(n*x)');
ncoeffs = numcoeffs(f)
ncoeffs =
     3
coeffs = coeffnames(f)
coeffs =
     'a'
     'b'
     'n'
```

## Version History

Introduced in R2006b

### See Also

`fittype` | `formula` | `coeffnames`

## optknt

Knot distribution “optimal” for interpolation

### Syntax

```
knots = optknt(tau,k,maxiter)
optknt(tau,k)
```

### Description

`knots = optknt(tau,k,maxiter)` provides the knot sequence  $\mathbf{t}$  that is *best* for interpolation from  $S_{k,t}$  at the site sequence  $\mathbf{tau}$ , with 10 the default for the optional input `maxiter` that bounds the number of iterations to be used in this effort. Here, *best* or *optimal* is used in the sense of Micchelli/Rivlin/Winograd and Gaffney/Powell, and this means the following: For any *recovery scheme*  $R$  that provides an interpolant  $Rg$  that matches a given  $g$  at the sites  $\mathbf{tau}(1), \dots, \mathbf{tau}(n)$ , we may determine the smallest constant  $\text{const}_R$  for which  $\|g - Rg\| \leq \text{const}_R \|D^k g\|$  for all smooth functions  $g$ .

Here,  $\|f\| := \sup_{\mathbf{tau}(1) < x < \mathbf{tau}(n)} |f(x)|$ . Then we may look for the optimal recovery scheme as the scheme  $R$  for which  $\text{const}_R$  is as small as possible. Micchelli/Rivlin/Winograd have shown this to be interpolation from  $S_{k,t}$  with  $\mathbf{t}$  uniquely determined by the following conditions:

- 1  $\mathbf{t}(1) = \dots = \mathbf{t}(k) = \mathbf{tau}(1)$ ;
- 2  $\mathbf{t}(n+1) = \dots = \mathbf{t}(n+k) = \mathbf{tau}(n)$ ;
- 3 Any absolutely constant function  $h$  with sign changes at the sites  $\mathbf{t}(k+1), \dots, \mathbf{t}(n)$  and nowhere else satisfies

$$\int_{\mathbf{tau}(1)}^{\mathbf{tau}(n)} f(x)h(x)dx = 0 \text{ for all } f \in S_{k,t}$$

Gaffney/Powell called this interpolation scheme *optimal* since it provides the *center* function in the band formed by all interpolants to the given data that, in addition, have their  $k$ th derivative between  $M$  and  $-M$  (for large  $M$ ).

`optknt(tau,k)` is the same as `optknt(tau,k,10)`.

### Examples

See the last part of the example “Spline Interpolation” for an illustration. For the following highly nonuniform knot sequence

```
t = [0, .0012+[0, 1, 2+[0,.1], 4]*1e-5, .002, 1];
```

the command `optknt(t,3)` will fail, while the command `optknt(t,3,20)`, using a high value for the optional parameter `maxiter`, will succeed.

### Algorithms

This is the Fortran routine `SPLOPT` in `PGS`. It is based on an algorithm described in [1], for the construction of that sign function  $h$  mentioned above. It is essentially Newton's method for the

solution of the resulting nonlinear system of equations, with `aveknt ( tau , k )` providing the first guess for  $t(k+1)$ , ...,  $t(n)$ , and some damping used to maintain the Schoenberg-Whitney conditions.

## References

- [1] C. de Boor. "Computational aspects of optimal recovery." In *Optimal Estimation in Approximation Theory*, C.A. Micchelli & T.J. Rivlin eds., Plenum Publ., New York, 1977, 69-91.
- [2] P.W. Gaffney & M.J.D. Powell. "Optimal interpolation." In *Numerical Analysis*, G.A. Watson ed., *Lecture Notes in Mathematics, No. 506*, Springer-Verlag, 1976, 90-99.
- [3] C.A. Micchelli, T.J. Rivlin & S. Winograd. "The optimal recovery of smooth functions." *Numer. Math.* **80**, (1974), 903-906.

## See Also

`aptknt` | `aveknt` | `newknt`

## plot

Plot `cf` or `sfit` object

### Syntax

```
plot(sfit)
plot(sfit,[x,y],z)
plot( ____,Name=Value)

plot(cf)
plot(cf,x,y)
plot(cf,x,y,DataLineSpec)
plot(cf,FitLineSpec,x,y,DataLineSpec)
plot(cf,x,y,outliers)
plot(cf,x,y,outliers,OutlierLineSpec)
plot( ____,ptype)
plot( ____,ptype,level)

plot(ax, ____)
H = plot( ____)
```

### Description

#### Surfaces

`plot(sfit)` plots the surface given in the `sfit` object `sfit` over the range of the current axes (`gca`). If no current axes exist, the function plots the surface over the range of the data used to create `sfit`.

`plot(sfit,[x,y],z)` plots `sfit` together with a scatter plot of the data in `x`, `y`, and `z`. The axes limits are given by the ranges of `x` and `y`.

`plot( ____,Name=Value)` specifies options using one or more name-value arguments in addition to any of the input argument combinations in the previous syntaxes for surfaces. For example, you can specify the type and limits of the plot.

#### Curves

`plot(cf)` plots the curve given in the `cf` object `cf` over the range of the current axes (`gca`). If no current axes exist, the function plots the curve over the range of the data used to create `cf`.

`plot(cf,x,y)` plots `cf` together with a scatter plot of the data in `x` and `y`. The axes limits are given by the range of `x`.


`plot(cf,x,y,DataLineSpec)` specifies the color, marker symbol, and line style used to plot the scatter plot data.

`plot(cf,FitLineSpec,x,y,DataLineSpec)` specifies the color, marker symbol, and line style that `plot` uses to plot the curve given in `cf`.

`plot(cf,x,y,outliers)` specifies the scatter plot data to treat as outliers, and plots them in a different color.







The plot shows that the Lowess smoothing fit is a wavy surface that lies between  $z=0$  and  $z=1.5$  across the values for  $x$  and  $y$ .

### Plot Curve Fit with Data

Load the titanium data set. Convert the data from row to column vectors.

```
[x, y] = titanium;  
x = x';  
y = y';
```

$x$  contains temperature measurements and  $y$  contains measurements for a property of titanium.


Fit a Gaussian model to the  $x$  and  $y$  data.

```
g = fit(x,y,"gauss2");
```

$g$  is a `cfits` object that contains the results of fitting the Gaussian model to the data.

Plot  $g$  with a scatter plot of the data.

```
plot(g,x,y)
```



The plot shows that  $g$  closely follows the majority of the data, and the  $y$  data spikes when  $x$  is approximately 900.

### Plot and Compare Fitting Methods

Generate some data for a baseline sinusoidal signal using the `linspace` and `sin` functions.

```
xdata = linspace(0,2*pi,60)';
y0 = sin(xdata);
```

`xdata` is a vector of 60 points between  $0$  and  $2\pi$ , and `y0` is a vector of values given by evaluating the sine function at the values in `xdata`.

Generate noise from a Gaussian distribution using the `randn` function.

```
rng(0,"twister") % For reproducibility
gnoise = y0.*randn(size(y0));
```

To generate impulse noise, first use the `randperm` and `round` functions to create a vector of random indices.

```
leny0 = length(y0);
p = randperm(leny0);
stop = round(leny0/5);
idx = p(1:stop);
```

`idx` is a vector of integers representing the indices of `y0`.

Create a vector of impulse noise using the `zeros` function. Then, use the `sign` function to assign the values `-5` and `5` to the noise vector at positions in `idx` where the elements of `y0` are negative and positive, respectively.

```
szy = size(y0);
spnoise = zeros(szy);
yidx = y0(idx);
spnoise(idx) = 5*sign(yidx);
```

Add the noise vectors to `y0`.

```
ydata = y0 + gnoise + spnoise;
```

`ydata` is a vector of noisy data with nonconstant variance.

Fit a sinusoidal model to `ydata`.

```
f = fittype("a*sin(b*x)");
fit1 = fit(xdata,ydata,f,StartPoint=[1 1]);
```

`fit1` contains the results of fitting a sinusoidal model using least-squares fitting.

Create a vector of outliers from the points in `xdata` and `ydata` that are more than 1.5 standard deviations away from the model in `fit1`.

```
fdata = feval(fit1,xdata);
outliers = abs(fdata - ydata) > 1.5*std(ydata);
```

Refit the data with the outliers excluded.

```
fit2 = fit(xdata,ydata,f,StartPoint=[1 1],...
          Exclude=outliers);
```

`fit2` contains the results of fitting a sinusoidal model to the data with the outliers excluded.


Fit a third model using a robust fitting algorithm.

```
fit3 = fit(xdata,ydata,f,StartPoint=[1 1],Robust="on");
```

`fit3` contains the results of fitting a sinusoidal model to the data using the bisquare-weights fitting algorithm.

To compare the fitted models, plot the data, outliers, and results of the fits. Plot each fit with a different color and line style, and plot the outliers with magenta asterisks.


```
plot(fit1,"r-",xdata,ydata,"k.",outliers,"m*")
hold on
plot(fit2,"c--")
plot(fit3,"b:")
xlim([0 2*pi])
legend("data","outlier","fit1","fit2","fit3")
```



The plot shows each fit with a different line color and style. All three fits follow the bulk of the data. fit1 comes closer to the outliers than the other two fits.

Plot the residuals for fit1.

```
figure
plot(fit1,xdata,ydata,"co","residuals")
hold on
xlabel("xdata")
ylabel("residuals")
hold off
```



The plot shows that the residuals for `fit1` have nonconstant variance across the values in `xdata`.

## Input Arguments

### **sfit** – Surface fit object

`sfit` object

Surface fit object to plot, specified as an `sfit` object.

### **cfit** – Curve fit object

`cfit` object

Curve fit object to plot, specified as a `cfit` object.

### **x** – x-coordinates for scatter plot data

numeric column vector

x-coordinates for the scatter plot data, specified as a numeric column vector. When plotting `cfit` objects, you must also specify `y` when you specify `x`. When plotting `sfit` objects, you must also specify `y` and `z` when you specify `x`. `x` and `y` must be the same size.

Data Types: `single` | `double`

### **y** – y-coordinates for scatter plot data

numeric column vector

y-coordinates for the scatter plot data, specified as a numeric column vector. When plotting `cf` objects, you must also specify `x` when you specify `y`. When plotting `sfit` objects, you must also specify `x` and `z` when you specify `y`. `x` and `y` must be the same size.

Data Types: `single` | `double`

### **z — z-coordinates for scatter plot data**

numeric column vector

z-coordinates for the scatter plot data, specified as a numeric column vector. You can specify `z` only when plotting `sfit` objects, and you must also specify `x` and `y`. `z` and `x` must be the same size.

Data Types: `single` | `double`

### **outliers — Indicator to treat scatter plot data as outliers**

logical expression | index vector | logical vector

Indicator to treat scatter plot data as outliers, specified as a logical expression, index vector, or a logical vector. You can specify `outliers` only when plotting `cf` objects.

- Logical expression — `plot` treats data points that satisfy the expression as outliers.
- Index vector — `plot` treats data points at the specified indices as outliers.
- Logical vector — `plot` treats data points at positions where `outliers` is `true` as outliers. You can create a logical vector to specify outliers by using the `excludedata` function.

For an example, see “Exclude Points from Fit” on page 13-90.

Example: `x > 10` treats data with values for `x` greater than 10 as outliers.

Example: `[1 10 25]` treats data at indices 1, 10, and 25 as outliers.

Example: `[zeros(100,1);ones(50,1)]` treats the last 50 data points as outliers.

Data Types: `logical` | `single` | `double`

### **DataLineStyle — Line style, marker, and color for data**

character vector | string scalar

Line style, marker, and color for the scatter plot data, specified as a character vector or string scalar containing symbols. The symbols can appear in any order. You do not need to specify all three characteristics (line style, marker, and color). For example, if you omit the line style and specify the marker, then the plot shows only the marker and no line.

You can specify `DataLineStyle` only when plotting `cf` objects.

| Line Style | Description          |
|------------|----------------------|
| -          | Solid line (default) |
| --         | Dashed line          |
| :          | Dotted line          |
| -.         | Dash-dot line        |

| Marker | Description |
|--------|-------------|
| o      | Circle      |

| Marker | Description                |
|--------|----------------------------|
| +      | Plus sign                  |
| *      | Asterisk                   |
| .      | Point                      |
| x      | Cross                      |
| s      | Square                     |
| d      | Diamond                    |
| ^      | Upward-pointing triangle   |
| v      | Downward-pointing triangle |
| >      | Right-pointing triangle    |
| <      | Left-pointing triangle     |
| p      | Pentagram                  |
| h      | Hexagram                   |

| Color | Description |
|-------|-------------|
| y     | Yellow      |
| m     | Magenta     |
| c     | Cyan        |
| r     | Red         |
| g     | Green       |
| b     | Blue        |
| w     | White       |
| k     | Black       |

Example: "--or" specifies a red dashed line with circle markers.

Data Types: char | string

### FitLineSpec – Line style, marker, and color for curve

character vector | string scalar

Line style, marker, and color for the curve given in `cfits`, specified as a character vector or string scalar containing symbols. The symbols can appear in any order. You do not need to specify all three characteristics (line style, marker, and color). For example, if you omit the line style and specify the marker, then the plot shows only the marker and no line.

| Line Style | Description          |
|------------|----------------------|
| -          | Solid line (default) |
| --         | Dashed line          |
| :          | Dotted line          |
| -.         | Dash-dot line        |



| Marker | Description                |
|--------|----------------------------|
| o      | Circle                     |
| +      | Plus sign                  |
| *      | Asterisk                   |
| .      | Point                      |
| x      | Cross                      |
| s      | Square                     |
| d      | Diamond                    |
| ^      | Upward-pointing triangle   |
| v      | Downward-pointing triangle |
| >      | Right-pointing triangle    |
| <      | Left-pointing triangle     |
| p      | Pentagram                  |
| h      | Hexagram                   |

| Color | Description |
|-------|-------------|
| y     | Yellow      |
| m     | Magenta     |
| c     | Cyan        |
| r     | Red         |
| g     | Green       |
| b     | Blue        |
| w     | White       |
| k     | Black       |

Example: "--or" specifies a red dashed line with circle markers.

Data Types: char | string

### OutlierLineSpec – Line style, marker, and color for outliers

character vector | string scalar

Line style, marker, and color used to plot the outliers, specified as a character vector or string scalar containing symbols. The symbols can appear in any order. You do not need to specify all three characteristics (line style, marker, and color). For example, if you omit the line style and specify the marker, then the plot shows only the marker and no line.

You can specify `OutlierLineSpec` only when plotting `cf` objects.

| Line Style | Description          |
|------------|----------------------|
| -          | Solid line (default) |
| --         | Dashed line          |
| :          | Dotted line          |

| Line Style | Description   |
|------------|---------------|
| - .        | Dash-dot line |

| Marker | Description                |
|--------|----------------------------|
| o      | Circle                     |
| +      | Plus sign                  |
| *      | Asterisk                   |
| .      | Point                      |
| x      | Cross                      |
| s      | Square                     |
| d      | Diamond                    |
| ^      | Upward-pointing triangle   |
| v      | Downward-pointing triangle |
| >      | Right-pointing triangle    |
| <      | Left-pointing triangle     |
| p      | Pentagram                  |
| h      | Hexagram                   |

| Color | Description |
|-------|-------------|
| y     | Yellow      |
| m     | Magenta     |
| c     | Cyan        |
| r     | Red         |
| g     | Green       |
| b     | Blue        |
| w     | White       |
| k     | Black       |

Example: "--or" specifies a red dashed line with circle markers.

Data Types: char | string

### **p**type — Plot type for curve fit

"fit" (default) | "predfunc" | "predobs" | "residuals" | "stresiduals" | "deriv1" | "deriv2" | "integral"

Plot type for a curve fit, specified as one of the following:

- "fit" — Data and fit
- "predfunc" — Data and fit with prediction bounds for the fit
- "predobs" — Data and fit with prediction bounds for new observations
- "residuals" — Residuals
- "stresiduals" — Standardized residuals (residuals divided by their standard deviation)

- "deriv1" — First derivative of the fit
- "deriv2" — Second derivative of the fit
- "integral" — Integral of the fit

Data Types: char | string

### **Level — Confidence level for prediction intervals**

0.95 (default) | scalar value in the range (0,1)

Confidence level for the prediction intervals of a curve fit when ptype is "predfunc" or "predobs", specified as a scalar value in the range (0,1).

Example: 0.99

Data Types: single | double

### **ax — Target axes**

Axes object

Target axes, specified as an Axes object. If you do not specify the axes, then plot uses the current axes (gca).

### **Name-Value Pair Arguments**

Specify optional pairs of arguments as Name1=Value1, . . . , NameN=ValueN, where Name is the argument name and Value is the corresponding value. Name-value arguments must appear after other arguments, but the order of the pairs does not matter.

*Before R2021a, use commas to separate each name and value, and enclose Name in quotes.*

Example: plot(sfit,[x,y],z,YLim=[0,1],Exclude=[1 10 25]) specifies the y-axis limits and points to treat as outliers.

### **Exclude — Indicator to treat scatter plot data as outliers**

logical expression | index vector | logical vector

Indicator to treat scatter plot data as outliers, specified as a logical expression, index vector, or logical vector.

- Logical expression — plot treats data points that satisfy the expression as outliers.
- Index vector — plot treats data points at the specified indices as outliers.
- Logical vector — plot treats data points at positions where outliers is true as outliers. You can create a logical vector to specify outliers by using the excludedata function.

You must also specify x, y, and z input arguments when you specify Exclude.

For an example, see "Exclude Points from Fit" on page 13-90.

Example: Exclude=x>10 treats data with values for x greater than 10 as outliers.

Example: Exclude=[1 10 25] treats data at indices 1, 10, and 25 as outliers.

Example: Exclude=[zeros(100,1);ones(50,1)] treats the last 50 data points as outliers.

Data Types: logical | single | double

**Style — Surface fit plot style**`'Surface'` (default) | `'PredFunc'` | `'PredObs'` | `'Residuals'` | `'Contour'`

Surface fit plot style, specified as one of the following:

- `"Surface"` — Plot the `sfit` object as a surface (default).
- `"PredFunc"` — Plot the `sfit` object as a surface with prediction bounds for the function.
- `"PredObs"` — Plot the `sfit` object as a surface with prediction bounds for new observations.
- `"Residuals"` — Plot the residuals for the `sfit` object. When you specify `Style` as `"Residuals"`, you must also specify `x`, `y`, and `z`.
- `"Contour"` — Plot the `sfit` object as a contour plot.

Example: `Style="Contour"`

Data Types: `char` | `string`

**Level — Confidence level for prediction intervals**`0.95` (default) | scalar value in the range (0,1)

Confidence level for the prediction intervals of a surface fit when `Style` is `"PredFunc"` or `"PredObs"`, specified as a scalar value in the range (0,1).

Example: `Level=0.99`

Data Types: `single` | `double`

**XLim — x-axis limit**

numeric vector

x-axis limit for a surface plot, specified as a numeric vector with two elements. If you provide `x`, `y`, and `z` data, the axes limits are given by `x` and `y`. Otherwise, `plot` uses the axes limits in `sfit`.

Example: `XLim=[0 1]`

Data Types: `single` | `double`

**YLim — y-axis limit**

numeric vector

y-axis limit for a surface plot, specified as a numeric vector with two elements. If you provide `x`, `y`, and `z` data, the axes limits are given by `x` and `y`. Otherwise, `plot` uses the axes limits in `sfit`.

Example: `YLim=[-100 100]`

Data Types: `single` | `double`

**Parent — Handle of axes**

Axes object

Handle of the axes for a surface plot, specified as an Axes object.

Example: `Parent=ax`

**Version History****Introduced before R2006a**

## See Also

### Apps

Curve Fitter

### Functions

fit | excludedata | differentiate | integrate

### Topics

“Introducing Spline Fitting” on page 8-2

## ppmak

Put together spline in pform

### Syntax

```
ppmak(breaks,coefs)
ppmak
ppmak(breaks,coefs,d)
ppmak(breaks,coefs,sizec)
```

### Description

The command `ppmak(...)` puts together a spline in pform from minimal information, with the rest inferred from that information. `fnbrk` provides any or all of the parts of the completed description. In this way, the actual data structure used for the storage of the pform is easily modified without any effect on the various `fn...` commands that use this construct. However, the casual user is not likely to use `ppmak` explicitly, relying instead on the various spline construction commands in the toolbox to construct particular splines.

`ppmak(breaks,coefs)` returns the pform of the spline specified by the break information in `breaks` and the coefficient information in `coefs`. How that information is interpreted depends on whether the function is univariate or multivariate, as indicated by `breaks` being a sequence or a cell array.

If `breaks` is a sequence, it must be nondecreasing, with its first entry different from its last. Then the function is assumed to be univariate, and the various parts of its pform are determined as follows:

- 1 The number  $l$  of polynomial pieces is computed as `length(breaks)-1`, and the basic interval is, correspondingly, the interval `[breaks(1) .. breaks(l+1)]`.
- 2 The dimension  $d$  of the function's target is taken to be the number of rows in `coefs`. In other words, each column of `coefs` is taken to be one coefficient. More explicitly, `coefs(:,i*k+j)` is assumed to contain the  $j$ th coefficient of the  $(i+1)$ st polynomial piece (with the first coefficient the highest and the  $k$ th coefficient the lowest, or constant, coefficient). Thus, with  $kl$  the number of columns of `coefs`, the order  $k$  of the piecewise-polynomial is computed as `fix(kl/l)`.

After that, the entries of `coefs` are reordered, by the command

```
coefs = reshape(permute(reshape(coefs,[d,k,l]),[1 3 2]),[d*l,k])
```

in order to conform with the internal interpretation of the coefficient array in the pform for a univariate spline. This only applies when you use the syntax `ppmak(breaks,coefs)` where `breaks` is a sequence (row vector), not when it is a cell-array. The permutation is not made when you use the three-argument forms of `ppmak`. For the three-argument forms only a reshape is done, not a permute.

If `breaks` is a cell array, of length  $m$ , then the function is assumed to be  $m$ -variate (tensor product), and the various parts of its pform are determined from the input as follows:

- 1 The  $m$ -vector  $l$  has `length(breaks{i})-1` as its  $i$ th entry and, correspondingly, the  $m$ -cell array of its basic intervals has the interval `[breaks{i}(1) .. breaks{i}(end)]` as its  $i$ th entry.

- 2 The dimension  $d$  of the function's target and the  $m$ -vector  $k$  of (coordinate-wise polynomial) orders of its pieces are obtained directly from the size of `coefs`, as follows.
  - a If `coefs` is an  $m$ -dimensional array, then the function is taken to be scalar-valued, i.e.,  $d$  is 1, and the  $m$ -vector  $k$  is computed as `size(coefs)./l`. After that, `coefs` is reshaped by the command `coefs = reshape(coefs,[1,size(coefs)])`.
  - b If `coefs` is an  $(r+m)$ -dimensional array, with `sizec = size(c)` say, then  $d$  is set to `sizec(1:r)`, and the vector  $k$  is computed as `sizec(r+(1:m))./l`. After that, `coefs` is reshaped by the command `coefs = reshape(coefs,[prod(d),sizec(r+(1:m))])`.

Then, `coefs` is interpreted as an equivalent array of size `[d,l(1),k(1),l(2),k(2),...,l(m),k(m)]`, with its `(:,i(1),r(1),i(2),r(2),...,i(m),r(m))`th entry the coefficient of

$$\prod_{\mu=1}^m (x(\mu) - \text{breaks}[\mu](i(\mu)))^{(k(\mu) - r(\mu))}$$

in the local polynomial representation of the function on the (hyper)rectangle with sides

$$[\text{breaks}[\mu](i(\mu)) .. \text{breaks}[\mu](i(\mu) + 1)], \quad \mu = 1:m$$

This is, in fact, the internal interpretation of the coefficient array in the `ppform` of a multivariate spline.

`ppmak` prompts you for `breaks` and `coefs`.

`ppmak(breaks,coefs,d)` with  $d$  a positive integer, also puts together the `ppform` of a spline from the information supplied, but expects the function to be univariate. In that case, `coefs` is taken to be of size `[d*l,k]`, with  $l$  obtained as `length(breaks)-1`, and this determines the order,  $k$ , of the spline. With this, `coefs(i*d+j,:)` is taken to be the  $j$ th components of the coefficient vector for the  $(i+1)$ st polynomial piece.

`ppmak(breaks,coefs,sizec)` with `sizec` a row vector of positive integers, also puts together the `ppform` of a spline from the information supplied, but interprets `coefs` to be of size `sizec` (and returns an error when `prod(size(coefs))` differs from `prod(sizec)`). This option is important only in the rare case that the input argument `coefs` is an array with one or more trailing singleton dimensions. For, MATLAB suppresses trailing singleton dimensions, hence, without this explicit specification of the intended size of `coefs`, `ppmak` would interpret `coefs` incorrectly.

## Examples

The two splines

```
p1 = ppmak([1 3 4],[1 2 5 6;3 4 7 8]);
p2 = ppmak([1 3 4],[1 2;3 4;5 6;7 8],2);
```

have exactly the same `ppform` (2-vector-valued, of order 2). But the second command provides the coefficients in the arrangement used internally.

`ppmak([0:2],[1:6])` constructs a piecewise-polynomial function with basic interval `[0..2]` and consisting of two pieces of order 3, with the sole interior break 1. The resulting function is scalar, i.e., the dimension  $d$  of its target is 1. The function happens to be continuous at that break since the first piece is  $x \mapsto x^2 + 2x + 3$ , while the second piece is  $x \mapsto 4(x - 1)^2 + 5(x - 1) + 6$ .

When the function is univariate and the dimension  $d$  is not explicitly specified, then it is taken to be the row number of `coefs`. The column number should be an integer multiple of the number  $l$  of pieces specified by breaks. For example, the statement `ppmak([0:2],[1:3;4:6])` leads to an error, since the break sequence `[0:2]` indicates two polynomial pieces, hence an even number of columns are expected in the coefficient matrix. The modified statement `ppmak([0:1],[1:3;4:6])` specifies the parabolic curve  $x \mapsto (1,4)x^2 + (2,5)x + (3,6)$ . In particular, the dimension  $d$  of its target is 2. The differently modified statement `ppmak([0:2],[1:4;5:8])` also specifies a planar curve (i.e.,  $d$  is 2), but this one is piecewise linear; its first polynomial piece is  $x \mapsto (1,5)x + (2,6)$ .

Explicit specification of the dimension  $d$  leads, in the univariate case, to a different interpretation of the entries of `coefs`. Now the column number indicates the polynomial order of the pieces, and the row number should equal  $d$  times the number of pieces. Thus, the statement `ppmak([0:2],[1:4;5:8],2)` is in error, while the statement `ppmak([0:2],[1:4;5:8],1)` specifies a scalar piecewise cubic whose first piece is  $x \mapsto x^3 + 2x^2 + 3x + 4$ .

If you wanted to make up the constant polynomial, with basic interval `[0..1]` say, whose value is the matrix `eye(2)`, then you would have to use the full optional third argument, i.e., use the command

```
pp = ppmak(0:1,eye(2),[2,2,1,1]);
```

Finally, if you want to construct a 2-vector-valued bivariate polynomial on the rectangle `[-1 .. 1] x [0 .. 1]`, linear in the first variable and constant in the second, say

```
coefs = zeros(2,2,1); coefs(:,:,1) = [1 0; 0 1];
```

then the straightforward

```
pp = ppmak([-1 1],[0 1],coefs);
```

will fail, producing a scalar-valued function of order 2 in each variable, as will

```
pp = ppmak([-1 1],[0 1],coefs,size(coefs));
```

while the following command will succeed:

```
pp = ppmak([-1 1],[0 1],coefs,[2 2 1]);
```

See the example “Intro to `ppform`” for other examples.

## See Also

`fnbrk`



## predint

Prediction intervals for `cf` or `sf` object

### Syntax

```
ci = predint(fitresult,x)
ci = predint(fitresult,x,level)
ci = predint(fitresult,x,level,intopt,simopt)
[ci,y] = predint(...)
```

### Description

`ci = predint(fitresult,x)` returns upper and lower 95% prediction bounds for response values associated with the `cf` object `fitresult` at the new predictor values specified by the vector `x`. `fitresult` must be an output from the `fit` function to contain the necessary information for `ci`. `ci` is an  $n$ -by-2 array where  $n = \text{length}(x)$ . The left column of `ci` contains the lower bound for each coefficient; the right column contains the upper bound.

`ci = predint(fitresult,x,level)` returns prediction bounds with a confidence level specified by `level`. `level` must be between 0 and 1. The default value of `level` is 0.95.

`ci = predint(fitresult,x,level,intopt,simopt)` specifies the type of bounds to compute.

Observation bounds are wider than functional bounds because they measure the uncertainty of predicting the fitted curve plus the random variation in the new observation. Non-simultaneous bounds are for individual elements of `x`; simultaneous bounds are for all elements of `x`.

`[ci,y] = predint(...)` returns the response values `y` predicted by `fitresult` at the predictors in `x`.

---

**Note** `predint` cannot compute prediction intervals for non-parametric regression methods such as `Interpolant`, `Lowess`, and `Spline`.

---

### Examples

#### Calculate Prediction Intervals from the Command Line

Calculate and plot observation and functional prediction intervals for a fit to noisy data.

Generate noisy data with an exponential trend.

```
x = (0:0.2:5)';
y = 2*exp(-0.2*x) + 0.5*randn(size(x));
```

Fit a curve to the data using a single-term exponential.

```
fitresult = fit(x,y,'exp1');
```

Compute 95% observation and functional prediction intervals, both simultaneous and nonsimultaneous. Nonsimultaneous bounds are for individual elements of  $x$ ; simultaneous bounds are for all elements of  $x$ .

```
p11 = predint(fitresult,x,0.95,'observation','off');
p12 = predint(fitresult,x,0.95,'observation','on');
p21 = predint(fitresult,x,0.95,'functional','off');
p22 = predint(fitresult,x,0.95,'functional','on');
```


Plot the data, fit, and prediction intervals. Observation bounds are wider than functional bounds because they measure the uncertainty of predicting the fitted curve plus the random variation in the new observation.

```
subplot(2,2,1)
plot(fitresult,x,y), hold on, plot(x,p11,'m--'), xlim([0 5]), ylim([-1 5])
title('Nonsimultaneous Observation Bounds','FontSize',9)
legend off

subplot(2,2,2)
plot(fitresult,x,y), hold on, plot(x,p12,'m--'), xlim([0 5]), ylim([-1 5])
title('Simultaneous Observation Bounds','FontSize',9)
legend off

subplot(2,2,3)
plot(fitresult,x,y), hold on, plot(x,p21,'m--'), xlim([0 5]), ylim([-1 5])
title('Nonsimultaneous Functional Bounds','FontSize',9)
legend off

subplot(2,2,4)
plot(fitresult,x,y), hold on, plot(x,p22,'m--'), xlim([0 5]), ylim([-1 5])
title('Simultaneous Functional Bounds','FontSize',9)
legend({'Data','Fitted curve','Prediction intervals'},...
       'FontSize',8,'Location','northeast')
```



## Input Arguments

### **fitresult** – **cfit** or **sfit** function

`cfit` | `sfit`

Function of which you want to find the prediction intervals, specified as a `cfit` or `sfit` object.

`fitresult` must be an output from the `fit` function to contain the necessary information for `ci`.

### **x** – **Predictor values**

vector

Predictor values used to compute the upper and lower prediction bounds of `fitresult`, specified as a vector.

### **level** – **Confidence level**

0.95 (default) | positive scalar in the range (0,1)

Confidence level of the prediction bounds, specified as a positive scalar between 0 and 1.

### **intopt** – **Type of bounds**

'observation' (default) | 'functional'

Type of bounds, specified as either:

- 'observation' — Bounds for a new observation (default)
- 'functional' — Bounds for the fitted curve

**simopt — Type of bounds**

'off' (default) | 'on'

Type of bounds, specified as either:

- 'off' — Non-simultaneous bounds (default)
- 'on' — Simultaneous bounds

**Output Arguments****ci — Prediction bounds**

array

Upper and lower prediction bounds, returned as an array of size n-by-2, where  $n = \text{length}(x)$ .

**y — Response values**

vector

Response values predicted by `fitresult` at the predictors in `x`, returned as a vector.

**Version History**

Introduced in R2013a

**See Also**

`confint` | `fit` | `plot`

**Topics**

“Introducing Spline Fitting” on page 8-2

# prepareCurveData

Prepare data inputs for curve fitting

## Syntax

```
[XOut,YOut] = prepareCurveData(XIn,YIn)
[XOut,YOut,WOut] = prepareCurveData(XIn,YIn,WIn)
```

## Description

`[XOut,YOut] = prepareCurveData(XIn,YIn)` transforms data, if necessary, for curve fitting with the `fit` function. The `prepareCurveData` function transforms data as follows:

- Return data as columns regardless of the input shapes. Error if the number of elements do not match. Warn if the number of elements match, but the sizes differ.
- Convert complex to real (remove imaginary parts) and warn of this conversion.
- Remove NaN or Inf from data and warn of this removal.
- Convert nondouble to double and warn of this conversion.

Specify `XIn` as empty if you want to fit curves to `y` data against the index. If `XIn` is empty, then `XOut` is a vector of indices into `YOut`. The `fit` function can use the vector `XOut` for the `x` data when there is only `y` data.

`[XOut,YOut,WOut] = prepareCurveData(XIn,YIn,WIn)` transforms data including weights (`WIn`) for curve fitting with the `fit` function.

When you generate code from the Curve Fitter app, the generated code includes a call to `prepareCurveData` (or `prepareSurfaceData` for surface fits). You can call the generated file from the command line with your original data or new data as input arguments, to recreate your fits and plots. If you call the generated file with new data, the `prepareCurveData` function ensures you can use any data that you can fit in the Curve Fitter app, by reshaping if necessary to column doubles and removing NaNs, Infs, or the imaginary parts of complex numbers.

## Examples


### Reshape Rows to Columns for Curve Fitting

The following commands load the example `titanium` data in which `x` and `y` are row vectors. Attempting to use rows as inputs to the `fit` function produces an error. The `prepareCurveData` function reshapes `x` and `y` to columns for use with the `fit` function.

```
[x,y] = titanium();
[x,y] = prepareCurveData(x,y);
```

Create and plot a fit using the reshaped data.

```
f = fit(x,y,'smoothingspline');
plot(f,x,y)
```



## Input Arguments

### **XIn** — X data variable for curve fitting

vector | matrix

X data variable for curve fitting, specified as a scalar, a vector or a matrix. XIn can be empty. Specify empty ([]) when you want to fit curves to y data against index ( $x=1:\text{length}(y)$ ). See YOut.

Data Types: double

### **YIn** — Y data variable for curve fitting

vector | matrix

Y data variable for curve fitting, specified as a scalar, a vector or a matrix.

Data Types: double

### **WIn** — Weights for curve fitting

vector | matrix

Weights variable for curve fitting specified, as a scalar, a vector or a matrix.

Data Types: double

## Output Arguments

### **X0ut — X data column variable for curve fitting**

vector

X data column variable prepared for curve fitting, returned as a vector.

If `XIn` is empty, then `X0ut` is a vector of indices into `Y0ut`. The `fit` function can use the vector `X0ut` for the x data when there is only y data.

Data Types: double

### **Y0ut — Y data column variable for curve fitting**

vector

Y data column variable prepared for curve fitting, returned as a vector.

Data Types: double

### **W0ut — Weights column variable for curve fitting**

vector

Weights column variable prepared for curve fitting, returned as a vector.

Data Types: double

## Version History

Introduced in R2013a

## See Also

### Functions

`fit` | `prepareSurfaceData` | `excludedata`

### Apps

Curve Fitter

## prepareSurfaceData

Prepare data inputs for surface fitting

### Syntax

```
[XOut, YOut, ZOut] = prepareSurfaceData(XIn, YIn, ZIn)
[XOut, YOut, ZOut, WOut] = prepareSurfaceData(XIn, YIn, ZIn, WIn)
```

### Description

`[XOut, YOut, ZOut] = prepareSurfaceData(XIn, YIn, ZIn)` transforms data, if necessary, for surface fitting with the `fit` function. The function transforms data as follows:

- For grid vectors, transform row (`YIn`) and column (`XIn`) headers into arrays `YOut` and `XOut` that are the same size as `ZIn`. Warn if `XIn` and `YIn` are reversed.
- Return data as columns regardless of the input shapes. Error if the number of elements do not match. Warn if the number of elements match, but the sizes are different.
- Convert complex to real (remove imaginary parts) and warn of this conversion.
- Remove NaN or Inf from data and warn of this removal.
- Convert nondouble to double and warn of this conversion.

`[XOut, YOut, ZOut, WOut] = prepareSurfaceData(XIn, YIn, ZIn, WIn)` transforms data including weights (`WIn`) for surface fitting with the `fit` function.

Use `prepareSurfaceData` if your data is not in column vector form. For example, you have 3 matrices. You can also use `prepareSurfaceData` if you have grid vectors, where `length(XIn) = n`, `length(YIn) = m` and `size(ZIn) = [m,n]`. You must process grid vector data for use with the `fit` function by using `prepareSurfaceData`. If you use the Curve Fitter app, you can select grid vector data and it automatically converts the data for you.

If your data is in a MATLAB table, you do not need to use `prepareSurfaceData`. You can specify variables in a MATLAB table as inputs to the `fit` function using the form `tablename.varname`.

When you generate code from the Curve Fitter app, the generated code includes a call to `prepareSurfaceData` (or `prepareCurveData` for curve fits). You can call the generated file from the command line with your original data or new data as input arguments, to recreate your fits and plots. If you call the generated file with new data, the `prepareCurveData` function ensures you can use any data that you can fit in the Curve Fitter app, by reshaping if necessary and removing NaNs, Infs, or the imaginary parts of complex numbers.

### Examples

#### Prepare Surface Data for the fit Function

Create some data that is unsuitable for the `fit` function without preprocessing, because it is nondouble, noncolumn, and contains some Nan and Inf values.



```
x = int32(1:4);
y = int32(1:5);
z = rand(5,4);
z(13) = Inf;
z(3) = NaN;
```

Use the `prepareSurfaceData` to convert rows to columns, nondoubles to doubles, and remove `Nan` and `Inf`.

```
[xo,yo,zo] = prepareSurfaceData(x,y,z);
```

The function displays the same warnings that you see if you select this data in the Curve Fitter app. The warnings tell you how your data is processed to be suitable for the `fit` function.

Use `whos` to check that the `prepareSurfaceData` converted the variables to column vectors that are doubles.

```
whos xo yo zo
```

## Input Arguments

### **XIn** — X data variable to prepare for surface fitting

vector | matrix

X data variable to prepare for surface fitting, specified as a scalar, a vector or a matrix.

Data Types: `double`

### **YIn** — Y data variable to prepare for surface fitting

vector | matrix

Y data variable to prepare for surface fitting, specified as a scalar, a vector or a matrix.

Data Types: `double`

### **ZIn** — Z data variable to prepare for surface fitting

vector | matrix

Z data variable to prepare for surface fitting, specified as a scalar, a vector or a matrix.

Data Types: `double`

### **WIn** — Weights variable

scalar | vector | matrix

Weights variable to prepare for surface fitting, specified as a scalar, a vector or a matrix.

Data Types: `double`

## Output Arguments

### **X0ut** — X data column variable prepared for surface fitting

vector

X data column variable prepared for surface fitting, returned as a vector.

Data Types: `double`

**Y0ut — Y data column variable prepared for surface fitting**

vector

Y data column variable prepared for surface fitting, returned as a vector.

Data Types: double

**Z0ut — Z data column variable prepared for surface fitting**

vector

Z data column variable prepared for surface fitting, returned as a vector.

Data Types: double

**W0ut — Weights column variable**

vector

Weights column variable prepared for surface fitting, returned as a vector.

Data Types: double

## Version History

Introduced in R2010b

### See Also

**Functions**

fit | prepareCurveData | excludedata

**Apps**

Curve Fitter

# probnames

Problem-dependent parameter names of `cf`, `sfit`, or `fitttype` object

## Syntax

```
pnames = probnames(fun)
```

## Description

`pnames = probnames(fun)` returns the names of the problem-dependent (fixed) parameters of the `cf`, `sfit`, or `fitttype` object `fun` as a cell array of character vectors.

## Examples

```
f = fitttype('(x-a)^n + b','problem',{'a','b'});
coeffnames(f)
ans =
    'n'
probnames(f)
ans =
    'a'
    'b'
```

```
load census
```

```
c = fit(cdate,pop,f,'problem',{cdate(1),pop(1)},...
        'StartPoint',2);
coeffvalues(c)
ans =
    0.9877
probvalues(c)
ans =
    1.0e+003 *
    1.7900    0.0039
```

## Version History

**Introduced in R2006b**

## See Also

`fitttype` | `coeffnames` | `probvalues`

## probvalues

Problem-dependent parameter values of `cf` or `sfit` object

### Syntax

```
pvals = probvalues(fun)
```

### Description

`pvals = probvalues(fun)` returns the values of the problem-dependent (fixed) parameters of the `cf` object `fun` as a row vector.

### Examples

```
f = fittype('(x-a)^n + b','problem',{'a','b'});
coeffnames(f)
ans =
    'n'
probnames(f)
ans =
    'a'
    'b'
```

```
load census
```

```
c = fit(cdate,pop,f,'problem',{cdate(1),pop(1)},...
        'StartPoint',2);
coeffvalues(c)
ans =
    0.9877
probvalues(c)
ans =
    1.0e+003 *
    1.7900    0.0039
```

## Version History

**Introduced in R2006b**

### See Also

`fit` | `fittype` | `probnames`

# quad2d

Numerically integrate `sfit` object

## Syntax

```
Q = quad2d(F0, a, b, c, d)
[Q,ERRBND] = quad2d(...)
[Q,ERRBND] = QUAD2D(F0,a,b,c,d,PARAM1,VAL1,PARAM2,VAL2,...)
```

## Description

`Q = quad2d(F0, a, b, c, d)` approximates the integral of the surface fit object `F0` over the planar region  $a \leq x \leq b$  and  $c(x) \leq y \leq d(x)$ . The bounds `c` and `d` can each be a scalar, a function handle, or a curve fit (`cfit`) object.

`[Q,ERRBND] = quad2d(...)` also returns an approximate upper bound on the absolute error, `ERRBND`.

`[Q,ERRBND] = QUAD2D(F0,a,b,c,d,PARAM1,VAL1,PARAM2,VAL2,...)` performs the integration with specified values of optional parameters.

See the MATLAB function `quad2d` for details of the upper bound and the optional parameters.

## Version History

Introduced in R2009b

## See Also

`quad2d` | `fit` | `sfit` | `cfit`

## rpmak

Put together rational spline

### Syntax

```
rp = rpmak(breaks,coefs)
rp = rpmak(breaks,coefs,d)
rpmak(breaks,coefs,sizec)
rs = rsmak(knots,coefs)
rs = rsmak(shape,parameters)
```

### Description

Both `rpmak` and `rsmak` put together a rational spline from minimal information. `rsmak` is also equipped to provide rational splines that describe standard geometric shapes. A rational spline must be scalar- or vector-valued.

`rp = rpmak(breaks,coefs)` has the same effect as the command `ppmak(breaks,coefs)` except that the resulting `ppform` is tagged as a rational spline, i.e., as a `rpform`.

To describe what this means, let  $R$  be the piecewise-polynomial put together by the command `ppmak(breaks,coefs)`, and let  $r(x) = s(x)/w(x)$  be the rational spline put together by the command `rpmak(breaks,coefs)`. If  $v$  is the value of  $R$  at  $x$ , then  $v(1:\text{end}-1)/v(\text{end})$  is the value of  $r$  at  $x$ . In other words,  $R(x) = [s(x);w(x)]$ . Correspondingly, the dimension of the target of  $r$  is one less than the dimension of the target of  $R$ . In particular, the dimension (of the target) of  $R$  must be at least 2, i.e., the coefficients specified by `coefs` must be  $d$ -vectors with  $d > 1$ . See `ppmak` for how the input arrays `breaks` and `coefs` are being interpreted, hence how they are to be specified in order to produce a particular piecewise-polynomial.

`rp = rpmak(breaks,coefs,d)` has the same effect as `ppmak(breaks,coefs,d+1)`, except that the resulting `ppform` is tagged as being a `rpform`. Note that the desire to have that optional third argument specify the dimension of the target requires different values for it in `rpmak` and `ppmak` for the same coefficient array `coefs`.

`rpmak(breaks,coefs,sizec)` has the same effect as `ppmak(breaks,coefs,sizec)` except that the resulting `ppform` is tagged as being a `rpform`, and the target dimension is taken to be `sizec(1)-1`.

`rs = rsmak(knots,coefs)` is similarly related to `spmak(knots,coefs)`, and `rsmak(knots,coefs,sizec)` to `spmak(knots,coefs,sizec)`. In particular, `rsmak(knots,coefs)` puts together a rational spline in B-form, i.e., it provides a `rBform`. See `spmak` for how the input arrays `knots` and `coefs` are being interpreted, hence how they are to be specified in order to produce a particular piecewise-polynomial.

`rs = rsmak(shape,parameters)` provides a rational spline in `rBform` that describes the shape being specified by the character vector or string scalar `shape` and the optional additional `parameters`. Specific choices are:

```
rsmak('arc',radius,center,[alpha,beta])
rsmak('circle',radius,center)
```

```
rsmak('cone',radius,halfheight)
rsmak('cylinder',radius,height)
rsmak('southcap',radius,center)
rsmak('torus',radius,ratio)
```

with 1 the default value for radius, halfheight and height, and the origin the default for center, and the arc running through all the angles from alpha to beta (default is  $[-\pi/2, \pi/2]$ ), and the cone, cylinder, and torus centered at the origin with their major circle in the (x,y)-plane, and the minor circle of the torus having radius  $\text{radius} \times \text{ratio}$ , the default for ratio being 1/3.

From these, one may generate related shapes by affine transformations, with the help of `fncmb(rs,transformation)`.

All `fn...` commands except `fnint`, `fnder`, `fndir` can handle rational splines.

## Examples


The commands

```
runge = rsmak([-5 -5 -5 5 5 5],[1 1 1; 26 -24 26]);
rungep = rpmak([-5 5],[0 0 1; 1 -10 26],1);
```

both provide a description of the rational polynomial  $r(x) = 1/(x^2 + 1)$  on the interval  $[-5 .. 5]$ . However, outside the interval  $[-5 .. 5]$ , the function given by runge is zero, while the rational spline given by rungep agrees with  $1/(x^2 + 1)$  for every  $x$ .

The figure of a rotated cone is generated by the commands


```
fnplt(fncmb(rsmak('cone',1,2),[0 0 -1;0 1 0;1 0 0]))
axis equal, axis off, shading interp
```



### A Rotated Cone Given by a Rational Quadratic Spline

“A Helix” on page 13-238, showing a helix with several windings, is generated by the commands

```
arc = rsmak('arc',2,[1;-1],[0 7.3*pi]);  
[knots,c] = fnbrk(arc,'k','c');  
helix = rsmak(knots, [c(1:2,:);aveknt(knots,3).*c(3,:)];  
c(3,:));  
fnplt(helix)
```



### A Helix

For further illustrated examples, see “NURBS and Other Rational Splines” on page 10-23

### See Also

rsmak | fnbrk | ppmak | spmak



## rscvn

Piecewise biarc Hermite interpolation

### Syntax

```
c = rscvn(p,u)
c = rscvn(p)
```

### Description

`c = rscvn(p,u)` returns a planar piecewise biarc curve (in quadratic rBform) that passes, in order, through the given points  $p(:,j)$  and is constructed in the following way (see “Construction of a Biarc” on page 13-240). Between any two distinct points  $p(:,j)$  and  $p(:,j+1)$ , the curve usually consists of two circular arcs (including straight-line segments) which join with tangent continuity, with the first arc starting at  $p(:,j)$  and normal there to  $u(:,j)$ , and the second arc ending at  $p(:,j+1)$  and normal there to  $u(:,j+1)$ , and with the two arcs written as one whenever that is possible. Thus the curve is tangent-continuous everywhere except, perhaps, at repeated points, where the curve may have a corner, or when the angle, formed by the two segments ending at  $p(:,j)$ , is unusually small, in which case the curve may have a cusp at that point.

$p$  must be a real matrix, with two rows, and at least two columns, and any column must be different from at least one of its neighboring columns.

$u$  must be a real matrix with two rows, with the same number of columns as  $p$  (for two exceptions, see below), and can have no zero column.

`c = rscvn(p)` chooses the normals in the following way. For  $j=2:\text{end}-1$ ,  $u(:,j)$  is the average of the (normalized, right-turning) normals to the vectors  $p(:,j)-p(:,j-1)$  and  $p(:,j+1)-p(:,j)$ . If  $p(:,1)=p(:,\text{end})$ , then both end normals are chosen as the average of the normals to  $p(:,2)-p(:,1)$  and  $p(:,\text{end})-p(:,\text{end}-1)$  thus preventing a corner in the resulting closed curve. Otherwise, the end normals are so chosen that there is only one arc over the first and last segment (not-a-knot end condition).

`rscvn(p,u)`, with  $u$  having exactly two columns, also chooses the interior normals as for the case when  $u$  is absent but uses the two columns of  $u$  as the end-point normals.

### Examples

**Example 1.** The following code generates a description of a circle, using just four pieces. Except for a different scaling of the knot sequence, it is the same description as is supplied by `rsmak('circle',1,[1;1])`.


```
p = [1 0 -1 0 1; 0 1 0 -1 0]; c = rscvn([p(1,:)+1;p(2,:)+1],p);
```

The same circle, but using just two pieces, is provided by

```
c2 = rscvn([0,2,0; 1,1,1]);
```

**Example 2.** The following code plots two letters. Note that the second letter is the result of interpolation to just four points. Note also the use of translation in the plotting of the second letter.


```
p = [-1 .8 -1 1 -1 -1 -1; 3 1.75 .5 -1.25 -3 -3 3];
i = eye(2); u = i(:, [2 1 2 1 2 1 1]); B = rscvn(p,u);
S = rscvn([1 -1 1 -1; 2.5 2.5 -2.5 -2.5]);
fnplt(B), hold on, fnplt(fncmb(S,[3;0])), hold off
axis equal, axis off
```



### Two Letters Composed of Circular Arcs

**Example 3.** The following code generates the “Construction of a Biarc” on page 13-240, of use in the discussion below of the biarc construction used here. Note the use of `fnplr` to find the tangent to the biarc at the beginning, at the point where the two arcs join, and at the end.


```
p = [0 1;0 0]; u = [.5 -.1;-.25 .5];
plot(p(1,:),p(2,:), 'k'), hold on
biarc = rscvn(p,u); breaks = fnbrk(biarc,'b');
fnplt(biarc,breaks(1:2),'b',3), fnplt(biarc,breaks(2:3),'r',3)
vd = fnplr(biarc,2,breaks);
quiver(vd(1,:),vd(2,:),vd(4,:),-vd(3,:)), hold off
```



### Construction of a Biarc


## Algorithms

Given two distinct points,  $p_1$  and  $p_2$ , in the plane and, correspondingly, two nonzero vectors,  $u_1$  and  $u_2$ , there is a one-parameter family of biarcs (i.e., a curve consisting of two arcs with common tangent at their join) starting at  $p_1$  and normal there to  $u_1$  and ending at  $p_2$  and normal there to  $u_2$ . One way to parametrize this family of biarcs is by the normal direction,  $v$ , at the point  $q$  at which the two arcs join. With a nonzero  $v$  chosen, there is then exactly one choice of  $q$ , hence the entire biarc is then determined. In the construction used in `rscvn`,  $v$  is chosen as the reflection, across the perpendicular to the segment from  $p_1$  to  $p_2$ , of the average of the vectors  $u_1$  and  $u_2$ , -- after both vectors have been so normalized that their length is 1 and that they both point to the right of the segment from  $p_1$  to  $p_2$ . This choice for  $v$  seems natural in the two standard cases: (i)  $u_2$  is the reflection of  $u_1$  across the perpendicular to the segment from  $p_1$  to  $p_2$ ; (ii)  $u_1$  and  $u_2$  are parallel. This choice of  $v$  is validated by "Biarcs as a Function of the Left Normal" on page 13-241 which shows the resulting biarcs when  $p_1$ ,  $p_2$ , and  $u_2 = [.809; .588]$  are kept fixed and only the normal at  $p_1$  is allowed to vary.



### Biarcs as a Function of the Left Normal

But it is impossible to have the interpolating biarc depend continuously at all four data,  $p_1$ ,  $p_2$ ,  $u_1$ ,  $u_2$ . There has to be a discontinuity as the normal directions,  $u_1$  and  $u_2$ , pass through the direction from  $p_1$  to  $p_2$ . This is illustrated in "Biarcs as a Function of One Endpoint" on page 13-242 which shows the biarcs when one point,  $p_1 = [0; 0]$ , and the two normals,  $u_1 = [1; 1]$  and  $u_2 = [1; -1]$ , are held fixed and only the other point,  $p_2$ , moves, on a circle around  $p_1$ .



**Bi-arcs as a Function of One Endpoint**

**See Also**

rsmak | cscvn

## rsmak

Put together rational spline for standard geometric shapes

### Syntax

```
rs = rsmak(shape,parameters)
```

### Description

`rs = rsmak(shape,parameters)` provides a rational spline in rBform that describes the shape being specified by the character vector or string scalar `shape` and the optional additional parameters. Specific choices for `shape` are:

```
rsmak('arc',radius,center,[alpha,beta])  
rsmak('circle',radius,center)  
rsmak('cone',radius,halfheight)  
rsmak('cylinder',radius,height)  
rsmak('southcap',radius,center)  
rsmak('torus',radius,ratio)
```

with 1 the default value for `radius`, `halfheight` and `height`, and the origin the default for `center`, and the arc running through all the angles from `alpha` to `beta` (default is `[-pi/2,pi/2]`), and the cone, cylinder, and torus centered at the origin with their major circle in the (x,y)-plane, and the minor circle of the torus having radius `radius*ratio`, the default for `ratio` being 1/3.

From these, one may generate related shapes by affine transformations, with the help of `fncmb(rs,transformation)`.

See `rpmak` for more information on other options.

### See Also

`rpmak`

## set

Assign values in fit options structure

### Syntax

```
set(options)
s = set(options)
set(options, field1, val1, field2, val2, ...)
set(options, fields, vals)
```

### Description

`set(options)` displays all property names of the fit options structure `options`. If a property has a finite list of possible character vector values, these values are also displayed.

`s = set(options)` returns a structure `s` with the same property names as `options`. If a property has a finite list of possible character vector values, the value of the property in `s` is a cell array containing the possible character vector values. If a property does not have a finite list of possible character vector values, the value of the property in `s` is an empty cell array.

`set(options, field1, val1, field2, val2, ...)` sets the properties specified by the character vectors `field1`, `field2`, ... to the values `val1`, `val2`, ..., respectively.

`set(options, fields, vals)` sets the properties specified by the cell array of character vectors `fields` to the corresponding values in the cell array `vals`.

### Examples

#### Set Property Values of a fitoptions Structure

Create a custom nonlinear model, and create a default fit options structure for the model:

```
f = fittype('a*x^2+b*exp(n*c*x)', 'problem', 'n');
options = fitoptions(f);
```

Set the Robust and Normalize properties of the fit options structure using property name/value pairs:

```
set(options, 'Robust', 'LAR', 'Normalize', 'On')
```

Set the Display, Lower, and Algorithm properties of the fit options structure using cell arrays of property names/values:

```
set(options, {'Disp', 'Low', 'Alg'}, ...
    {'Final', [0 0 0], 'Levenberg'})
```

### Input Arguments

**options** — fitoptions object  
fitoptions (default)

`fitoptions` object of which you want to set the property names and values, specified as a `fitoptions` object.

**field1, val1, field2, val2, ... — Property field**

character vector (default) | scalar | vector | matrix

Property fields, specified as a character vector, of the `fitoptions` object options that you want to set to the values `val1`, `val2`, ..., respectively, specified as a scalar, a vector, or a matrix.

Data Types: char

**fields — Property fields**

string scalar | character vector | cell array of character vectors

Property field of the `fitoptions` object options that you want to set, specified as string scalar, character vector, or a cell array of character vectors.

Data Types: char | string | cell

**vals — Property values**

cell array (default)

Values of the `fitoptions` object options that you want to set the fields to, specified as a cell array.

Data Types: cell

## Output Arguments

**s — fitoptions structure**

`fitoptions`

Copy of the `fitoptions` object options, returned as a `fitoptions` object.

## Version History

Introduced before R2006a

## See Also

`fitoptions` | `get`

## **setoptions**

Set model fit options

### **Syntax**

```
FT = setoptions(FT, options)
```

### **Description**

`FT = setoptions(FT, options)` sets the fit options of `FT` to `options`, where `FT` is a `fittype`, `cfit`, or `sfit` object. The `FT` output argument must match the `FT` input argument.

### **Version History**

**Introduced in R2009b**

### **See Also**

`fioptions` | `fit` | `fittype`



## sfit

Constructor for `sfit` object

### Syntax

```
surfacefit = sfit(fittype,coeff1,...,coeffn)
```

### Description

`surfacefit = sfit(fittype,coeff1,...,coeffn)` constructs the `sfit` object `surfacefit` using the model type specified by the `fittype` object and the coefficient values `coeff1`, `coeff2`, etc.

An `sfit` object encapsulates the result of fitting a surface to data. They are normally constructed by calling the `fit` function, or interactively by exporting a fit from the Curve Fitter app to the workspace. You can get and set coefficient properties of the `sfit` object.

You can treat an `sfit` object as a function to make predictions or evaluate the surface at values of X and Y.

Like the `cf` class, `sfit` inherits all `fittype` methods.

---

**Note** `sfit` is called by the `fit` function when fitting `fittype` objects to data. To create an `sfit` object that is the result of a regression, use `fit`.

You should call `sfit` directly only if you want to assign values to coefficients and problem parameters of a `fittype` object *without* performing a fit.

---

Methods of `sfit` objects:

|             |                                                                                                             |
|-------------|-------------------------------------------------------------------------------------------------------------|
| argnames    | Input argument names of <code>cfit</code> , <code>sfit</code> , or <code>fittype</code> object              |
| category    | Category of fit of <code>cfit</code> , <code>sfit</code> , or <code>fittype</code> object                   |
| coeffnames  | Coefficient names of <code>cfit</code> , <code>sfit</code> , or <code>fittype</code> object                 |
| dependnames | Dependent variable of <code>cfit</code> , <code>sfit</code> , or <code>fittype</code> object                |
| formula     | Formula of <code>cfit</code> , <code>sfit</code> , or <code>fittype</code> object                           |
| indepnames  | Independent variable of <code>cfit</code> , <code>sfit</code> , or <code>fittype</code> object              |
| islinear    | Determine if <code>cfit</code> , <code>sfit</code> , or <code>fittype</code> object is linear               |
| numargs     | Number of input arguments of <code>cfit</code> , <code>sfit</code> , or <code>fittype</code> object         |
| numcoeffs   | Number of coefficients of <code>cfit</code> , <code>sfit</code> , or <code>fittype</code> object            |
| probnames   | Problem-dependent parameter names of <code>cfit</code> , <code>sfit</code> , or <code>fittype</code> object |
| probvalues  | Problem-dependent parameter values of <code>cfit</code> or <code>sfit</code> object                         |
| quad2d      | Numerically integrate <code>sfit</code> object                                                              |
| setoptions  | Set model fit options                                                                                       |
| sfit        | Constructor for <code>sfit</code> object                                                                    |
| type        | Name of <code>cfit</code> , <code>sfit</code> , or <code>fittype</code> object                              |

## Examples

### Make predictions or evaluate the surface values of X and Y

You can treat an `sfit` object as a function to make predictions or evaluate the surface at values of X and Y.

```
x = 3 - 6 * rand( 49, 1 );
y = 3 - 6 * rand( 49, 1 );
z = peaks( x, y );
sf = fit( [x, y], z, 'poly32' );
zhat = sf( mean( x ), mean( y ) )
```

## Input Arguments

### **fittype** – Model type

`fittype` (default)

Model type the `sfit` function uses to construct the `sfit` object, specified as a `fittype` constructed with the `fittype` function.

Example: `fittype('linearinterp')`

### **coeff1, ..., coeffn** – Coefficient values

scalar (default)

Coefficient values of the `sfit` object, specified as scalars.

Data Types: `single` | `double`

## Output Arguments

**surfacefit** — **sfit** object

sfit

Function output, returned as an sfit object.

## Version History

Introduced in R2009a

## See Also

### Functions

fit | fitttype | feval | cfit

### Apps

Curve Fitter

### Topics

“Evaluate Surface Fit” on page 7-24

“Fit Postprocessing”

## sftool

(Removed) Open Curve Fitting app

---

**Note** `sftool` has been removed. Use `curveFitter` instead. See Curve Fitter. For information on updating your code, see “Compatibility Considerations”.

---

### Syntax

```
sftool
sftool(x,y,z)
sftool(x,y,z,w)
sftool(filename)
```

### Description

`sftool` opens the Curve Fitting app or brings focus to the tool if it is already open.

`sftool(x,y,z)` creates a fit to  $x$  and  $y$  inputs (or predictor data) and  $z$  output (or response data). `sftool` opens the Curve Fitting app if necessary.

$x$ ,  $y$ , and  $z$  must be numeric, have two or more elements, and have compatible sizes. Sizes are compatible if either:

- $x$ ,  $y$ , and  $z$  all have the same number of elements, or
- $x$  and  $y$  are vectors,  $z$  is a 2D matrix, where  $\text{length}(x) = n$ ,  $\text{length}(y) = m$ , and  $[m,n] = \text{size}(z)$ .

`sftool(x,y,z,w)` creates a fit with weights  $w$ .  $w$  must be numeric and have the same number of elements as  $z$ .

`sftool(filename)` loads the surface fitting session in *filename* into the Curve Fitting app. The *filename* should have the extension `.sfit`.

Infs, NaNs, and imaginary parts of complex numbers are ignored in the data.

The Curve Fitting app provides a flexible interface where you can interactively fit curves and surfaces to data and view plots. You can:

- Create, plot, and compare multiple fits
- Use linear or nonlinear regression, interpolation, local smoothing regression, or custom equations
- View goodness-of-fit statistics, display confidence intervals and residuals, remove outliers and assess fits with validation data
- Automatically generate code for fitting and plotting surfaces, or export fits to workspace for further analysis

## Version History

**Introduced in R2009a**

**R2022a: sftool has been removed**

*Errors starting in R2022a*

sftool has been removed. Use curveFitter instead. For more information, see the Curve Fitter app.

To update your code, change instances of sftool to curveFitter. You do not need to change the input arguments. For example, use curveFitter(x,y,z) to fit a surface to the x, y, and z data.

**See Also****Apps**

Curve Fitter

**Topics**

“Interactive Curve and Surface Fitting” on page 2-2

## smooth

Smooth response data

### Syntax

```
yy = smooth(y)
yy = smooth(y,span)
yy = smooth(y,method)
yy = smooth(y,span,method)
yy = smooth(y,'sgolay',degree)
yy = smooth(y,span,'sgolay',degree)
yy = smooth(x,y,___)
gpuarrayYY = smooth(gpuarrayY,___)
gpuarrayYY = smooth(gpuarrayX,gpuarrayY,___)
```

### Description

`yy = smooth(y)` smooths the response data in column vector `y` using a moving average filter.

The first few elements of `yy` follow.

```
yy(1) = y(1)
yy(2) = (y(1) + y(2) + y(3))/3
yy(3) = (y(1) + y(2) + y(3) + y(4) + y(5))/5
yy(4) = (y(2) + y(3) + y(4) + y(5) + y(6))/5
...
```

Because of the way `smooth` handles endpoints, the result differs from the result returned by the `filter` function.

`yy = smooth(y,span)` sets the span of the moving average to `span`.

`yy = smooth(y,method)` smooths the data in `y` using the method specified by `method` and the default span.

`yy = smooth(y,span,method)` sets the span of `method` to `span`.

`yy = smooth(y,'sgolay',degree)` uses the Savitzky-Golay method with the polynomial degree specified by `degree`.

`yy = smooth(y,span,'sgolay',degree)` uses the number of data points specified by `span` in the Savitzky-Golay calculation. `span` must be odd and `degree` must be less than `span`.

`yy = smooth(x,y,___)` specifies values for the independent variable `x`. You can use this syntax with any of the arguments in the previous syntaxes.

`gpuarrayYY = smooth(gpuarrayY,___)` performs the operation on a GPU using `gpuArray` data. You can use `gpuArray` response data with all previous syntaxes. This syntax requires Parallel Computing Toolbox™.

`gpuarrayYY = smooth(gpuarrayX,gpuarrayY,___)` performs the operation on a GPU using `gpuArray` input data. This syntax requires Parallel Computing Toolbox.

---

**Note** Using `gpuArray` `x` and `y` inputs with the `smooth` function is only recommended if you use the default method, `'moving'`. Using GPU data with other methods does not offer any performance advantage.

---

## Examples

### Smooth Data Using Moving Average Filter

Smooth data by linear index and by each column separately, using a moving average filter. Plot and compare the results.

Load the data in `count.dat`. The 24-by-3 array `count` contains traffic counts at three intersections for each hour of the day.

```
load count.dat
```

Suppose that the data are from a single intersection over three consecutive days. Smoothing all the data together would then indicate the overall cycle of traffic flow through the intersection. Use a moving average filter with a 5-hour span to smooth all the data simultaneously (by linear index).

```
c = smooth(count(:));
C1 = reshape(c,24,3);
```

However, the data are in fact from three different intersections. Thus, smoothing columnwise gives a more meaningful picture of the traffic through each intersection in a day. Use the same moving average filter to smooth each column of the data separately.


```
C2 = zeros(24,3);
for I = 1:3
    C2(:,I) = smooth(count(:,I));
end
```

Plot the original data and the data smoothed by linear index and by each column separately. Then, plot the difference between the two smoothed data sets. The two methods give different results near the endpoints.

```
subplot(3,1,1)
plot(count,':');
hold on
plot(C1,'-');
title('Smooth C1 (All Data)')

subplot(3,1,2)
plot(count,':');
hold on
plot(C2,'-');
title('Smooth C2 (Each Column)')

subplot(3,1,3)
plot(C2 - C1,'o-')
title('Difference C2 - C1')
```



### Smooth Data Using loess and rloess

Plot and compare the results of data smoothed using the `loess` and `rloess` methods. Then determine which method is less sensitive to outliers.

Create noisy data with two outliers.

```
x = (0:0.1:15)';
y = sin(x) + 0.5*(rand(size(x))-0.5);
y([90,110]) = 3;
```

Smooth the data with the `loess` and `rloess` methods. Use a span of 10% of the total number of data points.

```
yy1 = smooth(x,y,0.1,'loess');
yy2 = smooth(x,y,0.1,'rloess');
```

Plot the original and smoothed data. The outliers have less influence with the robust method `rloess`.


```
subplot(2,1,1)
plot(x,y,'b.',x,yy1,'r-')
set(gca,'YLim',[-1.5 3.5])
legend('Original data','Smoothed data using ''loess'',...
       'Location','NW')
```



```

subplot(2,1,2)
plot(x,y,'b.',x,yy2,'r-')
set(gca,'YLim',[-1.5 3.5])
legend('Original data','Smoothed data using ''rloess''',...
      'Location','NW')

```



## Input Arguments

### **y** — Data to smooth

column vector

Data to smooth, specified as a column vector.

If your data contains NaNs and you do not specify *x*, your data is treated as nonuniform and the smoothing method 'lowess' is used.

Data Types: `single` | `double`

### **span** — Number of data points for calculating the smoothed value

5 (default) | integer | scalar value in the range (0,1)

Number of data points for calculating the smoothed value, specified as an integer or as a scalar value in the range (0,1) denoting a fraction of the total number of data points.

If you use the moving average or Savitzky-Golay methods, the number of data points for calculating the smoothed value must be an odd integer. If you specify `span` as an even number or as a fraction that results in an even number of data points, `span` is automatically reduced by 1.

Example: `7; 0.6`

#### method — Smoothing method

'moving' (default) | 'lowess' | 'loess' | 'sgolay' | 'rloess' | 'rloess'

Smoothing method to smooth the response data, specified as one of the following methods.

| Method             | Description                                                                                                                                                                                                                                          |
|--------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 'moving' (default) | Moving average. A lowpass filter with filter coefficients equal to the reciprocal of the span.                                                                                                                                                       |
| 'lowess'           | Local regression using weighted linear least squares and a 1st degree polynomial model.                                                                                                                                                              |
| 'loess'            | Local regression using weighted linear least squares and a 2nd degree polynomial model.                                                                                                                                                              |
| 'sgolay'           | Savitzky-Golay filter. A generalized moving average with filter coefficients determined by an unweighted linear least-squares regression and a polynomial model of specified degree (default is 2). The method can accept nonuniform predictor data. |
| 'rloess'           | A robust version of 'lowess' that assigns lower weight to outliers in the regression. The method assigns zero weight to data outside six mean absolute deviations.                                                                                   |
| 'rloess'           | A robust version of 'loess' that assigns lower weight to outliers in the regression. The method assigns zero weight to data outside six mean absolute deviations.                                                                                    |

Data Types: `char` | `string`

#### degree — Polynomial degree for Savitzky-Golay method

scalar value

Polynomial degree for the model used in the Savitzky-Golay method, specified as a scalar value. `degree` must be less than `span`.

Example: `3`

#### x — Independent variable for response data y

vector

Independent variable for the response data `y`, specified as a column vector. If you do not provide `x`, methods that require `x` assume `x = 1:length(y)`. Specify `x` data when `y` is not sorted or uniformly spaced. If `x` is not uniform and you do not specify `method`, `lowess` is used. If you specify a smoothing method that requires `x` to be sorted, the function automatically sorts the `x` data.

Data Types: `single` | `double`

#### gpuarrayY — Data to smooth

gpuArray vector

Data to smooth, specified as a `gpuArray` column vector.

Data Types: `single` | `double`

### **gpuarrayX — Input data for response data gpuarrayY**

`gpuArray` vector

Input data for the response data `gpuarrayY`, specified as a `gpuArray` column vector. If you do not provide `gpuarrayX`, methods that require `gpuarrayX` assume `gpuarrayX = 1:length(y)`. Specify `gpuarrayX` data when the data are not uniformly spaced or sorted. If the `gpuarrayX` data is not uniform and you do not specify the smoothing method, 'lowess' is used. If you specify a smoothing method that requires `gpuarrayX` to be sorted, the function automatically sorts the `gpuarrayX` data.

Data Types: `single` | `double`

## **Output Arguments**

### **yy — Smoothed data**

vector

Smoothed data, returned as a column vector.

### **gpuarrayYY — Smoothed data**

`gpuArray` vector

Smoothed data, returned as a `gpuArray` column vector.

## **Tips**

- You can generate a smooth fit to your data using a smoothing spline. For more information, see `fit`.

## **Alternative Functionality**

You can also smooth data by using the MATLAB `smoothdata` function. With the exception of GPU array support, `smoothdata` includes all the functionality of the `smooth` function and has some advantages. Unlike `smooth`, the `smoothdata` function supports:

- Matrices, tables, and timetables
- Moving median and Gaussian methods
- Option to specify how the NaN values are treated
- Option to substitute smoothed data for the original matrix or append smoothed data to the original matrix
- Tall arrays, C/C++ code generation, and thread-based environments

## **Version History**

Introduced before R2006a

## Extended Capabilities

### GPU Arrays

Accelerate code by running on a graphics processing unit (GPU) using Parallel Computing Toolbox™.

Usage notes and limitations:

- Using `gpuArray` `x` and `y` inputs with the `smooth` function is only recommended if you use the default method, `'moving'`. Using GPU data with other methods does not offer any performance advantage.

For more information, see “Run MATLAB Functions on a GPU” (Parallel Computing Toolbox).

### See Also

`smoothdata` | `fit` | `sort`

### Topics

“Filtering and Smoothing Data” on page 6-34

“Smoothing Splines” on page 6-14

“Lowess Smoothing” on page 6-22

“Nonparametric Fitting” on page 6-2

# slvblk

Solve almost block-diagonal linear system

## Syntax

```
x = slvblk(blokmat,b)
x = slvblk(blockmat,b,w)
```

## Description

`x = slvblk(blokmat,b)` returns the solution (if any) of the linear system  $Ax = b$ , with the matrix  $A$  stored in `blokmat` in the spline almost block-diagonal form. At present, only the command `spcol` provides such a description, of the matrix whose typical entry is the value of some derivative (including the 0th derivative, i.e., the value) of a B-spline at some site. If the linear system is overdetermined (i.e., has more equations than unknowns but is of full rank), then the least-squares solution is returned.

The right side `b` may contain several columns, and is expected to contain as many rows as there are rows in the matrix described by `blokmat`.

`x = slvblk(blockmat,b,w)` returns the vector  $x$  that minimizes the *weighted* sum  $\sum_j w(j) ((Ax - b)(j))^2$ .

## Examples

`sp=spmak(knots,slvblk(spcol(knots,k,x,1),y.'))` provides in `sp` the B-form of the spline  $s$  of order  $k$  with knot sequence `knots` that matches the given data  $(x,y)$ , i.e., for which  $s(x)$  equals  $y$ .

## Algorithms

The command `bkbrk` is used to obtain the essential parts of the coefficient matrix described by `blokmat` (in one of two available forms).

A QR factorization is made of each diagonal block, after it was augmented by the equations not dealt with when factoring the preceding block. The resulting factorization is then used to solve the linear system by back substitution.

## See Also

`bkbrk` | `spap2` | `spapi` | `spcol`

## sorted

Locate sites with respect to mesh sites

### Syntax

```
pointer = sorted(meshsites,sites)
```

### Description

Various commands in this toolbox need to determine the index  $j$  for which a given  $x$  lies in the interval  $[t_j, t_{j+1}]$ , with  $(t_i)$  a given nondecreasing sequence, e.g., a knot sequence. This job is done by `sorted` in the following fashion.

`pointer = sorted(meshsites,sites)` is the integer row vector whose  $j$ -th entry equals the number of entries in `meshsites` that are  $\leq$  `ssites(j)`, with `ssites` the vector `sort(sites)`. Thus, if both `meshsites` and `sites` are nondecreasing, then

$$\text{meshsites}(\text{pointer}(j)) \leq \text{sites}(j) < \text{meshsites}(\text{pointer}(j)+1)$$

with the obvious interpretations when

$$\text{pointer}(j) < 1 \quad \text{or} \quad \text{length}(\text{meshsites}) < \text{pointer}(j) + 1$$

Specifically, having `pointer(j) < 1` then corresponds to having `sites(j)` strictly to the left of `meshsites(1)`, while having `length(meshsites) < pointer(j)+1` then corresponds to having `sites(j)` at, or to the right of, `meshsites(end)`.

### Examples

The statement

```
sorted([1 1 1 2 2 3 3 3],[0:4])
```

will generate the output `0 3 5 8 8`, as will the statement

```
sorted([3 2 1 1 3 2 3 1],[2 3 0 4 1])
```

### Algorithms

The indexing output from `sort([meshsites(:).',sites(:).'])` is used.

## spap2

Least-squares spline approximation

### Syntax

```
spline = spap2(knots,k,x,y)
spap2(l,k,x,y)
spline = spap2(...,x,y,w)
spap2({knorl1,...,knorlm},k,{x1,...,xm},y)
spap2({knorl1,...,knorlm},k,{x1,...,xm},y,w)
```

### Description

`spline = spap2(knots,k,x,y)` returns the B-form of the spline  $f$  of order  $k$  with the given knot sequence `knots` for which

(\*)  $y(:,j) = f(x(j))$ , all  $j$

in the weighted mean-square sense, meaning that the sum

$$\sum_j w(j) |y(:,j) - f(x(j))|^2$$

is minimized, with default weights equal to 1. The data values  $y(:,j)$  can be scalars, vectors, matrices, or ND-arrays, and  $|z|^2$  is the sum of the squares of all the entries of  $z$ . Data points with the same site are replaced by their average.

If the sites  $x$  satisfy the Schoenberg-Whitney conditions

$$\begin{aligned} & \text{knots}(j) < x(j) < \text{knots}(j+k) \\ (**) \quad & j = 1, \dots, \text{length}(x) = \text{length}(\text{knots}) - k \end{aligned}$$

then there is a unique spline of the given order and knot sequence satisfying (\*) exactly. No spline is returned unless (\*\*) is satisfied for some subsequence of  $x$ .

`spap2(l,k,x,y)`, with  $l$  a positive integer, returns the B-form of a least-squares spline approximant, but with the knot sequence chosen for you. The knot sequence is obtained by applying `aptknt` to an appropriate subsequence of  $x$ . The resulting piecewise-polynomial consists of  $l$  polynomial pieces and has  $k-2$  continuous derivatives. If you feel that a different distribution of the interior knots might do a better job, follow this up with

```
sp1 = spap2(newknt(spline),k,x,y);
```

`spline = spap2(...,x,y,w)` lets you specify the weights  $w$  in the error measure (given above).  $w$  must be a vector of the same size as  $x$ , with nonnegative entries. All the weights corresponding to data points with the same site are summed when those data points are replaced by their average.

`spap2({knorl1,...,knorlm},k,{x1,...,xm},y)` provides a least-squares spline approximation to *gridded* data. Here, each `knorli` is either a knot sequence or a positive integer. Further,  $k$  must be an  $m$ -vector, and  $y$  must be an  $(r+m)$ -dimensional array, with  $y(:,i1,...,im)$  the datum to be fitted at the site  $[x\{1\}(i1), \dots, x\{m\}(im)]$ , all  $i1, \dots, im$ . However, if the spline is

to be scalar-valued, then, in contrast to the univariate case,  $y$  is permitted to be an  $m$ -dimensional array, in which case  $y(i_1, \dots, i_m)$  is the datum to be fitted at the site  $[x\{1\}(i_1), \dots, x\{m\}(i_m)]$ , all  $i_1, \dots, i_m$ .

`spap2({knorl1, ..., knorlm}, k, {x1, ..., xm}, y, w)` also lets you specify the weights. In this  $m$ -variate case,  $w$  must be a cell array with  $m$  entries, with  $w\{i\}$  a nonnegative vector of the same size as  $x_i$ , or else  $w\{i\}$  must be empty, in which case the default weights are used in the  $i$ th variable.

## Examples

### Calculate the Least-Squares Approximation of a Cubic Spline

This example shows how to compute the least-squares approximation to the data  $x, y$ , by cubic splines with two continuous derivatives, basic interval  $[a..b]$ , and interior breaks  $x_i$ , provided  $x_i$  has all its entries in  $(a..b)$  and the conditions (\*\*\*) are satisfied.

```
sp = spap2(augknt([a, xi, b], 4), 4, x, y)
```

In that case, the approximation consists of  $\text{length}(x_i)+1$  polynomial pieces. If you only want to get a cubic spline approximation consisting of  $l$  polynomial pieces, use instead

```
sp = spap2(l, 4, x, y);
```

If the resulting approximation is not satisfactory, try using a larger  $l$ . Else use

```
sp = spap2(newknt(sp), 4, x, y);
```

for a better distribution of the knot sequence. Repeat this process multiple times to increase the fidelity of the distribution.

As another example, `spap2(1, 2, x, y);` provides the least-squares straight-line fit to data  $x, y$ , while

```
w = ones(size(x));
w([1 end]) = 100;
spap2(1, 2, x, y, w);
```

forces that fit to come very close to the first data point and to the last.

### Compute and Plot the Least Square Approximation of a Bivariate Function

This example shows how to create a bivariate function, and compute and plot its least-square approximation.


Generate the data for the approximation and the bivariate function.

```
x = -2:.2:2;
y = -1:.25:1;
[xx, yy] = ndgrid(x, y);
z = exp(-(xx.^2+yy.^2));
```

Compute the least-square approximation and plot it.

```
sp = spap2({augknt([-2:2], 3), 2}, [3 4], {x, y}, z);
fnplt(sp)
```





## Input Arguments

### **knots** — Sequence of knots

vector | cell array

Knot sequence of the spline, specified as a nondecreasing vector.

### **k** — Spline order

scalar

Order of the spline  $f$ , specified as a scalar.

### **l** — Number of polynomial pieces

positive integer

Number of polynomial pieces of the resulting piecewise-polynomial, specified as a positive integer.

### **w** — Error weights

nonnegative vector

Weights in the error measure, specified as a nonnegative vector of the same size as  $x$ .

### **x** — Data sites

vector | cell array

Data sites of data values  $y$  to be fit, specified as a vector or as a cell array for multivariate data. Spline  $f$  is created with knots at each data site  $x$  such that  $f(x(j)) = y(:, j)$  for all values of  $j$ .

For multivariate, gridded data, you can specify  $x$  as a cell array that specifies the data site in each variable dimension:  $f(x1(i), x2(j), \dots, xn(k)) = y(:, i, j, \dots, k)$ .

**y — Data values to fit**

scalar | vector | matrix | array

Data values to fit during creation of the spline, specified as a vector, matrix, or array. Data values  $y(:, j)$  can be scalars, matrices, or  $n$ -dimensional arrays. Data values given at the same data site  $x$  are averaged.

Data Types: single | double

**Output Arguments****spline — Spline structure**

spline structure

Spline, returned as a structure with these fields.

**Form — Form of spline**

B-

Form of the spline, returned as B-. B- indicates it is given in B-form.

**Knots — Knot locations of spline**

vector | cell array

Knot positions of the spline, returned as a vector or as a cell array of vectors for multivariate data. Vectors contain strictly increasing elements that represent the start and end of each of the intervals over which the polynomial pieces are defined.

**Coefs — Coefficients of polynomials**

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

**Number — Number of polynomial pieces**

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

**Order — Order of polynomials**

scalar | vector

Order of the polynomial function describing each polynomial piece of the spline, returned as a scalar or as a vector containing the order in each variable for multivariate data.

**Dim — Dimensionality**

scalar

Dimensionality of the target function, returned as a scalar.

## Algorithms

`spcol` is called on to provide the almost block-diagonal collocation matrix  $(B_{j,k}(x_i))$ , and `slvblk` solves the linear system (\*) in the (weighted) least-squares sense, using a block QR factorization.

Gridded data are fitted, in tensor-product fashion, one variable at a time, taking advantage of the fact that a univariate weighted least-squares fit depends linearly on the values being fitted.

## Version History

Introduced before R2006a

### See Also

`slvblk` | `spapi` | `spcol`

### Topics

“Introducing Spline Fitting” on page 8-2

## spapi

Spline interpolation

### Syntax

```
spline = spapi(knots,x,y)
spapi(k,x,y)
spapi({knork1,...,knorkm},{x1,...,xm},y)
spapi(...,'noderiv')
```

### Description

`spline = spapi(knots,x,y)` returns the spline  $f$  (if any) of order

$k = \text{length}(\text{knots}) - \text{length}(x)$

with knot sequence `knots` for which

(\*)  $f(x(j)) = y(:,j)$ , all  $j$ .

If some of the entries of `x` are the same, then:

$$D^{m(j)}f(x(j)) = y(:,j)$$

with  $m(j) = \{i < j: x(i) = x(j)\}$  and  $D^m f$  the  $m$ -th derivative of  $f$ . In this case, the  $r$ -fold repetition of a site  $z$  in `x` corresponds to the prescribing of value and the first  $r - 1$  derivatives of  $f$  at  $z$ . To match the average of all data values with the same data instead, call `spapi` with an additional fourth argument.

The data values,  $y(:,j)$ , can be scalars, vectors, matrices, or ND-arrays.

`spapi(k,x,y)`, with  $k$  a positive integer, specifies the desired spline order,  $k$ . In this case the `spapi` function calls the `aptknt` function to determine a workable, but not necessarily optimal, knot sequence for the given sites `x`. In other words, the command `spapi(k,x,y)` has the same effect as the more explicit command `spapi(aptknt(x,k),x,y)`.

`spapi({knork1,...,knorkm},{x1,...,xm},y)` returns the B-form of a tensor-product spline interpolant to *gridded* data. Here, each `knork $i$`  is either a knot sequence, or a positive integer specifying the polynomial order used in the  $i$ -th variable. The `spapi` function then provides a corresponding knot sequence for the  $i$ -th variable. Further, `y` must be an  $(r+m)$ -dimensional array, with  $y(:,i_1, \dots, i_m)$  the datum to fit at the site  $[x\{1\}(i_1), \dots, x\{m\}(i_m)]$ , for all  $i_1, \dots, i_m$ . In contrast to the univariate case, if the spline is scalar-valued, then `y` can be an  $m$ -dimensional array.

`spapi(...,'noderiv')` with the character vector or string scalar `'noderiv'` as a fourth argument, has the same effect as `spapi(...)` except that data values sharing the same site are interpreted differently. With the fourth argument present, the average of the data values with the same data site is interpolated at such a site. Without it, data values with the same data site are interpreted as values of successive derivatives to be matched at such a site, as described above, in the first paragraph of this Description.

### Examples

### Bivariate Spline Interpolant and Osculatory Interpolation to Gridded Data

The function `spapi([0 0 0 0 1 2 2 2 2], [0 1 1 1 2], [2 0 1 2 -1])` produces the unique cubic spline  $f$  on the interval  $[0..2]$  with exactly one interior knot, at 1, that satisfies the five conditions

$$f(0+) = 2, f(1) = 0, Df(1) = 1, D^2f(1) = 2, f(2-) = -1.$$

These include 3-fold matching at 1, i.e., matching there to prescribed values of the function and its first two derivatives.

Here is an example of osculatory interpolation, to values  $y$  and slopes  $s$  at the sites  $x$  by a quintic spline:

```
sp = spapi(augknt(x,6,2), [x,x,min(x),max(x)], [y,s,ddy0,ddy1]);
```

with `ddy0` and `ddy1` values for the second derivative at the endpoints.


As a related example, if you want to interpolate the  $\sin(x)$  function at the distinct data sites by a cubic spline, and to match its slope at a subsequence  $x(s)$ , then call the `spapi` function with these arguments:

```
sp = spapi(4,[x x(s)], [sin(x) cos(x(s))]).
```

The `aptknt` function will provide a suitable knot sequence. If you want to interpolate the same data by quintic splines, then simply change the value 4 to 6.

As a bivariate example, here is a bivariate interpolant.

```
x = -2:.5:2; y = -1:.25:1; [xx, yy] = ndgrid(x,y);
z = exp(-(xx.^2+yy.^2));
sp = spapi({3,4},{x,y},z); fnplt(sp)
```



As an illustration of osculatory interpolation to gridded data, here is complete bicubic interpolation, with the data explicitly derived from the bicubic polynomial  $g(u, v) = u^3v^3$ . This is helpful to see exactly where the slopes, and slopes of slopes (the cross derivatives), must be placed in the data values supplied. Since  $g$  is a bicubic polynomial, its interpolant,  $f$ , must be  $g$  itself. Test this:

```
sites = {[0,1],[0,2]}; coefs = zeros(4,4); coefs(1,1) = 1;
g = ppmak(sites,coefs);
Dxg = fnval(fnder(g,[1,0]),sites);
Dyg = fnval(fnder(g,[0,1]),sites);
Dxyg = fnval(fnder(g,[1,1]),sites);
f = spapi({4,4}, {sites{1}([1,2,1,2]),sites{2}([1,2,1,2])}, ...
          [fnval(g,sites), Dyg ; ...
           Dxg.'          , Dxyg]);
if any( squeeze( fnbrk(fn2fm(f,'pp'),'c') ) - coefs )
'something went wrong', end
```

## Input Arguments

### knots — Sequence of knots

vector | cell array

Knot sequence of the spline, specified as a nondecreasing vector.

### k — Evaluation points

vector | matrix | cell

Points at which you want to evaluate the spline function  $f$ , specified as a vector, matrix or cell array.

#### **x — Data sites**

vector | cell array

Data sites of data values  $y$  to be fit, specified as a vector or as a cell array for multivariate data. Spline  $f$  is created with knots at each data site  $x$  such that  $f(x(j)) = y(:, j)$  for all values of  $j$ .

For multivariate, gridded data, you can specify  $x$  as a cell array that specifies the data site in each variable dimension:  $f(x1(i), x2(j), \dots, xn(k)) = y(:, i, j, \dots, k)$ .

#### **y — Data values to fit**

vector | matrix | array

Data values to fit during creation of the spline, specified as a vector, matrix, or array. Data values  $y(:, j)$  can be scalars, matrices, or  $n$ -dimensional arrays. Data values given at the same data site  $x$  are averaged.

Data Types: single | double

## **Output Arguments**

#### **spline — Spline structure**

spline structure

Spline, returned as a structure with these fields.

#### **Form — Form of spline**

pp | B-

Form of the spline, returned as `pp` or `B-`. `pp` indicates that the spline is given in piecewise polynomial form, `B-` indicates it is given in B-form.

#### **Knots — Knot locations of spline**

vector | cell array

Knot positions of the spline, returned as a vector or as a cell array of vectors for multivariate data. Vectors contain strictly increasing elements that represent the start and end of each of the intervals over which the polynomial pieces are defined.

#### **Coefs — Coefficients of polynomials**

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

#### **Number — Number of polynomial pieces**

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

#### **Order — Order of polynomials**

scalar | vector

Order of the polynomial function describing each polynomial piece of the spline, returned as a scalar or as a vector containing the order in each variable for multivariate data.

**Dim — Dimensionality**

scalar

Dimensionality of the target function, returned as a scalar.

**Limitations**

The given (univariate) knots and sites must satisfy the Schoenberg-Whitney conditions for the interpolant to be defined. If the site sequence  $x$  is nondecreasing, then

$$\text{knots}(j) < x(j) < \text{knots}(j + k), \text{ all } j$$

with equality possible at  $\text{knots}(1)$  and  $\text{knots}(\text{end})$ ). In the multivariate case, these conditions must hold in each variable separately.

**Algorithms**

The function calls `spcol` to provide the almost-block-diagonal collocation matrix  $(B_{j,k}(x))$  (with repeats in  $x$  denoting derivatives, as described above), and `slvblk` solves the linear system (\*), using a block QR factorization.

The function fits gridded data, in tensor-product fashion, one variable at a time, taking advantage of the fact that a univariate spline fit depends linearly on the values that are being fitted.

**Version History**

Introduced in R2006b

**See Also**

`csapi` | `spap2` | `spaps` | `spline`

**Topics**

“Introducing Spline Fitting” on page 8-2

“The B-form” on page 10-13

“The ppform” on page 10-8



## spaps

Smoothing spline

### Syntax

```
sp = spaps(x,y,tol)
[sp,values] = spaps(x,y,tol)
[sp,values,rho] = spaps(x,y,tol)
[...] = spaps(x,y,tol,w,m)
[...] = spaps({x1,...,xr},y,tol,...)
```

### Description

---

**Note** For a simpler but less flexible method to generate smoothing splines, try the Curve Fitter app or the `fit` function.

---

`sp = spaps(x,y,tol)` returns the B-form of the smoothest function  $f$  that lies within the given tolerance `tol` of the given data points  $(x(j), y(:,j))$ ,  $j=1:\text{length}(x)$ . The data values  $y(:,j)$  are scalars, vectors, matrices, or even ND-arrays. Data points with the same data site are replaced by their weighted average, with its weight the sum of the corresponding weights, and the tolerance `tol` is reduced accordingly.

`[sp,values] = spaps(x,y,tol)` also returns the smoothed values. `values` is the same as `fnval(sp,x)`.

Here, the distance of the function  $f$  from the given data is measured by

$$E(f) = \sum_{j=1}^n w(j) |y(:,j) - f(x(j))|^2$$

with the default choice for the weights  $w$  making  $E(f)$  the composite trapezoidal rule approximation to  $\int_{\min(x)}^{\max(x)} |y - f|^2$ , and  $|z|^2$  denoting the sum of squares of the entries of  $z$ .

Further, *smoothest* means that the following roughness measure is minimized:

$$F(D^m f) = \int_{\min(x)}^{\max(x)} \lambda(t) |D^m f(t)|^2 dt$$

where  $D^m f$  denotes the  $m$ th derivative of  $f$ . The default value for  $m$  is 2, the default value for the roughness measure weight  $\lambda$  is the constant 1, and this makes  $f$  a cubic smoothing spline.

When `tol` is nonnegative, then the spline  $f$  is determined as the unique minimizer of the expression  $\rho E(f) + F(D^m f)$ , with the smoothing parameter  $\rho$  (optionally returned) so chosen that  $E(f)$  equals `tol`. Hence, when  $m$  is 2, then, after conversion to ppform, the result should be the same (up to round-off) as obtained by `csaps(x,y,rho/(rho + 1))`. Further, when `tol` is zero, then the “natural” or variational spline

interpolant of order  $2m$  is returned. For large enough `tol`, the least-squares approximation to the data by polynomials of degree  $<m$  is returned.

When `tol` is negative, then  $\rho$  is  $-\text{tol}$ .

The default value for the weight function  $\lambda$  in the roughness measure is the constant function 1. But you can choose it to be, more generally, a piecewise constant function, with breaks only at the data sites. Assuming the vector  $x$  to be strictly increasing, you specify such a piecewise constant  $\lambda$  by inputting `tol` as a vector of the same size as  $x$ . In that case, `tol(i)` is taken as the constant value of  $\lambda$  on the interval  $(x(i-1) .. x(i))$ ,  $i=2:\text{length}(x)$ , while `tol(1)` continues to be used as the specified tolerance.

`[sp,values,rho] = spaps(x,y,tol)` also returns the actual value of  $\rho$  used as the third output argument.

`[...] = spaps(x,y,tol,w,m)` lets you specify the weight vector  $w$  and/or the integer  $m$ , by supplying them as an `argi`. For this,  $w$  must be a nonnegative vector of the same size as  $x$ ;  $m$  must be 1 (for a piecewise linear smoothing spline), or 2 (for the default cubic smoothing spline), or 3 (for a quintic smoothing spline).

If the resulting smoothing spline, `sp`, is to be evaluated outside its basic interval, it should be replaced by `fnxtr(sp,m)` to ensure that its  $m$ -th derivative is zero outside that interval.


`[...] = spaps({x1,...,xr},y,tol,...)` returns the B-form of an  $r$ -variate tensor-product smoothing spline that is roughly within the specified tolerance to the given *gridded data*. For *scattered* data, use `tpaps`. Now  $y$  is expected to supply the corresponding gridded values, with `size(y)` equal to `[length(x1),...,length(xr)]` in case the function is scalar-valued, and equal to `[d,length(x1),...,length(xr)]` in case the function is  $d$ -valued. Further, `tol` must be a cell array with  $r$  entries, with `tol{i}` the tolerance used during the  $i$ -th step when a univariate (but vector-valued) smoothing spline in the  $i$ -th variable is being constructed. The optional input for  $m$  must be an  $r$ -vector (with entries from the set  $\{1,2,3\}$ ), and the optional input for  $w$  must be a cell array of length  $r$ , with `w{i}` either empty (to indicate that the default choice is wanted) or else a positive vector of the same length as  $x_i$ .

## Examples

### Compare Two Cubic Smoothing Splines Obtained from Noisy Data


This code returns a fit to the noisy data that is expected to be quite close to the underlying noise-free data since the latter come from a slowly varying function and since the used `TOL` is of the size appropriate for the size of the noise.

```
x = linspace(0,2*pi,21); y = sin(x) + (rand(1,21)-.5)*.2;
sp = spaps(x,y, (.05)^2*(x(end)-x(1)) );
fnplt(sp)
```




This code uses the same data and tolerance as before, but chooses the roughness weight to be only 0.1 in the right half of the interval and gives, correspondingly, a rougher but better fit there.

```
sp1 = spaps(x,y, [(.025)^2*(x(end)-x(1)),ones(1,10), repmat(.1,1,10)] );  
fnplt(sp1)
```



Finally, compare the two cubic smoothing splines obtained previously.


```
fnplt(sp);  
hold on  
fnplt(sp1, 'r')  
plot(x,y, 'ok')  
hold off  
title('Two cubic smoothing splines')  
xlabel('The red one has reduced smoothness requirement in right half.')
```



### Smooth Approximant to Noisy Data of a Bivariate Function

This example produces a smooth approximant to noisy data from a smooth bivariate function. Note the use of `ndgrid` here; use of `meshgrid` would produce an error.

```
x = -2:.2:2; y=-1:.25:1;
[xx,yy] = ndgrid(x,y);
rng(39);
z = exp(-(xx.^2+yy.^2)) + (rand(size(xx))-0.5)/30;
sp = spaps({x,y},z,8/(60^2));
fnplt(sp)
axis off
```



## Input Arguments

### **x** — Data sites

vector | cell array

Data sites of data values  $y$  to be fit, specified as a vector or as a cell array for multivariate data. Spline  $f$  is created with knots at each data site  $x$  such that  $f(x(j)) = y(:, j)$  for all values of  $j$ .

For multivariate, gridded data, you can specify  $x$  as a cell array that specifies the data site in each variable dimension:  $f(x1(i), x2(j), \dots, xn(k)) = y(:, i, j, \dots, k)$ .

Data Types: single | double

### **y** — Data values to fit

vector | matrix | array

Data values to fit during creation of the spline, specified as a vector, matrix, or array. Data values  $y(:, j)$  can be scalars, matrices, or  $n$ -dimensional arrays. Data values given at the same data site  $x$  are averaged.

Data Types: single | double

### **tol** — Tolerance

scalar

Tolerance of the given data points, specified as a scalar.

Data Types: `single` | `double`

**w — Data weights**

vector | cell array

Weights  $w$  of the data points, specified as a vector of nonnegative entries of the same size as  $x$ .

**m — Derivative order**

scalar

Derivative order, specified as a scalar. This value must be either 1 for a piecewise linear smoothing spline, 2 for the default cubic smoothing spline, or 3 for a quintic smoothing spline.

Data Types: `single` | `double`

## Output Arguments

**sp — Spline in B-form**

spline structure

Spline in B-form, returned as a structure with these fields.

**Form — Form of spline**

B-

Form of the spline, returned as B-. B- indicates that the spline is given in B-form.

**Knots — Knot locations of spline**

vector | cell array

Knot positions of the spline, returned as a vector or as a cell array of vectors for multivariate data. Vectors contain strictly increasing elements that represent the start and end of each of the intervals over which the polynomial pieces are defined.

**Coefs — Coefficients of polynomials**

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

**Number — Number of polynomial pieces**

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

**Order — Order of polynomials**

scalar | vector

Order of the polynomial function describing each polynomial piece of the spline, returned as a scalar or as a vector containing the order in each variable for multivariate data.

**Dim — Dimensionality**

scalar

Dimensionality of the target function, returned as a scalar.

**values — Evaluated spline**

vector | matrix | array

Values of the spline at the points in  $x$ , returned as a vector or as a matrix or array for multivariate data.

**rho — Smoothing parameter**

scalar | cell array

Smoothing parameter used to calculate the spline, returned as a scalar or as a cell array of scalar values for multivariate data.

**Algorithms**

This function uses the Reinsch's approach [1], including his way of choosing the equation for the optimal smoothing parameter in such a way that a good initial guess is available and Newton's method is guaranteed to converge and to converge fast.

**Version History****Introduced before R2006a****References**

[1] C. Reinsch. "Smoothing by spline functions." *Numer. Math.* 10 (1967), 177-183.

**See Also**

csaps | spap2 | spapi | tpaps

**Topics**

"Introducing Spline Fitting" on page 8-2



## spcol

B-spline collocation matrix

### Syntax

```
colmat = spcol(knots,k,tau)
colmat = spcol(knots,k,tau,arg1,arg2,...)
```

### Description

`colmat = spcol(knots,k,tau)` returns the matrix, with `length(tau)` rows and `length(knots) - k` columns, whose  $(i,j)$ th entry is

$$D^{m(i)}B_j(\tau(i))$$

This is the value at  $\tau(i)$  of the  $m(i)$ th derivative of the  $j$ th B-spline of order  $k$  for the knot sequence `knots`. Here,  $\tau$  is a sequence of sites, assumed to be *nondecreasing*, and  $m = \text{knt2mlt}(\tau)$ , i.e.,  $m(i)$  is  $\#\{j < i : \tau(j) = \tau(i)\}$ , all  $i$ .

`colmat = spcol(knots,k,tau,arg1,arg2,...)` also returns that matrix, but gives you the opportunity to specify some aspects.

If one of the `argi` is a character vector or string scalar with the same first two letters as in 'slvblk', the matrix is returned in the almost block-diagonal format (specialized for splines) required by `slvblk` (and understood by `bkbrk`).

If one of the `argi` is a character vector or string scalar with the same first two letters as in 'sparse', then the matrix is returned in the sparse format of MATLAB.

If one of the `argi` is a character vector or string scalar with the same first two letters as in 'noderiv', multiplicities are ignored, i.e.,  $m(i)$  is taken to be 1 for all  $i$ .

### Examples

To solve approximately the non-standard second-order ODE

$$D^2y(t) = 5 \cdot (y(t) - \sin(2t))$$

on the interval  $[0..\pi]$ , using cubic splines with 10 polynomial pieces, you can use `spcol` in the following way:

```
tau = linspace(0,pi,101); k = 4;
knots = augknt(linspace(0,pi,11),k);
colmat = spcol(knots,k,brk2knt(tau,3));
coefs = (colmat(3:3:end,:)/5 - colmat(1:3:end,:))\(-sin(2*tau).');
sp = spmak(knots,coefs.');
```

You can check how well this spline satisfies the ODE by computing and plotting the residual,  $D^2y(t) - 5 \cdot (y(t) - \sin(2t))$ , on a fine mesh:

```
t = linspace(0,pi,501);
yt = fnval(sp,t);
D2yt = fnval(fnder(sp,2),t);
plot(t,D2yt - 5*(yt-sin(2*t)))
title(['residual error; to be compared to max(abs(D^2y)) = ',...
      num2str(max(abs(D2yt)))])
```

The statement `spcol([1:6],3,.1+[2:4])` provides the matrix

ans =

```
    0.5900    0.0050         0
    0.4050    0.5900    0.0050
         0    0.4050    0.5900
```

in which the typical row records the values at 2.1, or 3.1, or 4.1, of all B-splines of order 3 for the knot sequence 1:6. There are three such B-splines. The first one has knots 1,2,3,4, and its values are recorded in the first column. In particular, the last entry in the first column is zero since it gives the value of that B-spline at 4.1, a site to the right of its last knot.

If you add the character vector or string scalar 'sl' as an additional input to `spcol`, then you can ask `bkbrk` to extract detailed information about the block structure of the matrix encoded in the resulting output from `spcol`. Thus, the statement `bkbrk(spcol(1:6,3,.1+2:4,'sl'))` gives:

```
block 1 has 2 row(s)
    0.5900    0.0050         0
    0.4050    0.5900    0.0050
next block is shifted over 1 column(s)
block 2 has 1 row(s)
    0.4050    0.5900    0.0050
next block is shifted over 2 column(s)
```

## Limitations

The sequence `tau` is assumed to be nondecreasing.

## Algorithms

This is the most complex command in this toolbox since it has to deal with various ordering and blocking issues. The recurrence relations are used to generate, simultaneously, the values of all B-splines of order  $k$  having any one of the `tau(i)` in their support.

A separate calculation is carried out for the (presumably few) sites at which derivative values are required. These are the sites `tau(i)` with  $m(i) > 0$ . For these, and for every order  $k - j, j = j_0, j_0 - 1, \dots, 0$ , with  $j_0$  equal to  $\max(m)$ , values of all B-splines of that order are generated by recurrence and used to compute the  $j$ th derivative at those sites of all B-splines of order  $k$ .

The resulting rows of B-spline values (each row corresponding to a particular `tau(i)`) are then assembled into the overall (usually rather sparse) matrix.

When the optional argument 'sl' is present, these rows are instead assembled into a convenient almost block-diagonal form that takes advantage of the fact that, at any site `tau(i)`, at most  $k$  B-splines of order  $k$  are nonzero. This fact (together with the natural ordering of the B-splines) implies that the collocation matrix is almost block-diagonal, i.e., has a staircase shape, with the individual blocks or steps of varying height but of uniform width  $k$ .

The command `slvblk` is designed to take advantage of this storage-saving form available when used, in `spap2`, `spapi`, or `spaps`, to help determine the B-form of a piecewise-polynomial function from interpolation or other approximation conditions.

**See Also**

`slvblk` | `spap2` | `spapi`

## spcrv

Spline curve by uniform subdivision

### Syntax

```
spcrv(c,k)
spcrv(c)
spcrv(c,k,maxpnt)
```

### Description

`spcrv(c,k)` provides a dense sequence  $f(tt)$  of points on the uniform B-spline curve  $f$  of order  $k$  with B-spline coefficients  $c$ . Explicitly, this is the curve

$$f:t \rightarrow \sum_{j=1}^n B(t - k/2 | j, \dots, j+k) c(j), \quad \frac{k}{2} \leq t \leq n + \frac{k}{2}$$

with  $B(\cdot | a, \dots, z)$  the B-spline with knots  $a, \dots, z$ , and  $n$  the number of coefficients in  $c$ , i.e.,  $[d, n]$  equals `size(c)`.

`spcrv(c)` chooses the order  $k$  to be 4.

`spcrv(c,k,maxpnt)` makes sure that at least `maxpnt` points are generated. The default value for the maximum number of sites `tt` to be generated is 100.

The parameter interval that the site sequence `tt` fills out uniformly is the interval  $[k/2 .. (n - k/2)]$ .

The output consists of the array  $f(tt)$ .

### Examples

The following would show a questionable broken line and its smoothed version:

```
points = [0 0 1 1 0 -1 -1 0 0 ;
          0 0 0 1 2 1 0 -1 -2];
plot(points(1,:),points(2,:),':')
values = spcrv(points,3);
hold on, plot(values(1,:),values(2,:)), hold off
```

### Algorithms

Repeated midpoint knot insertion is used until there are at least `maxpnt` sites. There are situations where use of `fnplt` would be more efficient.

### See Also

`fnplt`

# splinetool

Experiment with some spline approximation methods

## Syntax

```
splinetool  
splinetool(x,y)
```

## Description

`splinetool` opens the Spline Tool, which lets you experiment with various spline approximation methods. It provides you with choices for data, including the option of importing some data from the workspace.

`splinetool(x,y)` opens the tool with the specified data `x` and `y`, which must be vectors of the same length.

## Examples

### Experiment with Noisy Data


Run this code to open the Spline Tool and experiment with noisy data.

```
x = linspace(1,pi,101);  
y = cos(x)+(rand(size(x))-.5)/10;  
splinetool(x,y)
```

### Explore End Conditions for Cubic Spline Interpolation

This example shows how to explore the various end conditions available with cubic spline interpolation in the Spline Tool.

- 1 Type `splinetool` at the command line.
- 2 Select **Import your own data** from the initial screen, and accept the default function. You should see the following display.




The default approximation is the cubic spline interpolant with the not-a-knot end condition.

The vector  $x$  of data sites is `linspace(0, 2*pi, 31)` and the values are `cos(x)`. This differs from simply providing the vector  $y$  of values in that the cosine function is explicitly recorded as the underlying function. Therefore, the error shown in the graph is the error in the spline as an approximation to the cosine rather than as an approximation to the given values. Notice the resulting relatively large error, about  $5e-5$ , near the endpoints.

**3** For comparison, follow these steps:

- a** Click **New** in the **List of approximations**.
- b** In **Approximation method**, select **complete** from the list of **End conditions**.
- c** Since the first derivative of the cosine function is sine, adjust the first-derivative values to their known values of zero at both the left end and the right end.

This procedure results in the display shown below. The right end slope is zero only up to round-off. **Bottomline** tells you that the tool uses the function `csape` to create the spline.



The improvement in the error is only about  $5e-6$ .

4 For further comparison, follow these steps:

- a Click **New** in the **List of approximations**.
- b In **Approximation method**, select **natural** from the list of **End conditions**.

Note the deterioration of the approximation near the ends, an error of about  $2e-3$ , which is much worse than with the not-a-knot end conditions.

5 For a final comparison, follow these steps:

- a Click **New** in the **List of approximations**.
- b Since the cosine function is periodic, in **Approximation method**, select **periodic** from the list of **End conditions**.


Note the dramatic improvement in the approximation, back to an error of about  $5e-6$ , particularly compared to the **natural** end conditions.

### Estimate the Second Derivative at Endpoint

This example uses cubic spline interpolation and least-squares approximation in the Spline Tool to determine an estimate of the initial acceleration for a drag car.

- 1 Type `splinetool` at the command line or if the tool is already open, click **File > Restart**.
- 2 Select **Richard Tapia's drag race data**. The data shows the distance traveled by a drag car as a function of time. The message window asks you to estimate the initial acceleration by setting the initial speed to zero. Click **OK**, or press the space bar or **Enter**, to remove the message window.
- 3 In **Approximation method**, select **complete** from the list of **End conditions**.
- 4 Adjust the initial speed by changing the first derivative at the left endpoint to zero.
- 5 Look for the value of the initial acceleration, which is given by the value of the second derivative at the left endpoint. You can toggle between the first derivative and the second derivative at this endpoint by clicking on the **left end** button. The value of the second derivative should be around 187 in the units chosen. Select **View > Show 2nd Derivative** to see the result graphically.
- 6 For comparison, click **New**, then select **Least-Squares Approximation** as the **Approximation method**. With this method, you can no longer specify end conditions. Instead, you may vary the order of the method. Verify that the initial acceleration is close to the cubic interpolation value.

The results of this procedure are shown below.




### Explore Least-Squares Approximation

This example encourages you to place five interior knots in such a way that the least-squares approximation by cubic splines has an absolute error no bigger than  $.04$  everywhere.



- 1 Type `splinetool` at the command line or if the tool is already open, click **File > Restart**.
- 2 Select **Titanium heat data**.
- 3 Select **Least-Squares Approximation** as the **Approximation method**.
- 4 Notice how poorly this selection approximates the data since there are no interior knots. To view the current knots and add new knots, select **Knots** from **Data, breaks/knots, weights**. The knots are now listed in **Knots**, and also displayed in the data graph as vertical lines. There are just the two end knots, each with multiplicity 4.
- 5 Right-click in the data graph and select **Add Knot**. This option displays a crosshairs for you to move with the mouse. Its precise horizontal location is shown in the edit field below the list of knots. A mouse click places a new knot at the current location of the crosshairs. One possible strategy is to add the knot at the place of maximum absolute error, as shown in the auxiliary graph below the data graph.



If you right-click and select **Replicate Knot**, you increase the multiplicity of the current knot, which is reflected by its repeated occurrence in **Knots**. To delete a specific knot, first select it in either the list of knots or the data graph, and then right-click in the graph and select **Delete Knot**.

- 6 You can also opt for an approximation using six polynomial pieces, which corresponds to five interior knots. To specify this option, enter 6 as **# pieces** in **Data, breaks/knots, weights**.


- 7 After you have the five interior knots, try to make the error even smaller by moving the knots. To select the knot you want to move, click its vertical line in the graph, and then use the control below **Knots** in **Data, breaks/knots, weights** and observe how the error changes with the movement of the knot. You can also use the edit field to overwrite the current knot location. Also try **adjust**, which redistributes the current knot sequence.
- 8 Use **Replicate** in **List of approximations** to save any good knot distribution for later use. Rename the replicated approximation to `lstsqr` by using **Rename**. To return to the original approximation, click on its name in **List of approximations**.

### Smoothing Spline

This example experiments with smoothing splines using the Spline Tool.

- 1 Type `splinetool` at the command line or, if the tool is already open, click **File > Restart**.
- 2 Select **Titanium heat data**.
- 3 In **Approximation method**, select **Smoothing Spline**.
- 4 Vary **Parameter** between 0 and 1, which changes the approximation from the least-squares straight-line approximation to the “natural” cubic spline interpolant.
- 5 Vary **Tolerance** between 0 and some large value, even `inf`. The approximation changes from the best possible one, the “natural” cubic spline interpolant, to the least-squares straight-line approximation.
- 6 As you increase the **Parameter** value or decrease the **Tolerance** value, the error decreases. However, a smaller error corresponds to more roughness, as measured by the size of the second derivative. To see this result, select **View > Show 2nd Derivative** and vary the **Parameter** and **Tolerance** values once again.
- 7 Modify the weights in the roughness measure to permit a more accurate but less smooth approximation in the peak area while having a smoother, less accurate, approximation away from the peak area.
  - a Select **Jumps in Roughness Weight** from **Data, breaks/knots, weights**.
  - b Select **View > Show 2nd Derivative**.
  - c Select any data point to the left of the peak in the data.
  - d Set the jump at the selected site to `-1` by changing its value in the edit field below it. Since the roughness weight for the very first site interval is 1, you have just set the roughness weight to the right of the highlighted site to 0. Correspondingly, the second derivative has become relatively small to the left of that site.
  - e Select any data point to the right of the peak in the data.
  - f Set the jump across the selected site to 1. Since the roughness weight just to the left of the highlighted site is 0, you have just set the roughness weight to the right of the highlighted site to 1. Correspondingly, the second derivative has become relatively small to the right of that site. The total effect is a very smooth but not very accurate fit away from the peak, while in the peak area, the spline fit is much better but the second derivative is much larger, as is shown in the auxiliary graph below.

At the sites where there is a jump in the roughness weight, there is a corresponding jump in the second derivative. If you increase the **Parameter** value, the error across the peak area decreases, but the second derivative remains quite large, while the opposite holds true away from the peak area.



## Input Arguments

### **x** — Data sites

vector

Data sites, specified as a vector of the same length of **y**. The data sites do not need to be distinct or ordered, but there must be at least two distinct sites.


### **y** — Data values

vector

Data values, specified as a vector of the same length of **x**.

## Tips

Spline Tool is shown in the following figure comparing cubic spline interpolation with a smoothing spline on sample data created by adding noise to the cosine function.



### Select Approximation Methods

The approximation methods and options supported by the tool are shown below.

| Approximation Method        | Option                                                                                                                                                                                                                |
|-----------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Cubic Interpolating Spline  | Adjust the type and values of the end conditions.                                                                                                                                                                     |
| Smoothing Spline            | Choose between cubic (order 4) and quintic (order 6) splines. Adjust the value of the tolerance and/or smoothing parameter. Adjust the weights in the error and roughness measures.                                   |
| Least-Squares Approximation | Vary the order from 1 to 14. The default order is 4, which gives cubic approximating splines. Modify the number of polynomial pieces. Add and move knots to improve the fit. Adjust the weights in the error measure. |
| Spline Interpolation        | Vary the order from 2 to 14. The default order is 4, which gives cubic spline interpolants. If the default knots supplied are not satisfactory, you can move them around to vary the fit.                             |

### Plot Graphs

You can generate and compare several approximations to the same data. One of the approximations is always marked as “current” using a thicker line width. The following displays are available:

- Data graph. It shows:
  - Data
  - Approximations chosen for display in **List of approximations**
  - Current knot sequence or the current break sequence
- Auxiliary graph (if viewed) for the current approximation. You can view this graph by selecting any one of the items in the **View** menu. It shows one of the following:
  - First derivative
  - Second derivative
  - Error

By default, the error is the difference between the given data values and the value of the approximation at the data sites. In particular, the error is zero (up to round-off) when the approximation is an interpolant. However, if you provide the data values by specifying a function, then the error displayed is the difference between that function and the current approximation. This also happens if you change the y-label of the data graph to the name of a function.

### Try Menu Options

You can annotate and print the graphs with the **File > Print to Figure** menu.

You can export the data and approximations to the workspace for further use or analysis with the **File > Export Data** and **File > Export Spline** menus, respectively.

You can create, with the **File > Generate Code** menu, a function file that you can use to generate, from the original data, any or all graphs currently shown. This file also provides you with a written record of the commands used to generate the current graphs.

You can save, with the **Replicate** button, the current approximation before you experiment further. If, at a later time, you click the saved approximation, the tool restores everything to the way it was, including the data used in the construction of the saved approximation. The saved approximation persists even if you have edited the data while working on other approximations.

You can add, delete, or move data, knots, and breaks by right-clicking in the graph, or by selecting the appropriate item in the **Edit** menu.

You can toggle the grid or the legend in a graph with the **Tools** menu.

## Version History

Introduced before R2006a

### See Also

csape | csapi | csaps | spap2 | spapi | spaps

### Topics

“Introducing Spline Fitting” on page 8-2

## splpp, sprpp

Taylor coefficients from local B-coefficients

### Syntax

```
[v,b] = splpp(tx,a)
[v,b] = sprpp(tx,a)
```

### Description

These are utility commands of use in the conversion from B-form to ppform (and in certain evaluations), but of no interest to the casual user.

`[v,b] = splpp(tx,a)` provides the matrices `v` and `b`, both of the same size  $[r,k]$  as `a`, and related to the input in the following way.

For  $i=1:r$ , `b(i,:)` are the B-coefficients, with respect to the knot sequence  $[tx(i,1:k-1), 0, \dots, 0]$ , of the polynomial of order  $k$  on the interval  $[tx(i,k-1) \dots tx(i,k)]$  whose  $k$  B-spline coefficients, with respect to the knot sequence `tx(i,:)`, are in `a(i,:)`. This is done by repeated knot insertion (of the knot 0). It is assumed that  $tx(i,k-1) < 0 \leq tx(i,k)$ .

For  $i=1:r$ , `v(i,:)` are the polynomial coefficients for that polynomial, i.e.,  $v(i,j)$  is the number  $D^{k-j}s(0-)/k-j!$ ,  $j=1:k$ , with  $s$  having the knots `tx(i,:)` and the B-coefficients `a(i,:)`.

`[v,b] = sprpp(tx,a)` carries out exactly the same job, except that now `b(i,:)` are the B-coefficients for that polynomial with respect to the knot sequence  $[0, \dots, 0, tx(i,k: 2*(k-1))]$ , and, correspondingly,  $v(i,j)$  is  $D^{k-j}s(0+) / k-j!$ ,  $j=1:k$ . Also, now it is assumed that  $tx(i,k-1) \leq 0 < tx(i,k)$ .

### Examples

The statement `[v,b]=splpp([-2 -1 0 1],[0 1 0])` provides the sequence

$$v = -1.0000 \ -1.0000 \ 0.5000 = D^2s(0-)/2, Ds(0-), s(0-)$$

with  $s$  the B-spline with knots  $-2, -1, 0, 1$ . This is so because the `l` in `splpp` indicates the limit from the left, and the second argument, `[0 1 0]`, indicates the spline  $s$  in question to be

$$s = 0 \times B(\cdot | [?, -2, -1, 0]) + 1 \times B(\cdot | [-2, -1, 0, 1]) + 0 \times B(\cdot | [-1, 0, 1, ?])$$

i.e., this particular linear combination of the third-order B-splines for the knot sequence  $\dots, -2, -1, 0, 1, \dots$  (Note that the values calculated do not depend on the knots marked `?`.) The above statement also provides the sequence `b = 0 1.0000 0.5000` of B-spline coefficients for the polynomial piece of  $s$  on the interval  $[-1, 0]$ , and with respect to the knot sequence `?, -2, -1, 0, 0, ?`.

In other words, on the interval  $[-1, 0]$ , the B-spline with knots  $-2, -1, 0, 1$  can be written

$$0 \times B(\cdot | [?, -2, -1, 0]) + 1 \times B(\cdot | [-2, -1, 0, 0]) + 5 \times B(\cdot | [-1, 0, 0, ?])$$

The statement `[v,b]=sprpp([-1 0 1 2],[1 0 0])` provides the sequence

$$v = [0.5000 \ -1.0000 \ 0.5000] = D^2 s(0+), Ds(0+), s(0+)$$

with  $s$  the B-spline with knots  $?, -1, 0, 1$ . Its polynomial piece on the interval  $[0, 1]$  is independent of the choice of  $?$ , so we might as well think of  $?$  as  $-2$ , i.e., we are dealing with the same B-spline as before. Note that the last two numbers agree with the limits from the left computed above, while the first number does not. This reflects the fact that a quadratic B-spline with simple knots is continuous with continuous first, but discontinuous second, derivative. (It also reflects the fact that the leftmost knot of a B-spline is irrelevant for its right-most polynomial piece.) The sequence  $\mathbf{b} = [0.5000 \ 0 \ 0]$  also provided states that, on the interval  $[0, 1]$ , the B-spline  $B(\cdot | [?, -1, 0, 1])$  can be written

$$0.5 \times B(\cdot | [0, 0, 0, 1]) + 0 \times B(\cdot | [0, 0, 1, 2]) + 0 \times B(\cdot | [0, 1, 2, ?])$$

## spmak

Put together spline in B-form

### Syntax

```
spmak(knots,coefs)
spmak(knots,coefs,sizec)
spmak
sp = spmak(knots,coeffs)
```

### Description

The command `spmak(...)` puts together a spline function in B-form, from minimal information, with the rest inferred from the input. `fnbrk` returns all the parts of the completed description. In this way, the actual data structure used for the storage of this form is easily modified without any effect on the various `fn...` commands that use this construct.

`spmak(knots,coefs)` returns the B-form of the spline specified by the knot information in `knots` and the coefficient information in `coefs`.

The action taken by `spmak` depends on whether the function is univariate or multivariate, as indicated by `knots` being a sequence or a cell array. For the description, let `sizec` be `size(coefs)`.

If `knots` is a sequence (required to be non-decreasing), then the spline is taken to be univariate, and its order  $k$  is taken to be `length(knots) - sizec(end)`. This means that each 'column' `coefs(:,j)` of `coefs` is taken to be a B-spline coefficient of the spline, hence the spline is taken to be `sizec(1:end-1)`-valued. The basic interval of the B-form is [`knots(1) .. knots(end)`].

Knot multiplicity is held to be  $\leq k$ . This means that the coefficient `coefs(:,j)` is simply ignored in case the corresponding B-spline has only one distinct knot, i.e., in case `knots(j)` equals `knots(j+k)`.

If `knots` is a cell array, of length  $m$ , then the spline is taken to be  $m$ -variate, and `coefs` must be an  $(r+m)$ -dimensional array, - except when the spline is to be scalar-valued, in which case, in contrast to the univariate case, `coefs` is permitted to be an  $m$ -dimensional array, but `sizec` is reset by

```
sizec = [1, sizec]; r = 1;
```

The spline is `sizec(1:r)`-valued. This means the output of the spline is an array with  $r$  dimensions, e.g., if `sizec(1:2) = [2, 3]` then the output of the spline is a 2-by-3 matrix.

The spline is `sizec(1:r)`-valued, the  $i$ th entry of the  $m$ -vector  $k$  is computed as `length(knots{i}) - sizec(r+i)`,  $i=1:m$ , and the  $i$ th entry of the cell array of basic intervals is set to [`knots{i}(1), knots{i}(end)`].

`spmak(knots,coefs,sizec)` lets you supply the intended size of the array `coefs`. Assuming that `coefs` is correctly sized, this is of concern only in the rare case that `coefs` has one or more trailing singleton dimensions. For, MATLAB suppresses trailing singleton dimensions, hence, without this explicit specification of the intended size of `coefs`, `spmak` would interpret `coefs` incorrectly.

`spmak` prompts you for `knots` and `coefs`.



`sp = spmak(knots, coeffs)` returns the spline `sp`.

## Examples

`spmak(1:6, 0:2)` constructs a spline function with basic interval `[1. .6]`, with 6 knots and 3 coefficients, hence of order  $6 - 3 = 3$ .

`spmak(t, 1)` provides the B-spline  $B(\cdot|t)$  in B-form.

The coefficients may be  $d$ -vectors (e.g., 2-vectors or 3-vectors), in which case the resulting spline is a curve or surface (in  $R^2$  or  $R^3$ ).

If the intent is to construct a 2-vector-valued bivariate polynomial on the rectangle  $[-1..1] \times [0..1]$ , linear in the first variable and constant in the second, say

```
coeffs = zeros([2 2 1]); coeffs(:, :, 1) = [1 0; 0 1];
```

then the straightforward

```
sp = spmak({[-1 -1 1 1], [0 1]}, coeffs);
```

will result in the error message 'There should be no more knots than coefficients', because the trailing singleton dimension of `coeffs` will not be perceived by `spmak`, while proper use of that third argument, as in

```
sp = spmak({[-1 -1 1 1], [0 1]}, coeffs, [2 2 1]);
```

will succeed. Replacing here `[2 2 1]` by `size(coeffs)` would not work.

See the example "Intro to B-form" for other examples.

## Diagnostics

There will be an error return if the proposed knot sequence fails to be nondecreasing, or if the coefficient array is empty, or if there are not more knots than there are coefficients. If the spline is to be multivariate, then this last diagnostic may be due to trailing singleton dimensions in `coeffs`.

## See Also

`fnbrk`

## spterms

Explain spline terms

### Syntax

```
spterms(term)
expl = spterms(term)
[... ,term] = spterms(...)
```

### Description

`spterms(term)` provides, in a message box, an explanation of the technical term indicated by the character vector or string scalar `term` as used in the Curve Fitting Toolbox spline functions and, specifically, in the `splinetool`. Only the first few (but at least two) letters of the desired term need to be specified, and the full term is shown in the title of the message box.

`expl = spterms(term)` returns, in `expl`, the character vector, or cell array of character vectors, comprising the explanation of the desired term.

`[... ,term] = spterms(...)` also returns, in `term`, the fully spelled-out term actually used.

### Examples

`spterms('sp')` gives an explanation of the term `'spline'`, while `spterms('spline i')` explains the terms `'spline interpolation'`.

`help spterms` provides the list of all available terms.

### See Also

`splinetool`

## stcol

Scattered translates collocation matrix

### Syntax

```
colmat = stcol(centers,x,type)
colmat = stcol(...,'tr')
```

### Description

`colmat = stcol(centers,x,type)` is the matrix whose  $(i,j)$ th entry is

$$\psi_j(x(:,i)), \quad i = 1:\text{size}(x,2), j = 1:n$$

with the bivariate functions  $\psi_j$  and the number  $n$  depending on the `centers` and the character vector or string scalar `type`, as detailed in the description of `stmak`.

`centers` and `x` must be matrices with the same number of rows.

The default for `type` is the character vector `'tp'`, and for this default,  $n$  equals `size(centers,2)`, and the functions  $\psi_j$  are given by

$$\psi_j(x) = \psi(x - \text{centers}(:,j)), \quad j = 1:n$$

with  $\psi$  the thin-plate spline basis function

$$\psi(x) = |x|^2 \log|x|^2$$

and with  $|x|$  denoting the Euclidean norm of the vector  $x$ .

---

**Note** See `stmak` for a description of other possible values for `type`.

---

The matrix `colmat` is the coefficient matrix in the linear system

$$\sum_j a_j \psi_j(x(:,i)) = y_i, \quad i = 1:\text{size}(x,2)$$

that the coefficients  $a_j$  of the function  $f = \sum_j a_j \psi_j$  must satisfy in order that  $f$  interpolate the value  $y_i$  at the site  $x(:,i)$ , all  $i$ .

`colmat = stcol(...,'tr')` returns the transpose of the matrix returned by `stcol(...)`.


### Examples

**Example 1.** The following evaluates and plots the function

$$f(x) = \psi(x - c_1) + \psi(x - c_2) + \psi(x - c_3) - 3.5\psi(x)$$

on a regular mesh, with  $\psi$  the above thin-plate basis function, and with  $c_1, c_2, c_3$  three points on the unit circle; see the figure below.

```
a = [0,2/3*pi,4/3*pi]; centers = [cos(a), 0; sin(a), 0];
[xx,yy] = ndgrid(linspace(-2,2,45));
xy = [xx(:) yy(:)].';
coefs = [1 1 1 -3.5];
zz = reshape( coefs*stcol(centers,xy,'tr') , size(xx));
surf(xx,yy,zz), view([240,15]), axis off
```



**Example 2.** The following also evaluates, on the same mesh, and plots the length of the gradient of the function in Example 1.

```
zz = reshape( sqrt(...
    ([coefs,0]*stcol(centers,xy,'tp10','tr')).^2 + ...
    ([coefs,0]*stcol(centers,xy,'tr','tp01')).^2),
    size(xx));
figure, surf(xx,yy,zz), view([220,-15]), axis off
```

### See Also

spsol | stmak

# stmak

Put together function in stform

## Syntax

```
stmak(centers, coefs)
st = stmak(centers, x, type)
st = stmak(centers, coefs, type, interv)
```

## Description

`stmak(centers, coefs)` returns the stform of the function  $f$  given by

$$f(x) = \sum_{j=1}^n \text{coefs}(:, j) \cdot \psi(x - \text{centers}(:, j))$$

with

$$\psi(x) = |x|^2 \log|x|^2$$

the thin-plate spline basis function, and with  $|x|$  denoting the Euclidean norm of the vector  $x$ .

`centers` and `coefs` must be matrices with the same number of columns.

`st = stmak(centers, x, type)` stores in `st` the stform of the function  $f$  given by

$$f(x) = \sum_{j=1}^n \text{coefs}(:, j) \cdot \psi_j(x)$$

with the  $\psi_j$  as indicated by the character vector or string scalar `type`, which can be one of the following:

- `'tp00'`, for the thin-plate spline;
- `'tp10'`, for the first derivative of a thin-plate spline with respect to its first argument;
- `'tp01'`, for the first derivative of a thin-plate spline with respect to its second argument;
- `'tp'`, the default.

Here are the details.

|                     |                                                                                                                                                                                 |
|---------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>'tp00'</code> | $\psi_j(x) = \varphi( x - c_j ^2), c_j = \text{centers}(:, j), j=1:n-3$<br>with $\varphi(t) = t \log(t)$<br>$\psi_{n-2}(x) = x(1)$<br>$\psi_{n-1}(x) = x(2)$<br>$\psi_n(x) = 1$ |
|---------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|


|                   |                                                                                                                                                                                                                                        |
|-------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 'tp10'            | $\psi_j(x) = \varphi( x - c_j ^2)$ , $c_j = \text{centers}(:, j)$ , $j=1:n-1$<br>with $\varphi(t) = (D_1 t)(\log t + 1)$ , and $D_1 t$ the partial derivative of $t = t(x) =  x - c_j ^2$<br>with respect to $x(1)$<br>$\psi_n(x) = 1$ |
| 'tp01'            | $\psi_j(x) = \varphi( x - c_j ^2)$ , $c_j = \text{centers}(:, j)$ , $j=1:n-1$<br>with $\varphi(t) = (D_2 t)(\log t + 1)$ , and $D_2 t$ the partial derivative of $t = t(x) =  x - c_j ^2$<br>with respect to $x(2)$<br>$\psi_n(x) = 1$ |
| 'tp'<br>(default) | $\psi_j(x) = \varphi( x - c_j ^2)$ , $c_j = \text{centers}(:, j)$ , $j=1:n$<br>with $\varphi(t) = t \log(t)$                                                                                                                           |

`st = stmak(centers,coefs,type,interv)` also specifies the basic interval for the stform, with `interv{j}` specifying, in the form `[a,b]`, the range of the `j`th variable. The default for `interv` is the smallest such box that contains all the given centers.

## Examples

**Example 1.** The following generates the figure below, of the thin-plate spline basis function,  $\psi(x) = |x|^2 \log|x|^2$ , but suitably restricted to show that this function is negative near the origin. For this, the extra lines are there to indicate the zero level.

```
inx = [-1.5 1.5]; iny = [0 1.2];
fnplt(stmak([0;0],1),{inx,iny})
hold on, plot(inx, repmat(linspace(iny(1),iny(2),11),2,1), 'r')
view([25,20]),axis off, hold off
```




**Example 2.** We now also generate and plot, on the very same domain, the first partial derivative  $D_2\psi$  of the thin-plate spline basis function, with respect to its second argument.

```
inx = [-1.5 1.5]; iny = [0 1.2];  
fnplt(stmak([0;0],[1 0],'tp01',{inx,iny}))  
view([13,10]), shading flat, axis off
```

Note that, this time, we have explicitly set the basic interval for the stform.

The resulting figure, below, shows a very strong variation near the origin. This reflects the fact that the *second* derivatives of  $\psi$  have a logarithmic singularity there.



### See Also

stcol

## subplus

Calculate positive part of function

### Syntax

```
xp = subplus(x)
```

### Description

`xp = subplus(x)` returns the positive part of  $x$ ,  $(x)_+$ , which is  $x$  if  $x$  is nonnegative, and  $0$  if  $x$  is negative. In other words,  $xp$  equals  $\max(x, 0)$ . If  $x$  is an array, this operation is applied entry by entry.

### Examples

#### Plot Positive Part of Simple Function


Compute the positive part of integers in the range from -2 to 2 by using the `subplus` function.

```
x = -2:2;  
xp = subplus(x);
```

Plot the `subplus` function on the interval from -2 to 2.

```
plot(x,xp)  
ylim([-0.5 2.5])
```






### Plot Hat Function Using subplus Function

Create a hat function by creating an anonymous function `hat` that uses the `subplus` function.

```
hat = @(x) subplus(x) - 2*subplus(x-1) + subplus(x-2);
```

Plot the hat function on the interval from -0.5 to 2.5.

```
x = -0.5:0.5:2.5;  
plot(x,hat(x))  
xlim([-0.5 2.5])
```



You can also describe the hat function by using the spline `spmak(0:2,1)`.

## Input Arguments

### **x** — Input function

scalar | vector | matrix

Function of which you want to calculate the positive part, specified as a scalar, vector, or matrix.

Data Types: `single` | `double`

## Output Arguments

### **xp** — Positive part

scalar | vector | matrix

Positive part of `x`, returned as a scalar, vector, or matrix.

## Version History

Introduced in R2006b

**See Also**

spline | fit on page 13-80

**Topics**

“Introducing Spline Fitting” on page 8-2

## titanium

Titanium test data

### Syntax

```
[x,y] = titanium
```


### Description

`[x,y] = titanium` returns measurements of a certain property of titanium as a function of temperature. Since their use in [1], these data have become a standard test for data fitting since they are hard to fit by classical techniques and have a significant amount of noise.

### Examples

The plot of the data shown below is generated by the following commands:

```
[x,y] = titanium; plot(x,y,'ok'), set(gca,'FontSize',16)
```



### References

- [1] C. de Boor and J. R. Rice. "Least squares cubic spline approximation II - Variable knots." CSD TR 21, Comp.Sci., Purdue Univ., April 1968.

## tpaps

Thin-plate smoothing spline

### Syntax

```
st = tpaps(x,y)
st = tpaps(x,y,p)
[... ,P] = tpaps(...)
```

### Description

`st = tpaps(x,y)` is the stform of a thin-plate smoothing spline  $f$  for the given data sites  $x(:,j)$  and the given data values  $y(:,j)$ . The  $x(:,j)$  must be distinct points in the plane, the values can be scalars, vectors, matrices, even ND-arrays, and there must be exactly as many values as there are sites.

The thin-plate smoothing spline  $f$  is the unique minimizer of the weighted sum

$$pE(f) + (1 - p)R(f)$$

with  $E(f)$  the error measure

$$E(f) = \sum_j |y(:,j) - f(x(:,j))|^2$$

and  $R(f)$  the roughness measure

$$R(f) = \int (|D_1 D_1 f|^2 + 2|D_1 D_2 f|^2 + |D_2 D_2 f|^2)$$

Here, the integral is taken over all of  $R^2$ ,  $|z|^2$  denotes the sum of squares of all the entries of  $z$ , and  $D_i f$  denotes the partial derivative of  $f$  with respect to its  $i$ -th argument, hence the integrand involves second partial derivatives of  $f$ . The function chooses the smoothing parameter  $p$  so that  $(1-p)/p$  equals the average of the diagonal entries of the matrix  $A$ , with  $A + (1-p)/p \cdot \text{eye}(n)$  the coefficient matrix of the linear system for the  $n$  coefficients of the smoothing spline to be determined. This ensures staying in between the two extremes of interpolation (when  $p$  is close to 1 and the coefficient matrix is essentially  $A$ ) and complete smoothing (when  $p$  is close to 0 and the coefficient matrix is essentially a multiple of the identity matrix). This serves as a good first guess for  $p$ .

`st = tpaps(x,y,p)` also inputs the *smoothing parameter*,  $p$ , a number between 0 and 1. As the smoothing parameter varies from 0 to 1, the smoothing spline varies, from the least-squares approximation to the data by a linear polynomial when  $p$  is 0, to the thin-plate spline interpolant to the data when  $p$  is 1.


`[... ,P] = tpaps(...)` also returns the value of the smoothing parameter used in the final spline result whether or not you specify  $p$ . This syntax is useful for experimentation in which you can start with `[pp,P] = tpaps(x,y)` and obtain a reasonable first guess for  $p$ .

### Examples

### Recover the Underlying Exact Smooth Values from Noised Data

The following code obtains values of a smooth function at 31 randomly chosen sites, adds some random noise to these values, and then uses `tpaps` to recover the underlying exact smooth values. To illustrate how well `tpaps` does in this case, the code plots, in addition to the smoothing spline, the exact values (as black balls) as well as each arrow leading from a smoothed value to the corresponding noisy value.

```
rng(23); nxy = 31;
xy = 2*(rand(2,nxy)-.5); vals = sum(xy.^2);
noisyvals = vals + (rand(size(vals))-0.5)/5;
st = tpaps(xy,noisyvals); fnplt(st), hold on
avals = fnval(st,xy);
plot3(xy(1,:),xy(2,:),vals,'wo','markerfacecolor','k')
quiver3(xy(1,:),xy(2,:),avals,zeros(1,nxy),zeros(1,nxy), ...
        noisyvals-avals,'r'), hold off
```




### Use an Interpolating Thin-Plate Spline to Construct a Map

The following code uses an interpolating thin-plate spline to vector-valued data values to construct a map, from the plane to the plane, that carries the unit square  $\{x: |x(j)| \leq 1, j = 1:2\}$  approximately onto the unit disk  $\{x: x(1)^2 + x(2)^2 \leq 1\}$ .

```

n = 64; t = linspace(0,2*pi,n+1); t(end) = [];
values = [cos(t); sin(t)];
centers = values./repmat(max(abs(values)),2,1);
st = tpaps(centers, values, 1);
fnplt(st), axis equal

```



Note the choice of 1 for the smoothing parameter here, to obtain interpolation.

## Input Arguments

### **x** — Data sites

vector | cell array

Data sites of data values  $y$  to be fit, specified as a vector or as a cell array for multivariate data. Spline  $f$  is created with knots at each data site  $x$  such that  $f(x(j)) = y(:, j)$  for all values of  $j$ .

For multivariate, gridded data, you can specify  $x$  as a cell array that specifies the data site in each variable dimension:  $f(x_1(i), x_2(j), \dots, x_n(k)) = y(:, i, j, \dots, k)$ .

### **y** — Data values to fit

vector | matrix | array

Data values to fit during creation of the spline, specified as a vector, matrix, or array. Data values  $y(:, j)$  can be scalars, matrices, or  $n$ -dimensional arrays. Data values given at the same data site  $x$  are averaged.

Data Types: `single` | `double`

### **p** — Smoothing parameter

scalar in the range  $[0, 1]$  | vector | cell array | empty array

Smoothing parameter, specified as a scalar value between 0 and 1 or as a cell array of values for multivariate data. You can also specify values for the roughness measure weights  $\lambda$  by providing **p** as a vector. To provide roughness measure weights for multivariate data, use a cell array of vectors. If you provide an empty array, the function chooses a default value for **p** based on the data sites **x** and the default value of 1 for the roughness measure weight  $\lambda$ .

The smoothing parameter determines the relative weight to place on the contradictory demands of having  $f$  be smooth or having  $f$  be close to the data. For  $p = 0$ ,  $f$  is the least-squares straight-line fit to the data. For  $p = 1$ ,  $f$  is the variational, or natural, cubic spline interpolant. As  $p$  moves from 0 to 1, the smoothing spline changes from one extreme to the other.

The favorable range for  $p$  is often near  $1/(1 + h^3/6)$ , where  $h$  is the average spacing of the data sites. The function chooses a default value for  $p$  within this range. For uniformly spaced data, you can expect a close fit with  $p = 1/(1 + h^3/6)$  and some satisfactory smoothing with  $p = 1/(1 + h^3/0.6)$ . You can input  $p > 1$ , but this choice leads to a smoothing spline even rougher than the variational cubic spline interpolant.

If the input **p** is negative or empty, then the function uses the default value for **p**.

You can specify the roughness measure weights  $\lambda$  alongside the smoothing parameter by providing **p** as a vector. This vector must be the same size as **x**, with the  $i$ th entry the value of  $\lambda$  on the interval  $(x(i-1) \dots x(i))$ , for  $i = 2:\text{length}(x)$ . The first entry of the input vector **p** is the desired value of the smoothness parameter  $p$ . By providing roughness measure weights, you can make the resulting smoothing spline smoother (with larger weight values) or closer to the data (with smaller weight values) in different parts of the interval. Roughness measure weights must be nonnegative.

If you have difficulty choosing  $p$  but have some feeling for the size of the noise in **y**, consider using `spaps(x, y, tol)` instead. This function chooses  $p$  such that the roughness measure is as small as possible, subject to the condition that the error measure does not exceed **tol**. In this case, the error measure usually equals the specified value for **tol**.

Data Types: `single` | `double`

## Output Arguments

### **st** — Spline structure

spline structure

Spline, returned as a structure with these fields.

### Form — Form of spline

`st-tp00` | `st-tp10` | `st-tp01` | `st-tp`

Form of the spline, returned as `st-tp00`, `st-tp10`, `st-tp01`, or `st-tp`.

### Centers — Sequence of sites

matrix | array

Sequence of sites, returned as a matrix or as an array for multivariate data.



**Coefs — Coefficients of polynomials**

matrix | array

Coefficients of polynomials for each piece, returned as a matrix or as an array for multivariate data.

**Ncenters — Number of centers**

scalar | vector

Number of sequence of sites.

**Number — Number of polynomial pieces**

scalar | vector

Number of polynomial pieces describing the spline, returned as a scalar or as a vector of numbers of pieces in each variable for multivariate data.

**Dim — Dimensionality**

scalar

Dimensionality of the target function, returned as a scalar.

**Interv — Basic interval**

cell array

Basic interval for the stform that contains all the given centers, returned as an array.

**P — Smoothing parameter**

scalar | cell array

Smoothing parameter used to calculate the spline, returned as a scalar or as a cell array of scalar values for multivariate data. P is between 0 and 1.

**Limitations**

The determination of the smoothing spline involves the solution of a linear system with as many unknowns as there are data points. Since the matrix of this linear system is full, the solving can take a long time even if, as is the case here, an iterative scheme is used when there are more than 728 data points. The convergence speed of that iteration is strongly influenced by  $p$ , and is slower the larger  $p$  is. So, for large problems, use interpolation, i.e.,  $p$  equal to 1, only if you can afford the time.

**Version History****Introduced in R2006b****See Also**

csaps | spaps | stmak

**Topics**

"Introducing Spline Fitting" on page 8-2

"Constructing and Working with stform Splines" on page 10-28

"Multivariate and Rational Splines" on page 10-6

## type

Name of `cfit`, `sfit`, or `fittype` object

### Syntax

```
name = type(fun)
```

### Description

`name = type(fun)` returns the custom or library name name of the `cfit`, `sfit`, or `fittype` object `fun` as a character array.

### Examples

```
f = fittype('a*x^2+b*exp(n*x)');  
category(f)  
ans =  
custom  
type(f)  
ans =  
customnonlinear
```

```
g = fittype('fourier4');  
category(g)  
ans =  
library  
type(g)  
ans =  
fourier4
```

## Version History

**Introduced in R2006b**

### See Also

`fittype` | `category`

### Topics

“List of Library Models for Curve and Surface Fitting” on page 4-10

# Bibliography

- [1] Barber, C. B., D. P. Dobkin, and H. T. Huhdanpaa. "The Quickhull Algorithm for Convex Hulls." *ACM Transactions on Mathematical Software*. Vol. 22, No. 4, 1996, pp. 469-483.
- [2] Bevington, P. R., and D. K. Robinson. *Data Reduction and Error Analysis for the Physical Sciences*. 2nd ed. London: McGraw-Hill, 1992.
- [3] Branch, M. A., T. F. Coleman, and Y. Li. "A Subspace, Interior, and Conjugate Gradient Method for Large-Scale Bound-Constrained Minimization Problems." *SIAM Journal on Scientific Computing*. Vol. 21, No. 1, 1999, pp. 1-23.
- [4] Carroll, R. J., and D. Ruppert. *Transformation and Weighting in Regression*. London: Chapman & Hall, 1988.
- [5] Chambers, J., W. S. Cleveland, B. Kleiner, and P. Tukey. *Graphical Methods for Data Analysis*. Belmont, CA: Wadsworth International Group, 1983.
- [6] Cleveland, W. S. "Robust Locally Weighted Regression and Smoothing Scatterplots." *Journal of the American Statistical Association*. Vol. 74, 1979, pp. 829-836.
- [7] Cleveland, W. S., and S. J. Devlin. "Locally Weighted Regression: An Approach to Regression Analysis by Local Fitting." *Journal of the American Statistical Association*. Vol. 83, 1988, pp. 596-610.
- [8] Daniel, C., and F. S. Wood. *Fitting Equations to Data*. Hoboken, NJ: Wiley-Interscience, 1980.
- [9] DeAngelis, D. J., J. R. Calarco, J. E. Wise, H. J. Emrich, R. Neuhausen, and H. Weyand. "Multipole Strength in  $^{12}\text{C}$  from the  $(e, e'\alpha)$  Reaction for Momentum Transfers up to  $0.61 \text{ fm}^{-1}$ ." *Physical Review C*. Vol. 52, No. 1, 1995, pp. 61-75.
- [10] de Boor, C. *A Practical Guide to Splines*. Berlin: Springer-Verlag, 1978.
- [11] Draper, N. R., and H. Smith. *Applied Regression Analysis*. 3rd ed. Hoboken, NJ: Wiley-Interscience, 1998.
- [12] DuMouchel, W., and F. O'Brien. "Integrating a Robust Option into a Multiple Regression Computing Environment." *Computing Science and Statistics: Proceedings of the 21st Symposium on the Interface*. (K. Berk and L. Malone, eds.) Alexandria, VA: American Statistical Association, 1989, pp. 297-301.
- [13] Goodall, C. "A Survey of Smoothing Techniques." *Modern Methods of Data Analysis*. (J. Fox and J. S. Long, eds.) Newbury Park, CA: Sage Publications, 1990, pp. 126-176.
- [14] Holland, P. W., and R. E. Welsch. "Robust Regression Using Iteratively Reweighted Least-Squares." *Communications in Statistics—Theory and Methods*. Vol. A6, 1977, pp. 813-827.
- [15] Huber, P. J. *Robust Statistics*. Hoboken, NJ: Wiley-Interscience, 1981.

- [16] Hutcheson, M. C. "Trimmed Resistant Weighted Scatterplot Smooth." Master's Thesis. Cornell University, Ithaca, NY, 1995.
- [17] Levenberg, K. "A Method for the Solution of Certain Problems in Least Squares." *Quarterly of Applied Mathematics*. Vol. 2, 1944, pp. 164-168.
- [18] Marquardt, D. "An Algorithm for Least-Squares Estimation of Nonlinear Parameters." *SIAM Journal on Applied Mathematics*. Vol. 11, 1963, pp. 431-441.
- [19] Orfanidis, S. J. *Introduction to Signal Processing*. Englewood Cliffs, NJ: Prentice-Hall, 1996.
- [20] Press, W. H., S. A. Teukolsky, W. T. Vetterling, and B. P. Flannery. *Numerical Recipes in C: The Art of Scientific Computing*. Cambridge, UK: Cambridge University Press, 1993.
- [21] Street, J. O., R. J. Carroll, and D. Ruppert. "A Note on Computing Robust Regression Estimates Via Iteratively Reweighted Least Squares." *The American Statistician*. Vol. 42, 1988, pp. 152-154.
- [22] Watson, David E. *Contouring: A Guide to the Analysis and Display of Spatial Data*. Tarrytown, NY: Pergamon, 1992.